


A Document Preparation System

L^AT_EX

USER'S GUIDE AND
REFERENCE MANUAL



Leslie Lamport

Updated for
L^AT_EX 2 ϵ

Contents

Preface	xv
1 Getting Acquainted	1
1.1 How to Avoid Reading This Book	2
1.2 How to Read This Book	3
1.3 The Game of the Name	5
1.4 Turning Typing into Typography	5
1.5 Why L ^A T _E X?	7
1.6 Turning Ideas into Input	8
1.7 Trying It Out	8
2 Getting Started	11
2.1 Preparing an Input File	12
2.2 The Input	13
2.2.1 Sentences and Paragraphs	13
Quotation Marks	13
Dashes	14
Space After a Period	14
Special Symbols	15
Simple Text-Generating Commands	15
Emphasizing Text	16
Preventing Line Breaks	17
Footnotes	17
Formulas	18
Ignorable Input	19
2.2.2 The Document	19
The Document Class	19
The Title “Page”	20
2.2.3 Sectioning	21
2.2.4 Displayed Material	23
Quotations	24
Lists	24

	Poetry	25
	Displayed Formulas	26
2.2.5	Declarations	27
2.3	Running L ^A T _E X	28
2.4	Helpful Hints	31
2.5	Summary	32
3	Carrying On	35
3.1	Changing the Type Style	36
3.2	Symbols from Other Languages	38
3.2.1	Accents	38
3.2.2	Symbols	38
3.3	Mathematical Formulas	39
3.3.1	Some Common Structures	40
	Subscripts and Superscripts	40
	Fractions	40
	Roots	40
	Ellipsis	40
3.3.2	Mathematical Symbols	41
	Greek Letters	41
	Calligraphic Letters	42
	A Menagerie of Mathematical Symbols	42
	Log-like Functions	44
3.3.3	Arrays	45
	The <code>array</code> Environment	45
	Vertical Alignment	46
	More Complex Arrays	46
3.3.4	Delimiters	46
3.3.5	Multiline Formulas	47
3.3.6	Putting One Thing Above Another	49
	Over- and Underlining	49
	Accents	49
	Stacking Symbols	50
3.3.7	Spacing in Math Mode	50
3.3.8	Changing Style in Math Mode	51
	Type Style	51
	Math Style	52
3.3.9	When All Else Fails	52
3.4	Defining Commands and Environments	53
3.4.1	Defining Commands	53
3.4.2	Defining Environments	55
3.4.3	Theorems and Such	56
3.5	Figures and Other Floating Bodies	58

3.5.1	Figures and Tables	58
3.5.2	Marginal Notes	59
3.6	Lining It Up in Columns	60
3.6.1	The <code>tabbing</code> Environment	60
3.6.2	The <code>tabular</code> Environment	62
3.7	Simulating Typed Text	63
4	Moving Information Around	65
4.1	The Table of Contents	66
4.2	Cross-References	67
4.3	Bibliography and Citation	69
4.3.1	Using <code>BibTeX</code>	70
4.3.2	Doing It Yourself	71
4.4	Splitting Your Input	72
4.5	Making an Index or Glossary	74
4.5.1	Compiling the Entries	74
4.5.2	Producing an Index or Glossary by Yourself	75
4.6	Keyboard Input and Screen Output	76
4.7	Sending Your Document	77
5	Other Document Classes	79
5.1	Books	80
5.2	Slides	80
5.2.1	Slides and Overlays	81
5.2.2	Notes	83
5.2.3	Printing Only Some Slides and Notes	83
5.2.4	Other Text	84
5.3	Letters	84
6	Designing It Yourself	87
6.1	Document and Page Styles	88
6.1.1	Document-Class Options	88
6.1.2	Page Styles	89
6.1.3	The Title Page and Abstract	90
6.1.4	Customizing the Style	91
6.2	Line and Page Breaking	93
6.2.1	Line Breaking	93
6.2.2	Page Breaking	96
6.3	Numbering	97
6.4	Length, Spaces, and Boxes	99
6.4.1	Length	99
6.4.2	Spaces	101
6.4.3	Boxes	103
	LR Boxes	104

	Parboxes	104
	Rule Boxes	106
	Raising and Lowering Boxes	107
	Saving Boxes	107
6.4.4	Formatting with Boxes	108
6.5	Centering and “Flushing”	111
6.6	List-Making Environments	112
6.6.1	The <code>list</code> Environment	112
6.6.2	The <code>trivlist</code> Environment	115
6.7	Fonts	115
6.7.1	Changing Type Size	115
6.7.2	Special Symbols	116
7	Pictures and Colors	117
7.1	Pictures	118
7.1.1	The <code>picture</code> Environment	119
7.1.2	Picture Objects	120
	Text	120
	Boxes	120
	Straight Lines	122
	Arrows	123
	Stacks	123
	Circles	124
	Ovals and Rounded Corners	124
	Framing	125
7.1.3	Curves	125
7.1.4	Grids	126
7.1.5	Reusing Objects	127
7.1.6	Repeated Patterns	127
7.1.7	Some Hints on Drawing Pictures	128
7.2	The <code>graphics</code> Package	129
7.3	Color	131
8	Errors	133
8.1	Finding the Error	134
8.2	$\LaTeX$ ’s Error Messages	136
8.3	$\TeX$ ’s Error Messages	140
8.4	$\LaTeX$ Warnings	145
8.5	$\TeX$ Warnings	147
A	Using <i>MakeIndex</i>	149
A.1	How to Use <i>MakeIndex</i>	150
A.2	How to Generate Index Entries	150
A.2.1	When, Why, What, and How to Index	150

A.2.2	The Basics	151
A.2.3	The Fine Print	153
A.3	Error Messages	154
B	The Bibliography Database	155
B.1	The Format of the bib File	156
B.1.1	The Entry Format	156
B.1.2	The Text of a Field	157
Names		157
Titles		158
B.1.3	Abbreviations	158
B.1.4	Cross-References	159
B.2	The Entries	160
B.2.1	Entry Types	160
B.2.2	Fields	162
C	Reference Manual	165
C.1	Commands and Environments	166
C.1.1	Command Names and Arguments	166
C.1.2	Environments	167
C.1.3	Fragile Commands	167
C.1.4	Declarations	168
C.1.5	Invisible Commands and Environments	169
C.1.6	The \ Command	169
C.2	The Structure of the Document	170
C.3	Sentences and Paragraphs	170
C.3.1	Making Sentences	170
C.3.2	Making Paragraphs	171
C.3.3	Footnotes	172
C.3.4	Accents and Special Symbols	173
C.4	Sectioning and Table of Contents	174
C.4.1	Sectioning Commands	174
C.4.2	The Appendix	175
C.4.3	Table of Contents	175
C.4.4	Style Parameters	176
C.5	Classes, Packages, and Page Styles	176
C.5.1	Document Class	176
C.5.2	Packages	178
C.5.3	Page Styles	179
C.5.4	The Title Page and Abstract	181
C.6	Displayed Paragraphs	183
C.6.1	Quotations and Verse	184
C.6.2	List-Making Environments	184

C.6.3	The <code>list</code> and <code>trivlist</code> Environments	185
C.6.4	Verbatim	186
C.7	Mathematical Formulas	187
C.7.1	Math Mode Environments	187
C.7.2	Common Structures	189
C.7.3	Mathematical Symbols	189
C.7.4	Arrays	190
C.7.5	Delimiters	190
C.7.6	Putting One Thing Above Another	190
C.7.7	Spacing	191
C.7.8	Changing Style	191
C.8	Definitions, Numbering, and Programming	192
C.8.1	Defining Commands	192
C.8.2	Defining Environments	192
C.8.3	Theorem-like Environments	193
C.8.4	Numbering	194
C.8.5	The <code>ifthen</code> Package	195
C.9	Figures and Other Floating Bodies	197
C.9.1	Figures and Tables	197
C.9.2	Marginal Notes	200
C.10	Lining It Up in Columns	201
C.10.1	The <code>tabbing</code> Environment	201
C.10.2	The <code>array</code> and <code>tabular</code> Environments	204
C.11	Moving Information Around	207
C.11.1	Files	207
C.11.2	Cross-References	209
C.11.3	Bibliography and Citation	209
C.11.4	Splitting the Input	210
C.11.5	Index and Glossary	211
	Producing an Index	211
	Compiling the Entries	212
C.11.6	Terminal Input and Output	212
C.12	Line and Page Breaking	213
C.12.1	Line Breaking	213
C.12.2	Page Breaking	214
C.13	Lengths, Spaces, and Boxes	215
C.13.1	Length	215
C.13.2	Space	216
C.13.3	Boxes	217
C.14	Pictures and Color	219
C.14.1	The <code>picture</code> Environment	219
	Picture-Mode Commands	220
	Picture Objects	221

Picture Declarations	223
C.14.2 The <code>graphics</code> Package	223
C.14.3 The <code>color</code> Package	224
C.15 Font Selection	225
C.15.1 Changing the Type Style	225
C.15.2 Changing the Type Size	226
C.15.3 Special Symbols	226
D What's New	227
E Using Plain TeX Commands	231
Bibliography	235
Index	237

List of Figures

Preface

The first edition of this book appeared in 1985. It described $\text{\LaTeX}$ 2.09, the first widely used version of $\text{\LaTeX}$. Since then, $\text{\LaTeX}$ has become extremely popular, with many thousands of users around the world. Its functionality has grown through the efforts of many people. The time has come for a new version, $\text{\LaTeX} 2_\epsilon$, which is described in this edition. $\text{\LaTeX} 2_\epsilon$ includes many of the enhancements that were made to $\text{\LaTeX}$ 2.09, as well as some new ones.

I implemented most of $\text{\LaTeX}$ 2.09 myself. $\text{\LaTeX} 2_\epsilon$ was implemented by a group led by Frank Mittelbach, which included Johannes Braams, David Carlisle, Michael Downes, Alan Jeffrey, Chris Rowley, Sebastian Rahtz, and Rainer Schöpf. They were assisted by many testers of the new version, and by the following organizations: the American Mathematical Society, the Open University (UK), and the Zentrum für Datenverarbeitung der Universität Mainz. Lyle Ramshaw helped with the implementation of Bezier curves. My thanks to all of these people—especially Frank and Chris, with whom I have spent many enjoyable hours arguing about $\text{\LaTeX}$.

$\text{\LaTeX}$ has been made more useful by two programs: $\text{\BibTeX}$, written by Oren Patashnik, and *MakeIndex*, written by Pehong Chen and modified by Nelson Beebe.

Many people helped me write this book—often without knowing it. Advice given to me over the years by Cynthia Hibbard and Mary-Claire van Leunen has found its way onto a number of these pages. Andrei Broder was my local informant for Romanian. Helen Goldstein assisted with research on matters ranging from art to zoology.

This edition was improved by the corrections and suggestions of Marc Brown, Michel Goossens, and the implementers of $\text{\LaTeX} 2_\epsilon$. Stephen Harrison helped produce the final output. Errors and infelicities in the first printing were found by Rosemary Bailey, Malcolm Clark, and Ellen Gilkerson. The following people found errors in, or suggested improvements to, the previous edition: Martín Abadi, Helmer Aslaksen, Barbara Beeton, Rick Clark, John DeTreville, Mathieu Federspiel, Michael Fischer, Stephen Gildea, Andy Hisgen, Joseph Hurler, Louis E. Janus, Dave Johnson, Charles Karney, Nori Kawasaki, Steve Kelem, Mark Kent, William LeFebvre, Jerry Leichter, Hank Lewis, Stephen Peckham,

Hal Perkins, Flavio Rose, Scott Simpson, David Sullivan, Matthew Swift, Walter Taylor, Joe Weening, Sam Whidden, Edgar Whipple, Chris Wilson, David Wise, and Rusty Wright. I also received helpful comments and complaints about preliminary versions of L^AT_EX and of the first edition of this book from Todd Allen, Robert Amsler, David Bacon, Stephen Barnard, Per Bothner, David Braunegg, Daniel Brotsky, Chuck Buckley, Pavel Curtis, Russell Greiner, Andrew Hanson, Michael Harrison, B. J. Herbison, Calvin W. Jackson, David Kosower, Kenneth Laws, Tim Morgan, Mark Moriconi, Stuart Reges, A. Wayne Slawson, David Smith, Michael Spivak, Mark Stickel, Gary Swanson, Mike Urban, Mark Wadsworth, and Gio Wiederhold. Assistance in the development of L^AT_EX 2.09 was provided by David Fuchs, Richard Furuta, Marshall Henrichs, Lynn Ruggles, Richard Southall, Chris Torek, Howard Trickey, and SRI International.

Since the introduction of version 2.09, my work on L^AT_EX has been supported by Digital Equipment Corporation. I want to thank Robert Taylor and all the other members of Digital's Systems Research Center for making it a fun place to work.

Finally, I want to express my special thanks to two men who made this book possible. Donald Knuth created T_EX, the program on which L^AT_EX is based. He also answered all my questions, even the stupid ones, and was always willing to explain T_EX's mysteries. Peter Gordon persuaded me to write the first edition, despite my doubts that anyone would buy a book about a typesetting system. Over the years, he has provided advice, fine dining, and friendship.


L. L.

Palo Alto, California

September 1994

CHAPTER 1

Getting Acquainted



L^AT_EX is a system for typesetting documents. Its first widely available version, mysteriously numbered 2.09, appeared in 1985. L^AT_EX is now extremely popular in the scientific and academic communities, and it is used extensively in industry. It has become a *lingua franca* of the scientific world; scientists send their papers electronically to colleagues around the world in the form of L^AT_EX input.

Over the years, various nonstandard enhancements were made to L^AT_EX 2.09 to overcome some of its limitations. L^AT_EX input that made use of these enhancements would not work properly at all sites. A new version of L^AT_EX was needed to keep a Tower of Babel from rising. The current version of L^AT_EX, with the somewhat less mysterious number 2_ε, was released in 1994. L^AT_EX 2_ε contains an improved method for handling different styles of type, commands for including graphics and producing colors, and many other new features.

Almost all standard L^AT_EX 2.09 input files will work with L^AT_EX 2_ε. However, to take advantage of the new features, users must learn a few new L^AT_EX 2_ε conventions. L^AT_EX 2.09 users should read Appendix D to find out what has changed. The rest of this book is about L^AT_EX, which, until a newer version appears, means L^AT_EX 2_ε.

L^AT_EX is available for just about any computer made today. The versions that run on these different systems are essentially the same; an input file created according to the directions in this book should produce the same output with any of them. However, how you actually run L^AT_EX depends upon the computer system. Moreover, some new features may not be available on all systems when L^AT_EX 2_ε is first released. For each computer system, there is a short companion to this book, titled something like *Local Guide to L^AT_EX for the McKludge PC*, containing information specific to that system. I will call it simply the *Local Guide*. It is distributed with the L^AT_EX software.

There is another companion to this book, *The L^AT_EX Companion* by Goossens, Mittelbach, and Samarin [3]. This companion is an in-depth guide to L^AT_EX and to its *packages*—standard enhancements that can be used at any site to provide additional features. The *L^AT_EX Companion* is the place to look if you can't find what you need in this book. It describes more than a hundred packages.

1.1 How to Avoid Reading This Book

Many people would rather learn about a program at their computer than by reading a book. There is a small sample L^AT_EX input file named `small2e.tex` that shows how to prepare your own input files for typesetting simple documents. Before reading any further, you might want to examine `small2e.tex` with a text editor and modify it to make an input file for a document of your own, then run L^AT_EX on this file and see what it produces. The *Local Guide* will tell you how to find `small2e.tex` and run L^AT_EX on your computer; it may also contain information about text editors. Be careful not to destroy the original version of `small2e.tex`; you'll probably want to look at it again.

The file `small2e.tex` is only forty lines long, and it shows how to produce only very simple documents. There is a longer file named `sample2e.tex` that contains more information. If `small2e.tex` doesn't tell you how to do something, you can try looking at `sample2e.tex`.

If you prefer to learn more about a program before you use it, read on. Almost everything in the sample input files is explained in the first two chapters of this book.

1.2 How to Read This Book

While `sample2e.tex` illustrates many of L^AT_EX's features, it is still only about two hundred lines long, and there is a lot that it doesn't explain. Eventually, you will want to typeset a document that requires more sophisticated formatting than you can obtain by imitating the two sample input files. You will then have to look in this book for the necessary information. You can read the section containing the information you need without having to read everything that precedes it. However, all the later chapters assume you have read Chapters 1 and 2. For example, suppose you want to set one paragraph of a document in small type. Looking up "type size" in the index or browsing through the table of contents will lead you to Section 6.7.1, which talks about "declarations" and their "scope"—simple concepts that are explained in Chapter 2. It will take just a minute or two to learn what to do if you've already read Chapter 2; it could be quite frustrating if you haven't. So, it's best to read the first two chapters now, before you need them.

L^AT_EX's input is a file containing the document's text together with commands that describe the document's structure; its output is a file of typesetting instructions. Another program must be run to convert these instructions into printed output. With a high-resolution printer, L^AT_EX can generate book-quality typesetting.

This book tells you how to prepare a L^AT_EX input file. The current chapter discusses the philosophy underlying L^AT_EX; here is a brief sketch of what's in the remaining chapters and appendices:

Chapter 2 explains what you should know to handle most simple documents and to read the rest of the book. Section 2.5 contains a summary of everything in the chapter; it serves as a short reference manual.

Chapter 3 describes logical structures for handling a variety of formatting problems. Section 3.4 explains how to define your own commands, which can save typing when you write the document and retyping when you change it. It's a good idea to read the introduction—up to the beginning of Section 3.1—before reading any other part of the chapter.

Chapter 4 contains features especially useful for large documents, including automatic cross-referencing and commands for splitting a large file into smaller pieces. Section 4.7 discusses sending your document electronically.

Chapter 5 is about making books, slides, and letters (the kind you send by post).

Chapter 6 describes the visual formatting of the text. It has information about changing the style of your document, explains how to correct bad line and page breaks, and tells how to do your own formatting of structures not explicitly handled by L^AT_EX.

Chapter 7 discusses pictures—drawing them yourself and inserting ones prepared with other programs—and color.

Chapter 8 explains how to deal with errors. This is where you should look when L^AT_EX prints an error message that you don't understand.

Appendix A describes how to use the *MakeIndex* program to make an index.

Appendix B describes how to make a bibliographic database for use with BIB_TE_X, a separate program that provides an automatic bibliography feature for L^AT_EX.

Appendix C is a reference manual that compactly describes all L^AT_EX's features, including many advanced ones not described in the main text. If a command introduced in the earlier chapters seems to lack some necessary capabilities, check its description here to see if it has them. This appendix is a convenient place to refresh your memory of how something works.

Appendix D describes the differences between the current version of L^AT_EX and the original version, L^AT_EX 2.09.

Appendix E is for the reader who knows T_EX, the program on which L^AT_EX is built, and wants to use T_EX commands that are not described in this book.

When you face a formatting problem, the best place to look for a solution is in the table of contents. Browsing through it will give you a good idea of what L^AT_EX has to offer. If the table of contents doesn't work, look in the index; I have tried to make it friendly and informative.

Each section of Chapters 3–7 is reasonably self-contained, assuming only that you have read Chapter 2. Where additional knowledge is required, explicit cross-references are given. Appendix C is also self-contained, but a command's description may be hard to understand without first reading the corresponding description in the earlier chapters.

The descriptions of most L^AT_EX commands include examples of their use. In this book, examples are formatted in two columns, as follows:

The left column shows the printed output; the right column contains the input that produced it.

The left column shows the printed output; the right column contains the input that produced it.

Note the special typewriter type style in the right column. It indicates what you type—either text that you put in the input file or something like a file name that you type as part of a command to the computer.

Since the sample output is printed in a narrower column, and with smaller type, than $\text{\LaTeX}$ normally uses, it won't look exactly like the output you'd get from that input. The convention of the output appearing to the left of the corresponding input is generally also used when commands and their output are listed in tables.

1.3 The Game of the Name

The $\text{\TeX}$ in $\text{\LaTeX}$ refers to Donald Knuth's $\text{\TeX}$ typesetting system. The $\text{\LaTeX}$ program is a special version of $\text{\TeX}$ that understands $\text{\LaTeX}$ commands. Think of $\text{\LaTeX}$ as a house built with the lumber and nails provided by $\text{\TeX}$. You don't need lumber and nails to live in a house, but they are handy for adding an extra room. Most $\text{\LaTeX}$ users never need to know any more about $\text{\TeX}$ than they can learn from this book. However, the lower-level $\text{\TeX}$ commands described in *The $\text{\TeX}$ book* [4] can be very useful when creating a new package for $\text{\LaTeX}$.

I will use the term “ $\text{\TeX}$ ” when describing standard $\text{\TeX}$ features and “ $\text{\LaTeX}$ ” when describing features unique to $\text{\LaTeX}$, but the distinction will be of interest mainly to readers already familiar with $\text{\TeX}$. You may ignore it and use the two names interchangeably.

One of the hardest things about using $\text{\LaTeX}$ is deciding how to pronounce it. This is also one of the few things I'm not going to tell you about $\text{\LaTeX}$, since pronunciation is best determined by usage, not fiat. $\text{\TeX}$ is usually pronounced *teck*, making *lah-teck*, *lah-teck*, and *lay-teck* the logical choices; but language is not always logical, so *lay-tecks* is also possible.

The written word carries more legal complications than the spoken, and the need to distinguish $\text{\TeX}$ and $\text{\LaTeX}$ from similarly spelled products restricts how you may write them. The best way to refer to these programs is by their logos, which can be generated with simple $\text{\LaTeX}$ commands. When this is impossible, as in an e-mail message, you should write them as $\text{\TeX}$ and $\text{\LaTeX}$, where the unusual capitalization identifies these computer programs.

1.4 Turning Typing into Typography

Traditionally, an author provides a publisher with a typed manuscript. The publisher's typographic designer decides how the manuscript is to be formatted, specifying the length of the printed line, what style of type to use, how much

space to leave above and below section headings, and many other things that determine the printed document's appearance. The designer writes a series of instructions to the typesetter, who uses them to decide where on the page to put each of the author's words and symbols. In the old days, typesetters produced a matrix of metal type for each page; today they produce computer files. In either case, their output is used to control the machine that does the actual typesetting.

L^AT_EX is your typographic designer, and T_EX is its typesetter. The L^AT_EX commands that you type are translated into lower-level T_EX typesetting commands. Being a modern typesetter, T_EX produces a computer file, called the *device-independent* or *dvi* file. The *Local Guide* explains how to use this file to generate a printed document with your computer. It also explains how to view your document on your computer, using a screen previewer. Unless your document is very short, you will want to see the typeset version as you're writing it. Use a previewer instead of laying waste to our planet's dwindling forests by printing lots of intermediate versions. In fact, unless you want to take a copy with you on a wilderness expedition, you may never have to print it at all. It is easier and faster to distribute your document electronically than by mailing paper copies.

A human typographic designer knows what the manuscript is generally about and uses this knowledge in deciding how to format it. Consider the following typewritten manuscript:

The German mathematician Kronecker, sitting
quietly at his desk, wrote:

God created the whole numbers; all
the rest is man's work.

Seated in front of the terminal, with Basic
hanging on my every keystroke, I typed:

```
for i = 1 to infinity
let number[i] = i
```

A human designer knows that the first indented paragraph (God created ...) is a quotation and the second is a computer program, so the two should be formatted differently. He would probably set the quotation in ordinary roman type and the computer program in a typewriter type style. L^AT_EX is only a computer program and can't understand English, so it can't figure all this out by itself. It needs more help from you than a human designer would.

The function of typographic design is to help the reader understand the author's ideas. For a document to be easy to read, its visual structure must reflect its logical structure. Quotations and computer programs, being logically distinct structural elements, should be distinguished visually from one another. The designer should therefore understand the document's logical structure. Since L^AT_EX can't understand your prose, you must explicitly indicate the logical structure by typing special commands. The primary function of almost all the L^AT_EX

commands that you type should be to describe the logical structure of your document. As you are writing your document, you should be concerned with its logical structure, not its visual appearance. The L^AT_EX approach to typesetting can therefore be characterized as *logical design*.

1.5 Why L^AT_EX?

When L^AT_EX was introduced in 1985, few authors had the facilities for typesetting their own documents. Today, desktop publishing is commonplace. You can buy a “WYSIWYG” (what you see is what you get) program that lets you see exactly what your document will look like as you type it. WYSIWYG programs are very appealing. They make it easy to put text wherever you want in whatever size and style of type you want. Why use L^AT_EX, which requires you to tell it that a piece of text is a quotation or a computer program, when a WYSIWYG program allows you to format the text just the way you want it?

WYSIWYG programs replace L^AT_EX’s logical design with *visual design*. Visual design is fine for short, simple documents like letters and memos. It is not good for more complex documents such as scientific papers. WYSIWYG has been characterized as “what you see is all you’ve got”.¹ To illustrate the advantage of logical over visual design, I will consider a simple example from the file `sample2e.tex`.

Near the top of the second page of the document is the mathematical term (A, B) . With a WYSIWYG program, this term is entered by typing `(A,B)`. You could type it the same way in the L^AT_EX input. However, the term represents a mathematical structure—the inner product of A and B . An experienced L^AT_EX user will define a command to express this structure. The file `sample2e.tex` defines the command `\ip` so that `\ip{A}{B}` produces (A, B) . The term (Γ, ψ') near the end of the document is also an inner product and is produced with the `\ip` command.

Suppose you decide that there should be a little more space after the comma in an inner product. Just changing the definition of the `\ip` command will change (A, B) to (A, B) and (Γ, ψ') to (Γ, ψ') . With a WYSIWYG program, you would have to insert the space by hand in each formula—not a problem for a short document with two such terms, but a mathematical paper could contain dozens and a book could contain hundreds. You would probably produce inconsistent formatting by missing some formulas or forgetting to add the space when entering new ones. With L^AT_EX, you don’t have to worry about formatting while writing your document. Formatting decisions can be made and changed at any time.

The advantage of logical design becomes even more obvious if you decide that you prefer the notation $\langle A|B \rangle$ for the inner product of A and B . The

¹Brian Reid attributes this phrase to himself and/or Brian Kernighan.

file `sample2e.tex` contains an alternate definition of `\ip` that produces this notation.

Typing `\ip{A}{B}` is just a little more work than typing `(A,B)` (though it's a lot easier than entering `\langle A|B \rangle` if the symbols “`\langle`” and “`\rangle`” must be chosen with a mouse from a pull-down menu). But this small effort is rewarded by the benefits of maintaining the logical structure of your document instead of just its visual appearance.

One advantage of WYSIWYG programs is that you can see the formatted version of your document while writing it. Writing requires reading what you have already written. Although you want $\text{\LaTeX}$ to know that the term is an inner product, you would like to read (A,B) or $\langle A|B \rangle$, not `\ip{A}{B}`. The speed of modern computers has eliminated much of this advantage. I now type a couple of keystrokes and, a few seconds later, a typeset version of the section I am working on appears on my screen. As computers get faster, those few seconds will turn into a fraction of a second.

1.6 Turning Ideas into Input

The purpose of writing is to present your ideas to the reader. This should always be your primary concern. It is easy to become so engrossed with form that you neglect content. Formatting is no substitute for writing. Good ideas couched in good prose will be read and understood, regardless of how badly the document is formatted. $\text{\LaTeX}$ was designed to free you from formatting concerns, allowing you to concentrate on writing. If you spend a lot of time worrying about form, you are misusing $\text{\LaTeX}$.

Even if your ideas are good, you can probably learn to express them better. The classic introduction to writing English prose is Strunk and White's brief *Elements of Style* [6]. A more complete guide to using language properly is Theodore Bernstein's *The Careful Writer* [1]. These two books discuss general writing style. Writers of scholarly or technical prose need additional information. Mary-Claire van Leunen's *Handbook for Scholars* [7] is a delightful guide to academic and scholarly writing. The booklet titled *How to Write Mathematics* [5] can help scientists and engineers as well as mathematicians. It's also useful to have a weightier reference book at hand; *Words into Type* [8] and the *Chicago Manual of Style* [2] are two good ones.

1.7 Trying It Out

You may already have run $\text{\LaTeX}$ with input based on the sample files. If not, this is a good time to learn how. The section in the *Local Guide* titled *Running a Sample File* explains how to obtain a copy of the file `sample2e.tex` and run $\text{\LaTeX}$ with it as input. Follow the directions and see what $\text{\LaTeX}$ can do.

After printing the document generated in this way, try changing the document's format. Using a text editor, examine the file `sample2e.tex`. A few lines down from the beginning of the file is a line that reads

```
\documentclass{article}
```

Change that line to

```
\documentclass[twocolumn]{article}
```

Save the changed file under the name `chgsam.tex`, and use this file to print a new version of the document. To generate the new version, do exactly what you did the last time, except type `chgsam` wherever you had typed `sample2e`. Comparing the two printed versions shows how radically the appearance of the document can be altered by a simple change to a command. To try still another format, change `chgsam.tex` so the line above reads

```
\documentclass[12pt]{article}
```

and use the changed file to print a third version of the document.

From now on, I will usually ignore the process of going from the L^AT_EX input file to the printed output and will write something like: "Typing --- produces a long dash." What this really means is that putting the three characters --- in your input file will, when that file is processed by L^AT_EX and the device-independent file printed, produce a long dash in the printed output.

CHAPTER 2

Getting Started



2.1 Preparing an Input File

The input to $\text{\LaTeX}$ is a text file. I assume that you know how to use a text editor to create such a file, so I will tell you only what should go into your input file, not how to get it there. A good text editor can be customized by the user to make it easier to prepare $\text{\LaTeX}$ input files. Consult the *Local Guide* to find out how to customize the text editors on your computer.

On most computers, file names have two parts separated by a period, like `sample2e.tex`. I will call the first part its *first name* and the second part its *extension*, so `sample2e` is the first name of `sample2e.tex`, and `tex` is its extension. Your input file's first name can be any name allowed by your computer system, but its extension should be `tex`.

Let's examine the characters that can appear in your input file. First, there are the upper- and lowercase letters and the ten digits 0 ... 9. Don't confuse the uppercase letter O (oh) with the digit 0 (zero), or the letter l (the lowercase *el*) with the digit 1 (one). Next, there are the following sixteen punctuation characters:

. : ; , ? ! ' ' () [] - / * @

Note that there are two different quote symbols: ' and '. You may think of ' as an ordinary "single quote" and ' as a funny symbol, perhaps displayed like ` on your screen. The *Local Guide* should tell where to find ' and ' on your keyboard, if they're not obvious. The characters (and) are ordinary parentheses, while [and] are called *square brackets*, or simply *brackets*.

The ten special characters

\$ % & ~ _ ^ \ { }

are used only in $\text{\LaTeX}$ commands. Check the *Local Guide* for help in finding them on your keyboard. The character \ is called *backslash*, and should not be confused with the more familiar /, as in 1/2. Most $\text{\LaTeX}$ commands begin with a \ character, so you will soon become very familiar with it. The { and } characters are called *curly braces* or simply *braces*.

The five characters

+ = | < >

are used mainly in mathematical formulas, although + and = can be used in ordinary text. The character " (double quote) is hardly ever used.

Unless your *Local Guide* tells you otherwise, these are the only characters that you should see when you look at a $\text{\LaTeX}$ input file. However, there are other "invisible" characters in your file: space characters, such as the one you usually enter by pressing the *space* bar, and special characters that indicate the end of a line, usually entered by pressing the *return* key (sometimes labeled *enter*). These invisible characters are all considered the same by $\text{\TeX}$, and I will

treat them as if they were a single character called *space*, which I will sometimes denote by $\square$. Any sequence of space characters is handled the same as a single one, so it doesn't matter if the space between two words is formed by one space character or several of them. However, a blank line—one containing nothing but space characters—is interpreted by $\text{\TeX}$ as the end of a paragraph. Some text editors organize a file into pages. $\text{\TeX}$ acts as if there were a blank line between the pages of such a file.

2.2 The Input

Most $\text{\LaTeX}$ commands describe the logical structure of the document. To understand these commands, you must know how $\text{\LaTeX}$ perceives that logical structure. A document contains logical structures of different sizes, from chapters down through individual letters. We start by considering the very familiar intermediate-sized structures: sentences and paragraphs.

2.2.1 Sentences and Paragraphs

Describing simple sentences and paragraphs to $\text{\LaTeX}$ poses no problem; you pretty much type what comes naturally.

The ends of words and sentences are marked by spaces. It doesn't matter how many spaces you type; one is as good as 100.

One or more blank lines denote the end of a paragraph.

The ends of words and sentences are marked by spaces. It doesn't matter how many spaces you type; one is as good as 100.

One or more blank lines denote the end of a paragraph.

$\text{\TeX}$ ignores the way the input is formatted, paying attention only to the logical concepts end-of-word, end-of-sentence, and end-of-paragraph.

That's all you have to know for typing most of your text. The remainder of this book is about how to type the rest, starting with some other things that occur fairly frequently in ordinary sentences and paragraphs.

Quotation Marks

Typewritten text uses only two quotation-mark symbols: a double quote " and single quote ', the latter serving also as an apostrophe. Printed text, however, uses a left and a right version of each, making four different symbols. $\text{\TeX}$ interprets the character ' as a single left quote, and the character ' as a single right quote. To get a double quote, just type two single quotes.

'Convention' dictates that punctuation go inside quotes, like "this," but I think it's better to do "this".

'Convention' dictates that punctuation go inside quotes, like "this," but I think it's better to do "this".

Remember that the right-quote character `'` is the one you're used to thinking of as a single quote, and the left-quote character `'` is the one you're probably unfamiliar with. An apostrophe is produced with the usual `'` character.

Typing a double quote followed by a single quote, or vice versa, poses a problem because something like `''` would be ambiguous. The solution is to type the command `\,` (a `\` character followed by a comma) between the two quotation marks.

`"'Fi' or 'fum?'"` he asked.

`""\,'Fi' or 'fum?'\,"` he asked.

The `\,` is a typesetting command that causes $\text{\TeX}$ to insert a small amount of space. Don't leave any space in the input file before or after the `\,` command.

Dashes

You can produce three different sizes of dash by typing one, two, or three `"-` characters:

An intra-word dash or hyphen, as in X-ray.
A medium dash for number ranges, like 1–2.
A punctuation dash—like this.

An intra-word dash or hyphen, as in X-ray.
A medium dash for number ranges, like 1--2.
A punctuation dash---like this.

There is usually no space before or after a dash. Minus signs are not dashes; they should appear only in mathematical formulas, which are discussed below.

Space After a Period

Typesetters often put a little extra space after a sentence-ending period. This is easy for a human typesetter, but not for a program like $\text{\TeX}$ that has trouble deciding which periods end sentences. Instead of trying to be clever, $\text{\TeX}$ simply assumes that a period ends a sentence unless it follows an uppercase letter. This works most of the time, but not always—abbreviations like “etc.” being the most common exception. You tell $\text{\TeX}$ that a period doesn't end a sentence by using a `\.` command (a `\` character followed by a space or the end of a line) to make the space after the period.

Tinker et al. made the double play.

Tinker et al.\ made the double play.

It doesn't matter how many spaces you leave after the `\` character, but don't leave any space between the period and the backslash. The `\.` command produces an ordinary interword space, which can also be useful in other situations.

On the rare occasions that a sentence-ending period follows an uppercase letter, you will have to tell $\text{\TeX}$ that the period ends the sentence. You do this by preceding the period with a `\@` command.

The Romans wrote $I + I = II$. Really!

The Romans wrote $I + I = II\@$. Really!

If a sentence-ending period is followed by a right parenthesis or a right quote (single or double), then the period's extra space goes after the parenthesis or quote. In these cases too, $\text{T}_{\text{E}}\text{X}$ will need a hand if its assumption that a period ends a sentence unless it follows an uppercase letter is wrong.

"Beans (lima, etc.) have vitamin B."

'Beans (lima, etc.)\ have vitamin B\@.'

Extra space is also added after a question mark (?), exclamation point (!), or colon (:) just as for a period—that is, unless it follows an uppercase letter. The $\backslash$ and $\backslash$ commands are used the same way with each of these punctuation characters.

Special Symbols

Remember those ten special characters, mentioned on page 12, that you type only as part of $\text{L}^{\text{A}}\text{T}_{\text{E}}\text{X}$ commands? Some of them, like \$, represent symbols that you might very well want in your document. Seven of those symbols can be produced by typing a $\backslash$ in front of the corresponding character.

\$ & % # - { } are easy to produce.

\\$ \& \% \# _ \{ \} are easy to produce.

The other three special characters ($\sim$, $\hat{}$, and $\backslash$) usually appear only in simulated keyboard input, which is produced with the commands described in Section 3.7.

You can get $\text{L}^{\text{A}}\text{T}_{\text{E}}\text{X}$ to produce any symbol that you're likely to want, and many more besides, such as: § £ ψ $\star$ $\otimes$ $\approx$ $\bowtie$ $\Leftarrow$ ♣. Sections 3.2 and 3.3.2 tell how.

Simple Text-Generating Commands

Part of a sentence may be produced by a text-generating command. For example, the $\text{T}_{\text{E}}\text{X}$ and $\text{L}^{\text{A}}\text{T}_{\text{E}}\text{X}$ logos are produced by the commands $\backslash\text{TeX}$ and $\backslash\text{LaTeX}$, respectively.

Some people use plain $\text{T}_{\text{E}}\text{X}$, but I prefer $\text{L}^{\text{A}}\text{T}_{\text{E}}\text{X}$.

Some people use plain $\backslash\text{TeX}$, but I prefer $\backslash\text{LaTeX}$.

A useful text-generating command is $\backslash\text{today}$, which produces the current date.

This page was produced on May 18, 1994.

This page was produced on $\backslash\text{today}$.

Another useful text-generating command is $\backslash\text{ldots}$, which produces an *ellipsis*—the sequence of three dots used to denote omitted material. (Simply typing three periods doesn't produce the right spacing between the dots.)

If nominated ..., I will not serve.

If nominated $\backslash\text{ldots}$, I will not serve.

Most of the command names you've seen so far have consisted of a `\` (backslash) followed by a single nonletter. From now on, most commands you will encounter have names consisting of a `\` followed by one or more letters. In reading the input file, `TEX` knows it has come to the end of such a command name when it finds a nonletter: a digit like “7”, a punctuation character like “;”, a special character like “\”, a space, or the end of a line. The most common way to end this kind of command name is with a space or end of line, so `TEX` ignores all spaces following it. If you want a space after the logo produced by the `\LaTeX` command, you can't just leave a space after the command name; all such spaces are ignored. You must tell `TEX` to put in the space by typing a `\_` command.

This page of the `LATEX` manual was produced on
May 18, 1994.

This page of the `\LaTeX\` manual was
produced on `\today` .

Note how `TEX` ignored the space after the `\today` command in the input and did not produce any space after the date in the output.

The case of letters matters in a command name; typing `\Today` produces an error, because the correct command name is `\today`. Most command names have only lowercase letters.

Emphasizing Text

Emphasized text is usually underlined in a typewritten manuscript and *italicized* in a printed document. Underlining and italics are visual concepts; when typing your document, you should be concerned only with the logical concept of emphasis. The `\emph` command tells `LATEX` that text is to be emphasized.

Here is some silly *emphasized text*.

Here is some silly `\emph{emphasized text}`.

In the `\emph{emphasized text}` command, `\emph` is the command name and `emphasized text` is its *argument*. Most commands have either no arguments, like `\today`, or a single argument, like `\emph`. However, there are a few with multiple arguments, each of which is enclosed in braces. Spaces are ignored between the arguments, and between the command name and its first argument.

Commands like `\emph` can be nested within one another in the obvious way. Most styles use ordinary roman type for emphasized text that appears inside emphasized text.

You can have *emphasized text* within *emphasized text* too.

You can have `\emph{emphasized text}`
`\emph{within} emphasized text` too.

Emphasis should be used sparingly. Like raising your voice, it is an effective way to get attention, but an annoying distraction if done too often.

Preventing Line Breaks

In putting text onto paper, a paragraph must be broken into lines of print. Text becomes hard to read if a single logical unit is split across lines in an arbitrary fashion, so typesetters break lines between words when possible and split words only between syllables (inserting a hyphen at the break). Sometimes a line should not be broken between or within certain words. Human typesetters recognize these situations, but $\text{\TeX}$ must be told about some of them.

Line breaking should be prevented at certain interword spaces. For example, the expression “Chapter 3” looks strange if the “Chapter” ends one line and the “3” begins the next. Typing `~` (a tilde character) produces an ordinary interword space at which $\text{\TeX}$ will never break a line. Below are some examples indicating when a `~` should be used.

Mr. <code>~</code> Jones	Figure <code>~</code> 7	(1) <code>~</code> gnats
U. <code>~</code> S. <code>~</code> Grant	from 1 to <code>~</code> 10	

It is best not to break a line within certain words. For example, you should try to avoid splitting a name (especially your own). The `\mbox` command tells $\text{\TeX}$ to print its entire argument on the same line. In the following example, $\text{\TeX}$ will never split “Lamport” across lines.

Doctor Lamport, I presume?	Doctor <code>\mbox{Lamport}</code> , I presume?
----------------------------	---

Most line breaks separate logically related units, and it would be nice if they could be avoided. However, unless you print your document on a mile-long strip of paper tape, line breaking is a necessary evil. Using too many `~` and `\mbox` commands leaves too few places to break lines. Inhibit line breaking only where necessary.

Footnotes

Footnotes are produced with a `\footnote` command having the text of the footnote as its argument.

Gnus ¹ can be quite a gnuance.	<code>Gnus\footnote{A gnu is a big animal.}</code> can
:	be quite a gnuance.
:	

¹A gnu is a big animal.

There is no space between the `Gnus` and the `\footnote` in this example; adding space would have put an unwanted space between the text and the footnote marker (the ¹).

A `\footnote` command cannot be used in the argument of most commands; for example, it can’t appear in the argument of an `\mbox` command. Section C.3.3 explains how to footnote text that appears in a command argument.

Formulas

If you're writing a technical document, it's likely to contain mathematical formulas. A formula appearing in the middle of a sentence is enclosed by `\(` and `\)` commands.

The formula $x - 3y = 7$ is easy to type.

The formula `\( x-3y = 7 \)` is easy to type.

Any spaces that you type in the formula are ignored.

Does $x + y$ always equal $y + x$?

Does `\( x + y \)` always equal `\(y+x\)`?

TeX regards a formula as a word, which may be broken across lines at certain points, and space before the `\(` or after the `\)` is treated as an ordinary interword separation.

Subscripts are produced by the `_` command and superscripts by the `^` command.

$a_1 > x^{2n}/y^{2n}$

`\( a_{1} > x^{2n} / y^{2n} \)`

These two commands can be used only inside a mathematical formula.

When used in a formula, the right-quote character `'` produces a prime ($'$), two in a row produce a double prime, and so on.

This proves that $x' < x'' - y'_3 < 10x'''z$.

`\( x' < x'' - y'_{3} < 10 x''' z \)`.

Mathematical formulas can get very complex; Section 3.3 describes many additional commands for producing them. Here, I consider the use of formulas in the text. A formula is a grammatical unit; it should be treated as such in the sentence structure.

The formula $a < 7$ is a noun in this sentence. It is sometimes used as a clause by writing that $a < 7$.

The formula `\( a<7 \)` is a noun in this sentence. It is sometimes used ...

Beginning a sentence with a formula makes it hard to find the start of the sentence; don't do it. It is best to use a formula as a noun; it should certainly never appear as a complete sentence in the running text.

A variable like x is a formula. To save you some typing, L^AT_EX treats $\$...\$$ the same as `\(...\)`.

Let x be a prime such that $y > 2x$.

Let `\$x\$` be a prime such that `\$y>2x\$`.

Use $\$...\$$ only for a short formula, such as a single variable. It's easy to forget one of the $\$$ characters that surrounds a long formula. You can also type

`\begin{math} ... \end{math}`

instead of `\(...\)`. You might want to use this form for very long formulas.

Ignorable Input

When $\text{\TeX}$ encounters a `%` character in the input, it ignores the `%` and all characters following it on that line—including the space character that ends the line. $\text{\TeX}$ also ignores spaces at the beginning of the next line.

```
Gnus and armadillos are generally tolerant of one   Gnus and armadi%   More   @_#!$~{&   gnus?
another and seldom quarrel.                        llos are generally ...
```

The `%` has two uses: ending a line without producing any space in the output¹ and putting a comment (a note to yourself) in the input file.

2.2.2 The Document

We now jump from the document's intermediate-sized logical units to its largest one: the entire document itself. The text of every document starts with a `\begin{document}` command and ends with an `\end{document}` command. $\text{\LaTeX}$ ignores anything that follows the `\end{document}`. The part of the input file preceding the `\begin{document}` command is called the *preamble*.

The Document Class

The preamble begins² with a `\documentclass` command whose argument is one of the predefined classes of document that $\text{\LaTeX}$ knows about. The file `sample2e.tex` begins with

```
\documentclass{article}
```

which selects the `article` class. The other standard $\text{\LaTeX}$ class used for ordinary documents is the `report` class. The `article` class is generally used for shorter documents than the `report` class. Other standard classes are described in Chapter 5.

In addition to choosing the class, you can also select from among certain document-class options. The options for the `article` and `report` classes include the following:

- 11pt** Specifies a size of type known as *eleven point*, which is ten percent larger than the ten-point type normally used.
- 12pt** Specifies a twelve-point type size, which is twenty percent larger than ten point.
- twoside** Formats the output for printing on both sides of the page. ($\text{\LaTeX}$ has no control over the actual printing.)

¹However, you can't split a command name across two lines.

²As explained in Section 4.7, the `\documentclass` command may actually be preceded by prepended files.

`twocolumn` Produces two-column output.

Other options are described elsewhere in this book; all the standard ones are listed in Section C.5.1. Your *Local Guide* tells what others are available on your computer.

You specify a document-class option by enclosing it in square brackets immediately after the “`\documentclass`”, as in

```
\documentclass [twoside]{report}
```

Multiple options are separated by commas.

```
\documentclass [twocolumn,12pt]{article}
```

Don't leave any space inside the square brackets.

The `\documentclass` command can be used either with or without the option-choosing part. The options, enclosed in square brackets, are an *optional argument* of the command. It is a L^AT_EX convention that optional arguments are enclosed in square brackets, while mandatory arguments are enclosed in curly braces. T_EX ignores spaces after a command name like `\documentclass` and between command arguments.

The document class defines the commands for specifying L^AT_EX's standard logical structures. Additional structures are defined by *packages*, which are loaded by the `\usepackage` command. For example, the command

```
\usepackage{latexsym}
```

loads the `latexsym` package, which defines commands to produce certain special math symbols. (See Section 3.3.2.) A package can have options, specified by an optional argument of `\usepackage` just like the one for `\documentclass`.

You will probably want to define some new commands for the special structures used in your particular document. For example, if you're writing a cookbook you will probably define your own commands for formatting recipes, as explained in Section 3.4. These definitions should go in the preamble, after the `\documentclass` and `\usepackage` commands. The preamble can also contain commands to change some aspects of the formatting. If you have commands or format changes that you use in several documents, you may want to define your own package, as described in Section 6.1.4.

The Title “Page”

A document usually has a title “page” listing its title, one or more authors, and a date. I write “page” in quotes because, for a short document, this information may be listed on the first page of text rather than on its own page. The title information consists of the title itself, the author(s), and the date; it is specified by the three declarations `\title`, `\author`, and `\date`. The actual title “page” is generated by a `\maketitle` command.

Gnus of the World

R. Dather J. Pennings B. Talkmore

4 July 1997

```
\title{Gnus of the World}
\author{R. Dather \and J. Pennings
        \and B. Talkmore}
\date{4 July 1997}
...
\maketitle
```

Note how multiple authors are separated by `\and` commands.

The `\maketitle` command comes after the `\begin{document}`, usually before any other text. The `\title`, `\author`, and `\date` commands can come anywhere before the `\maketitle`. The `\date` is optional; $\text{\LaTeX}$ supplies the current date if the declaration is omitted, but the `\title` and `\author` must appear if a `\maketitle` command is used. Commands for adding other information, such as the author's address and an acknowledgment of support, are described in Section C.5.4.

2.2.3 Sectioning

Sentences are organized into paragraphs, and paragraphs are in turn organized into a hierarchical *section structure*. You are currently reading Subsection 2.2.3, titled *Sectioning*, which is part of Section 2.2, titled *The Input*, which in turn is part of Chapter 2, titled *Getting Started*. I will use the term *sectional units* for things like chapters, sections, and subsections.

A sectional unit is begun by a sectioning command with the unit's title as its argument.

4.7 A Sectioning Command

$\text{\LaTeX}$ automatically generates the section number. Blank lines before or after a sectioning command have no effect.

```
\subsection{A Sectioning Command}
```

$\text{\LaTeX}$ automatically generates the section number. Blank lines before or after a ...

The document class determines what sectioning commands are provided, the standard classes have the following ones:³

<code>\part</code>	<code>\subsection</code>	<code>\paragraph</code>
<code>\chapter</code>	<code>\subsubsection</code>	<code>\subparagraph</code>
<code>\section</code>		

The `article` document class does not contain the `\chapter` command, which makes it easy to include an “article” as a chapter of a “report”. The example above, like most others in this book, assumes the `article` document class, the 4.7 indicating that this is the seventh subsection of Section 4. In the `report` class, this subsection might be numbered 5.4.7, with “5” being the chapter number.

³The names `\paragraph` and `\subparagraph` are unfortunate, since they denote units that are often composed of several paragraphs; they have been retained for historical reasons.

The sectional unit denoted by each of these commands must appear as a subunit of the one denoted by the preceding command, except that the use of `\part` is optional. A subsection must be part of a section, which, in the `report` class, must be part of a chapter.

The `\part` command is used for major divisions of long documents; it does not affect the numbering of smaller units—in the `article` class, if the last section of Part 1 is Section 5, then the first section of Part 2 is Section 6.

If there is an appendix, it is begun with an `\appendix` command and uses the same sectioning commands as the main part of the document. The `\appendix` command does not produce any text; it simply causes sectional units to be numbered properly for an appendix.

The document class determines the appearance of the section title, including whether or not it is numbered. Declarations to control section numbering are described in Section C.4, which also tells you how to make a table of contents.

The argument of a sectioning command may be used for more than just producing the section title; it can generate a table of contents entry and a running head at the top of the page. (Running heads are discussed in Section 6.1.2.) When carried from where it appears in the input file to the other places it is used, the argument of a sectioning command is shaken up quite a bit. Some $\text{\LaTeX}$ commands are *fragile* and can break when they appear in an argument that is shaken in this way. Fragile commands are rarely used in the argument of a sectioning command. Of the commands introduced so far, the only fragile ones are `\(`, `\)`, `\begin`, `\end`, and `\footnote`—none of which you're likely to need in a section title.⁴ On the rare occasions when you have to put a fragile command in a section title, you simply protect it with a `\protect` command. The `\protect` command goes right before every fragile command's name, as in:

```
\subsection {Is \protect\( x+y \protect\) Prime?}
```

This is actually a silly example because `$` is not a fragile command, so you can instead type

```
\subsection {Is $x + y$ Prime?}
```

but, because the problem is so rare, it's hard to find a good example using the commands described in this chapter.

An argument in which fragile commands need `\protect` will be called a *moving* argument. Commands that are not fragile will be called *robust*. For any command that one might reasonably expect to use in a moving argument, I will indicate whether it is robust or fragile. Except in special cases mentioned in Chapter 6 and Appendix C, a `\protect` command can't hurt, so it is almost always safe to use one when you're not sure if it's necessary.

⁴Section C.3.3 tells you how to footnote a section title.

2.2.4 Displayed Material

We return now to the level of the individual sentence. A sentence like

He turned and said to me, “My answer is no!”, and then he left.

contains a complete sentence quoted within it. An entire paragraph can even appear inside a sentence, as in

He turned and said to me: “I’ve done all I’m going to. I refuse to have any further part in it. My answer is no!”, and then he left.

It’s hard to understand this sentence the way it is written. However, there’s no problem if you read it aloud using a different tone of voice for the quotation. The typographic analog of changing your tone of voice is setting text off by indentation, also called *displaying*. The sentence above is much easier to read when typeset as follows:

He turned and said to me:

I’ve done all I’m going to. I refuse to have any further part
in it. My answer is no!

and then he left.

Displayed material functions logically as a lower-level unit than a sentence, though grammatically it may consist of part of a sentence, a whole sentence, or even several paragraphs. To decide whether a portion of text should be a display or a separate sectional unit, you must determine if it is logically subordinate to the surrounding text or functions as an equal unit.

Quotations are often displayed.

The following is an example of a short displayed quotation.

... it’s a good idea to make your input
file as easy to read as possible.

It is indented at both margins.

... example of a short displayed quotation.

```
\begin{quote}
  \ldots\ it’s a good idea to make your
    input file as easy to read as possible.
\end{quote}
```

It is indented at both margins.

This example illustrates a type of L^AT_EX construction called an *environment*, which is typed

```
\begin{name} ... \end{name}
```

where *name* is the name of the environment. The `quote` environment produces a display suitable for a short quotation. You’ve already encountered two other examples of environments: the `math` environment and the `document` environment.

The standard L^AT_EX document classes provide environments for producing several different kinds of displays. Blank lines before or after the environment

mark a new paragraph. Thus, a blank line after the `\end` command means that the following text starts a new paragraph. Blank lines before and after the environment mean that it is a complete paragraph. It's a bad idea to start a paragraph with displayed material, so you should not have a blank line before a display environment without a blank line after it. Blank lines immediately following a display environment's `\begin` command and immediately preceding its `\end` command are ignored.

Quotations

L^AT_EX provides two different environments for displaying quotations. The `quote` environment is used for either a short quotation or a sequence of short quotations separated by blank lines.

Our presidents have been known for their pithy remarks.

The buck stops here. *Harry Truman*

I am not a crook. *Richard Nixon*

It's no exaggeration to say the undecideds could go one way or another.
George Bush

Our presidents ... pithy remarks.

`\begin{quote}`

The buck stops here. `\emph{Harry Truman}`

I am not a crook. `\emph{Richard Nixon}`

It's no exaggeration ... `\emph{George Bush}`
`\end{quote}`

The `quotation` environment is used for quotations of more than one paragraph; as usual, the paragraphs are separated by blank lines.

Here is some advice to remember when you are using L^AT_EX:

Environments for making quotations can be used for other things as well.

Many problems can be solved by novel applications of existing environments.

Here is some advice to remember when you are using L^AT_EX:

`\begin{quotation}`

Environments for making quotations
... other things as well.

Many ... existing environments.
`\end{quotation}`

Lists

L^AT_EX provides three list-making environments: `itemize`, `enumerate`, and `description`. In all three, each new list item is begun with an `\item` command. Itemized lists are made with the `itemize` environment and enumerated lists with the `enumerate` environment.

- Each list item is marked with a *label*. The labels in this itemized list are bullets.
- Lists can be nested within one another.
 1. The item labels in an enumerated list are numerals or letters.
 2. A list should have at least two items.

L^AT_EX permits at least four levels of nested lists, which is more than enough.

- Blank lines before an item have no effect.

```
\begin{itemize}
\item Each list item is ... bullets.
\item Lists can be ... one another.
\begin{enumerate}
\item The item labels ... letters.
\item A list should ... two items.
\end{enumerate}
\LaTeX\ permits ... more than enough.

\item Blank lines ... have no effect.
\end{itemize}
```

In the `description` environment, you specify the item labels with an optional argument to the `\item` command, enclosed in brackets. (Although the argument is optional, the item will look funny if you omit it.)

Three animals you should know about are:

gnat A small animal, found in the North Woods, that causes no end of trouble.

gnu A large animal, found in crossword puzzles, that causes no end of trouble.

armadillo A medium-sized animal, named after a medium-sized Texas city.

Three animals you should know about are:

```
\begin{description}
\item[gnat] A small animal ...
\item[gnu] A large animal ....
\item[armadillo] A medium-sized ...
\end{description}
```

The characters `[` and `]` are used both to delimit an optional argument and to produce square brackets in the output. This can cause some confusion if the text of an item begins with a `[` or if an `\item` command's optional argument contains a square bracket. Section C.1.1 explains what to do in these uncommon situations. All commands that have an optional argument are fragile.

Poetry

Poetry is displayed with the `verse` environment. A new stanza is begun with one or more blank lines; lines within a stanza are separated by a `\\` command.

```
There is an environment for verse
Whose features some poets will curse.
For instead of making
Them do all line breaking,
It allows them to put too many words
on a line when they'd rather be
forced to be terse.
```

```
\begin{verse}
There is an environment for verse \\
Whose features some poets will curse.

For instead of making\\
Them do \emph{all} line breaking, \\
It allows them ... to be terse.
\end{verse}
```

The `\\*` command is the same as `\\` except that it prevents L^AT_EX from starting a new page at that point. It can be used to prevent a poem from being

broken across pages in a distracting way. The commands `\` and `\*` are used in all environments in which you tell $\text{\LaTeX}$ where to break lines; several such environments are described in the next chapter. The `\*` command is called the `*`-form of the `\` command. Several other commands also have `*`-forms—versions of the command that are slightly different from the ordinary one—that are obtained by typing `*` after the command name.

The `\` and `\*` commands have a little-used optional argument described in Section C.1.6, so putting a `[` after them presents the same problem as for the `\item` command. Moreover, the `*` in the `\*` command is somewhat like an optional argument for the `\` command, so following a `\` with a `*` in the text poses a similar problem. See Section C.1.1 for the solutions to these unlikely problems. Almost every command that has a `*`-form is fragile, and its `*`-form is also fragile.

Displayed Formulas

A mathematical formula is displayed when either it is too long to fit comfortably in the running text, it is so important that you want it to stand out, or it is to be numbered for future reference. $\text{\LaTeX}$ provides the `displaymath` and `equation` environments for displaying formulas; they are the same except that `equation` numbers the formula and `displaymath` doesn't. Because displayed equations are used so frequently in mathematics, $\text{\LaTeX}$ allows you to type `\[...\]` instead of

```
\begin{displaymath} ... \end{displaymath}
```

Here is an example of an unnumbered displayed equation:

$$x' + y^2 = z_i^2$$

and here is the same equation numbered:

$$x' + y^2 = z_i^2 \quad (8)$$

Here is an example of an unnumbered displayed equation:

```
\[ x' + y^2 = z_{i}^2 \]
```

and here is the same equation numbered:

```
\begin{equation}
  x' + y^2 = z_{i}^2
\end{equation}
```

The document class determines how equations are numbered. Section 4.2 describes how $\text{\LaTeX}$ can automatically handle references to equation numbers so you don't have to keep track of the numbers.

A displayed formula, like any displayed text, should not begin a paragraph. Moreover, it should not form a complete paragraph by itself. These two observations are summed up in a simple rule: in the input, never leave a blank line before a displayed formula.

$\text{\TeX}$ will not break the formula in a `displaymath` or `equation` environment across lines. See Section 3.3.5 for commands to create a single multiple-line formula or a sequence of displayed formulas.

2.2.5 Declarations

You may want to emphasize a large piece of text, such as a quotation. You can do this with the `\emph` command, but that makes the input file hard to read because you have to search for the closing right brace to see where the argument ends. Moreover, it's easy accidentally to delete the closing brace when you edit the text. Instead, you can use the `\em` command, which tells $\text{\TeX}$ to start emphasizing text.

This prose is very dull.

Wait! *Here is an exciting quote.*

Aren't you glad all that excitement is over?

This prose is very dull.

`\begin{quote}`

Wait! `\em` Here is an exciting quote.

`\end{quote}`

Aren't you glad ...

As explained below, the `\end{quote}` caused $\text{\TeX}$ to stop emphasizing text.

Unlike other commands you've encountered so far, `\em` produces neither text nor space; instead, it affects the way $\text{\LaTeX}$ prints the text that follows it. Such a command is called a *declaration*. Most aspects of the way $\text{\LaTeX}$ formats a document—the type style, how wide the margins are, and so on—are determined by declarations. The `\em` declaration instructs $\text{\LaTeX}$ to change the type style to the appropriate one for indicating emphasis. The *scope* of a declaration is ended by an `\end` command or a right brace. In the input, braces and `\begin` and `\end` commands must come in matched pairs. The scope of a declaration is ended by the first `\end` or `}` whose matching `\begin` or `{` precedes the declaration. The following example shows only the braces, `\begin` and `\end` commands (without their arguments and argument-enclosing braces), and an `\em` declaration from some input text; matching braces and matching `\begin` and `\end` commands have the same numbers. The shaded region is the scope of the `\em` declaration.

```
\begin1    {2 }2 {3 \em \begin4 {5 }5 \end4 }3 \end1
```

The braces can be the ones that surround a command argument or ones that are inserted just to delimit the scope of a declaration, as in the first emphasized *that* of⁵

That *that* that *that* thatcher thought thrilling ... That `{\em that}` that `\emph{that}` ...

The `\{` and `\}` commands do not count for purposes of brace matching and delimiting the scope of declarations. Also, as explained in Section 3.4, argument braces for commands you define yourself do not act as scope delimiters.

Every declaration has a corresponding environment of the same name (minus the `\` character). Typing

⁵You should use the `\emph` command rather than the `\em` declaration for emphasizing small pieces of text because it produces better spacing.

```
\begin{em} ... \end{em}
```

is equivalent to typing `{\em ... }`. (If a declaration has arguments, they become additional arguments of the corresponding environment's `\begin` command.) Using the environment form of a declaration instead of delimiting its scope with braces can make your input file easier to read.

2.3 Running L^AT_EX

If you followed the directions in Section 1.7, you now know how to run L^AT_EX on an input file. If not, consult the *Local Guide* to find out. When you use your own input file for the first time, things are unlikely to go as smoothly as they did for `sample2e.tex`. There will probably be a number of errors in your file—most of them simple typing mistakes. Chapter 8 gives detailed help in diagnosing errors. Here I will tell you how to apply first aid from the keyboard while L^AT_EX is still running.

When you start L^AT_EX, it will probably be running in one of several windows on your computer's screen. For historical reasons, I will call that window the *terminal*. (If L^AT_EX runs by itself and takes up the entire screen, then your whole computer is the terminal.) What you type directly to L^AT_EX, and what it types back at you, are called terminal input and output.

With your text editor, produce a new file named `errsam.tex` by making the following four changes to `sample2e.tex`:

- Line 174 of the file contains an `\end{enumerate}` command. Delete the `t` to produce `\end{enumerae}`, simulating a typical typing error.
- Four lines below is an `\item` command. Turn it into `\itemt`, another typical typo.
- The sixth line down from there begins with the word `Whose`. Add a pair of brackets to change that word to `[W]hose`.
- About a dozen lines further down in the file is a line consisting of the single word `is`. Add a space followed by `gnomonly` to the end of that line.

Now run L^AT_EX with `errsam.tex` as input and see what error messages it produces. You needn't write them down because everything T_EX writes on your screen is also written in a file called the *log* file.⁶ For the input file `errsam.tex`, the log file is named `errsam.log` on most computers, but it may have a different extension on yours; check your *Local Guide*.

L^AT_EX begins by typing pretty much what it did when you ran it on the `sample2e.tex` file, but then writes the following message on your screen and stops.

⁶The log file also has some things that don't appear on your screen, including blank lines inserted in strange places.


```
! LaTeX Error: \begin{enumerate} on input line 167 ended by \end{enumerae}.
```

See the LaTeX manual or LaTeX Companion for explanation.

Type H <return> for immediate help.

...

```
1.174      \end{enumerae}
```

```
?
```

L^AT_EX translates a command like `\end`, which describes the document's logical structure, into T_EX's typesetting commands. Some errors are caught by L^AT_EX; others cause it to generate typesetting commands containing errors that T_EX finds. The first line of this message, called the *error indicator*, tells us that the error was found by L^AT_EX rather than T_EX. Like all error messages, this one begins with an exclamation point.

The error indicator tells what the problem is. Chapter 8 explains the meaning of the error indicators for most L^AT_EX-detected errors and for the most common errors that T_EX finds. Here, L^AT_EX is complaining that the `\end` command that matches the `\begin{enumerate}` is not an `\end{enumerate}`, as it should be. The line beginning with 1.174 is the *error locator*, telling you where in your input file the error was discovered. In this case, it was on line 174, after T_EX read the `\end{enumerae}` command. The `?` that ends the message indicates that L^AT_EX has stopped and is waiting for you to type something.

Just pass over the error by pressing the *return* key, which instructs L^AT_EX to continue processing the input. L^AT_EX now writes

```
! Undefined control sequence.
```

```
1.178      \itemt
```

```
          This is the third item of the list.
```

```
?
```

The absence of the LaTeX Error at the beginning of the message tells you that this error was detected by T_EX rather than L^AT_EX. T_EX knows nothing about L^AT_EX commands, so you can't expect much help from the error indicator. The error locator indicates that the error was detected on line 178 of the input file, after reading `\itemt` and before reading `This`. (The error indicator line is broken at the point where T_EX stopped reading input.) Of course, this error is caused by `\itemt`, which is a command name T_EX has never heard of.

Continue past this error by pressing *return*. L^AT_EX next writes

```
! Missing number, treated as zero.
```

```
<to be read again>
```

```
W
```

```
1.184      [W]
```

```
          hose features some poets % within a stanza.
```

```
?
```

This error was found by $\text{\TeX}$ not $\text{\LaTeX}$, and the error indicator isn't very helpful. $\text{\TeX}$ has just read the `[w]`, which looks all right, so the error must have been caused by something that came before it. Right before the `[w]` in the input file is a `\` command. Do you now see what the error is? If not, look in the index under "`\`, [after".

Press *return* to continue. You immediately get another error message very similar to the preceding one, with the same error locator. $\text{\TeX}$ has discovered a second error in the low-level typesetting commands generated by the `\` command. Type *return* again to get past this problem.

When you find the first error, it's tempting to stop the program, correct it, and start over again. However, if you've made one error, you've probably made more. It's a good idea to find several errors at once, rather than running $\text{\LaTeX}$ over and over to find one mistake at a time. Keep typing *return* and try to get as far as you can. You may reach an impasse. A single mistake can cause $\text{\TeX}$ to produce hundreds of error messages, or to keep generating the same message over and over again forever. You can stop $\text{\LaTeX}$ before it's finished by typing `X` followed by *return* in response to an error message.

$\text{\TeX}$ may write a `*` and stop without any error message. This is probably due to a missing `\end{document}` command, but other errors can also cause it. If it happens, type `\stop` followed by *return*. If that doesn't work, you'll have to use your computer's standard method for halting recalcitrant programs, which is described in the *Local Guide*.

Instead of sitting at your keyboard waiting for errors, you can let $\text{\LaTeX}$ run unattended and find out what happened later by reading the log file. A `\batchmode` command at the very beginning of the input file causes $\text{\TeX}$ to process the file without stopping—much as if you were to type *return* in response to every error message, except the messages are not actually written on your screen. This is a convenient way to run $\text{\LaTeX}$ while you go out to lunch, but you could return to find that a small error resulted in a very long list of error messages in the log file.

Meanwhile, $\text{\LaTeX}$ has finished processing your input file `errsam.tex`. After the last error message, it wrote

```
Overfull \hbox (10.51814pt too wide) in paragraph at lines 195--200
[]\OT1/cmr/m/n/10 Mathematical for-mu-las may also be dis-played. A dis-played
for-mula is gnomonly
```

This is a *warning* message; $\text{\LaTeX}$ did not stop (it didn't print a `?`), but continued to the end of the input file without further incident. $\text{\TeX}$ generated the warning because it does not know how to hyphenate the word *gnomonly*, so it couldn't find a good place to break the line. If you look at the output, you'll find *gnomonly* extending beyond the right margin. This is not a serious problem; Section 6.2.1 describes how to correct it.

When you process your input file for the first time, $\text{\LaTeX}$ is likely to produce lots of error messages and warnings that you may not understand right away.

The most important thing to remember is, DON'T PANIC. Instead, turn to Chapter 8 to find out what to do.

2.4 Helpful Hints

The descriptions of individual L^AT_EX features include suggestions about their use. Here are a few general recommendations that can make your life easier.

As soon as you have some experience with L^AT_EX, read Section 3.4 to learn how to define your own commands and environments. When I write a paper, I change my notation much more than I change my concepts. Defining commands to express concepts allows me to change notation by simply modifying the command definitions, without having to change every occurrence in the text. This saves a lot of work.

To avoid errors and simplify making changes, keep your input file as easy to read as possible. Spacing and indentation can help. Use comments, especially to explain your command definitions. T_EX doesn't care how the input file is formatted, but you should.

As you write your document, you will be continually running L^AT_EX on it so you can view the latest version. As the document gets longer, L^AT_EX takes longer to process it. When you make some changes to Section 7, don't run L^AT_EX on Sections 1–6 just to find errors in the new material. Find those errors fast by running L^AT_EX only on Section 7. Process the entire document only when you're pretty sure Section 7 has no more errors.

There are two ways to run L^AT_EX only on what's changed. The first is to create a new file containing just the preamble, a `\begin{document}` command, the new material, and an `\end{document}` command. This is easy to do with a good text editor. I have programmed my editor so, at the stroke of a couple of keys, it will create this file, run L^AT_EX on it, and display the output with a screen previewer—while I keep editing my document. The second way to run L^AT_EX just on what has changed is to keep your input in several files, using the commands of Section 4.4 to process one part at a time. Experiment to find out what method works best for you.

Perhaps the most annoying aspect of a computer program is the way it reacts to your errors. As with most programs, L^AT_EX's train of thought is derailed by simple errors that any person would easily correct. The best way to avoid this problem is to avoid those simple errors. Here are some common ones that are easy to eliminate by being careful:

- A misspelled command or environment name.
- Improperly matching braces.
- Trying to use one of the ten special characters `#` `$` `%` `&` `_` `{` `}` `~` `^` `\` as an ordinary printing symbol.

- Improperly matching formula delimiters—for example, a `\(` command without the matching `\)`.
- The use in ordinary text of a command like `^` that can appear only in a mathematical formula.
- A missing `\end` command.
- A missing command argument.

A good text editor can detect or help prevent some of these errors.

Because of a bit of fossilized stupidity, e-mail programs on the Unix operating system often add a `>` character to the beginning of every line that begins with the five characters `From`. The input `>From` causes `TeX` to produce the output “`>From`”. It’s a good idea to search all `LaTeX` files received by e-mail for `>From`, and to add a space to the beginning of every line that starts with `From` in all files that you send by e-mail.

2.5 Summary

This chapter has explained everything you have to know to prepare a simple document. There is quite a bit to remember. Here is a summary to refresh your memory.

Input Characters

The input file may contain the following characters: upper- and lowercase letters, the ten digits, the sixteen punctuation characters

`. : ; , ? ! ‘ ’ ( ) [ ] - / * @`

the ten special characters

`# $ % & _ { } ~ ^ \`

(the first seven are printed by the commands `\#`, `\$`, etc.), and the five characters `+` `=` `|` `<` `>` used mainly in mathematical formulas. There are also invisible characters, which are all denoted by `\_`, that produce spaces in the input file.

Commands and Environments

Command names consist of either a single special character like `~`, a `\` followed by a single nonletter (as in `\@`), or a `\` followed by a string of letters. Spaces and a single end-of-line following the latter kind of command name are ignored; use a `\_` command to put an interword space after such a command. The case of letters in command names counts; most `LaTeX` command names contain only

lowercase letters. A few commands have a *-form, a variant obtained by typing * after the command name.

Command arguments are enclosed in curly braces { and }, except for optional arguments, which are enclosed in square brackets [and]. See Section C.1.1 if an optional argument has a square bracket or if a [in the text could be confused with the start of an optional argument. Do not leave any extra space within an argument; use a % to end a line without introducing space.

Some commands have *moving arguments*. The name of a fragile command must be preceded by a \protect command when it appears in a moving argument. Fragile commands include \(), \), \[, \], \begin, \end, \\\, \item, and \footnote. A \protect command seldom hurts; when in doubt use one.

A declaration is a command that directs L^AT_EX to change the way it is formatting the document. The scope of a declaration is delimited by enclosing it within curly braces or within an environment.

An environment has the form

```
\begin{name} ... \end{name}
```

To every declaration corresponds an environment whose name is the same as the declaration's name without the \.

Sentences and Paragraphs

Sentences and paragraphs are typed pretty much as expected. T_EX ignores the formatting of the input file. A blank line indicates a new paragraph.

Quotes are typed with the ' and ' characters, used in pairs for double quotes. The \, command separates multiple quotation marks, as in '\, 'Fum', ''.

Dashes of various sizes are produced with one, two, or three “-” characters.

A period, question mark, or exclamation point is considered to end a sentence unless it follows an uppercase letter. A \@ command before the punctuation character forces T_EX to treat it as the end of a sentence, while a _ command placed after it produces an interword space.

The T_EX and L^AT_EX logos are produced by the \TeX and \LaTeX commands. The \today command produces the current date, and \ldots produces an ellipsis (...).

Text is emphasized with the \emph command.

The ~ command produces an interword space at which T_EX will not start a new line. The \mbox command prevents T_EX from breaking its argument across lines.

Footnotes are typed with the \footnote command, whose argument is the text of the footnote.

In-line mathematical formulas are enclosed by \(\dots\) or \$\dots\$. Subscripts and superscripts are made with the _ and ^ commands. The ' character produces a prime symbol (').

Larger Structures

The document begins with the preamble. The preamble begins (after any prepended files—see Section 4.7) with a `\documentclass` command, which may be followed by one or more `\usepackage` commands. The rest of the preamble may contain command definitions and special style declarations for the document. The actual text is contained in a document environment.

A title is produced by using the `\title`, `\author`, and `\date` commands to declare the necessary information, and the `\maketitle` command to generate the title. Multiple authors are separated by `\and` commands in the argument of `\author`.

A sectional unit is begun with one of the following sectioning commands

<code>\part</code>	<code>\subsection</code>	<code>\paragraph</code>
<code>\chapter</code>	<code>\subsubsection</code>	<code>\subparagraph</code>
<code>\section</code>		

whose argument produces the unit's heading and is a moving argument.

Displayed Material

Short quotations are displayed with the `quote` environment and long quotations with the `quotation` environment.

L^AT_EX provides three list-making environments: `itemize` for itemized lists, `enumerate` for enumerated lists, and `description` for lists with user-specified labels. Each item is begun with an `\item` command whose optional argument provides the item labels in the `description` environment.

The `verse` environment is used for poetry. A blank line begins a new stanza, and a line that does not end a stanza is followed by a `\\` command—use `\\*` instead of `\\` to prevent a page break after the line. (See Section C.1.1 if a `*` follows an ordinary `\\` command.)

Displayed mathematical formulas are produced with the `displaymath` environment or the equivalent `\[ ... \]` construction. The `equation` environment produces numbered displayed formulas.

CHAPTER 3

Carrying On



Chapter 2 described commands for simple documents. Sooner or later, you'll write something that requires more sophisticated formatting. The commands and environments described in this chapter will handle most of those situations. Before getting to them, you should know a little more about how $\text{\TeX}$ operates.

As $\text{\TeX}$ processes your input text, it is always in one of three *modes*: paragraph mode, math mode, or left-to-right mode (called LR mode for short).¹ Paragraph mode is $\text{\TeX}$'s normal mode—the one it's in when processing ordinary text. In paragraph mode, $\text{\TeX}$ regards your input as a sequence of words and sentences to be broken into lines, paragraphs, and pages.

$\text{\TeX}$ is in math mode when it's generating a mathematical formula. More precisely, it enters math mode upon encountering a command like `$` or `\(` (or `\[` or `\begin{equation}`) that begins a mathematical formula, and it leaves math mode after finding the corresponding command like `\)` that ends the formula. When $\text{\TeX}$ is in math mode, it considers letters in the input file to be mathematical symbols, treating *i* as the product of *i* and *s*, and ignores any space characters between them.

In LR mode, as in paragraph mode, $\text{\TeX}$ considers your input to be a string of words with spaces between them. However, unlike paragraph mode, $\text{\TeX}$ produces output that keeps going from left to right; it never starts a new line in LR mode. The `\mbox` command (Section 2.2.1) causes $\text{\TeX}$ to process its argument in LR mode, which is what prevents the argument from being broken across lines.

Different modes can be nested within one another. If you put an `\mbox` command inside a mathematical formula, $\text{\TeX}$ is in LR mode when processing that command's argument, not in math mode. In the example

$y > z$ if x^2 real.

`\( y > z \mbox{ if } x^{\{2\}} \text{ real} \)`.

$\text{\TeX}$ is in math mode when processing `y`, `z`, in LR mode when processing `if` and `real`, and in math mode when processing `x^{\{2\}}`. The space between “*z*” and “if” is produced by the first `\` in the `\mbox` command's argument, since space characters in the input produce space in the output when $\text{\TeX}$ is in LR mode. The `\` in `real}\)` is processed in math mode, so it produces no space between “real” and “.” in the output.

3.1 Changing the Type Style

Type style is used to indicate logical structure. In this book, emphasized text appears in *italic* style type and $\text{\LaTeX}$ input in `typewriter` style. In $\text{\LaTeX}$, a type style is specified by three components: shape, series, and family.

¹Paragraph mode corresponds to the vertical and ordinary horizontal modes in *The $\text{\TeX}$ book*, and LR mode is called restricted horizontal mode there. $\text{\LaTeX}$ also has a restricted form of LR mode called *picture* mode that is described in Section 7.1.

Upright shape. Usually the default.	<code>\textup{Upright shape...}</code>
<i>Italic shape. Often used for emphasized text.</i>	<code>\textit{Italic shape...}</code>
<i>Slanted shape. A bit different from italic.</i>	<code>\textsl{Slanted shape...}</code>
SMALL CAPS SHAPE. USE SPARINGLY.	<code>\textsc{Small caps shape...}</code>
Medium series. Usually the default.	<code>\textmd{Medium series...}</code>
Boldface series. Often used for headings.	<code>\textbf{Boldface series...}</code>
Roman family. Usually the default.	<code>\textrm{Roman family...}</code>
Sans serif family. Often used in ads.	<code>\textsf{Sans serif family...}</code>
Typewriter family. Popular with hackers.	<code>\texttt{Typewriter family...}</code>

These commands can be combined in a logical fashion to produce a wide variety of type styles.

Who on Earth is *ever* going to use a boldface sans serif or an italic typewriter type style? `\textsf{\textbf{Who \textmd{on} Earth}} is \textit{\texttt{ever}} ...`

Some type styles may be unavailable on your computer. If you specify a style that isn't available, L^AT_EX will write a warning message and substitute a style that it thinks is similar. (You may think otherwise.)

Each of the text-style commands described above has a corresponding declaration. Boldface text can be obtained with either the `\textbf` text-producing command or the `\bfseries` declaration.

More and **more** armadillos are crossing the road. `\textbf{More}` and `{\bfseries more}` ...

The declarations corresponding to the text-producing command are:

<i>cmd</i>	<i>decl</i>	<i>cmd</i>	<i>decl</i>	<i>cmd</i>	<i>decl</i>
<code>\textup</code>	<code>\upshape</code>	<code>\textsc</code>	<code>\scshape</code>	<code>\textrm</code>	<code>\rmfamily</code>
<code>\textit</code>	<code>\itshape</code>	<code>\textmd</code>	<code>\mdseries</code>	<code>\textsf</code>	<code>\sffamily</code>
<code>\textsl</code>	<code>\slshape</code>	<code>\textbf</code>	<code>\bfseries</code>	<code>\texttt</code>	<code>\ttfamily</code>

None of these text-producing commands or declarations can be used in math mode. Section 3.3.8 explains how to change type style in a mathematical formula.

Type style is a visual property. Commands to specify visual properties belong not in the text, but in the definitions of commands that describe logical structure. L^AT_EX provides the `\emph` command for emphasized text; Section 3.4 explains how to define your own commands for the logical structures in your document. For example, suppose you want the names of genera to appear in italic in your book on African mammals. Don't use `\textit` throughout the text; instead, define a `\genus` command and write

Connochaetes seems to pop up everywhere. `\genus{Connochaetes}` seems to pop up ...

Then, if you decide that *Connochaetes* and all other genera should appear in slanted rather than italic type, you just have to change the definition of `\genus`.

3.2 Symbols from Other Languages

Languages other than English have a variety of accents and special symbols. This section tells you how to generate the ones used in most Western languages. These accents and symbols are not available in the typewriter family of type styles. All the commands introduced in this section are robust.

Commands to produce accents and symbols from other languages allow you to put small pieces of non-English text in an English document. They are not adequate for writing a complete document in another language. The `babel` package allows you to produce documents in languages other than English, as well as multilanguage documents. Consult the *L^AT_EX Companion* for details.

3.2.1 Accents

Table 3.1 shows how to make a wide variety of accents. In this and all similar tables, the T_EX output is followed by the input that produces it, the first entry in Table 3.1 showing that you produce `ò` by typing `\'o`. The letter `o` appears in this table, but the commands can accent any letter.

El señor está bien, garçon.

El se\~{n}or est\'{a} bien, gar\c{c}on.

The letters *i* and *j* need special treatment because they should lose their dots when accented. The commands `\i` and `\j` produce a dotless *i* and *j*, respectively.

Él está aquí.

\'E1 est\'{a} aqu\'{i}.

The commands in Table 3.1 can be used only in paragraph and LR modes. Accents in math mode, which produce accented symbols in mathematical formulas, are made with commands described in Section 3.3.6.

3.2.2 Symbols

Table 3.2 shows how to make some symbols from non-English languages. Note that the symbols *¿* and *¡* are produced by typing a pair of punctuation characters, in much the same way that a medium-length dash is produced by typing two - characters. The commands in Table 3.2 can appear only in paragraph and LR modes; use an `\mbox` command to put one inside a mathematical formula.

ò \'{o}	õ \~{o}	ö \v{o}	q \c{o}
ó \'{o}	ō \={o}	ő \H{o}	q \d{o}
ô \^o}	ó \.o}	oo \t{oo}	q \b{o}
ö \"o}	ö \u{o}		

Table 3.1: Accents.

œ \oe	å \aa	l \l	¿ ?'
Œ \OE	Å \AA	L \L	¡ !'
æ \ae	ø \o	ß \ss	
Æ \AE	Ø \O		

Table 3.2: Non-English Symbols.

The following six special punctuation symbols can be used in any mode:

† \dag	§ \S	© \copyright
‡ \ddag	¶ \P	£ \pounds

Remember also that the seven symbols # \$ % & _ { } are produced by the seven commands \# \\$ \% \& _ \{ \}.

In addition to the symbol-making commands described here, there are many others that can be used only in math mode. They are described in Section 3.3.2.

3.3 Mathematical Formulas

A formula that appears in the running text, called an *in-text* formula, is produced by the `math` environment. This environment can be invoked with either of the two short forms `\(...\)` or `$...$`, as well as by the usual `\begin ... \end` construction. The `displaymath` environment, which has the short form `\[...]`, produces an unnumbered displayed formula. The short forms `$...$`, `\(...\)`, and `\[...]` act as full-fledged environments, delimiting the scope of declarations contained within them. A numbered displayed formula is produced by the `equation` environment. Section 4.2 describes commands for assigning names to equation numbers and referring to the numbers by name, so you don't have to keep track of the actual numbers.

The `math`, `displaymath`, and `equation` environments put TeX in math mode. TeX ignores spaces in the input when it's in math mode (but space characters may still be needed to mark the end of a command name). Section 3.3.7 describes how to add and remove space in formulas. Remember that TeX is in LR mode, where spaces in the input generate space in the output, when it begins processing the argument of an `\mbox` command—even one that appears inside a formula.

All the commands introduced in this section can be used only in math mode, unless it is explicitly stated that they can be used elsewhere. Except as noted, they are all robust. However, `\begin`, `\end`, `\(`, `\)`, `\[`, and `\]` are fragile commands.

3.3.1 Some Common Structures

Subscripts and Superscripts

Subscripts and superscripts are made with the `_` and `^` commands. These commands can be combined to make complicated subscript and superscript expressions.

$$\begin{array}{lll} x^{2y} & x^{\{2y\}} & x^{y^2} & x^{\{y^{\{2\}}\}} & x_1^y & x^{\{y\}}_{\{1\}} \\ x_{2y} & x_{\{2y\}} & x^{y_1} & x^{\{y_{\{1\}}\}} & x_1^y & x_{\{1\}}^{\{y\}} \end{array}$$

Fractions

Fractions denoted by the `/` symbol are made in the obvious way.

Multiplying by $n/2$ gives $(m+n)/n$.

Multiplying by $\$n/2\$$ gives $\backslash ((m+n)/n \backslash)$.

Most fractions in the running text are written this way. The `\frac` command is used for large fractions in displayed formulas; it has two arguments: the numerator and denominator.

$$\begin{array}{ll} x = \frac{y+z/2}{y^2+1} & \backslash [x = \frac{\{y+z/2\}}{\{y^{\{2\}}+1\}} \backslash \\ \frac{x+y}{1+\frac{y}{z+1}} & \backslash [\frac{\{x+y\}}{\{1 + \frac{\{y\}}{\{z+1\}}\}} \backslash \end{array}$$

The `\frac` command can be used in an in-text formula to produce a fraction like $\frac{1}{2}$ (by typing `\frac{1}{2}`), but this is seldom done.

Roots

The `\sqrt` command produces the square root of its argument; it has an optional first argument for other roots. It is a fragile command.

A square root $\sqrt{x+y}$ and an n th root $\sqrt[n]{2}$.

$\dots \backslash (\sqrt{x+y} \backslash) \dots \backslash (\sqrt[n]{2} \backslash)$.

Ellipsis

The commands `\ldots` and `\cdots` produce two different kinds of ellipsis (...).

A low ellipsis: $x_1, \dots, x_n$.

A low ellipsis: `\$x_{\{1\}}, \ldots, x_{\{n\}}\$`.

A centered ellipsis: $a + \cdots + z$.

A centered ellipsis: `\$a + \cdots + z\$`.

Use `\ldots` between commas and between juxtaposed symbols like $a \dots z$; use `\cdots` between symbols like $+$, $-$, and $=$. TeX can also produce vertical and diagonal ellipses, which are used mainly in arrays.

$\vdots$ `\vdots` $\ddots$ `\ddots`

The `\ldots` command works in any mode, but `\cdots`, `\vdots`, and `\ddots` can be used only in math mode.

3.3.2 Mathematical Symbols

There are TeX commands to make almost any mathematical symbol you're likely to need. Remember that they can be used only in math mode.

Greek Letters

The command to produce a lowercase Greek letter is obtained by adding a `\` to the name of the letter. For an uppercase Greek letter, just capitalize the first letter of the command name.

Making Greek letters is as easy as π (or Π). ... is as easy as `$_pi$` (or `$_Pi$`).

(The `$`'s are needed because these commands can be used only in math mode.) If the uppercase Greek letter is the same as its Roman equivalent, as in uppercase alpha, then there is no command to generate it. A complete list of the commands for making Greek letters appears in Table 3.3. Note that some of the lowercase letters have variant forms, made by commands beginning with `\var`. Also, observe that there's no special command for an omicron; you just use an `o`.

<i>Lowercase</i>			
α <code>\alpha</code>	θ <code>\theta</code>	o <code>o</code>	τ <code>\tau</code>
β <code>\beta</code>	ϑ <code>\vartheta</code>	π <code>\pi</code>	υ <code>\upsilon</code>
γ <code>\gamma</code>	ι <code>\iota</code>	ϖ <code>\varpi</code>	ϕ <code>\phi</code>
δ <code>\delta</code>	κ <code>\kappa</code>	ρ <code>\rho</code>	φ <code>\varphi</code>
ϵ <code>\epsilon</code>	λ <code>\lambda</code>	ϱ <code>\varrho</code>	χ <code>\chi</code>
ε <code>\varepsilon</code>	μ <code>\mu</code>	σ <code>\sigma</code>	ψ <code>\psi</code>
ζ <code>\zeta</code>	ν <code>\nu</code>	ς <code>\varsigma</code>	ω <code>\omega</code>
η <code>\eta</code>	ξ <code>\xi</code>		
<i>Uppercase</i>			
Γ <code>\Gamma</code>	Λ <code>\Lambda</code>	Σ <code>\Sigma</code>	Ψ <code>\Psi</code>
Δ <code>\Delta</code>	Ξ <code>\Xi</code>	Υ <code>\Upsilon</code>	Ω <code>\Omega</code>
Θ <code>\Theta</code>	Π <code>\Pi</code>	Φ <code>\Phi</code>	

Table 3.3: Greek Letters.

Calligraphic Letters

TeX provides twenty-six uppercase calligraphic letters $\mathcal{A}, \mathcal{B}, \dots, \mathcal{Z}$, also called script letters. They are produced by a special type style invoked with the `\mathcal` command.

Choose $\mathcal{F}$ such that $\mathcal{F}(x) > 0$.

Choose $\mathcal{F}$ such that...

Only the twenty-six uppercase letters are available in the calligraphic type style.

A Menagerie of Mathematical Symbols

TeX can make dozens of special mathematical symbols. A few of them, such as $+$ and $>$, are produced by typing the corresponding keyboard character. Others are obtained with the commands in Tables 3.4 through 3.7. The shaded symbols require the `latexsym` package to be loaded with a `\usepackage` command. (See Section 2.2.2.) Additional symbols can be made by stacking one symbol on top of another with the `\stackrel` command of Section 3.3.6 or the `array` environment of Section 3.3.3. You can also put a slash through a symbol by typing `\not` before it.

If $x \not\leq y$ then $x \leq y - 1$.

If $x \not\leq y$ then $(x \not\leq y - 1)$.

If the slash doesn't come out in exactly the right spot, put one of the math-mode spacing commands described in Section 3.3.7 between the `\not` command and the symbol.

There are some mathematical symbols whose size depends upon what kind of math environment they appear in; they are bigger in the `displaymath` and `equation` environments than in the ordinary `math` environment. These symbols are listed in Table 3.8, where both the large and small versions are shown. Subscript-sized expressions that appear above and below them are typed as ordinary subscripts and superscripts.

$\pm$ <code>\pm</code>	$\cap$ <code>\cap</code>	$\diamond$ <code>\diamond</code>	$\oplus$ <code>\oplus</code>
$\mp$ <code>\mp</code>	$\cup$ <code>\cup</code>	$\triangleup$ <code>\bigtriangleup</code>	$\ominus$ <code>\ominus</code>
$\times$ <code>\times</code>	$\uplus$ <code>\uplus</code>	$\triangledown$ <code>\bigtriangledown</code>	$\otimes$ <code>\otimes</code>
$\div$ <code>\div</code>	$\sqcap$ <code>\sqcap</code>	$\triangleleft$ <code>\triangleleft</code>	$\oslash$ <code>\oslash</code>
$*$ <code>\ast</code>	$\sqcup$ <code>\sqcup</code>	$\triangleright$ <code>\triangleright</code>	$\odot$ <code>\odot</code>
$\star$ <code>\star</code>	$\vee$ <code>\vee</code>	$\triangleleft$ <code>\lhd</code>	$\bigcirc$ <code>\bigcirc</code>
$\circ$ <code>\circ</code>	$\wedge$ <code>\wedge</code>	$\triangleright$ <code>\rhd</code>	$\dagger$ <code>\dagger</code>
$\bullet$ <code>\bullet</code>	$\setminus$ <code>\setminus</code>	$\triangleleft$ <code>\unlhd</code>	$\ddagger$ <code>\ddagger</code>
$\cdot$ <code>\cdot</code>	$\wr$ <code>\wr</code>	$\triangleright$ <code>\unrhd</code>	$\amalg$ <code>\amalg</code>

Table 3.4: Binary Operation Symbols. (Shaded ones require `latexsym` package.)

$\leq$	<code>\leq</code>	$\geq$	<code>\geq</code>	$\equiv$	<code>\equiv</code>	$\models$	<code>\models</code>
$\prec$	<code>\prec</code>	$\succ$	<code>\succ</code>	$\sim$	<code>\sim</code>	$\perp$	<code>\perp</code>
$\preceq$	<code>\preceq</code>	$\succeq$	<code>\succeq</code>	$\simeq$	<code>\simeq</code>	$\mid$	<code>\mid</code>
$\ll$	<code>\ll</code>	$\gg$	<code>\gg</code>	$\asymp$	<code>\asymp</code>	$\parallel$	<code>\parallel</code>
$\subset$	<code>\subset</code>	$\supset$	<code>\supset</code>	$\approx$	<code>\approx</code>	$\bowtie$	<code>\bowtie</code>
$\subseteq$	<code>\subseteq</code>	$\supseteq$	<code>\supseteq</code>	$\cong$	<code>\cong</code>	$\Join$	<code>\Join</code>
$\sqsubset$	<code>\sqsubset</code>	$\sqsupset$	<code>\sqsupset</code>	$\neq$	<code>\neq</code>	$\smile$	<code>\smile</code>
$\sqsubseteq$	<code>\sqsubseteq</code>	$\sqsupseteq$	<code>\sqsupseteq</code>	$\doteq$	<code>\doteq</code>	$\frown$	<code>\frown</code>
$\in$	<code>\in</code>	$\ni$	<code>\ni</code>	$\notin$	<code>\notin</code>	$\propto$	<code>\propto</code>
$\vdash$	<code>\vdash</code>	$\dashv$	<code>\dashv</code>				

Table 3.5: Relation Symbols. (Shaded ones require `latexsym` package.)

$\leftarrow$	<code>\leftarrow</code>	$\longleftarrow$	<code>\longleftarrow</code>	$\uparrow$	<code>\uparrow</code>
$\Leftarrow$	<code>\Leftarrow</code>	$\Longleftarrow$	<code>\Longleftarrow</code>	$\Uparrow$	<code>\Uparrow</code>
$\rightarrow$	<code>\rightarrow</code>	$\longrightarrow$	<code>\longrightarrow</code>	$\downarrow$	<code>\downarrow</code>
$\Rightarrow$	<code>\Rightarrow</code>	$\Longrightarrow$	<code>\Longrightarrow</code>	$\Downarrow$	<code>\Downarrow</code>
$\leftrightarrow$	<code>\leftrightarrow</code>	$\longleftrightarrow$	<code>\longleftrightarrow</code>	$\updownarrow$	<code>\updownarrow</code>
$\Leftrightarrow$	<code>\Leftrightarrow</code>	$\Longleftrightarrow$	<code>\Longleftrightarrow</code>	$\Updownarrow$	<code>\Updownarrow</code>
$\mapsto$	<code>\mapsto</code>	$\longmapsto$	<code>\longmapsto</code>	$\nearrow$	<code>\nearrow</code>
$\hookrightarrow$	<code>\hookrightarrow</code>	$\hookrightarrow$	<code>\hookrightarrow</code>	$\searrow$	<code>\searrow</code>
$\leftharpoonup$	<code>\leftharpoonup</code>	$\rightharpoonup$	<code>\rightharpoonup</code>	$\swarrow$	<code>\swarrow</code>
$\leftharpoondown$	<code>\leftharpoondown</code>	$\rightharpoondown$	<code>\rightharpoondown</code>	$\nwarrow$	<code>\nwarrow</code>
$\rightleftharpoons$	<code>\rightleftharpoons</code>	$\leadsto$	<code>\leadsto</code>		

Table 3.6: Arrow Symbols. (Shaded ones require `latexsym` package.)

$\aleph$	<code>\aleph</code>	$\prime$	<code>\prime</code>	$\forall$	<code>\forall</code>	∞	<code>\infty</code>
$\hbar$	<code>\hbar</code>	$\emptyset$	<code>\emptyset</code>	$\exists$	<code>\exists</code>	$\Box$	<code>\Box</code>
$\imath$	<code>\imath</code>	∇	<code>\nabla</code>	$\neg$	<code>\neg</code>	$\Diamond$	<code>\Diamond</code>
$\jmath$	<code>\jmath</code>	$\surd$	<code>\surd</code>	$\flat$	<code>\flat</code>	$\triangle$	<code>\triangle</code>
ℓ	<code>\ell</code>	$\top$	<code>\top</code>	$\natural$	<code>\natural</code>	$\clubsuit$	<code>\clubsuit</code>
$\wp$	<code>\wp</code>	$\bot$	<code>\bot</code>	$\sharp$	<code>\sharp</code>	$\diamondsuit$	<code>\diamondsuit</code>
$\Re$	<code>\Re</code>	$\parallel$	<code>\parallel</code>	$\backslash$	<code>\backslash</code>	$\heartsuit$	<code>\heartsuit</code>
$\Im$	<code>\Im</code>	$\angle$	<code>\angle</code>	∂	<code>\partial</code>	$\spadesuit$	<code>\spadesuit</code>
$\mho$	<code>\mho</code>						

Table 3.7: Miscellaneous Symbols. (Shaded ones require `latexsym` package.)

Σ	$\sum$	<code>\sum</code>	$\bigcap$	$\bigcap$	<code>\bigcap</code>	$\odot$	$\odot$	<code>\bigodot</code>
$\prod$	$\prod$	<code>\prod</code>	$\bigcup$	$\bigcup$	<code>\bigcup</code>	$\otimes$	$\otimes$	<code>\bigotimes</code>
$\coprod$	$\coprod$	<code>\coprod</code>	$\bigsqcup$	$\bigsqcup$	<code>\bigsqcup</code>	$\oplus$	$\oplus$	<code>\bigoplus</code>
$\int$	$\int$	<code>\int</code>	$\bigvee$	$\bigvee$	<code>\bigvee</code>	$\biguplus$	$\biguplus$	<code>\biguplus</code>
$\oint$	$\oint$	<code>\oint</code>	$\bigwedge$	$\bigwedge$	<code>\bigwedge</code>			

Table 3.8: Variable-sized Symbols.

Here's how they look when displayed:

$$\sum_{i=1}^n x_i = \int_0^1 f$$

and in the text: $\sum_{i=1}^n x_i = \int_0^1 f$.

Here's how they look when displayed:

`\[\sum_{i=1}^n x_i = \int_0^1 f \]`
and in the text:

`\(\sum_{i=1}^n x_i = \int_0^1 f \)`.

Section 3.3.8 tells how to coerce $\text{\TeX}$ into producing $\sum_{i=1}^n$ in a displayed formula and $\sum_{i=1}^n$ in an in-text formula.

Log-like Functions

In a formula like $\log(x + y)$, the “log”, which represents the logarithm function, is a single word that is usually set in roman type. However, typing `\log` in a formula denotes the product of the three quantities *l*, *o*, and *g*, which is printed as *log*. The logarithm function is denoted by the `\log` command.

Logarithms obey the law: $\log xy = \log x + \log y$ `\( \log xy = \log x + \log y \)`.

Other commands like `\log` for generating function names are listed in Table 3.9. Two additional commands produce the “mod” (modulo) function: `\bmod` for a binary relation and `\pmod` for a parenthesized expression. (Remember **b** as in *binary* and **p** as in *parenthesized*.)

<code>\arccos</code>	<code>\cos</code>	<code>\csc</code>	<code>\exp</code>	<code>\ker</code>	<code>\limsup</code>	<code>\min</code>	<code>\sinh</code>
<code>\arcsin</code>	<code>\cosh</code>	<code>\deg</code>	<code>\gcd</code>	<code>\lg</code>	<code>\ln</code>	<code>\Pr</code>	<code>\sup</code>
<code>\arctan</code>	<code>\cot</code>	<code>\det</code>	<code>\hom</code>	<code>\lim</code>	<code>\log</code>	<code>\sec</code>	<code>\tan</code>
<code>\arg</code>	<code>\coth</code>	<code>\dim</code>	<code>\inf</code>	<code>\liminf</code>	<code>\max</code>	<code>\sin</code>	<code>\tanh</code>

Table 3.9: Log-like Functions.

$$\gcd(m, n) = a \bmod b$$

$$x \equiv y \pmod{a+b}$$

```
\( \gcd(m,n) = a \bmod b \)
\(\ x \equiv y \pmod{a+b} \)
```

Note that `\pmod` has an argument and produces parentheses, while `\bmod` produces only the “mod”.

Some log-like functions act the same as the variable-sized symbols of Table 3.8 with respect to subscripts.

As a displayed formula:

$$\lim_{n \rightarrow \infty} x = 0$$

but in text: $\lim_{n \rightarrow \infty} x = 0$.

As a displayed formula:

```
\[ \lim_{n \rightarrow \infty} x = 0 \]
```

but in text:

```
\( \lim_{\dots} x = 0 \)
```

3.3.3 Arrays

The array Environment

Arrays are produced with the `array` environment. It has a single argument that specifies the number of columns and the alignment of items within the columns. For each column in the array, there is a single letter in the argument that specifies how items in the column should be positioned: `c` for centered, `l` for flush left, or `r` for flush right. Within the body of the environment, adjacent rows are separated by a `\\` command and adjacent items within a row are separated by an `&` character.

$a + b + c$	uv	$x - y$	27
$a + b$	$u + v$	z	134
a	$3u + vw$	xyz	2,978

```
\( \begin{array}{clcr}
a+b+c & & uv & & x-y & & 27 & \\
a+b & & u+v & & z & & 134 & \\
a & & 3u+vw & & xyz & & 2,978 & \\
\end{array} \)
```

There must be no `&` after the last item in a row and no `\\` after the last row. $\text{\TeX}$ is in math mode when processing each array element, so it ignores spaces. Don't put any extra space in the argument.

In mathematical formulas, array columns are usually centered. However, a column of numbers often looks best flush right. Section 3.3.4 describes how to put large parentheses or vertical lines around an array to make a matrix or determinant.

Each item in an array is a separate formula, just as if it were in its own math environment. A declaration that appears in an item is local to the item; its scope is ended by the `&`, `\\`, or `\end{array}` that ends the item. The `\\` command is fragile.

Vertical Alignment

$\text{\TeX}$ draws an imaginary horizontal center line through every formula, at the height where a minus sign at the beginning of the formula would go. An individual array item is itself a formula with a center line. The items in a row of an array are positioned vertically so their center lines are all at the same height.

Normally, the center line of an array lies where you would expect it, halfway between the top and bottom. You can change the position of an array's center line by giving an optional one-letter argument to the `array` environment: the argument `t` makes it line up with the top row's center line, while `b` makes it line up with the bottom row's center line.

The box around each array in the following formula is for clarity; it is not produced by the input:

$$x - \begin{array}{c} a_1 \\ \vdots \\ a_n \end{array} - \begin{array}{cc} u - v & 13 \\ u + v & \begin{array}{c} 12 \\ -345 \end{array} \end{array}$$

```
... \[ x - \begin{array}{c}
  a_{1} \\\vdots \\ a_{n}
\end{array}
- \begin{array}{t}{cl}
  u-v & 13 \\
  u+v & \begin{array}{b}{r}
    12 \\ -345
  \end{array}
\end{array} \]
```

More Complex Arrays

Visual formatting is sometimes necessary to get an array to look right. Section C.1.6 explains how to change the vertical space between two rows; Sections 3.3.7 and 6.4.2 describe commands for adding horizontal space within an item; and Section C.10.2 tells how to add horizontal space between columns. The `array` environment has a number of additional features for making more complex arrays; they are described in Section C.10.2. The *L^AT_EX Companion* describes packages that provide additional features for the `array` environment.

The `array` environment can be used only in math mode and is meant for arrays of formulas; Section 3.6.2 describes an analogous `tabular` environment for making arrays of ordinary text items. The `array` environment is almost always used in a displayed formula, but it can appear in an in-text formula as well.

3.3.4 Delimiters

A *delimiter* is a symbol that acts logically like a parenthesis, with a pair of delimiters enclosing an expression. Table 3.10 lists every symbol that $\text{\TeX}$ regards as a delimiter, together with the command or input character that produces it. These commands and characters produce delimiters of the indicated size. However, delimiters in formulas should be big enough to “fit around” the expressions

((	))	↑ \uparrow
[[	]]	↓ \downarrow
{ \{	} \}	↕ \updownarrow
⌊ \lfloor	⌋ \rfloor	↑ \Uparrow
⌈ \lceil	⌉ \rceil	↓ \Downarrow
⟨ \langle	⟩ \rangle	↕ \Updownarrow
/ /	\ \backslash	
	\lvert	

Table 3.10: Delimiters.

that they delimit. To make a delimiter the right size, type a `\left` or `\right` command before it.

Big delimiters are most often used with arrays.

$$\left(\begin{array}{cc} x_{11} & x_{12} \\ x_{21} & x_{22} \\ y \\ z \end{array} \right)$$

```
... \[ \left( \begin{array}{c}
\left| \begin{array}{cc}
... \end{array} \end{array} \right. \\
\right| \\
y \\ z \\
\end{array} \right) \]
```

The `\left` and `\right` commands must come in matching pairs, but the matching delimiters need not be the same.

$$\vec{x} + \vec{y} + \vec{z} = \begin{pmatrix} a \\ b \end{pmatrix}$$

```
\[ ... = \left( \begin{array}{c}
a \\ b \\
\end{array} \right) \]
```

Some formulas require a big left delimiter with no matching right one, or vice versa. The `\left` and `\right` commands must match, but you can make an invisible delimiter by typing a “.” after the `\left` or `\right` command.

$$x = \begin{cases} y & \text{if } y > 0 \\ z + y & \text{otherwise} \end{cases}$$

```
\[ x = \left\{ \begin{array}{l}
y & \& \mbox{if } \$y>0\$ \\
z+y & \& \mbox{otherwise} \\
\end{array} \right. . \]
```

3.3.5 Multiline Formulas

The `displaymath` and `equation` environments make one-line formulas. A formula is displayed across multiple lines if it is a sequence of separate formulas or is too long to fit on a single line. A sequence of equations or inequalities is displayed with the `eqnarray` environment. It is very much like a three-column `array` environment, with consecutive rows separated by `\\` and consecutive items

within a row separated by & (Section 3.3.3). However, an equation number is put on every line unless that line has a `\nonumber` command.

The middle column can be anything, not just a '='.

$$x = 17y \quad (2)$$

$$y > a + b + c + d + e + f + g + h + i + j + k + l + m + n + o + p \quad (3)$$

```
... \begin{eqnarray}
x & = & 17y \\
y & > & a + \dots + j + \nonumber \\
& & k + l + m + n + o + p
\end{eqnarray}
```

Section 4.2 describes how to let L^AT_EX handle references to equations so you don't have to remember equation numbers.

The `eqnarray*` environment is the same as `eqnarray` except it does not generate equation numbers.

$$\begin{aligned} x &\ll y_1 + \dots + y_n \\ &\leq z \end{aligned}$$

```
\begin{eqnarray*}
x & \ll y_{\{1\}} + \cdots + y_{\{n\}} \\
& \leq z
\end{eqnarray*}
```

A + or - that begins a formula (or certain subformulas) is assumed to be a unary operator, so typing `$-x$` produces $-x$ and typing `$$\sum -x_{\{i\}}$` produces $\sum -x_i$, with no space between the “-” and the “ x ”. If the formula is part of a larger one that is being split across lines, T_EX must be told that the + or - is a binary operator. This is done by starting the formula with an invisible first term, produced by an `\mbox` command with a null argument.

$$y = a + b + c + d + e + f + g + h + i + j + k + l + m + n + o + p$$

```
\begin{eqnarray*}
y & = & a + b + c + \dots + h + i + j \\
& & \mbox{} + k + \dots
\end{eqnarray*}
```

A formula can often be split across lines using a `\lefteqn` command in an `eqnarray` or `eqnarray*` environment, as indicated by the following example:

$$w + x + y + z = a + b + c + d + e + f + g + h + i + j + k + l + m + n + o + p$$

```
\begin{eqnarray*}
\lefteqn{w+x+y+z = } \\
& a + \dots + j + \\
& k + \dots + o + p
\end{eqnarray*}
```

The `\lefteqn` command works by making T_EX think that the formula it produces has zero width, so the left-most column of the `eqnarray` or `eqnarray*` environment is made suitably narrow. The indentation of the following lines can be increased by adding space (with the commands of Section 6.4.2) between the `\lefteqn` command and the `\\`.

Breaking a single formula across lines in this way is visual formatting, and I wish L^AT_EX could do it for you. However, doing it well requires more intelligence than L^AT_EX has, and doing it poorly can make the formula hard to understand, so you must do it yourself. This means that the formula may have to be reformatted if you change notation (changing the formula's length) or if you change the style of your document (changing the line length).

3.3.6 Putting One Thing Above Another

Symbols in a formula are sometimes placed one above another. The `array` environment is good for vertically stacking subformulas, but not smaller pieces—you wouldn't use it to put a bar over an x to form $\bar{x}$. L^AT_EX provides special commands for doing this and some other common kinds of symbol stacking.

Over- and Underlining

The `\overline` command puts a horizontal line above its argument.

You can have nested overlining: $\overline{\overline{x^2} + 1}$. `... \(\overline{\overline{x}^2} + 1\) \.`

There's an analogous `\underline` command for underlining that works in paragraph and LR mode as well as math mode, but it's seldom used in formulas.

The value is $3x$. `\underline{The} value is $\underline{3x}$.`

The `\underline` command is fragile.

Horizontal braces are put above or below an expression with the `\overbrace` and `\underbrace` commands.

$\overbrace{a + b + c + d}$ `\overbrace{a+ \underbrace{b + c} + d}`

In a displayed formula, a subscript or superscript puts a label on the brace.

$\underbrace{a + b + \cdots + y + z}_{26}^{24}$ `\[ \underbrace{a + \overbrace{b + \cdots + y}^{24}}_{26} + z ]_{26} \]`

Accents

The accent commands described in Section 3.2.1 are for ordinary text and cannot be used in math mode. Accents in formulas are produced with the commands shown in Table 3.11. The letter a is used as an illustration; the accents work with any letter.

Wide versions of the `\hat` and `\tilde` accent are produced by the `\widehat` and `\widetilde` commands. These commands try to choose the appropriately-sized accent to fit over their argument, but they can't produce very wide accents.

$\hat{a}$ <code>\hat{a}</code>	$\acute{a}$ <code>\acute{a}</code>	$\bar{a}$ <code>\bar{a}</code>	$\dot{a}$ <code>\dot{a}</code>
$\check{a}$ <code>\check{a}</code>	$\grave{a}$ <code>\grave{a}</code>	$\vec{a}$ <code>\vec{a}</code>	$\ddot{a}$ <code>\ddot{a}</code>
$\breve{a}$ <code>\breve{a}</code>	$\tilde{a}$ <code>\tilde{a}</code>		

Table 3.11: Math Mode Accents.

Here are two sizes of wide hat: $\widehat{1-x} = \widehat{-y}$.
`\( \widehat{1-x} = \widehat{-y} \)`

The letters i and j should lose their dots when accented. The commands `\imath` and `\jmath` produce a dotless i and j , respectively.

There are no dots in $\vec{i} + \tilde{j}$.
`\( \vec{\imath} + \tilde{\jmath} \)`

Stacking Symbols

The `\stackrel` command stacks one symbol above another.

$A \stackrel{a'}{\rightarrow} B \stackrel{b'}{\rightarrow} C$
 $\vec{x} \stackrel{\text{def}}{=} (x_1, \dots, x_n)$

`\( A \stackrel{a'}{\rightarrow} B \stackrel{b'}{\rightarrow} C \)`
`\( \vec{x} \stackrel{\mathrm{def}}{=} (x_1, \dots, x_n) \)`

See Section 3.3.8 for an explanation of the `\mathrm` command. The `\stackrel` command's first argument is printed in small type, like a superscript; use the `\textstyle` declaration of Section 3.3.8 to print it in regular-size type.

3.3.7 Spacing in Math Mode

In math mode, $\text{\TeX}$ ignores the spaces you type and formats the formula the way it thinks is best. Some authors feel that $\text{\TeX}$ cramps formulas, and they want to add more space. $\text{\TeX}$ knows more about typesetting formulas than many authors do. Adding extra space usually makes a formula prettier but harder to read, because it visually “fractures” the formula into separate units. Study how formulas look in ordinary mathematics texts before trying to improve $\text{\TeX}$'s formatting.

Although fiddling with the spacing is dangerous, you sometimes have to do it to make a formula look just right. One reason is that $\text{\TeX}$ may not understand the formula's logical structure. For example, it interprets $y \, dx$ as the product of three quantities rather than as y times the differential dx , so it doesn't add the little extra space after the y that appears in $y \, dx$. Section 3.4 explains how to define your own commands for expressing this kind of logical structure, so you need worry about the proper spacing only when defining the commands, not when writing the formulas.

Like any computer program that makes aesthetic decisions, $\text{\TeX}$ sometimes needs human assistance. You'll have to examine the output to see if the spacing

needs adjustment. Pay special attention to square root signs, integral signs, and quotient symbols (/).

The following five commands add the amount of horizontal space shown between the vertical lines:

<code>\,</code>	thin space	<code>\:</code>	medium space	<code>_</code>	interword space
<code>\!</code>	negative thin space	<code>\;</code>	thick space		

The `\!` acts like a backspace, removing the same amount of space that `\,` adds. The `\,` command can be used in any mode; the others can appear only in math mode. Here are some examples of their use, where the result of omitting the spacing commands is also shown.

$\sqrt{2}x$	<code>\sqrt{2} \,</code>	x	instead of	$\sqrt{2}x$
$n/\log n$	<code>n / \! \log n</code>		instead of	$n/\log n$
$\iint z \, dx \, dy$	<code>\int\!\!\!\int z \,, dx \,, dy</code>		instead of	$\iint z dx dy$

As with all such fine tuning, you should not correct the spacing in formulas until you've finished writing the document and are preparing the final output.

3.3.8 Changing Style in Math Mode

Type Style

L^AT_EX provides the following commands for changing type style in math mode:

<i>italic</i> + $2^{\text{ft}}\Psi \log[\psi]$	<code>\mathit{italic + 2^{ft} \Psi \log[\psi]}</code>
roman + $2^{\text{ft}}\Psi \log[\psi]$	<code>\mathrm{roman + 2^{ft} \Psi \log[\psi]}</code>
bold + $2^{\text{ft}}\Psi \log[\psi]$	<code>\mathbf{bold + 2^{ft} \Psi \log[\psi]}</code>
sans serif + $2^{\text{ft}}\Psi \log[\psi]$	<code>\mathsf{sans serif + ... }</code>
typewriter + $2^{\text{ft}}\Psi \log[\psi]$	<code>\mathtt{typewriter + ... }</code>
<i>CAL UPPERCASE LETTERS ONLY</i>	<code>\mathcal{CAL UPPERCASE LETTERS ONLY}</code>

They change the style only of letters, numbers, and uppercase Greek letters. Nothing else is affected. L^AT_EX normally uses an italic type style for letters in math mode. However, it interprets each letter as a separate mathematical symbol, and it produces very different spacing than an ordinary italic typestyle. You should use `\mathit` for multiletter symbols in formulas.

Is *different* any *different* from df^2e^2rnt ?

Is `\mathit{different}` any `\mathit{different}`...

As is evident from this example, you should not use `...$` as a shorthand for `\emph{...}` or `\textit{...}`.

The `\boldmath` declaration causes everything in a formula to be bold, including the symbols.

$diff + 2^{\text{ft}}\Psi \log[\psi]$

`\boldmath ${diff + 2^{ft}\Psi \log[\psi]}`

This declaration cannot be used in math mode. To produce a bold subformula, put the subformula in an `\mbox`.

$$x + \nabla f = 0$$

```
\(x + \mbox{\boldmath $\nabla f$} = 0\)
```

The `\boldmath` command generates a warning if any font (size and style of type) that you *might* use in a formula isn't available. For example, it might issue a warning that L^AT_EX does not have the font needed to produce a bold sans serif subsubscript, even though you never dreamed of producing such a subsubscript. You should examine your output to make sure that the fonts you do use are the right ones.

Math Style

T_EX uses the following four *math styles* when typesetting formulas:

display For normal symbols in a displayed formula.

text For normal symbols in an in-text formula.

script For subscripts and superscripts.

scriptscript For further levels of sub- and superscripting, such as subscripts of superscripts.

Display and text math styles are the same except for the size of the variable-sized symbols in Table 3.8 on page 44 and the placement of subscripts and superscripts on these symbols, on some of the log-like functions in Table 3.9 on page 44, and on horizontal braces. T_EX uses small type in script style and even smaller type in scriptscript style. The declarations `\displaystyle`, `\textstyle`, `\scriptstyle`, and `\scriptscriptstyle` force T_EX to use the indicated style.

Compare the small superscript in $e^{x(i)}$ with the large one in $e^{y(i)}$.

```
... small superscript in \( e^{\scriptstyle x(i)} \)
... large one in \( e^{\textstyle y(i)} \).
```

3.3.9 When All Else Fails

If you write a lot of complicated formulas, sooner or later you'll encounter one that can't be handled with the commands described so far. When this happens, the first thing to do is look at the advanced L^AT_EX features described in Sections C.7 and C.10.2. If you don't find what you need there, consider using the `amstex` package, described in the L^AT_EX *Companion*. This package was created for mathematicians by the American Mathematical Society.

If you are not a mathematician and don't write many complicated formulas, you may be satisfied with an *ad hoc* solution to your problem that uses visual formatting. Try the commands in Section 6.4.3 that move text around and change how big T_EX thinks it is. L^AT_EX's `picture` environment, described in

Section 7.1, allows you to put a symbol anywhere you want, and to draw lines and arrows. The `graphics` package described in Section 7.2 contains commands to shrink, stretch, and rotate text. With a little effort, you can handcraft just about any kind of formula you want.

3.4 Defining Commands and Environments

The input file should display as clearly as possible the logical structures in your document. Any structure, such as a special mathematical notation, that appears several times in the document should be expressed with its own command or environment. The following two sections explain how to define commands and environments. Section 3.4.3 describes how to type theorems and similar structures.

3.4.1 Defining Commands

The simplest type of repeated structure occurs when the same text appears in different places. The `\newcommand` declaration defines a new command to generate such text; its first argument is the command name and its second argument is the text.

Let Γ_i be the number of gnats per cubic meter,
where Γ_i is normalized with respect to $\nu(s)$.

```
\newcommand{\gn}{\Gamma_i}
...
Let \gn be the ... where \gn is ...
```

The `\_` commands are needed because $\text{\TeX}$ ignores space characters following the command name `\gn`.

This example illustrates a common problem in defining commands to produce mathematical formulas. The `\Gamma` command can be used only in math mode, which is why the `$`'s are needed in the `\newcommand` argument. However, the command `\gn` cannot be used in math mode because the first `$` would cause $\text{\TeX}$ to leave math mode and encounter the `\Gamma` while in paragraph mode. To solve this problem, $\text{\LaTeX}$ provides the `\ensuremath` command, which ensures that its argument is typeset in math mode, regardless of the current mode. Thus, `\ensuremath{x^2}` is equivalent to `$x^2$` if it appears in LR or paragraph mode, and it is equivalent to `x^2` if it appears in math mode. With `\ensuremath`, we define `\gn` so it can be used in any mode.

Let Γ_i be the number of gnats per cubic meter,
where $e^{\Gamma_i} = \nu(s)$.

```
\newcommand{\gn}{\ensuremath{\Gamma_i}}
...
Let \gn be the ... where $e^{\gn}=\nu(s)$.
```

You should use `\ensuremath` when defining a command to be used both in and out of math mode.

In addition to making the input more readable, defining your own commands can save typing. L^AT_EX's command and environment names have generally been chosen to be descriptive rather than brief. You can use `\newcommand` to define abbreviations for frequently used commands. For example, the declarations

```
\newcommand{\be}{\begin{enumerate}}
\newcommand{\ee}{\end{enumerate}}
```

define `\be ... \ee` to be equivalent to

```
\begin{enumerate} ... \end{enumerate}
```

For repetitive structures having components that vary, you can define commands with arguments by giving `\newcommand` an optional argument.

Since $gnu(5x; y)$ and $gnu(5x-1; y+1)$ represent adjacent populations, they are approximately equal.

```
\newcommand{\gnaw}[2]{\ensuremath{\mathit{gnu}(\#1;\#2)}}
Since \gnaw{5x}{y} and \gnaw{5x-1}{y+1} ...
```

The optional argument 2 (in square brackets) specifies that `\gnaw` has two arguments. The `#1` and `#2` in the last argument of `\newcommand` are called *parameters*; they are replaced by the first and second arguments, respectively, of `\gnaw` when that command is used. A command may have up to nine arguments. Section C.8.1 explains how to define a command that has an optional argument.

When you define a command like `\gnaw`, the definition is saved exactly as it appears in the `\newcommand` declaration. When T_EX encounters a use of `\gnaw`, it replaces `\gnaw` and its arguments by the definition, with the arguments substituted for the corresponding *parameters*—the `#1` replaced by the first argument and the `#2` replaced by the second. T_EX then processes this text pretty much as if you had typed it instead of typing the `\gnaw` command. However, defining a command to have space at the end is usually a bad idea, since it can lead to extra space in the output when the command is used.

One command can be defined in terms of another.

The definition above of $gnu(0; 1)$ gives $gnu(5x; y)$ the expected value.

```
\newcommand{\usegnaw}{\gnaw{5x}{y}}
... of \gnaw{0}{1} gives \usegnaw the ...
```

It doesn't matter whether the `\newcommand` declaration defining `\usegnaw` comes before or after the one defining `\gnaw`, so long as they both come before any use of `\usegnaw`. However, a command cannot be defined in terms of itself, since T_EX would chase its tail forever trying to figure out what such a definition meant.²

When T_EX encounters a command, it looks for that command's arguments before interpreting it or any subsequent commands. Thus, you can't type

²This kind of recursive definition is possible using more advanced T_EX commands, but it cannot be done with the L^AT_EX commands described in this book.

```
\newcommand{\gnawargs}{\{5x\}{y}} \gnaw\gnawargs is wrong
```

because TeX expects the `\gnaw` command to be followed by two arguments enclosed in braces, not by another command.

The braces surrounding the last argument of the `\newcommand` declaration do not become part of the command's definition, and the braces surrounding an argument are thrown away before substituting the argument for the corresponding parameter. This means that the braces delimiting an argument do not delimit the scope of declarations in the argument. To limit the scope of declarations contained within an argument, you must add explicit braces in the command definition.

gnus(x;54) is fine, but in *gnus(x;54)*, the scope of the *emphasis* declaration extends into the following text.

```
\newcommand{\good}[3]{\#{1}$({\#{2};{\#{3}}$}
\newcommand{\bad}[3]{\#{1}$({\#{2};{\#{3}}$}
...
\good{\em gnus}{x}{54} is fine, but in
\bad{\em gnus}{x}{54}, the scope ...
```

Using `\newcommand` to define a command that already exists produces an error. The `\renewcommand` declaration redefines an already defined command; it has the same arguments as `\newcommand`. Don't redefine an existing command unless you know what you're doing. Even if you don't explicitly use a command, redefining it can produce strange and unpleasant results. Also, never define or redefine any command whose name begins with `\end`.

The `\newcommand` and `\renewcommand` commands are declarations; their scopes are determined by the rules given in Section 2.2.1. It's best to put all command definitions together in the preamble, with comments describing what the commands do. You're likely to re-use many of them in subsequent documents.

3.4.2 Defining Environments

The `\newenvironment` command is used to define a new environment. A command of the form

```
\newenvironment{cozy}{begin text}{end text}
```

defines a *cozy* environment for which TeX replaces a `\begin{cozy}` command by the *begin text* and an `\end{cozy}` command by the *end text*. A new environment is usually defined in terms of an existing environment such as *itemize*, with the *begin text* beginning the *itemize* environment and the *end text* ending it.

Here is an example of a user-defined environment:

- *This environment produces items that are emphasized.*
- *It is defined in terms of L^AT_EX's `itemize` environment and `\em` command.*

```
\newenvironment{emphit}{\begin{itemize}
  \em}{\end{itemize}}
... example of a user-defined environment:
\begin{emphit}
  \item This environment produces ...
\end{emphit}
```

An optional argument of the `\newenvironment` command allows you to define an environment that has arguments; it works the same as described above for `\newcommand`.

Observe how a new logical structure—in this example, a labeled description of a single item—can be defined in terms of existing environments.

Armadillos: This witty description of the armadillo was produced by the `descit` environment.

```
\newenvironment{descit}[1]{\begin{quote}
  \textit{#1}}{\end{quote}}
...
defined in terms of existing environments.
\begin{descit}{Armadillos}
This witty description of the armadillo ...
\end{descit}
```

The parameters (the #1, #2, etc.) can appear only in the *begin text*. The comments made above about the scope of declarations that appear inside arguments of a command defined with `\newcommand` apply to the arguments of environments defined with `\newenvironment`. Section C.8.2 explains how to define an environment with an optional argument.

The `\newenvironment` command produces an error if the environment is already defined. Use `\renewenvironment` to redefine an existing environment. If `\newenvironment` complains that an environment you've never heard of already exists, choose a different environment name. Use `\renewenvironment` only when you know what you're doing; don't try redefining an environment that you don't know about.

3.4.3 Theorems and Such

Mathematical text usually includes theorems and/or theorem-like structures such as lemmas, propositions, axioms, conjectures, and so on. Nonmathematical text may contain similar structures: rules, laws, assumptions, principles, etc. Having a built-in environment for each possibility is out of the question, so L^AT_EX provides the `\newtheorem` declaration to define environments for the particular theorem-like structures in your document.

The `\newtheorem` command has two arguments: the first is the name of the environment, the second is the text used to label it.

Conjectures are numbered consecutively from the beginning of the document; this is the fourth one:

Conjecture 4 *All conjectures are interesting, but some conjectures are more interesting than others.*

```
\newtheorem{guess}{Conjecture}
...
document; this is the fourth one:
\begin{guess}
  All conjectures ... than others.
\end{guess}
```

The `\newtheorem` declaration is best put in the preamble, but it can go anywhere in the document.

A final optional argument to `\newtheorem` causes the theorem-like environment to be numbered within the specified sectional unit.

This is the first Axiom of Chapter 3:

Axiom 3.1 *All axioms are very dull.*

```
\newtheorem{axiom}{Axiom}[chapter]
...
\begin{axiom}
  All axioms are very dull.
\end{axiom}
```

Theorem-like environments can be numbered within any sectional unit; using `section` instead of `chapter` in the example above causes axioms to be numbered within sections.

Sometimes one wants different theorem-like structures to share the same numbering sequence—so, for example, the hunch immediately following Conjecture 5 should be Hunch 6.

Conjecture 5 *Some good conjectures are numbered.*

Hunch 6 *There are no sure-fire hunches.*

```
\newtheorem{guess}{Conjecture}
\newtheorem{hunch}[guess]{Hunch}
...
\begin{guess} Some good ... \end{guess}
\begin{hunch} There are ... \end{hunch}
```

The optional argument `guess` in the second `\newtheorem` command specifies that the `hunch` environment should be numbered in the same sequence as the `guess` environment.

A theorem-like environment defined with `\newtheorem` has an optional argument that is often used for the inventor or common name of a theorem, definition, or axiom.

Conjecture 7 (Wiles, 1985) *There do exist integers $n > 2$, x , y , and z such that $x^n + y^n = z^n$.*

```
\begin{guess}[Wiles, 1985]
  There do exist integers  $n > 2$ ,  $x$ ,  $y$ , ...
\end{guess}
```

See Section C.1.1 if the body of a theorem-like environment begins with a [.

3.5 Figures and Other Floating Bodies

3.5.1 Figures and Tables

TeX will break a sentence across pages to avoid a partially filled page. But some things, such as pictures, cannot be split; they must be “floated” to convenient places, like the top of the following page, to prevent half-empty pages. L^AT_EX provides two environments that cause their contents to float in this way: `figure` and `table`. There are packages that define or allow you to define other environments for floating objects, such as a `program` environment for computer programs. L^AT_EX doesn’t care what you use any of these environments for; so far as it’s concerned, the only difference between them is how they are captioned.

The caption on a figure or table is made with a `\caption` command having the caption’s text as its argument. This is a moving argument, so fragile commands must be `\protect`’ed (see Section 2.2.3). The `figure` or `table` environment is placed in with the text, usually just past the point where the figure or table is first mentioned.

The body of the figure goes here. This figure happened to float to the top of the current page.

Figure 7: The caption goes here.

⋮

This is the place in the running text that mentions Figure 7 for the first time. The figure will not be put on an earlier page than the text preceding the `figure` environment.

This is the place in the running text that mentions Figure~7 for the first time.

```
\begin{figure}
  The body of the figure goes here.
  This figure ... the current page.
  \caption{The caption goes here.}
\end{figure}
```

The figure will not be put on an ...

Tables are numbered separately from figures, using the same numbering scheme. Section 4.2 explains how to number cross-references automatically, so you never have to type the actual figure numbers.

You can put anything you want in the body of a figure or table; L^AT_EX processes it in paragraph mode just like any other text. The `figure` environment is generally used for pictures and the `table` environment for tabular information. Simple pictures can be drawn with the `picture` environment of Section 7.1. You can insert pictures prepared with other programs using the `graphics` package, described in Section 7.2. You can also use the `\vspace` command of Section 6.4.2 to leave room for a picture to be pasted in later. Tabular material can be formatted with the `tabular` environment of Section 3.6.2. Section 6.5 explains how to center the figure or table.

The body of a figure or table is typeset as a paragraph the same width as in the ordinary running text. Section 6.4.3 explains how to make paragraphs of different widths, position two half-width figures side by side, and do other

formatting within a `figure` or `table` environment. More than one `\caption` command can appear in the same `figure` or `table` environment, producing a single floating object with multiple numbered captions. The `\caption` command can be used only in a `figure` or `table` environment.

L^AT_EX ordinarily tries to place a figure or table either above the text at the top of a page, below the text at the bottom of a page, or on a separate page containing nothing but figures and tables. Section C.9.1 describes the rules by which L^AT_EX decides where a floating object should float and how you can influence its decision; read that section if you don't understand why L^AT_EX put a figure or table where it did.

3.5.2 Marginal Notes

A marginal note is made with the `\marginpar` command, having the text as its argument. The note is placed in the margin, its first line even with the line of text containing the command. T_EX is in paragraph mode when processing the marginal note. The following example shows how I typed this paragraph:

and, having the text as its
line even with the line of *This is a mar-*
mode when processing the *ginal note.*
yped this paragraph.

... placed in the margin,
`\marginpar{\em This is a marginal note.}`
its first line even with the line of
... how I typed this paragraph.

The standard styles put notes in the right margin for one-sided printing (the default), in the outside margin for two-sided printing (specified by the `twoside` document-class option), and in the nearest margin for two-column formatting (the `twocolumn` option). Section C.9.2 describes commands for getting L^AT_EX to put them in the opposite margin.

You may want a marginal note to vary depending upon which margin it's in. For example, to make an arrow pointing to the text, you need a left-pointing arrow in the right margin and a right-pointing one in the left margin. If the `\marginpar` command is given an optional first argument, it uses that argument if the note goes in the left margin and uses the second (mandatory) argument if the note goes in the right margin. The command

```
\marginpar [{$\Rightarrow$}]{${\Leftarrow$}}
```

makes an arrow that points towards the text, whichever margin the note appears in.³

A marginal note is never broken across pages; a note that's too long will extend below the page's bottom margin. L^AT_EX moves a marginal note down on the page to keep it from bumping into a previous one, warning you when it does

³The arrows won't be symmetrically placed, since both will be at the left of the space reserved for marginal notes. The `\hfill` command of Section 6.4.2 can be used to adjust their horizontal position.

so. When using notes more than two or three lines long, you may have to adjust their placement according to where they happen to fall on the page. The vertical position of a note is changed by beginning it with a vertical spacing command (Section 6.4.2). You may also have to use the commands of Section 6.2.2 to control where L^AT_EX starts a new page. This is visual design, which means reformatting if you make changes to the document. Save this job until the very end, after you've finished all the writing.

Marginal notes are not handled efficiently by L^AT_EX; it may run out of space if you use too many of them. How many you can use before this happens depends upon what computer you're running L^AT_EX on and how many figures and tables you have.

3.6 Lining It Up in Columns

The `tabbing` and `tabular` environments both can align text in columns. The `tabbing` environment allows you to set tab stops similar to the ones on a typewriter, while the `tabular` environment is similar to the `array` environment described in Section 3.3.3, except that it is for ordinary text rather than formulas. The `tabbing` and `tabular` environments differ in the following ways:

- The `tabbing` environment can be used only in paragraph mode and makes a separate paragraph. The `tabular` environment can be used in any mode; it can put a table in the middle of a formula or line of text.
- T_EX can start a new page in the middle of a `tabbing` environment, but not in the middle of a `tabular` environment. Thus, a long `tabbing` environment can appear in the running text, but a long `tabular` environment should go in a figure or table (Section 3.5.1).
- T_EX automatically determines the widths of columns in the `tabular` environment; you have to do that yourself in the `tabbing` environment by setting tab stops.
- A change of format in the middle of the environment is easier in the `tabbing` than in the `tabular` environment. This makes the `tabbing` environment better at formatting computer programs.

If neither the `tabbing` nor the `tabular` environment does what you want, consult the *L^AT_EX Companion*. It describes several packages that provide very powerful commands to format tabular material.

3.6.1 The `tabbing` Environment

In the `tabbing` environment, you align text in columns by setting tab stops and tabbing to them, somewhat as you would with an ordinary typewriter. Tab

stops are set with the `\=` command, and `\>` moves to the next tab stop. Lines are separated by the `\\` command.

The `tabbing` environment starts a new line.

```
If it's raining
  then put on boots,
      take hat;
  else smile.
Leave house.
```

The text that follows starts on a new line, beginning a new paragraph if you leave a blank line after the `\end{tabbing}` command.

Unlike a typewriter's tabbing key, the `\>` command tabs to the logically next tab stop, even if that means tabbing to the left.

```
A short column
This is too long / / /

... environment starts a new line.
\begin{tabbing}
If \= it's raining      \\
  \> then \= put on boots, \\
    \>      \> take hat;    \\
  \> else \> smile.        \\
Leave house.
\end{tabbing}
The text that follows starts on a new ...

\begin{tabbing}
A short              \= column.      \\
  This is too long. \> / / / / / / /
\end{tabbing}
\mbox{}
```

Remember that the input file's format doesn't matter; one space is the same as a hundred.

The `\=` command resets the logically next tab stop.

```
Old Column 1 Old Col 2 Old Col 3
Col 1        Col 2
New Col 1 New 2      Same Col 3
Col 1        Col 2      Col 3

\begin{tabbing}
Old Column 1 \= Old Col 2 \= Old Col 3 \\
Col 1      \>      Col 2          \\
New Col 1 \= New 2          \> Same Col 3 \\
Col 1      \> Col 2          \> Col 3
\end{tabbing}
```

Spaces in the input are ignored after a `\=` or `\>` command, but not before it.

A line that ends with a `\kill` command instead of a `\\` produces no output, but can be used for setting tabs.

```
Gnat      Gnu      Gnome
Armadillo Armament Armorer

\begin{tabbing}
Armadillo \= Armament \=      \kill
Gnat      \> Gnu      \> Gnome \\
Armadillo \> Armament \> Armorer
\end{tabbing}
```

A declaration made in a `tabbing` environment is local to the current item; its scope is ended by the next `\=`, `\>`, `\\`, `\kill`, or `\end{tabbing}` command.

A lively *gnat*

A dull gnu

A lively \em gnat \> A dull gnu \>

The `tabbing` environment has a number of additional features that are described in Section C.10.1.

3.6.2 The tabular Environment

The `tabular` environment is similar to the `array` environment, so you should read Section 3.3.3 before reading any further here. It differs from the `array` environment in two ways: it may be used in any mode, not just in math mode, and its items are processed in LR mode instead of in math mode. This makes `tabular` better for tabular lists and `array` better for mathematical formulas. This section describes some features used mainly with the `tabular` environment, although they apply to `array` as well. Many additional features of these environments are described in Section C.10.2.

A `|` in the `tabular` environment's argument puts a vertical line extending the full height of the environment in the specified place. An `\hline` command after a `\>` or at the beginning of the environment draws a horizontal line across the full width of the environment. The `\cline{i-j}` command draws a horizontal line across columns *i* through *j*, inclusive.

gnats	gram	\$13.65
	each	.01
gnu	stuffed	92.50
emu		33.33
armadillo	frozen	8.99

```
\begin{tabular}{||l|lr||}      \hline
gnats    & gram    & \$13.65 \> \cline{2-3}
          & each    & .01 \> \hline
gnu      & stuffed & 92.50
          &         & \> \cline{1-1} \cline{3-3}
emu      &         & 33.33 \> \hline
armadillo & frozen  & 8.99 \> \hline
\end{tabular}
```

This is the only situation in which a `\>` goes after the last row of the environment.

Single (not doubled) `|` specifiers in the argument of a `tabular` (or `array`) environment do not change the width of the table. Tables not enclosed by vertical lines therefore have extra space around them. Section C.10.2 explains how to remove this space.

A single item that spans multiple columns is made with a `\multicolumn` command, having the form

```
\multicolumn{n}{pos}{item}
```

where *n* is the number of columns to be spanned, *pos* specifies the horizontal positioning of the item—just as in the environment's argument—and *item* is the item's text. The *pos* argument replaces the portion of the environment's argument corresponding to the *n* spanned columns; it must contain a single `l`, `r`, or `c` character and may contain `|` characters.

Note the placement of “ITEM” and “PRICE”:

ITEM		PRICE
gnat	(dozen)	3.24
gnu	(each)	24,985.47

```
... \begin{tabular}{llr}
    \multicolumn{2}{c}{ITEM} &
    \multicolumn{1}{c}{PRICE} \\
    gnat & (dozen) & 3.24 \\
    gnu & (each) & 24,985.47
\end{tabular}
```

A `\multicolumn` command spanning a single column serves to override the item positioning specified by the environment argument.

When the environment argument has 1 characters, it’s not obvious which of them get replaced by a `\multicolumn`’s positioning argument. The rule is: *the part of the environment argument corresponding to any column other than the first begins with an l, r, or c character*. By this rule, the argument `|l|l|r|` is split into parts as `|l|`, `|l|`, `|r|`.

<i>type</i>	<i>style</i>	
smart	red	short
rather silly	puce	tall

```
\begin{tabular}{|l|l|r|} \hline \hline
\emph{type} &
\multicolumn{2}{c|}{\emph{style}} \\ \hline
smart & red & short \\
rather silly & puce & tall \\ \hline \hline
\end{tabular}
```

The `tabular` environment produces an object that TeX treats exactly like a single, big letter. You could put it in the middle of a paragraph, or in the middle of a word—but that would look rather strange. A `tabular` environment is usually put in a figure or table (Section 3.5.1), or else displayed on a line by itself, using the `center` environment of Section 6.5.

The `tabular` environment makes it easy to draw tables with horizontal and vertical lines. Don’t abuse this feature. Lines usually just add clutter to a table; they are seldom helpful. The numbered tables in this book do not contain a single line.

3.7 Simulating Typed Text

A printed document may contain simulated typed text—for example, the instruction manual for a computer program usually shows what the user types. The `\ttfamily` declaration causes TeX to produce text in a typewriter type style (Section 3.1), but it doesn’t stop TeX from breaking the text into lines as it sees fit. The `verbatim` environment allows you to type the text exactly the way you want it to appear in the document.

The `verbatim` environment is the one place where $\text{\LaTeX}$ pays attention to how the input file is formatted.

What the `##!&$\_~~` is ‘‘going’’ {on}
here `\today \\\????`

... to how the input file is formatted.
`\begin{verbatim}`
What the `##!&$\_~~` is ‘‘going’’ {on}
here `\today \\\????`
`\end{verbatim}`

Each space you type produces a space in the output, and new lines are begun just where you type them. Special characters such as `\` and `{` are treated like ordinary characters in a `verbatim` environment. In fact, you can type anything in the body of a `verbatim` environment except for the fourteen-character sequence `\end{verbatim}`.

The `verbatim` environment begins on a new line of output, as does the text following it. A blank line after the `\end{verbatim}` starts a new paragraph as usual.

The `\verb` command simulates a short piece of typed text inside an ordinary paragraph. Its argument is not enclosed in braces, but by a pair of identical characters.

The `%\} {&& gnat` and `--#$ gnus` are silly.

The `\verb+%\} {&&+ gnat` and `\verb2--#$2 ...`

The argument of the first `\verb` command is contained between the two `+` characters, the argument of the second between two `2` characters. Instead of `+` or `2`, you can use any character that does not appear in the argument except a space, a letter, or a `*`.

There are also a `verbatim*` environment and a `\verb*` command. They are exactly like `verbatim` and `\verb` except that a space produces a `_` symbol instead of a blank space.

You can type `$x\_y$` or `\_x=y\_`.

... `\verb*|x = y$|` or `\verb*/ $x=y$ /`.

The `verbatim` environment and `\verb` command are inherently anomalous, since characters like `$` and `}` don't have their usual meanings. This results in the following restrictions on their use:

- A `verbatim` environment or `\verb` command may not appear within an argument of any other command. (However, they may appear inside another environment.)
- There may be no space between a `\verb` or `\verb*` command and its argument. The command and its argument must all appear on a single line of the input file.
- There may be no space between `\end` and `{` in `\end{verbatim}`.

The `verbatim` environment is for simulating typed text; it is not intended to turn $\text{\LaTeX}$ into a typewriter. If you're tempted to use it for visual formatting, don't; use the `tabbing` environment of Section 3.6.1 instead.

CHAPTER 4

Moving Information Around



L^AT_EX often has to move information from one place to another. For example, the information contained in a table of contents comes from the sectioning commands that are scattered throughout the input file. Similarly, the L^AT_EX command that generates a cross-reference to an equation must get the equation number from the `equation` environment, which may occur several sections later. This chapter describes the features that cause L^AT_EX to move information around. You also move information around when you send your document to friends and colleagues. Section 4.7 describes commands that make this easier.

L^AT_EX requires two passes over the input to move information around: one pass to find the information and a second pass to put it into the text. (It occasionally even requires a third pass.) To compile a table of contents, one pass determines the titles and starting pages of all the sections and a second pass puts this information into the table of contents. Instead of making two passes every time it is run, L^AT_EX reads your input file only once and saves the cross-referencing information in special files for use the next time. For example, if `sample2e.tex` had a command to produce a table of contents, then L^AT_EX would write the necessary information into the file `sample2e.toc`. It would use the information in the current version of `sample2e.toc` to produce the table of contents, and would write a new version of that file to produce the table of contents the next time L^AT_EX is run with `sample2e.tex` as input.

L^AT_EX's cross-referencing information is therefore always “old”, since it was gathered on a previous execution. This will be noticeable mainly when you are first writing the document—for example, a newly added section won't be listed in the table of contents. However, the last changes you make to your document will normally be minor ones that polish the prose rather than add new sections or equations. The cross-referencing information is unlikely to change the last few times you run L^AT_EX on your file, so all the cross-references will almost always be correct in the final version. In any case, if the cross-referencing is incorrect, L^AT_EX will type a warning message when it has finished. (But, L^AT_EX won't warn you about changes to table-of-contents entries.) Running it again on the same input will correct any errors.¹

An error in your input file could produce an error in one of the special cross-referencing files. The error in the cross-referencing file will not manifest itself until that file is read, the next time you run L^AT_EX. Section 8.1 explains how to recognize such an error.

4.1 The Table of Contents

A `\tableofcontents` command produces a table of contents. More precisely, it does two things:

¹If you're a computer wizard or are very good at mathematical puzzles, you may be able to create a file in which a reference to a page number always remains incorrect. The chance of that happening by accident is small.

- It causes L^AT_EX to write a new `toc` file—that is, a file with the same first name as the input file and the extension `toc`—with the information needed to generate a table of contents.
- It reads the information from the previous version of the `toc` file to produce a table of contents, complete with heading.

The commands `\listoffigures` and `\listoftables` produce a list of figures and a list of tables, respectively. They work just like the `\tableofcontents` command, except that L^AT_EX writes a file with extension `lof` when making a list of figures and a file with extension `lot` when making a list of tables.

Occasionally, you may find that you don't like the way L^AT_EX prints a table of contents or a list of figures or tables. You can fine-tune an individual entry by using the optional argument to the sectioning command or `\caption` command that generates it; see Sections C.4.1 and C.9.1. Formatting commands can also be introduced with the `\addtocontents` command described in Section C.4.3. If all else fails, you can edit the `toc`, `lof`, and `lot` files yourself. Edit these files only when preparing the final version of your document, and use a `\nofiles` command (described in Section C.11.1) to suppress the writing of new versions of the files.

4.2 Cross-References

One reason for numbering things like figures and equations is to refer the reader to them, as in: “See Figure 3 for more details.” You don't want the “3” to appear in the input file because adding another figure might make this one become Figure 4. Instead, you can assign a *key* of your choice to the figure and refer to it by that key, letting L^AT_EX translate the reference into the figure number. The key is assigned a number by the `\label` command, and the number is printed by the `\ref` command. A `\label` command appearing in ordinary text assigns to the key the number of the current sectional unit; one appearing inside a numbered environment assigns that number to the key.

Equation 4.12 in Section 2.3 below is Euler's famous result.

⋮

2.3 Early Results

Euler's equation

$$e^{i\pi} + 1 = 0 \quad (4.12)$$

combines the five most important numbers in mathematics in a single equation.

Equation~\ref{eq:euler} in
Section~\ref{sec-early} below

...

\subsection{Early Results}

\label{sec-early}

Euler's equation

\begin{equation}

$$e^{i\pi} + 1 = 0 \quad \label{eq:euler}$$

\end{equation}

combines the five most important ...

In this example, the `\label{eq:euler}` command assigns the key `eq:euler` to the equation number, and the command `\ref{eq:euler}` generates that equation number.

A key can consist of any sequence of letters, digits, or punctuation characters (Section 2.1). Upper- and lowercase letters are different, so `gnu` and `Gnu` are distinct keys. In addition to sectioning commands, the following environments also generate numbers that can be assigned to keys with a `\label` command: `equation`, `eqnarray`, `enumerate` (assigns the current item's number), `figure`, `table`, and any theorem-like environment defined with the `\newtheorem` command of Section 3.4.3.

The `\label` command can usually go in any natural place. To assign the number of a sectional unit to a key, you can put the `\label` command anywhere within the unit except within a command argument or environment in which it would assign some other number, or you can put it in the argument of the sectioning command. To refer to a particular equation in an `eqnarray` environment, put the `\label` command anywhere between the `\` or `\begin{eqnarray}` that begins the equation and the `\` or `\end{eqnarray}` that ends it. The position of the `\label` command in a figure or table is less obvious: it must go after the `\caption` command or in its argument.

Figure 17 shows the evolution of the salamander (order Urodela) from its origin in the Jurassic ...

Body of Figure

Figure 17: Newts on parade.

```
Figure~\ref{fig:newt} shows the evolution
\begin{figure}
  \centering Body of Figure
  \caption{Newts on parade.} \label{fig:newt}
\end{figure}
of the salamander...
```

(See Section 2.2.1 for an explanation of the `~` command.) A `\caption` command within its `figure` or `table` environment acts like a sectioning command within the document. Just as a document has multiple sections, a figure or table can have multiple captions.

The `\pageref` command is similar to the `\ref` command except it produces the page number of the place in the text where the corresponding `\label` command appears.

See page 42 for more details.

:

Text on page 42:

The meaning of life, the universe, and ...

See page~\pageref{‘meaning’} for more

...

The \label{‘meaning’} meaning of life, ...

A `\ref` or `\pageref` command generates only the number, so you have to type the page to produce “page 42”.

The numbers generated by `\ref` and `\pageref` were assigned to the keys the previous time you ran `LATEX` on your document. Thus, the printed output

will be incorrect if any of these numbers have changed. $\text{\LaTeX}$ will warn you if this may have happened, in which case you should run it again on the input file to make sure the cross-references are correct. (This warning will occur if any number assigned to a key by a $\text{\label}$ command has changed, even if that number is not referenced.) Each $\text{\ref}$ or $\text{\pageref}$ referring to an unknown key produces a warning message; such messages appear the first time you process any file containing these commands.

A $\text{\label}$ can appear in the argument of a sectioning or $\text{\caption}$ command, but in no other moving argument.

Using keys for cross-referencing saves you from keeping track of the actual numbers, but it requires you to remember the keys. You can produce a list of the keys by running $\text{\LaTeX}$ on the input file `lablst.tex`. (You probably do this by typing “`latex lablst`”; check your *Local Guide* to be sure.) $\text{\LaTeX}$ will then ask you to type in the name of the input file whose keys you want listed, as well as the name of the document class specified by that file’s $\text{\documentclass}$ command.

4.3 Bibliography and Citation

A citation is a cross-reference to another publication, such as a journal article, called the *source*. The modern method of citing a source is with a cross-reference to an entry in a list of sources at the end of the document. With $\text{\LaTeX}$, the citation is produced by a $\text{\cite}$ command having the citation key as its argument.

Knudson [67] showed that, in the Arctic ...

`Knudson~\cite{kn:gнус}` showed ...

You can cite multiple sources with a single $\text{\cite}$, separating the keys by commas. The $\text{\cite}$ command has an optional argument that adds a note to the citation.

Although they had disappeared from Fiji [4,15,36],
Knudson [67, pages 222–333] showed that ...

`... Fiji~\cite{tom-ix,dick:ens,harry+d},`
`Knudson~\cite[pages 222--333]{kn:gнус} ...`

A citation key can be any sequence of letters, digits, and punctuation characters, except that it may not contain a comma. As usual in $\text{\LaTeX}$, upper- and lowercase letters are considered to be different.

In the preceding examples, $\text{\LaTeX}$ has to determine that citation key `kn:gнус` corresponds to source label 67. How $\text{\LaTeX}$ does this depends on how you produce the list of sources. The best way to produce the source list is with a separate program called $\text{\BibTeX}$, described in Section 4.3.1. You can also produce it yourself, as explained in Section 4.3.2.

4.3.1 Using BibTeX

BibTeX is a separate program that produces the source list for a document, obtaining the information from a bibliographic database. To use BibTeX, you must include in your L^AT_EX input file a `\bibliography` command whose argument specifies one or more files that contain the database. The names of the database files must have the extension `bib`. For example, the command

```
\bibliography{insect,animal}
```

specifies that the source list is to be obtained from entries in the files `insect.bib` and `animal.bib`. There must be no space following the comma. Appendix B explains how to make bibliographic database files.

BibTeX creates a source list containing entries for all the citation keys specified by `\cite` commands. The data for the source list is obtained from the bibliographic database, which must have an entry for every citation key. A `\nocite` command in the L^AT_EX input file causes the specified entries to appear in the source list, but produces no output. For example, `\nocite{g:nu,g:nat}` causes BibTeX to put bibliography database entries having keys `g:nu` and `g:nat` in the source list. The command `\nocite{*}` causes all entries in the bibliographic database to be put in the source list. A `\nocite` command can go anywhere after the `\begin{document}` command, but it is fragile.

To use BibTeX, your L^AT_EX input file must contain a `\bibliographystyle` command. This command specifies the *bibliography style*, which determines the format of the source list. For example, the command

```
\bibliographystyle{plain}
```

specifies that entries should be formatted as specified by the `plain` bibliography style. The `\bibliographystyle` command can go anywhere after the `\begin{document}` command. L^AT_EX's standard bibliography styles are:

plain Formatted more or less as suggested by van Leunen in *A Handbook for Scholars* [7]. Entries are sorted alphabetically and are labeled with numbers.

unsrt The same as `plain` except that entries appear in the order of their first citation.

alpha The same as `plain` except that source labels like "Knu66", formed from the author's name and the year of publication, are used.

abbrv The same as `plain` except that entries are more compact because first names, month names, and journal names are abbreviated.

Dozens of other bibliography styles exist, including ones that produce source lists in the formats used by a number of scientific journals. Consult the L^AT_EX

Companion and the *Local Guide* to find out what styles are available. Documentation for the `BIBTEX` program explains how to create your own bibliography style.

The source list is normally formatted in what van Leunen calls a *compressed* style. The `openbib` document-class option causes it to be formatted in an *open* style. (Document-class options are specified by the `\documentclass` command; see Section 2.2.2.)

Once you've created an input file containing the appropriate `LATEX` commands, you perform the following sequence of steps to produce the final output:

- Run `LATEX` on the input file, which I assume is called `myfile.tex`. `LATEX` will complain that all your citations are undefined, since there is no source list yet.
- Run `BIBTEX` by typing something like `bibtex myfile`. (Consult your *Local Guide* to find out what you actually type.) `BIBTEX` will generate the file `myfile.bbl` containing `LATEX` commands to produce the source list.
- Run `LATEX` again on `myfile.tex`. `LATEX`'s output will now contain the source list. However, `LATEX` will still complain that your citations are undefined, since the output produced by a `\cite` command is based on information obtained from the source list the last time `LATEX` was run on the file.
- Run `LATEX` one more time on `myfile.tex`.

If you add or remove a citation, you will have to go through this whole procedure again to get the citation labels and source list right. But they don't have to be right while you're writing, so you needn't do this very often.

`BIBTEX` almost always produces a perfectly fine source list. However, it is only a computer program, so you may occasionally encounter a source that it does not handle properly. When this happens, you can usually correct the problem by modifying the bibliographic database—perhaps creating a special database entry just for this document. As a last resort, you can edit the `bbl` file that `BIBTEX` generated. (Of course, you should do this only when you are producing the final output.)

4.3.2 Doing It Yourself

A source list is created with the `thebibliography` environment, which is like the `enumerate` environment described in Section 2.2.4 except that:

- Each list item is begun with a `\bibitem` command whose argument is the citation key. (The `\bibitem` and `\cite` commands work much like the `\label` and `\ref` commands of Section 4.2.)

- The `thebibliography` environment has an argument that should be a piece of text the same width as or slightly wider than the widest item label in the source list.

Knudson [67] showed that, in the Arctic ...	<code>Knudson~\cite{kn:gnus} showed ...</code>
⋮	<code>...</code>
References	<code>\begin{thebibliography}{99}</code>
⋮	<code>...</code>
⋮	<code>\bibitem{kn:gnus} D. E. Knudson.</code>
[67] D. E. Knudson. <i>1966 World Gnus Almanac</i> .	<code>\emph{1966 World Gnus Almanac.}</code>
Permafrost Press, Novosibirsk.	<code>...</code>
	<code>\end{thebibliography}</code>

In most type styles, “99” is at least as wide as all other two-digit numbers.

Instead of using numbers, you can choose your own labels for the sources by giving an optional argument to the `\bibitem` command.

Knudson [Knud 66] showed that, in the Arctic ...	<code>Knudson~\cite{kn:gnus} showed ...</code>
⋮	<code>...</code>
⋮	<code>\begin{thebibliography}{Dillo 83}</code>
References	<code>...</code>
⋮	<code>\bibitem[Knud 66]{kn:gnus} D. E. Knudson.</code>
⋮	<code>\emph{1966 World Gnus Almanac.}</code>
[Knud 66] D. E. Knudson. <i>1966 World Gnus Almanac</i> .	<code>...</code>
Permafrost Press, Novosibirsk.	<code>\end{thebibliography}</code>

In this example, “[Dillo 83]” should be the longest label. The optional argument of `\bibitem` is a moving argument.

As in any kind of cross-reference, citations are based upon the information gathered the previous time $\text{\LaTeX}$ was run on the file. So, when you change the source list, you have to run $\text{\LaTeX}$ two more times to change the citations.

4.4 Splitting Your Input

A large document requires a lot of input. Rather than putting the whole input in a single large file, you may find it more convenient to split the input into several smaller files. Regardless of how many separate files you use, there is one that is the *root* file; it is the one whose name you type when you run $\text{\LaTeX}$.

The `\input` command provides the simplest way to split your input into several files. The command `\input{gnu}` in the root file causes $\text{\LaTeX}$ to insert the contents of the file `gnu.tex` right at the current spot in your manuscript—just as if the `\input{gnu}` command were removed from the root file and replaced by the contents of the file `gnu.tex`. (However, the input files are not changed.) The file `gnu.tex` may also contain an `\input` command, calling another file that may have its own `\input` commands, and so on.

Besides splitting your input into conveniently sized chunks, the `\input` command also makes it easy to use the same input in different documents. While text is seldom recycled in this way, you might want to reuse declarations. You can keep a file containing declarations that are used in all your documents, such as the definitions of commands and environments for your own logical structures (Section 3.4). You can even begin your root file with an `\input` command and put the `\documentclass` command in your declarations file.

Another reason for splitting the input into separate files is to run $\text{\LaTeX}$ on only part of the document so, when you make changes, only the parts that have changed need to be processed. For this, you must use the `\include` command instead of `\input`. The two commands are similar in that `\include{gnu}` also specifies that the contents of the file `gnu.tex` should be inserted in its place. However, with the `\include` command, you can tell $\text{\LaTeX}$ either to insert the file or to omit it and process all succeeding text as if the file had been inserted, numbering pages, sections, equations, etc., as if the omitted file's text had been included.

To run $\text{\LaTeX}$ on only part of the document, the preamble must contain an `\includeonly` command whose argument is a list of files (first names only). The file specified by an `\include` command is processed only if it appears in the argument of the `\includeonly` command. Thus, if the preamble contains the command

```
\includeonly{gnu,gnat,gnash}
```

then an `\include{gnat}` command causes the file `gnat.tex` to be included, while the command `\include{rmdlo}` causes $\text{\LaTeX}$ *not* to include the file `rmdlo.tex`, but to process the text following it as if the file had been included. More precisely, it causes $\text{\LaTeX}$ to process the succeeding text under the assumption that the omitted file is exactly the same as it was the last time it was included. $\text{\LaTeX}$ does not read an omitted file and is unaware of any changes made to the file since it was last included.

The entire root file is always processed. If the preamble does not contain an `\includeonly` command, then every `\include` command inserts its file. The command `\includeonly{}` (with a null argument) instructs $\text{\LaTeX}$ to omit all `\include'd` files. An `\include` can appear only after the `\begin{document}` command.

The `\include` command has one feature that limits its usefulness: the included text always starts a new page, as does the text immediately following the `\include` command. It therefore works right only if the `\include'd` text and the text following it should begin on a new page—for example, if it consists of one or more complete chapters. While writing a chapter, you might want to split it into smaller files with `\include` commands. When you've finished writing that chapter, you can combine those files into a single one.

Another difficulty with the `\include` mechanism is that changing the docu-

ment may require reprocessing some unchanged `\include`'d files in order to get the correct numbering of pages, sections, etc. When skipping an `\include`'d file, the numbering in the succeeding text is based upon the numbering in the file's text the last time it was processed. Suppose that the root file contains the commands

```
\include{gnu}  
\chapter{Armadillo}
```

and an `\includeonly` in the preamble causes the `\include` command to omit file `gnu.tex`. If the text in `gnu.tex` ended in Chapter 5 on page 56 the last time it was processed, even if you've added seven more chapters and sixty pages of text before the `\include` command since then, the `\chapter` command will produce Chapter 6 starting on page 57. In general, to make sure everything is numbered correctly, you must reprocess an `\include`'d file if a change to the preceding text changes the numbering in the text produced by that file.

When writing a large document, you should probably make each chapter a separate `\include`'d file. (You may find it convenient to enter the `\includeonly` command from the terminal, using the `\typein` command described in Section 4.6.) Process each file separately as you write or revise it, and don't worry about numbers not matching properly. If the inconsistent numbering gets too confusing, generate a coherent version by processing all the files at once. (You can do this by removing the `\includeonly` command before running $\LaTeX$.) When you've finished making changes, run $\LaTeX$ on the entire document. You can then produce the final output either all at once by running $\LaTeX$ again on the entire document, or a few chapters at a time by using the `\includeonly` command.

4.5 Making an Index or Glossary

There are two steps in making an index or glossary: gathering the information that goes in it, and generating the $\LaTeX$ input to produce it. Section 4.5.1 describes the first step. The easiest way to perform the second step is with the *MakeIndex* program, described in Appendix A. Section 4.5.2 describes how to produce an index or glossary if you don't use *MakeIndex*.

4.5.1 Compiling the Entries

Compiling an index or a glossary is not easy, but $\LaTeX$ can help by writing the necessary information onto a special file. If the root file is named `myfile.tex`, index information is written on the "idx file" `myfile.idx`. $\LaTeX$ makes an `idx` file if the preamble contains a `\makeindex` command. The information on the file is written by `\index` commands; the command `\index{gnu}` appearing with the text for page 42 causes $\LaTeX$ to write

```
\indexentry{gnu}{42}
```

on the `idx` file. If there is no `\makeindex` command, the `\index` command does nothing. The `showidx` package causes L^AT_EX to print the arguments of all index commands in the margin.

The `\index` command produces no text, so you type

```
A gnat\index{gnat} with gnarled wings gnashed ...
```

to index this instance of “gnat”. It’s best to put the `\index` command next to the word it references, with no space between them; this keeps the page number from being off by one if the word ends or begins a page. I find it best to put index entries on a separate line, as in

```
When in the Course of
  \index{human events}%
  \index{events, human}%
human events, it becomes necessary for one people
```

This use of the `%` character is explained on page 19.

The procedure for making a glossary is completely analogous. In place of `\index` there is a `\glossary` command. The `\makeglossary` command produces a file with the extension `glo` that is similar to the `idx` file except with `\glossaryentry` entries instead of `\indexentry` entries.

The argument of `\index` or `\glossary` can contain any characters, including special characters like `\` and `$`. However, curly braces must be properly balanced, each `{` having a matching `}`. The `\index` and `\glossary` commands are fragile. Moreover, an `\index` or `\glossary` command should not appear in the argument of any other command if its own argument contains any of L^AT_EX’s ten special characters (Section 2.1).

4.5.2 Producing an Index or Glossary by Yourself

If you don’t use the *MakeIndex* program, you can use the `theindex` environment to produce an index in two-column format. Each main index entry is begun by an `\item` command. A subentry is begun with `\subitem`, and a subsubentry is begun with `\subsubitem`. Blank lines between entries are ignored. An extra vertical space is produced by the `\indexspace` command, which is usually put before the first entry that starts with a new letter.

gnats 13, 97	<code>\item gnats 13, 97</code>
gnus 24, 37, 233	<code>\item gnus 24, 37, 233</code>
bad, 39, 236	<code> \subitem bad, 39, 236</code>
very, 235	<code> \subsubitem very, 235</code>
good, 38, 234	<code> \subitem good, 38, 234</code>
	<code>\indexspace</code>
harmadillo 99, 144	<code>\item harmadillo 99, 144</code>

There is no environment expressly for glossaries. However, the description environment of Section 2.2.4 may be useful.

4.6 Keyboard Input and Screen Output

When creating a large document, it's often helpful to leave a reminder to yourself in the input file—for example, to note a paragraph that needs rewriting. The use of the % character for putting comments into the text is described in Section 2.2.1. However, a passive comment is easy to overlook, so L^AT_EX provides the `\typeout` command for printing messages on the terminal. In the examples in this section, the left column shows what is produced on the terminal by the input in the right column; the oval represents the terminal.

Don't forget to revise this!

`\typeout{Don't forget to    revise this!}`

Remember that everything L^AT_EX writes on the terminal is also put in the log file.

It is sometimes useful to type input to L^AT_EX directly from your keyboard—for example, to enter an `\includeonly` command. This is done with a `\typein` command, such as the following:

Enter 'includeonly', boss!

`\typein {Enter 'includeonly', boss!}`

`\@typein=`

When this appears on your terminal, L^AT_EX is waiting for you to enter a line of input, ended by pressing the *return* key. L^AT_EX then processes what you typed just as if it had appeared in the input file in place of the `\typein` command.

The `\typein` command has an optional first argument, which must be a command name. When this optional argument is given, instead of processing your typed input at that point, L^AT_EX defines the specified command to be equivalent to the text that you have typed.

Enter lover's name.

`\typein [\lover]{Enter lover's name.}`
I love \lover\ very much.

`\lover=`

Typing `Chris` and pressing the return key causes the `\typein` command to define the command `\lover` to be equivalent to `Chris`—just like the `\newcommand` or `\renewcommand` commands of Section 3.4. Thus, the input following this `\typein` command would produce

I love Chris very much.

The argument of the `\typeout` or `\typein` command is a moving argument. Both of these commands are fragile.

4.7 Sending Your Document

Today, you are likely to send a document electronically—by e-mail or on a diskette—rather than on paper. Putting a file in an e-mail message or on a diskette is no problem. However, to process your document, $\text{\LaTeX}$ must read a number of files in addition to the main input file. Some files, such as the `toc` file (Section 4.1), are generated by $\text{\LaTeX}$ itself. The rest must be sent if the recipient does not already have them. These files include the `bb1` file (Section 4.3.1), files required by any nonstandard packages the document uses, and files that are read by `\input` or `\include` commands. You can combine all these files into a single $\text{\LaTeX}$ input file by using the `filecontents` environment. Instead of sending the file `name.tex` separately, put the environment

```
\begin{filecontents}{name.tex}
contents of file
\end{filecontents}
```

at the beginning of your input file. When $\text{\LaTeX}$ is run on this input file, it writes the file `name.tex` if no file by that name already exists. If such a file does exist, $\text{\LaTeX}$ prints a warning message. You can put any number of `filecontents` environments in an input file, but they must all precede the `\documentclass` command.

To find out what files you need to send, put a `\listfiles` command in the preamble. $\text{\LaTeX}$ will then print out a list of the files it reads when processing the document. The list will not include files generated by $\text{\LaTeX}$, and it will identify standard files that are always present on a computer that runs $\text{\LaTeX}$. However, the list may not tell you in what directories the files are. The terminal output might include complete file names. (As explained in Section 8.1, when $\text{\LaTeX}$ starts to read a file, it writes the file's name on the terminal and in the log file.) You can also consult the *Local Guide* to find out what directories contain the files read by packages.

When sending files by e-mail, don't forget about the problem of lines beginning with `From_` that is discussed in Section 2.4.

CHAPTER 5

Other Document Classes



5.1 Books

Books differ from reports mainly in their front and back matter. The front matter of a book usually includes a half-title page, a main title page, a copyright page, a preface or foreword, and a table of contents. It may also contain acknowledgements, a dedication, a list of figures, a list of other books in the same series, and so on. The back matter usually includes an index and may contain an afterword, acknowledgements, a bibliography, a colophon, etc.

The `book` document class does not attempt to provide commands for all the logical structures that could appear in a book's front and back matter. It is just the same as the `report` class except for the differences described below. Individual publishers might have packages with additional commands for the particular structures they want in their books.

The front matter, main matter (the main body of the book, including appendices), and back matter are begun with the three commands `\frontmatter`, `\mainmatter`, and `\backmatter`, respectively. In the standard `book` class, front matter pages are numbered with roman numerals; main and back matter pages are numbered with arabic numerals. In the front and back matter, the `\chapter` command does not produce a chapter number, but it does make a table of contents entry. Thus, you can begin a preface with

```
\chapter{Preface}
```

Only the `*` forms of other sectioning commands should be used in the front and back matter (see Section C.4.1).

Two-sided printing is the norm for books, so the `twoside` option is the default in the `book` class. Another default option is `openright`, which causes new chapters to begin on a right-hand page. The contrary option, `openany`, is the default for the `report` class.

A book can have more than one title page, and each title page can contain a variety of information besides the title and author—for example, the publisher, series, and illustrator. The `\maketitle` command is therefore of little use in a book.

You will probably have to do a considerable amount of customizing of the style parameters for a book—especially of the page-style parameters, described in Section C.5.3. The time this takes should be infinitesimal compared with the time you spend writing the book.

5.2 Slides

The `slides` document class is used for making slides. Slides are usually printed or photocopied onto transparencies for projection on a screen.


Producing good slides requires visual formatting, which means that L^AT_EX is not well suited for the task. Here are a few reasons why you may want to use L^AT_EX anyway:

- Your slides are based on material from a L^AT_EX document.
- Your slides have a lot of mathematical formulas.
- You don't make slides often enough to bother learning how to use another system.

The `slides` document class's default fonts were specially designed to be easy to read from a distance. To my knowledge, no other system makes slides that are so readable. The `slides` class's fonts are much larger than the usual ones; `\normalsize` produces roughly the same size characters as `\LARGE` in other document classes (Section 6.7.1). Moreover, the roman family is similar to the ordinary sans serif family. The only type families generally available are roman and typewriter, and the only type shapes are upright and italic. (See Section 3.1.) The `\emph` command works as usual.

5.2.1 Slides and Overlays

An individual slide is produced with a `slide` environment:




```
\begin{slide}
  \begin{center}
    GNATS and GNUS
  \end{center}

  Gnats are very small and have a bad
  temper.

  Gnus are big.
\end{slide}
```

The text appearing on a slide is produced with ordinary L^AT_EX commands. Any commands that make sense for slides can be used. Commands that *don't* make sense include sectioning commands, `figure` and `table` environments, and page-breaking commands. The latter make no sense in a slide because each slide must fit on a single page. To make colored slides, use the `color` package described in Section 7.3.


The `overlay` environment is used for an overlay—a slide that is meant to be put on top of another slide. It is the same as the `slide` environment except for the numbering; the first overlay following slide number 3 is numbered “3-a”, the second one is numbered “3-b”, and so on. The best way to get the text on the slide and the overlay to line up properly is to have all the text on both of them and make text that isn’t supposed to appear invisible by coloring it white (Section 7.3).



```
\begin{slide}
  \begin{center}
    GNATS \textcolor{white}{and GNUS}
  \end{center}

  Gnats are very small
  and have a bad temper.

  \textcolor{white}{Gnus are big.}
\end{slide}
```



```
\begin{overlay}
  \begin{center}
    \textcolor{white}{GNATS} and GNUS
  \end{center}

  \textcolor{white}{Gnats are very small
    and have a bad temper.}


  Gnus are big.
\end{overlay}
```

Superimposing this slide and overlay yields the preceding slide (plus an extra “a” next to the slide number). If the `color` package is not available on your computer, you can use the commands of Section 6.4.2 to produce the blank spaces.

5.2.2 Notes

When giving a lecture, it helps if you put notes to yourself in with the slides to remind you of what to say. The `note` environment produces a one-page note. Notes that follow slide number 3 are numbered “3-1”, “3-2”, etc. I always make a note to accompany each slide. (You can print the slides and notes separately by using the `\onlyslides` and `\onlynotes` commands described below.)

A good lecturer plans a talk carefully and does not run out of time. The `slides` document class’s `clock` option helps you keep track of time during your lecture. Right before or after each slide, put an `\addtime` command giving the number of seconds you should spend on that slide. The total amount of time (in minutes) that you should have taken so far will be printed at the bottom of each note.



```
\documentclass[clock]{slides}
...
\addtime{180} % Slide 1: 3 minutes
...
\addtime{150} % Slide 2: 2-1/2 minutes
...
\addtime{120} % Slide 3: 2 minutes

\begin{note}
Don't forget to swat those gnats.
\end{note}
```

L^AT_EX will also type out on your terminal the total elapsed time at the end of the document.

You can reset the elapsed time with the `\settime` command. The command `\settime{120}` sets the total elapsed time to 120 seconds (2 minutes). Do not put an `\addtime` or `\resettime` command inside a `slide`, `overlay`, or `note` environment.

5.2.3 Printing Only Some Slides and Notes

For making corrections, it’s convenient to generate only some of the slides and notes from your input file. The command

```
\onlyslides{4,7-13,23}
```

in the preamble will cause L^AT_EX to generate only slides numbered 4, 7–13 (inclusive), and 23, plus all of their overlays. The slide numbers in the argument

must be in ascending order, and can include nonexistent slides—for example, you can type

```
\onlyslides{10-9999}
```

to produce all but the first nine slides. The argument of the `\onlyslides` command must be nonempty.

There is also an analogous `\onlynotes` command to generate a subset of the notes. Notes numbered 11-1, 11-2, etc. will all be generated by specifying page 11 in the argument of the `\onlynotes` command. If the input file has an `\onlyslides` command but no `\onlynotes` command, then no notes are produced, and vice versa. Including both an `\onlyslides` and an `\onlynotes` command has the expected effect of producing only the specified slides and notes.

5.2.4 Other Text

Your input file can include text that appears outside a `slide`, `overlay`, or `note` environment. Such other text is formatted like a slide, but without a slide number. It can be used to make a title page. This other text is always printed, even when an `\onlyslides` or `\onlynotes` command is given.

Text outside a slide or note differs from text inside one only in that page-breaking commands are allowed. Use a `\pagebreak` command if you want to tell $\text{\LaTeX}$ where to start a new page in the middle of the text.

5.3 Letters

For making letters—the kind that are put in an envelope and mailed— $\text{\LaTeX}$ provides the `letter` document class. To use this class, begin your input file with a `\documentclass` command having `letter` as its main (nonoptional) argument (Section 2.2.2).

You can make any number of letters with a single input file. Your name and address, which are likely to be the same for all letters, are specified by declarations. The return address is declared by an `\address` command, with multiple output lines separated by `\\` commands.

```
\address{1234 Ave.\ of the Armadillos\\
        Gnu York, G.Y. 56789}
```

The `\signature` command declares your name, as it appears at the end of the letter, with the usual `\\` commands separating multiple lines.

```
\signature{R. (Ma) Dillo \\ Director of Cuisine}
```

These declarations are usually put in the preamble, but they are ordinary declarations with the customary scoping rules and can appear anywhere in the document.

Each letter is produced by a separate `letter` environment, having the name and address of the recipient as its argument. The argument of the `letter` environment is a moving argument. The letter itself begins with an `\opening` command that generates the salutation.

1234 Ave. of the Armadillos
Gnu York, G.Y. 56789

July 4, 1996

Dr. G. Nathaniel Picking
Acme Exterminators
33 Swat Street
Hometown, Illinois 62301

Dear Nat,

I'm afraid that the armadillo problem is still with us. I did everything ...

The return address is determined by the `\address` declaration; $\text{\LaTeX}$ supplies the date. An `\address` and/or `\signature` command that applies just to this letter can be put between the `\begin{letter}` and the `\opening` command.

The main body of the letter is ordinary $\text{\LaTeX}$ input, but commands like `\section` that make no sense in a letter should not be used. The letter closes with a `\closing` command.

... and I hope you can get rid of the nasty beasts this time.

Best regards,

R. (Ma) Dillo
Director of Cuisine

The name comes from the `\signature` declaration.

The `\cc` command can be used after the closing to list the names of people to whom you are sending copies.

cc: Bill Clinton
George Bush

There's a similar `\encl` command for a list of enclosures.

```
\begin{letter}{Dr.\ G. Nathaniel Picking \\
Acme Exterminators\\ 33 Swat Street \\
Hometown, Illinois 62301}
```

```
\opening{Dear Nat,}
```

```
I'm afraid that the armadillo problem
is still with us. I did everything
...
```

... and I hope you can get rid of the nasty beasts this time.

```
\closing{Best regards,}
```

```
\cc {Bill Clinton \\ George Bush}
```

Additional text after the closing must be preceded by a `\ps` command. This command generates no text—you'll have to type the "P.S." yourself—but is needed to format the additional text correctly.

You can change the date on your letters by using `\renewcommand` (Section 3.4.1) to redefine `\today`. Put the `\renewcommand` in the preamble to change the date on all letters; put it right before the `\opening` command to change the date on a single letter.

1234 Ave. of the Armadillos
Gnu York, G.Y. 56789

Thursday, 15842 B.C.

Mr. A. Oop
Kingdom of Moo

Dear Mr. Oop:

In your last shipment of stegosaur steaks, ...

```
\begin{letter}{Mr.\ A. Oop \\
  Kingdom of Moo}
```

```
\renewcommand{\today}{Thursday, 15842 B.C.}
```

```
\opening{Dear Mr.\ Oop:}
```

```
In your last shipment of stegosaur steaks,
...
```

Redefining `\today` will not alter the postmark printed on the envelope by the post office.

A `\makelabels` command in the preamble will cause $\text{\LaTeX}$ to print a list of mailing labels, one for each `letter` environment, in a format suitable for xerographic copying onto "peel-off" labels. A mailing label without a corresponding letter is produced by an empty `letter` environment—one with nothing between the argument and the `\end{letter}` command.

There may be other features for making letters—especially if you are using $\text{\LaTeX}$ at a company or university. For example, you may be able to format letters for copying onto the company letterhead. Consult the *Local Guide* for more information.

CHAPTER 6

Designing It Yourself



The preceding chapters describe L^AT_EX commands and environments for specifying a document's logical structure. This chapter explains how to specify its visual appearance. Before reading it, you should review the discussion in Section 1.4 of the dangers of visual design. Commands specifying the visual appearance of the document are usually confined to the preamble, either as style declarations or in the definitions of commands and environments for specifying logical structures. The notable exceptions are the line- and page-breaking commands of Section 6.2 and the picture-drawing commands of Section 7.1.

6.1 Document and Page Styles

6.1.1 Document-Class Options

The style of the document can be changed by using the optional argument of the `\documentclass` command to specify style options. The `11pt`, `12pt`, `twoside`, and `twocolumn` options are described in Section 2.2.2. Three other standard options are:

titlepage Causes the `\maketitle` command to generate a separate title page and the `abstract` environment to make a separate page for the abstract. This option is the default for the `report` document class.

leqno Causes the formula numbers produced by the `equation` and `eqnarray` environments to appear on the left instead of the right.

fleqn Causes formulas to be aligned on the left, a fixed distance from the left margin, instead of being centered.

A complete list of the standard options appears in Section C.5.1. The *Local Guide* will tell you if there are any other options available on your computer.

The `twocolumn` option is used for a document that consists mostly of double-column pages. It sets various style parameters, such as the amount of paragraph indentation, to values appropriate for such pages. You may want double-column pages for just part of the document, such as a glossary. The `\twocolumn` declaration starts a new page and begins producing two-column output. It does not change any style parameters except the ones required to produce two-column output. The inverse `\onecolumn` declaration starts a new page and begins producing single-column output.

In books, it is conventional for the height of the text to be the same on all full pages. The `\flushbottom` declaration makes all text pages the same height, adding extra vertical space when necessary to fill out the page. The `\raggedbottom` declaration has the opposite effect, letting the height of the text vary a bit from page to page. The default is `\raggedbottom` except when the `twoside` option is in effect. You can change the default by putting the appropriate declaration in the preamble.

6.1.2 Page Styles

A page of output consists of three units: the *head*, the *body*, and the *foot*. In most pages of this book, the head contains a page number, a chapter or section title, and a horizontal line, while the foot is empty; but in the table of contents and the preface, the page head is empty and the foot contains the page number. The body consists of everything between the head and foot: the main text, footnotes, figures, and tables.

The information in the head and foot, which usually includes a page number, helps the reader find his way around the document. You can specify arabic page numbers with a `\pagenumbering{arabic}` command and roman numerals with a `\pagenumbering{roman}` command, the default being arabic numbers. The `\pagenumbering` declaration resets the page number to one, starting with the current page. To begin a document with pages i, ii, etc. and have the first chapter start with page 1, put `\pagenumbering{roman}` anywhere before the beginning of the text and `\pagenumbering{arabic}` right after the first `\chapter` command.

Page headings may contain additional information to help the reader. They are most useful in two-sided printing, since headings on the two facing pages convey more information than the single heading visible with one-sided printing. Page headings are generally not useful in a short document, where they tend to be distracting rather than helpful.

The *page style* determines what goes into the head and foot; it is specified with a `\pagestyle` declaration having the page style's name as its argument. There are four standard page styles:

plain The page number is in the foot and the head is empty. It is the default page style for the `article` and `report` document classes.

empty The head and foot are both empty. L^AT_EX still assigns each page a number, but the number is not printed.

headings The page number and other information, determined by the document style, is put in the head; the foot is empty.

myheadings Similar to the `headings` page style, except you specify the "other information" that goes in the head, using the `\markboth` and `\markright` commands described below.

The `\pagestyle` declaration obeys the normal scoping rules. What goes into a page's head and foot is determined by the page style in effect at the end of the page, so the `\pagestyle` command usually comes after a command like `\chapter` that begins a new page.

The `\thispagestyle` command is like `\pagestyle` except it affects only the current page. Some commands, such as `\chapter`, change the style of the current

page. These changes can be overridden with a subsequent `\thispagestyle` command.

The contents of the page headings in the `headings` and `myheadings` styles are set by the following commands:

```
\markboth{left_head}{right_head}
\markright{right_head}
```

The *left_head* and *right_head* arguments specify the information to go in the page heads of left-hand and right-hand pages, respectively. In two-sided printing, specified with the `twoside` document-class option, the even-numbered pages are the left-hand ones and the odd-numbered pages are the right-hand ones. In one-sided printing, all pages are considered to be right-hand ones.

In the `headings` page style, the sectioning commands choose the headings for you; Section C.5.3 explains how to use `\markboth` and `\markright` to override their choices. In the `myheadings` option, you must use these commands to set the headings yourself. The arguments of `\markboth` and `\markright` are processed in LR mode; they are moving arguments.

6.1.3 The Title Page and Abstract

The `\maketitle` command produces a title page when the `titlepage` document-class option is in effect; it is described in Sections 2.2.2 and C.5.4. You can also create your own title page with the `titlepage` environment. This environment creates a page with the `empty` page style, so it has no printed page number or heading. It causes the following page to be numbered 1.

You are completely responsible for what appears on a title page made with the `titlepage` environment. The following commands and environments are useful in formatting a title page: the type-size-changing commands of Section 6.7.1, the type-style-changing commands of Section 3.1, and the `center` environment of Section 6.5. Recall also that the `\today` command, described in Section 2.2.1, generates the date. You will probably produce several versions of your document, so it's important to include a date on the title page.

An abstract is made with the `abstract` environment.

Abstract

The mating habits of insects are quite different from those of large mammals.

```
\begin{abstract}
The mating habits of insects are quite
different from those of large mammals.
\end{abstract}
```

The abstract is placed on a separate page if the `titlepage` document-class option is in effect; otherwise, it acts like an ordinary displayed-paragraph environment.

6.1.4 Customizing the Style

If you don't like the style of the output produced by $\text{\LaTeX}$ with the standard style options, you should check the *$\text{\LaTeX}$ Companion* and the *Local Guide* to see if there are other options available. If there aren't, you must change the style of your document yourself. Changing the style means changing the way the standard structures such as paragraphs and itemized lists are formatted, not creating new structures. Section 3.4 describes how to define new logical structures.

Before changing your document's style, remember that many authors make elementary errors when they try to design their own documents. The only way to avoid these errors is by consulting a trained typographic designer or reading about typographic design. All I can do here is warn you against the very common mistake of making lines that are too wide to read easily—a mistake you won't make if you follow this suggestion: *Use lines that contain no more than 75 characters, including punctuation and spaces.*

The style of a particular document can be customized by adding declarations to its preamble. If the same style modifications are used in several documents, it is more convenient to put them in a separate package. A package is created by writing the appropriate declarations in a `sty` file—a file whose first name is the package name and whose extension is `sty`. For example, to define a package named `vacation`, you would create the file `vacation.sty`. The command `\usepackage{vacation}` would then cause $\text{\LaTeX}$ to read the file `vacation.sty`.

When reading a package's `sty` file, $\text{\TeX}$ regards an `@` character as a letter, so it can be part of a command name like `\@listi`. Such a command name cannot be used in your document, since $\text{\TeX}$ would interpret it as the command `\@` followed by the text characters `listi`. Many of $\text{\LaTeX}$'s internal commands have an `@` in their name to prevent their accidental use within the document; these include some parameters described in Appendix C that you may want to change.

The simplest way to modify a document's style is by changing parameters such as the ones that control the height and width of the text on the page. $\text{\LaTeX}$'s style parameters are described in this chapter and in Appendix C. Other modifications require redefining $\text{\LaTeX}$ commands. For example, if you want to change the style of chapter headings, you will have to redefine the `\chapter` command. If the change is complicated—for example, if you want the chapter heading to list the titles of all preceding chapters—then you will need to learn advanced $\text{\TeX}$ commands. However, it isn't hard to figure out how to make most of the changes you are likely to want. To illustrate the process, I will now describe how you would make a typical style change: printing chapter titles in a bold sans serif type style, rather than in the standard bold roman style.

You have to change the definition of `\chapter`, so the first problem is finding that definition. Commands that exist in all document classes are usually *preloaded*. The file `source2e.tex` lists the names of the files in which the defi-

nitions of preloaded commands can be found. (Consult the *Local Guide* to find out in what directory these files are.) Commands like `\chapter` that exist only in some document classes or are defined by a package are not preloaded. The definitions of these commands are in files read by L^AT_EX when it processes your document. Section 4.7 explains how to find out what files L^AT_EX reads.

For this example, I assume that your document uses the `report` document class. You will find that L^AT_EX reads the file `report.cls`. Searching this file for “`\chapter`”, you will come across

```
\newcommand\chapter{\ifopenright\cleardoublepage\else...
                                \thispagestyle{plain}%
                                \global\@topnum\z@
                                \@afterindentfalse
                                \secdef\@chapter\@schapter}
```

This is where the `\chapter` command is defined. (Macho T_EX programmers sometimes remove the braces around the first argument of `\newcommand`; don't do it yourself.) Looking at this definition, it's not hard to guess that the chapter heading is produced by `\@chapter` or `\@schapter`. Immediately below the definition of `\chapter` is

```
\def\@chapter[#1]#2{...
```

This is where `\@chapter` is defined. (Macho T_EX programmers also use the T_EX command `\def` to define commands; don't you do it.) Examining this definition will lead you to suspect that the heading is produced by the `\@makechapterhead` command. The definition of `\@makechapterhead` contains two `\bfseries` commands. An obvious guess is that adding `\sfseries` commands right before or after these `\bfseries` commands will produce bold sans serif chapter headings. So, you will create a file named `sfchap.sty` containing the modified definition of `\@makechapterhead`, add a `\usepackage{sfchap}` command to the preamble of your document, and run L^AT_EX. You will then discover that you have guessed right; L^AT_EX has produced the bold sans serif headings you wanted.

This detective work was good practice, but there's a way to avoid much of it. Comments at the beginning of `report.cls` indicate that this file was generated from a source file named `classes.dtx`. (The file `source2e.tex` also directs you to `classes.dtx`.) A `dtx` file contains comments and additional formatting commands. You can run a `dtx` file through L^AT_EX to produce a printed version, or you can just read the `dtx` file itself. The file `classes.dtx` reveals that the `\@schapter` command prints unnumbered chapter headings. (Such headings are produced by the `\chapter*` command described in Section C.4.1.) Aided by the comments, you should now be able to figure out how to change the way unnumbered chapter headings are printed.

This example shows how to modify a command; modifying an environment is similar. To find its definition, you need to know that some environments are

defined with $\text{\TeX}$'s `\def` command instead of `\newenvironment`. For example, the `equation` environment is defined by defining `\equation`, which is executed by the `\begin{equation}` command, and `\endequation`, which is executed by `\end{equation}`.

Remember that before creating your own package of style changes, you should check the *L^AT_EX Companion* and the *Local Guide* to see if someone has already created a document class or package that does what you want.

6.2 Line and Page Breaking

$\text{\TeX}$ usually does a good job of breaking text into lines and pages, but it sometimes needs help. Don't worry about line and page breaks until you prepare the final version. Most of the bad breaks that appear in early drafts will disappear as you change the text. Many $\text{\TeX}$ users waste time formatting when they should be writing. **Don't worry about line and page breaks until you prepare the absolutely final version.**

6.2.1 Line Breaking

Let's return to the line-breaking problem that we inserted into the `sample2e` input file in Section 2.3. Recall that it produced the following warning message:

```
Overfull \hbox (10.51814pt too wide) in paragraph at lines 195--200
[]\OT1/cmr/m/n/10 Mathematical for-mu-las may also be dis-played. A dis-played
for-mula is gnomonly
```

$\text{\TeX}$ could not find a good place to break the line and left the word “gnomonly” extending past the right margin. The first line of this warning message states that the output line extends 10.51814 points past the right margin—a point is about $1/72^{\text{nd}}$ of an inch—and is in the paragraph generated by lines 195 through 200 of the input file. The next part of the message shows the input that produced the offending line, except $\text{\TeX}$ has inserted a “-” character every place that it's willing to hyphenate a word. The `draft` document-class option causes $\text{\TeX}$ to put a black box next to the extra-long line, making it easy to find.

$\text{\TeX}$ is quite good at hyphenating words; an English-language version never¹ incorrectly hyphenates an English word and usually finds all correct possibilities. However, it does miss some. For example, it does not know how to hyphenate the word *gnomonly* (which isn't a very gnomonly used word), nor can it hyphenate *gnomon*.

A `\-` command tells $\text{\TeX}$ that it is allowed to hyphenate at that point. We could correct our sample hyphenation problem by changing `gnomonly` to `gno\-\monly`, allowing $\text{\TeX}$ to break the line after *gno*. However, it's better to change it to `gno\-\mon\-\ly`, which also allows $\text{\TeX}$ to break right before the *ly*.

¹Well, hardly ever.

While T_EX will still break this particular sample line after *gno*, further changes to the text might make *gnomon-ly* better.

T_EX will not hyphenate a word with a nonletter in the middle, where it treats any sequence of nonspace characters as a single word. While it hyphenates *ra-di-a-tion* properly, it does not hyphenate *x-radiation*—though it will break a line after the *x*-. You must type `x-ra\di\-\a\-\tion` for T_EX to consider all possible hyphenation points. However, it is generally considered a bad idea to hyphenate a hyphenated compound; you should do so only when there is no better alternative.

When writing a paper about sundials, in which the word *gnomon* appears frequently, it would be a nuisance to type it as `gno\mon` everywhere it is used. You can teach T_EX how to hyphenate words by putting one or more `\hyphenation` commands in the preamble. The command

```
\hyphenation{gno-mon gno-mons gno-mon-ly}
```

tells T_EX how to hyphenate *gnomon*, *gnomons*, and *gnomonly*—but it still won't know how to hyphenate *gnomonic*.

While it's very good at hyphenating English, an English-language version of L^AT_EX does not respect the hyphenation rules of other languages. For example, it uses the English hyphenation *re-spect* rather than the Romanian *res-pect*. If your document contains only a few phrases in Romanian, you can correct hyphenation errors as they occur by using `\hyphenation` or `\-` commands to tell T_EX where it can hyphenate a word. If your document contains a lot of text in Romanian or some other language(s), use the *babel* package described in the L^AT_EX *Companion*.

Not all line-breaking problems can be solved by hyphenation. Sometimes there is just no good way to break a paragraph into lines. T_EX is normally very fussy about line breaking; it lets you solve the problem rather than producing a paragraph that doesn't meet its high standards. There are three things you can do when this happens. The first is to rewrite the paragraph. However, having carefully polished your prose, you may not want to change it just to produce perfect line breaks.

The second way to handle a line-breaking problem is to use a `sloppypar` environment or `\sloppy` declaration, which direct T_EX not to be so fussy about where it breaks lines. Most of the time, you just enclose the entire paragraph that contains the bad line break between `\begin{sloppypar}` and `\end{sloppypar}` commands. However, sometimes it's easier to use a `\sloppy` declaration. To explain how to use this declaration, it helps to introduce the concept of a *paragraph unit*. A paragraph unit is a portion of text that is treated as a single string of words to be broken into lines at any convenient point. For example, a paragraph containing a displayed equation would consist of two paragraph units—the parts of the paragraph that come before and after the equation. (Since the equation itself can't be broken across lines, it is not a paragraph unit.) Similarly, each

item in a list-making environment begins a new paragraph unit.

$\text{\TeX}$ does its line breaking for a paragraph unit when it encounters the command or blank line that ends the unit, based upon the declarations in effect at that time. So, the scope of the $\text{\sloppy}$ declaration should include the command or blank line that ends the paragraph unit with the bad line break. You can either delimit the scope of the $\text{\sloppy}$ declaration with braces, or else use a countermanding $\text{\fussy}$ declaration that restores $\text{\TeX}$ to its ordinary compulsive self. The $\text{\begin{sloppypar}}$ command is equivalent to a blank line followed by $\text{\sloppy}$, and $\text{\end{sloppypar}}$ is equivalent to a blank line followed by a $\text{}$.

The third way to fix a bad line break is with a $\text{\linebreak}$ command, which forces $\text{\TeX}$ to break the line at that spot. The $\text{\linebreak}$ is usually inserted right before the word that doesn't fit. An optional argument converts the $\text{\linebreak}$ command from a demand to a request. The argument must be a digit from 0 through 4, a higher number denoting a stronger request. The command $\text{\linebreak[0]}$ allows $\text{\TeX}$ to break the line there, but neither encourages nor discourages its doing so, while $\text{\linebreak[4]}$ forces the line break just like an ordinary $\text{\linebreak}$ command. The arguments 1, 2, and 3 provide intermediate degrees of insistence, and may succeed in coaxing $\text{\TeX}$ to overcome a bad line break. They can also be used to help $\text{\TeX}$ find the most aesthetically pleasing line breaks. The $\text{\linebreak[0]}$ command allows a line break where it would normally be forbidden, such as within a word.

Both of these methods handle line-breaking problems by sweeping them under the rug. The “lump in the carpet” that they may leave is one or more lines with too much blank space between words. Such a line will produce an “Underfull $\text{\hbox}$ ” warning message.

Although unwanted line breaks are usually prevented with the $\text{\sim}$ and $\text{\mbox}$ commands described in Section 2.2.1, $\text{\LaTeX}$ also provides a $\text{\nolinebreak}$ command that forbids $\text{\TeX}$ from breaking the line at that point. Like the $\text{\linebreak}$ command, $\text{\nolinebreak}$ takes a digit from 0 through 4 as an optional argument to convert the prohibition into a suggestion that this isn't a good place for a line break—the higher the number, the stronger the suggestion. A $\text{\nolinebreak[0]}$ command is equivalent to $\text{\linebreak[0]}$, and $\text{\nolinebreak[4]}$ is equivalent to $\text{\nolinebreak}$.

A $\text{\linebreak}$ command causes $\text{\TeX}$ to justify the line, stretching the space between words so the line extends to the right margin. The $\text{\newline}$ command ends a line without justifying it.

I can think of no good reason why you would want to make a short line like this
in the middle of a paragraph, but perhaps you can think of one.

I can think of no good reason why you would want to make a short line like this
 $\text{\newline}$
in the middle of a paragraph,
but perhaps you can think of one.

You can type `\`, which is the usual $\text{\LaTeX}$ command for ending a line, in place of `\newline`. In fact, $\text{\LaTeX}$ provides the `\newline` command only to maintain a complete correspondence between the line-breaking commands and the page-breaking commands described below.

The `\linebreak`, `\nolinebreak`, and `\newline` commands can be used only in paragraph mode. They are fragile commands. See Section C.1.1 if a `[` follows a `\linebreak` or `\nolinebreak` command that has no optional argument.

Remember, **don't worry about line breaks until you prepare the ultimate, absolutely final version.**

6.2.2 Page Breaking

$\text{\TeX}$ is as fussy about page breaks as it is about line breaks. As with line breaking, sometimes $\text{\TeX}$ can find no good place to start a new page. A bad page break usually causes $\text{\TeX}$ to put too little rather than too much text onto the page. When the `\flushbottom` declaration (Section 6.1.1) is in effect, this produces a page with too much extra vertical space; with the `\raggedbottom` declaration, it produces a page that is too short. In the first case, $\text{\TeX}$ warns you about the extra space by generating an “Underfull \vbox” message. With `\raggedbottom` in effect, $\text{\TeX}$ does not warn you about bad page breaks, so you should check your final output for pages that are too short.

The $\text{\LaTeX}$ page-breaking commands are analogous to the line-breaking commands described in Section 6.2.1 above. As with line breaking, $\text{\LaTeX}$ provides commands to demand or prohibit a page break, with an optional argument transforming the commands to suggestions. The `\pagebreak` and `\nopagebreak` commands are the analogs of `\linebreak` and `\nolinebreak`. When used between paragraphs, they apply to that point; when used in the middle of a paragraph, they apply immediately after the current line. Thus, a `\pagebreak` command within a paragraph insists that $\text{\TeX}$ start a new page after the line in which the command appears, and `\nopagebreak[3]` suggests rather strongly that $\text{\TeX}$ *not* start a new page there.

You will sometimes want to squeeze a little more text on a page than $\text{\TeX}$ thinks you should. The best way of doing this is to make room on the page by removing some vertical space, using the commands of Section 6.4.2. If that doesn't work, you can try using a `\nopagebreak` command to prevent $\text{\TeX}$ from breaking the page before you want it to. However, $\text{\TeX}$ often becomes adamant about breaking a page at a certain point, and it will not be deterred by `\nopagebreak`. When this happens, you can put extra text on the page as follows:

- Add the command `\enlargethispage*{1000pt}` to the text on the current page, before the point where $\text{\TeX}$ wants to start a new page.
- Add a `\pagebreak` command to break the page where you want.

Squeezing in extra text in this way will make the page longer than normal, which may look bad in two-sided printing. Section C.12.2 describes a less heavy-handed approach. But **don't worry about page breaks until you prepare the ultimate, absolutely final, no-more-changes (really!) version.**

The `\newpage` command is the analog of `\newline`, creating a page that ends prematurely right at that point. Even when a `\flushbottom` declaration is in effect, a shortened page is produced. The `\clearpage` command is similar to `\newpage`, except that any leftover figures or tables are put on one or more separate pages with no text. The `\chapter` and `\include` commands (Section 4.4) use `\clearpage` to begin a new page. Adding an extra `\newpage` or `\clearpage` command will not produce a blank page; two such commands in a row are equivalent to a single one. To generate a blank page, you must put some invisible text on it, such as an empty `\mbox`.

When using the `twoside` style option for two-sided printing, you may want to start a sectional unit on a right-hand page. The `\cleardoublepage` command is the same as `\clearpage` except that it produces a blank page if necessary so that the next page will be a right-hand (odd-numbered) one.

When used in two-column format, the `\newpage` and `\pagebreak` commands start a new column rather than a new page. However, the `\clearpage` and `\cleardoublepage` commands start a new page.

The page-breaking commands can be used only where it is possible to start a new page—that is, in paragraph mode and not inside a box (Section 6.4.3). They are all fragile.

6.3 Numbering

Every number that L^AT_EX generates has a *counter* associated with it. The name of the counter is usually the same as the name of the environment or command that produces the number, except with no `\`. Below is a list of the counters used by L^AT_EX's standard document styles to control numbering.

<code>part</code>	<code>paragraph</code>	<code>figure</code>	<code>enumi</code>
<code>chapter</code>	<code>subparagraph</code>	<code>table</code>	<code>enumii</code>
<code>section</code>	<code>page</code>	<code>footnote</code>	<code>enumiii</code>
<code>subsection</code>	<code>equation</code>	<code>mpfootnote</code>	<code>enumiv</code>
<code>subsubsection</code>			

The counters `enumi` ... `enumiv` control different levels of `enumerate` environments, `enumi` for the outermost level, `enumii` for the next level, and so on. The `mpfootnote` counter numbers footnotes inside a `minipage` environment (Section 6.4.3). In addition to these, an environment created with the `\newtheorem` command (Section 3.4.3) has a counter of the same name unless an optional argument specifies that it is to be numbered the same as another environment.

There are also some other counters used for document-style parameters; they are described in Appendix C.

The value of a counter is a single integer—usually nonnegative. Multiple numbers are generated with separate counters, the “2” and “4” of “Subsection 2.4” coming from the `section` and `subsection` counters, respectively. The value of a counter is initialized to zero and is incremented by the appropriate command or environment. For example, the `subsection` counter is incremented by the `\subsection` command before the subsection number is generated, and it is reset to zero when the `section` counter is incremented, so subsection numbers start from one in a new section.

The `\setcounter` command sets the value of a counter, and `\addtocounter` increments it by a specified amount.

Because¹⁸ counters¹⁷ are stepped before being used, you set them to one less than the number you want.

```
\setcounter{footnote}{17}
Because\footnote{...}
\addtocounter{footnote}{-2}%
counters\footnote{...} are stepped ...
```

When used in the middle of a paragraph, these commands should be attached to a word to avoid adding extra space.

The `\setcounter` and `\addtocounter` commands affect only the specified counter; for example, changing the `section` counter with these commands does not affect the `subsection` counter. The commands to change counter values are global declarations (Section C.1.4); their effects are not limited by the normal scope rules for declarations.

The `page` counter is used to generate the page number. It differs from other counters in that it is incremented *after* the page number is generated, so its value is the number of the current page rather than the next one. A `\setcounter{page}{27}` command in the middle of the document therefore causes the current page to be numbered 27. For this reason, the `page` counter is initialized to one instead of zero.

L^AT_EX provides the following commands for printing counter values; the list shows what they produce when the `page` counter has the value four.

4	<code>\arabic{page}</code>	iv	<code>\roman{page}</code>	d	<code>\alph{page}</code>
		IV	<code>\Roman{page}</code>	D	<code>\Alph{page}</code>

To generate a printed number, L^AT_EX executes a command whose name is formed by adding `\the` to the beginning of the appropriate counter’s name; redefining this command changes the way the number is printed. For example, a subsection number is made by the `\thesubsection` command. To change the numbering of sections and subsections so the fourth subsection of the second section is numbered “II-D”, you type the following (see Section 3.4 for an explanation of `\renewcommand`):

```
\renewcommand{\thesection}{\Roman{section}}
\renewcommand{\thesubsection}{\thesection-\Alph{subsection}}
```

Since sections are usually numbered the same throughout the document (at least until the appendix), the obvious place for this command is in the preamble.

A new counter is created with a `\newcounter` command having the name of the counter as its argument. The new counter's initial value is zero, and its initial `\the...` command prints the value as an arabic numeral. See Section 6.6 for an example of how a new counter is used in defining an environment. The `\newcounter` declaration should be used only in the preamble.

6.4 Length, Spaces, and Boxes

In visual design, one specifies how much vertical space to leave above a chapter heading, how wide a line of text should be, and so on. This section describes the basic tools for making these specifications.

6.4.1 Length

A length is a measure of distance. An amount of space or a line width is specified by giving a length as an argument to the appropriate formatting command. A length of one inch is specified by typing `1in`; it can also be given in metric units as `2.54cm` or `25.4mm`, or as `72.27pt`, where `pt` denotes *point*—a unit of length used by printers. A length can also be negative—for example, `-2.54cm`.

The number 0 by itself is not a length. A length of zero is written `0in` or `0cm` or `0pt`, not 0. Writing 0 as a length is a common mistake.

While inches, centimeters, and points are convenient units, they should be avoided because they specify fixed lengths. A .25-inch horizontal space that looks good in one-column output may be too wide in a two-column format. It's better to use units of length that depend upon the appropriate style parameters. The simplest such units are the `em` and the `ex`, which depend upon the font (the size and style of type). A `1em` length is about equal to the width of an "M", and `1ex` is about the height of an "x". The `em` is best used for horizontal lengths and the `ex` for vertical lengths. An `em` ruler for the current font is given below, and an `ex` ruler is in the margin.



In addition to writing explicit lengths such as `1in` or `3.5em`, you can also express lengths with *length commands*. A length command has a *value* that is a length. For example, `\parindent` is a length command whose value specifies the width of the indentation at the beginning of a normal paragraph. Typing



`\parindent` as the argument of a command is equivalent to typing the current value of `\parindent`. You can also type `2.5\parindent` for a length that is 2.5 times as large as `\parindent`, or `-2.5\parindent` for the negative of that length; `-\parindent` is the same as `-1.0\parindent`.

A length such as `1.5em` or `\parindent` is a *rigid* length. Specifying a space of width `1cm` always produces a one-centimeter-wide space. (It may not be exactly one centimeter wide because your output device might uniformly change all dimensions—for example, enlarging them by 5%.) However, there are also *rubber* lengths that can vary.² Space specified with a rubber length can stretch or shrink as required. For example, $\text{\TeX}$ justifies lines (produces an even right margin) by stretching or shrinking the space between words to make each line the same length.

A rubber length has a natural length and a degree of elasticity. Of particular interest is the special length command `\fill` that has a natural length of zero but is infinitely stretchable, so a space of width `\fill` tends to expand as far as it can. The use of such stretchable space is described in Section 6.4.2 below. Multiplying a length command by a number destroys its elasticity, producing a rigid length. Thus, `1\fill` and `.7\fill` are rigid lengths of value zero inches.

Most lengths used in $\text{\LaTeX}$ are rigid. Unless a length is explicitly said to be rubber, you can assume it is rigid. All length commands are robust; a `\protect` command should never precede a length command.

Below are some of $\text{\LaTeX}$'s *length parameters*—length commands that define a document's style parameters; others are given in Appendix C. By expressing lengths in terms of these parameters, you can define formatting commands that work properly with different styles.

`\parindent` The amount of indentation at the beginning of a normal paragraph.

`\textwidth` The width of the text on the page.

`\textheight` The height of the body of the page—that is, the normal height of everything on a page excluding the head and foot (Section 6.1.2).

`\parskip` The extra vertical space inserted between paragraphs. It is customary not to leave any extra space between paragraphs, so `\parskip` has a natural length of zero (except in the `letter` document class). However, it is a rubber length, so it can stretch to add vertical space between paragraphs when the `\flushbottom` declaration (Section 6.1.1) is in effect.

`\baselineskip` The normal vertical distance from the bottom of one line to the bottom of the next line in the same paragraph. Thus, `\textheight ÷ \baselineskip` equals the number of lines of text that would appear on a page if it were all one paragraph.³

²A rigid length is called a *(dimen)* and a rubber length is called a *(skip)* in the *TeXbook*.

³This is only approximately correct—see the `\topskip` command in Section C.5.3 to find out why.

L^AT_EX provides the following declarations for changing the values of length commands and for creating new ones. These declarations obey the usual scoping rules.

\newlength Defines a new length command. You type `\newlength{\gnat}` to make `\gnat` a length command with value 0cm. An error occurs if a `\gnat` command is already defined.

\setlength Sets the value of a length command. The value of `\parskip` is set to 1.01 millimeters by the command `\setlength{\parskip}{1.01mm}`.

\addtolength Increments the value of a length command by a specified amount. If the current value of `\parskip` is .01 inches, then executing the command `\addtolength{\parskip}{-.1\parskip}` changes its value to .009 inches—the original value plus $-.1$ times its original value.

\settowidth Sets the value of a length command equal to the width of a specified piece of text. The command `\settowidth{\parindent}{\em small}` sets the value of `\parindent` to the width of *small*—the text produced by typesetting `{\em small}` in LR mode.

\settoheight, **\settodepth** These commands act like `\settowidth`, except they set the value of the length command to the height and depth, respectively, of the text. For example, `\settoheight{\parskip}{Gnu}` sets the value of `\parskip` to the height of the letter “G” in the current font, while `\settodepth{\parskip}{gnu}` sets the value of `\parskip` to the distance the letter “g” extends below the line. Height and depth are explained below, in Section 6.4.3.

The value of a length command created with `\newlength` can be changed at any time. This is also true for some of L^AT_EX’s length parameters, while others should be changed only in the preamble and still others should never be changed. Consult Appendix C to find out when you can safely change the value of a L^AT_EX parameter.

6.4.2 Spaces

A horizontal space is produced with the `\hspace` command. Think of `\hspace` as making a blank “word”, with spaces before or after it producing an interword space.

Here $\leftarrow .5\text{ in } \rightarrow$ is a .5 inch space.
 Here is a .5 inch space.
 Here is a .5 inch space.
 Negative space is a backspace—like this.
 $\leftarrow .5\text{ in } \rightarrow$

Here`\hspace{.5in}`is a .5 inch space.
 Here `\hspace{.5in}`is a .5 inch space.
 Here `\hspace{.5in}` is a .5 inch space.
 ...--like this.`\hspace{-.5in}`////

$\text{\TeX}$ removes space from the beginning or end of each line of output text, except at the beginning and end of a paragraph—including space added with $\text{\hspace}$. The $\text{\hspace*}$ command is the same as $\text{\hspace}$ except that the space it produces is never removed, even when it comes at the beginning or end of a line. The $\text{\hspace}$ and $\text{\hspace*}$ commands are robust.

The $\text{\vspace}$ command produces vertical space. It is most commonly used between paragraphs; when used within a paragraph, the vertical space is added after the line in which the $\text{\vspace}$ appears.

You seldom add space like this between lines in

 a paragraph, but you sometimes remove space between them by adding some negative space.



You more often add space between paragraphs—especially before or after displayed material.

$\text{\vspace{.25in}}$ seldom add space like this between lines in a paragraph, but you ... by adding some negative space.

$\text{\vspace{7 mm}}$

You more often add space between ...

Just as it removes horizontal space from the beginning and end of a line, $\text{\TeX}$ removes vertical space that comes at the beginning or end of a page. The $\text{\vspace*}$ command creates vertical space that is never removed.

If the argument of an $\text{\hspace}$ or $\text{\vspace}$ command (or its *-form) is a rubber length, the space produced will be able to stretch and shrink. This is normally relevant only for the fine tuning of the formatting commands of a package or document class. However, a space made with an infinitely stretchable length such as $\text{\fill}$ is useful for positioning text because it stretches as much as it can, pushing everything else aside. The command $\text{\hfill}$ is an abbreviation for $\text{\hspace{\fill}}$.

Here is a
Here are

stretched space.
two equal ones.

Here is a $\text{\hfill}$ stretched space.
Here are $\text{\hfill}$ two $\text{\hfill}$ equal ones.

Note that when two equally stretchable spaces push against each other, they stretch the same amount. You can use stretchable spaces to center objects or to move them flush against the right-hand margin. However, $\text{\LaTeX}$ provides more convenient methods of doing that, described in Section 6.5.

Infinitely stretchable space can be used in the analogous way for moving text vertically. The $\text{\vfill}$ command is equivalent to a blank line followed by $\text{\vspace{\fill}}$. Remember that spaces produced by $\text{\hfill}$ or $\text{\vfill}$ at the beginning and end of a line or page disappear. You must use $\text{\hspace*{\fill}}$ or $\text{\vspace*{\fill}}$ for space that you don't want to disappear.

The $\text{\dotfill}$ command acts just like $\text{\hfill}$ except it produces dots instead of spaces. The command $\text{\hrulefill}$ works the same way, but it produces a horizontal line.

Gnats and gnus see pests.
 This is _____ really _____ it.

Gnats and gnus \dotfill\ see pests.
 This is \hrulefill\ really \hrulefill\ it.

6.4.3 Boxes

A *box* is a chunk of text that $\text{\TeX}$ treats as a unit, just as if it were a single letter. No matter how big it is, $\text{\TeX}$ will never split a box across lines or across pages. The `\mbox` command introduced in Section 2.2.1 prevents its argument from being split across lines by putting it in a box. Many other $\text{\LaTeX}$ commands and environments produce boxes. For example, the `array` and `tabular` environments (Section 3.6.2) both produce a single box that can be quite big, as does the `picture` environment described in Section 7.1.

A box has a *reference point*, which is at its left-hand edge. $\text{\TeX}$ produces lines by putting boxes next to one another with their reference points aligned, as shown in Figure 6.1. The figure also shows how the width, height, and depth of a box are computed.

$\text{\LaTeX}$ provides additional commands and environments for making three kinds of boxes: LR boxes, in which the contents of the box are processed in LR mode; parboxes, in which the contents of the box are processed in paragraph mode; and rule boxes, consisting of a rectangular blob of ink.

A box-making command or environment can be used in any mode. $\text{\LaTeX}$ uses the declarations in effect at that point when typesetting the box's contents, so the contents of a box appearing in the scope of an `\em` declaration will be emphasized—usually by being set in an italic type style. However, box-making commands that appear in a mathematical formula are not affected by the commands described in Section 3.3.8 that change the type style in the formula.

The `\mbox` in the formula $x = y * \text{\textbf{ab}} + xyz + cd / z$ uses the same type style as the surrounding text.

... in the formula

$$x = y * \text{\textbf{\scriptstyle ab}} + \text{\mbox{xyz}} + cd \text{\textstyle / z}$$
 uses ...

Since the input that produces a box's contents is either the argument of a box-making command or the text of a box-making environment, any declarations made inside it are local to the box.




Figure 6.1: Boxes and how $\text{\TeX}$ puts them together.

A box is often displayed on a line by itself. This can be done by treating the box as a formula and using the `displaymath` environment (`\[ ... \]`). The `center` environment described in Section 6.5 can also be used.

LR Boxes

The `\mbox` command makes an LR box—a box whose contents are obtained by processing the command's argument in LR mode. It is an abbreviated version of the `\makebox` command; `\makebox` has optional arguments that `\mbox` doesn't. The box created by an `\mbox` command is just wide enough to hold its contents. You can specify the width of the box with a `\makebox` command that has an optional first argument. The default is to center the contents in the box, but this can be overridden by a second optional argument that consists of a single letter: `l` to move the contents to the left side of the box, and `r` to move it to the right.

Good ← 1 in → <i>gnus</i> Good <i>gnus</i> Good	are here at last. are here at last. <i>gnus</i> are here at last.	<code>Good \makebox[1in]{\em gnus} are here ...</code> <code>Good \makebox[1in][l]{\em gnus} are ...</code> <code>Good \makebox[1in][r]{\em gnus} are ...</code>
---	---	--

A box is treated just like a word; space characters on either side produce an interword space.

The `\framebox` command is exactly the same as `\makebox` except it puts a frame around the outside of the box. There is also an `\fbox` command, the abbreviation for a `\framebox` command with no optional arguments.

There was not a ← 1 in → gnu or armadillo in sight.	<code>There was not a \framebox[1in][l]{gnu}</code> <code>or \fbox{armadillo} in sight.</code>
--	---

When you specify a box of a fixed width, $\text{\TeX}$ acts as if the box has exactly that width. If the contents are too wide for the box, they will overflow into the surrounding text.


<code>X X X \mbox{wide armadillo} X X X</code>	<code>X X X \framebox[.5in]{wide armadillos} X X X</code>
--	---

Parboxes

A *parbox* is a box whose contents are typeset in paragraph mode, with $\text{\TeX}$ producing a series of lines just as in ordinary text. The `figure` and `table` environments (Section 3.5.1) create parboxes. There are two ways to make a parbox at a given point in the text: with the `\parbox` command and the `minipage` environment. They can be used to put one or more paragraphs of text inside a picture or in a table item.

For $\text{\TeX}$ to break text into lines, it must know how wide the lines should be. Therefore, `\parbox` and the `minipage` environment have the width of the parbox

as an argument. The second mandatory argument of the `\parbox` command is the text to be put in the parbox.

 ← 1 in → Breaking lines in a narrow parbox is hard.	YOU CAN	expect to get a lot of bad line breaks if you try this sort of thing.	<pre>\parbox{1in}{Breaking lines in a narrow parbox is hard.} \ YOU CAN \ \parbox{1in}{expect to get a lot of bad line breaks if you try ...}</pre>
---	----------------	--	---

There is no indentation at the beginning of a paragraph in these parboxes; $\text{\LaTeX}$ sets the `\parindent` parameter, which specifies the amount of indentation, to zero in a parbox. You can set it to any other value with `\setlength` (Section 6.4.1).

In the example above, the parboxes are positioned vertically so the center of the box is aligned with the center of the text line. An optional first argument of `t` (for *top*) or `b` (*bottom*) aligns the top or bottom line of the parbox with the text line. More precisely, the optional argument causes the reference point of the box to be the reference point of the top or bottom line of its contents.

This is a parbox aligned on its bot- tom line.	AND THIS	one is aligned on its top line.	<pre>\parbox[b]{1in}{This is a parbox aligned on its bottom line.} \ AND THIS \ \parbox[t]{1in}{one is aligned on its top line.}</pre>
---	-----------------	--	--

Finer control of the vertical positioning is obtained with the `\raisebox` command described below.

The `\parbox` command is generally used for a parbox containing a small amount of text. For a larger parbox or one containing a `\tabbing` environment, a list-making environment, or any of the paragraph-making environments described in Section 6.5, you should use a `\minipage` environment. The `\minipage` environment has the same optional positioning argument and mandatory width argument as the `\parbox` command.

When used in a `\minipage` environment, the `\footnote` command puts a footnote at the bottom of the parbox produced by the environment. This is particularly useful for footnotes inside figures or tables. Moreover, unlike in ordinary text, the `\footnote` command can be used anywhere within the environment—even inside another box or in an item of a `\tabular` environment. To footnote something in a `\minipage` environment with an ordinary footnote at the bottom of the page, use the `\footnotemark` and `\footnotetext` commands described in Section C.3.3.

gnat: a tiny bug AND *gnu*: a beast^a that
that is very hard is hard to miss.
to find.

^aSee armadillo.

```
\begin{minipage}[t]{1in}
  {\em gnat}: a tiny bug ...
\end{minipage} \AND \
\begin{minipage}[t]{1in}
  {\em gnu}: a beast\footnote{See
    armadillo.} that is hard to miss.
\end{minipage}
```

If you have one `minipage` environment nested inside another, footnotes may appear at the bottom of the wrong one.

You may find yourself wishing that $\text{\TeX}$ would determine the width of a parbox by itself, making it just wide enough to hold the text inside. This is normally impossible because $\text{\TeX}$ must know the line width to do its line breaking. However, it doesn't have to know a line width when typesetting a `tabbing` environment because the input specifies where every line ends. Therefore, if a `minipage` environment consists of nothing but a `tabbing` environment, then $\text{\TeX}$ will set the width of the parbox to be either the width specified by the `minipage` environment's argument or the actual width of the longest line, choosing whichever is smaller.

Rule Boxes

A rule box is a rectangular blob of ink. It is made with the `\rule` command, whose arguments specify the width and height of the blob. The reference point of the rule box is its lower-left corner. There is also an optional first argument that specifies how high to raise the rule (a negative value lowers it).

Rule 1: 

Rule 2: 

```
Rule 1: \rule{1mm}{5mm}
Rule 2: \rule[.1in]{.25in}{.02in}
```

A thin enough rule is just a line, so the `\rule` command can draw horizontal or vertical lines of arbitrary length and thickness.

A rule box of width zero is called a *strut*. Having no width, a strut is invisible; but it does have height, and $\text{\TeX}$ will adjust the vertical spacing to leave room for it.

Compare this box with .

```
Compare \fbox{this box} with
\fbox{\rule[-.5cm]{0cm}{1cm}this box}.
```

Struts provide a convenient method of adding vertical space in places where `\vspace` can't be used, such as within a mathematical formula.

Raising and Lowering Boxes

The `\raisebox` command raises text by a specified length (a negative length lowers the text). It makes an LR box, just like the `\mbox` command.

You can *raise* or *lower* text.

You can `\raisebox{.6ex}{\em raise}` or
`\raisebox{-.6ex}{\em lower}` text.

It is sometimes useful to change how big TeX thinks a piece of text is without changing the text. The `\makebox` command tells TeX how wide the text is, while a strut can increase the text's apparent height but cannot decrease it. Optional arguments of `\raisebox` tell TeX how tall it should pretend that the text is. The command


```
\raisebox{.4ex}[1.5ex][.75ex]{\em text}
```

not only raises *text* by `.4ex`, but also makes TeX think that it extends `1.5ex` above the bottom of the line and `.75ex` below the bottom of the line. (The bottom of the line is where most characters sit; a letter like *y* extends below it.) If you omit the second optional argument, TeX will think the text extends as far below the line as it actually does. By changing the apparent height of text, you change how much space TeX leaves for it. This is sometimes used to eliminate space above or below a formula or part of a formula.

Saving Boxes

If a single piece of text appears in several places, you can define a command with `\newcommand` (Section 3.4) to generate it. While this saves typing, TeX doesn't save any time because it must do the work of typesetting the text whenever it encounters the command. If the text is complicated—especially if it contains a `picture` environment (Section 7.1)—TeX could waste a lot of time typesetting it over and over again.

TeX can typeset something once as a box and then save it in a named *storage bin*, from which it can be used repeatedly. The name of a storage bin is an ordinary command name; a new bin is created and named by the `\newsavebox` declaration. The `\savebox` command makes a box and saves it in a specified bin; it has the bin name as its first argument and the rest of its arguments are the same as for the `\makebox` command. The `\usebox` command prints the contents of a bin.

		<code>\newsavebox{\toy}</code>
		<code>\savebox{\toy} [.65in] {gnats}</code>
		...
	and	<code>\usebox{\toy}</code> and <code>\usebox{\toy}</code> and
It's	gnats	<code>\usebox{\toy}</code> , wherever we go.

The `\sbox` command is the short form of `\savebox`, with no optional arguments. The `\savebox` and `\sbox` commands are declarations that have the usual scope. However, the `\newsavebox` declaration is global (Section C.1.4) and does not obey the customary scoping rules.

The `lrbox` environment is like an `\sbox` command, except that it ignores spaces at the beginning and end of the text. Thus,

```
\begin{lrbox}{\jewel}
  Text
\end{lrbox}
```

is equivalent to `\sbox{\jewel}{Text}`. This environment is used to define an environment in terms of a command. For example, suppose we want to define a `boxit` environment that produces a boxed, 1-inch-wide paragraph.

Here is a	silly boxed paragraph that no one will ever use	for anything.	<pre>... a \begin{boxit} silly boxed paragraph ... \end{boxit} for anything.</pre>
-----------	---	---------------	---

We define this environment by using its body (the text between `\begin{boxit}` and `\end{boxit}`) as the argument of an `\fbox` command. Making the paragraph box with a `minipage` environment, we can define the `boxit` environment by:

```
\newsavebox{\savepar}
\newenvironment{boxit}{\begin{lrbox}{\savepar}
  \begin{minipage}[b]{1in}}
  {\end{minipage}\end{lrbox}\fbox{\usebox{\savepar}}}
```

6.4.4 Formatting with Boxes

Many L^AT_EX users fail to realize how much they can do with the box-making commands described above. I will illustrate the power of these commands with a silly example: defining a `\face` command to put a funny face around a word, like the faces around “funny” and “face” in this sentence. The face is composed of two diamonds (◊) produced with the `\diamond` command, and a smile (☺) produced with `\smile`. The trick, of course, is positioning these symbols correctly relative to the word being “faced”.

The left eye of the face (the one near the “f”) is positioned above the word and 15% of the way from the word’s left edge to its right edge. First, we see how to put a piece of text a fixed distance to the right of the left-hand edge of a word. Recall that if the specified width of a `\makebox` is less than the width of its contents, the contents extend outside the box. With the `l` position specified, the contents extend to the right of the box. In the extreme case of a zero-width box, the entire contents lie to the right.

The gnuuuuu began to moooooo~~x~~oooooo.

...to `\makebox[Opt][l]{\hspace{1cm}X}`moo...

Because the box produced by this `\makebox` command has zero width, it doesn't change the position of the "moo...".

We want the face's left eye to be shifted to the right by .15 times the width of the word and raised by the height of the word. So, the `\face` command must measure the width and height of its argument using the `\settoheight` and `\settowidth` commands. These lengths are saved in two new length commands, `\faceht` and `\facewd`, that are defined with `\newlength`. The eye is raised with the `\raisebox` command. Before figuring out how to draw the rest of the face, we define a `\lefteye` command so `\lefteye{\emph{moooo}}` produces $\hat{m}oooo$.

```
\newlength{\facewd} \newlength{\faceht}      %% Define length commands
\newcommand{\lefteye}[1]{%                    Definition of \lefteye:
  \settowidth{\facewd}{\#1}\settoheight{\faceht}{\#1}% - Save width & height
  \raisebox{\faceht}{%                         - Raise by height
    \makebox[Opt][l]{\hspace{.15\facewd}%      - Move right .15 * width
      $\diamond$}}%                             - Print eye
  \#1}%                                         - Print argument
```

Each line in the definition of `\lefteye` ends with a %. This both allows comments and splits the definition across lines without introducing unwanted interword spaces. (See Section 2.2.1.) Unintentional spaces are a common source of error in command definitions; be careful not to introduce any.

To make the right eye of the `\face` command, we put immediately after the word a zero-width box whose contents extend to the left. Such a box is produced by a `\makebox` command with the `r` positioning specifier:

```
\makebox[Opt][r]{$\diamond$\hspace{.15\facewd}}
```

The right eye, like the left, is raised with a `\raisebox` command.

The face's smile is centered beneath the word. To achieve the correct horizontal positioning, `\makebox` is used to center the smile in a box the same width as the word. This box is in turn put inside and extending to the right of a zero-width box that is placed before the word.

```
\makebox[Opt][l]{\makebox[\facewd]{$\smile$}}
```

A bit of experimentation reveals that the smile should be lowered (raised by a negative distance of) 1.4 ex.

The complete definition of `\face` appears in Figure 6.2. (Like all such definitions, it should go in the preamble.) The definition has been refined to solve two problems. First, the eyes and smile would normally increase the height and depth of the line, causing $\text{\TeX}$ to add extra space above and below it. To prevent this, the optional arguments to `\raisebox` have been used to make $\text{\TeX}$ pretend that the eyes have zero height and the smile has zero (height and) depth.

```

\newlength{\facewd} \newlength{\faceht} %% Define length commands
\newcommand{\face}[1]{%
  \settowidth{\facewd}{#1}\settoheight{\faceht}{#1}% * Save width & height.
  \raisebox{\faceht}[0pt]{\makebox[0pt][l]{% * Print left eye.
    \hspace{.15\facewd}$\diamond$}}%
  \raisebox{-1.4ex}[0pt][0pt]{\makebox[0pt][l]{% * Print smile.
    \makebox[\facewd]{$\smile$}}}%
  {#1}% * Print argument
  \raisebox{\faceht}[0pt]{\makebox[0pt][r]{% * Print right eye.
    $\diamond$\hspace{.15\facewd}}}%
}

```

Figure 6.2: The complete definition of the `\face` command.

The second problem occurs in the definition of `\lefteye` given above. As explained in Section 3.4.1, that definition fails to limit the scope of declarations that appear in its argument.

The `\em` declaration in *gnu escapes its argument*. ... in `\lefteye{\em gnu} escapes ...`

This problem is solved by putting an extra pair of braces around the part of the definition that prints the argument.

A `\face` command uses the argument three times—to measure its height, to measure its width, and to print it. Each time, the argument is processed anew by $\text{\LaTeX}$. This could be a problem. For example, if the argument contains a `\typein` command, each occurrence of `\face` causes $\text{\LaTeX}$ to request three separate inputs. We can modify the definition to make `\face` process its argument only once by using a `\savebox` command to save the argument and replacing the three uses (the `#1`'s) with `\usebox` commands.

Solving a formatting problem is often a matter of figuring out how to position some text. The definition of the `\face` command shows how we can use space- and box-making commands to put one object (for example, an eye or a smile) in any desired position relative to another object. The two objects can be arbitrarily far apart. Consider the box around this complete line of text. It is easy to produce the box itself by putting a strut (a zero-width rule) and some horizontal space in an `\fbox` command.

```
\fbox{\rule{0pt}{.5\baselineskip}\hspace{\textwidth}}
```

But, how did I position the box? I could have positioned it relative to the first or last word on the line. However, that would have required knowing where the line breaks occur, and they change every time I revise the paragraph. Instead, I positioned the box relative to an invisible marginal note, produced with an `\mbox{}` inside a `\marginpar` command (described in Section 3.5.2).

Suppose you want to put a box around an entire page of text. Again, producing a box of the right size is easy; the problem is positioning it. Since the

box appears at a fixed point on the page, it must be positioned relative to some object that appears at a fixed location on the page. One such object is the page heading; another is the page number. You just have to add a suitable zero-width box to either of these objects. Section C.5.3 describes how to set page headings; the page number is produced by the `\thepage` command (Section 6.3).

6.5 Centering and “Flushing”

The `center` environment is used to produce one or more lines of centered text; a `\` command starts a new line.

This is the last line of text in the preceding paragraph.

Here are three
centered
lines of text.

This is the text immediately following the environment. It begins a new paragraph only if you leave a blank line after the `\end{center}`.

```
... of text in the preceding paragraph.
\begin{center}
  Here are three\\ centered \\
  lines of text.
\end{center}
This is the text immediately ...
```

L^AT_EX is in paragraph mode inside the `center` environment, so it breaks lines where necessary to keep them from extending past the margins.

The `flushleft` and `flushright` environments are similar, except instead of each line of text being centered, it is moved to the left or right margin, respectively.

These are the last lines of text from the preceding paragraph.

These are two
flushed right lines.

```
... of text from the preceding paragraph.
\begin{flushright}
  These are two \\ flushed right lines.
\end{flushright}
```

The `center` and `flushright` environments are most commonly used with each new line started by an explicit `\` command. There is little purpose to using the `flushleft` environment in this way, since the `\` command in ordinary text produces a flushed-left line. By letting T_EX do the line breaking, `flushleft` produces ragged-right text.

Notice how T_EX leaves these lines uneven, without stretching them out to reach the right margin. This is known as “ragged-right” text.

```
\begin{flushleft}
  Notice how \TeX\ leaves these lines
  uneven, without stretching them out ...
\end{flushleft}
```

The centering and flushing environments work by using certain declarations that change how T_EX makes paragraphs. These declarations are available as

L^AT_EX commands; the declaration that corresponds to each environment is shown below:

<i>environment:</i>	<code>center</code>	<code>flushleft</code>	<code>flushright</code>
<i>declaration:</i>	<code>\centering</code>	<code>\raggedright</code>	<code>\raggedleft</code>

These declarations can be used inside an environment such as `quote` or in a `parbox` (Section 6.4.3).

This is text that comes at the end of the preceding paragraph.

Here is a quote environment
whose lines are
flushed right.

```
... at the end of the preceding paragraph.
\begin{quote}
  \raggedleft Here is a quote environment\\
  whose lines are \\ flushed right.
\end{quote}
```

The text of a figure or table can be centered on the page by putting a `\centering` declaration at the beginning of the `figure` or `table` environment.

Unlike the environments, the centering and flushing declarations do not start a new paragraph; they simply change how T_EX formats paragraph units (Section 6.2.1). To affect a paragraph unit's format, the scope of the declaration must contain the blank line or `\end` command (of an environment like `quote`) that ends the paragraph unit.

6.6 List-Making Environments

A *list* is a sequence of items typeset in paragraph mode with indented left and right margins, each item begun with a label. A label can be empty and an indentation can be of length zero, so an environment not normally thought of as a list can be regarded as one. In fact, almost every one of L^AT_EX's environments that begins on a new line is defined as a list. The list-making environments are: `quote`, `quotation`, `verse`, `itemize`, `enumerate`, `description`, `thebibliography`, `center`, `flushleft`, and `flushright`, as well as the theorem-like environments declared by `\newtheorem`.

L^AT_EX provides two primitive list-making environments: `list` and `trivlist`, the latter being a restricted version of `list`. They are flexible enough to produce most lists and are used to define the environments listed above.

6.6.1 The list Environment

The `list` environment has two arguments. The first specifies how items should be labeled when no argument is given to the `\item` command; the second contains declarations to set the formatting parameters. The general form of a list and the meaning of most of its formatting parameters are shown in Figure 6.3. The vertical-space parameters are rubber lengths; the horizontal-space param-




Figure 6.3: The format of a list.

ters are rigid ones. The extra `\partopsep` space is added at the top of the list only if the input file has a blank line before the environment. The vertical space following the environment is the same as the one preceding it.

Inside the list, the values of `\parskip` and `\parindent` are set to the values of `\parsep` and `\listparindent`, respectively. When one list is nested inside another, the `\leftmargin` and `\rightmargin` distances of the inner list are measured from the margins of the outer list.

The default values of these parameters are determined by the document class (and its options), as described in Section C.6.3; they depend upon the level of nesting of the list. These default values can be changed by declarations in the `list` environment's second argument. It is best to maintain the same spacing in all lists, so the default values of the vertical spacing and margin parameters should be used. However, the width and placement of the label may differ in different kinds of lists.

The label is typeset in LR mode. If it fits within a box of width `\labelwidth`, it is placed flush with the right-hand edge of a box of that width, which is positioned as shown in Figure 6.3. (It can be moved to a different position with the `\hfill` command of Section 6.4.2.) If the label is wider than `\labelwidth`, it extends to the right of the position shown in Figure 6.3 and the indentation of the first line of the item is increased by the extra width of the label.

The first argument of the environment is the text to be used as the label for any `\item` command with no optional argument. To number the items automatically, the second argument of the `list` environment should contain a `\usecounter{ctr}` command whose argument is the name of a counter—usually one defined with `\newcounter` (Section 6.3). This counter is reset to zero at the beginning of the environment and is incremented by one before the execution of any `\item` command that has no optional argument, so it can be used to generate a label number.

This sentence represents the end of the text that precedes the list.

B-I This is the first item of the list. Observe how the left and right margins are indented by the same amount.

B-II This is the second item.

As usual, the following text starts a new paragraph only if the `list` environment is followed by a blank line.

```
\newcounter{bean}
... the text that precedes the list.
\begin{list}
  {B--\Roman{bean}}{\usecounter{bean}
    \setlength{\rightmargin}{\leftmargin}}
  \item This is the first item of the list.
    Observe how the left and ...
  \item This is the second item.
\end{list}
As usual, the following text starts a ...
```

A `list` environment like this would be used to produce a one-of-a-kind list. The `list` environment is more commonly used with the `\newenvironment` command (Section 3.4) to define a new environment. Having many different list formats tends to confuse the reader. Instead of formatting each list individually, you should define a small number of list-making environments.

6.6.2 The `trivlist` Environment

The `trivlist` environment is a restricted form of the `list` environment in which margins are not indented and an `\item` command with no optional argument produces no text. The environment has no arguments and is very much like a `list` environment whose second argument sets `\leftmargin`, `\rightmargin`, `\labelwidth`, and `\itemindent` to a length of zero.

The `trivlist` environment is used to define other environments that create a one-item list, usually with an empty label. For example, the `center` environment (Section 6.5) is equivalent to

```
\begin{trivlist} \centering \item ... \end{trivlist}
```

6.7 Fonts

A *font* is a particular size and style of type. Section 3.1 explains how to change the type style; Section 6.7.1 explains how to change the size. As its default, L^AT_EX uses the Computer Modern fonts designed by Donald Knuth. There are a variety of packages that cause L^AT_EX to use fonts other than Computer Modern. Many of these packages are described in the *L^AT_EX Companion*; your *Local Guide* will tell you which of them are available on your computer. You should use one of these packages to change the fonts that are used throughout the document.

6.7.1 Changing Type Size

L^AT_EX's normal default type size is ten-point, but the `11pt` document-class option makes the default size eleven-point and the `12pt` option makes it twelve-point. L^AT_EX provides the following declarations for changing the type size within a document.

Gnu	<code>\tiny</code>	Gnu	<code>\normalsize</code>	Gnu	<code>\LARGE</code>
Gnu	<code>\scriptsize</code>	Gnu	<code>\large</code>	Gnu	<code>\huge</code>
Gnu	<code>\footnotesize</code>	Gnu	<code>\Large</code>	Gnu	<code>\Huge</code>
Gnu	<code>\small</code>				

These declarations can be combined in the natural way with the commands for changing the type style described in Section 3.1.

get big and bigger and bolder	<code>\sffamily get \large big and \Large bigger \bfseries and \LARGE bolder</code>
-------------------------------	---

The precise size of type produced by these declarations depends upon the default type size; the examples appearing here are for a ten-point default size. The `\normalsize` declaration produces the default size, `\footnotesize` produces the

size used for footnotes, and `\scriptsize` produces the size used for subscripts and superscripts in `\normalsize` formulas.

When you typeset an entire paragraph unit (Section 6.2.1) in a certain size, the scope of the size-changing declaration should include the blank line or `\end` command that ends the paragraph unit. A size-changing command may not be used in math mode. To set part of a formula in a different size of type, you can put it in an `\mbox` containing the size-changing command. All size-changing commands are fragile.

Not every type style is available in every size. If you try to use a font that is not available, L^AT_EX will issue a warning and substitute a font of the same size that is as close as possible in style to the one you wanted.


6.7.2 Special Symbols

You may need a special symbol not normally provided by L^AT_EX. Such symbols can exist in special fonts. The *Local Guide* should tell you what special fonts are available; the L^AT_EX *Companion* describes how to get L^AT_EX to use a special font.

A symbol in a special font is often identified by its *character-code*, which is a number from 0 to 255. When describing a special font, the *Local Guide* should tell you how to find the character codes for its special symbols. The command `\symbol{26}` produces the symbol with character code 26 in the currently chosen font. Character codes are often given in octal (base 8) or hexadecimal (base 16). An octal character code is prefaced by `'` and a hexadecimal one by `"`, so `\symbol{'32}` and `\symbol{"1A}` produce the same symbol as `\symbol{26}`, since 32 is the octal and 1A the hexadecimal representation of 26.

CHAPTER 7

Pictures and Colors



This chapter explains how to draw pictures, include graphics prepared with other programs in your document, and produce colors. Of these features, only simple picture-drawing commands are implemented in standard $\text{\TeX}$. The others are implemented by the `graphics` and `color` packages, which need special help from the device driver—the program that turns the `dvi` file into the output you see. Different device drivers may require different `dvi` files, which are created by giving different options to the `\usepackage` commands that load the `graphics` and `color` packages.

Eventually, these special features should be available with all device drivers. However, when $\text{\LaTeX 2}_\epsilon$ is first released, some drivers will not implement these features, and some drivers may implement only some of them. Check the *Local Guide* to find out about the device drivers on your computer.

7.1 Pictures

The `picture` environment is used to draw pictures composed of text, straight lines, arrows, circles, and simple curves. This environment and its associated commands are implemented with standard $\text{\TeX}$; they do not require special support from the device driver. However, the `pict2e` package uses device-driver support to provide enhanced versions of these commands that remove some of their restrictions. The enhanced commands can draw straight lines and arrows of any slope, circles of any size, and lines (straight and curved) of any thickness.

In the `picture` environment, you position objects in a picture by specifying their x and y coordinates. So, before getting to the picture-making commands, let us first review a little bit of coordinate geometry.

A *coordinate* is a number such as 5, -7 , 2.3, or -3.1416 . Given an *origin* and a *unit length*, a pair of coordinates specifies a position. As shown in Figure 7.1, the coordinate pair $(-1.8, 1)$ specifies the position reached by starting at the origin and moving left 1.8 units and up 1 unit.

The unit length used in determining positions in a `picture` environment is the value of the length command `\unitlength`. Not just positions but all lengths in a `picture` environment are specified in terms of `\unitlength`. Its default value is 1 point (about $1/72^{\text{nd}}$ of an inch or .35mm), but it can be changed with the `\setlength` command described in Section 6.4.1. Changing the value of `\unitlength` magnifies or reduces a picture—halving the value halves the lengths of all lines and the diameters of all circles. This makes it easy to adjust the size of a picture. However, changing `\unitlength` does not change the widths of lines or the size of text characters, so it does not provide true magnification and reduction. (The `graphics` package, described in Section 7.2, provides true magnifying and reducing commands.)

$\text{\LaTeX}$ provides two standard thicknesses for the lines in a picture—thin as in  and thick as in . They are specified by the declarations `\thinlines`




Figure 7.1: Points and their coordinates.

and `\thicklines`, with `\thinlines` as the default. These commands are ordinary declarations and can be used at any time.

Many picture-drawing commands have a coordinate pair as an argument. Such an argument is not enclosed in braces, but is just typed with parentheses and a comma, as in `(-2,3.7)` or `(0,-17.2)`.

7.1.1 The `picture` Environment

The `picture` environment has a coordinate-pair argument that specifies the picture's size (in terms of `\unitlength`). The environment produces a box (Section 6.4.3) whose width and height are given by the two coordinates. The origin's default position is the lower-left corner of this box. However, the `picture` environment has an optional second coordinate-pair argument that specifies the coordinates of the box's lower-left corner, thereby determining the position of the origin. For example, the command

```
\begin{picture}(100,200)(10,20)
```

produces a picture of width 100 units and height 200 units, whose lower-left corner has coordinates `(10,20)`, so the upper-right corner has coordinates `(110,220)`. Unlike ordinary optional arguments, the `picture` environment's optional argument is not enclosed in square brackets.

When first drawing a picture, you will usually omit the optional argument, leaving the origin at the lower-left corner. Later, if you want to modify the picture by shifting everything, you just add the appropriate optional argument.

The environment's first argument specifies the nominal size of the picture, which is used by `TeX` to determine how much room to leave for it. This need

bear no relation to how large the picture really is; L^AT_EX allows you to draw things outside the picture, or even off the page.

The `\begin{picture}` command puts L^AT_EX in *picture mode*, a special mode that occurs nowhere else.¹ The only things that can appear in picture mode are `\put`, `\multiput`, `\qbezier`, and `\graphpaper` commands (described below) and declarations such as `\em`, `\thicklines`, and `\setlength`. You should not change `\unitlength` in picture mode.

The examples in this section all illustrate commands in picture mode, but the `\begin{picture}` and `\end{picture}` commands are not shown. To help you think in terms of arbitrary unit lengths, the examples assume different values of `\unitlength`. They are all drawn with the `\thicklines` declaration in effect. The pictures in the examples also contain lines and arrows, not produced by the commands being illustrated, that indicate positions and dimensions; these are drawn with `\thinlines` in effect, allowing you to compare the two line thicknesses.

Remember that the `picture` environment produces a box, which T_EX treats just like a single (usually) large letter. See Section 6.5 for commands and environments to position the entire picture on the page. All the picture-drawing commands described in this section are fragile.

7.1.2 Picture Objects

Most things in a picture are drawn by the `\put` command. The command

```
\put (11.3,-.3){picture object}
```

puts the *picture object* in the picture with its *reference point* having coordinates (11.3, −.3). The various kinds of picture objects and their reference points are described below.

Text


The simplest kind of picture object is ordinary text, which is typeset in LR mode to produce a box with the usual reference point (see Section 6.4.3).

(2.3, 5) ↗
gang of armadillos \put(2.3,5){gang of armadillos}


Boxes

A box picture object is made with the `\makebox` or `\framebox` command. These commands, and the related `\savebox` command, have a special form for use with pictures. The first argument is a coordinate pair that specifies the width and height of the box.

¹L^AT_EX's picture mode is really a restricted form of LR mode.




The reference point is the lower-left corner of the box. The default is to center the text both horizontally and vertically within the box, but an optional argument specifies other positioning. This argument consists of one or two of the following letters: **l** (left), **r** (right), **t** (top), and **b** (bottom). The letters in a two-letter argument can appear in either order.




Unlike the ordinary `\framebox` command described in Section 6.4.3, the picture-making version adds no space between the frame and the text. There is a corresponding version of `\makebox` that works the same as `\framebox` except it does not draw the frame. These picture-making versions are used mainly as picture objects, although they can be used anywhere that an ordinary box-making command can.

The discussion of zero-width boxes in Section 6.4.4 should explain why a `\makebox(0,0)` command with no positioning argument puts the center of the text on the reference point, and with a positioning argument puts the indicated edge or corner of the text on the reference point.



A `\makebox(0,0)` command is very useful for positioning text in a picture.

The `\dashbox` command is similar to `\framebox` but draws the frame with dashed lines. It has an additional first argument that specifies the width of each dash.



A dashed box looks best when the width and the height are both multiples of the dash length—in this example, the width is ten times and the height four times the length of a dash.

Straight Lines

Straight lines can be drawn with only a fixed, though fairly large, choice of slopes. A line is not specified by giving its endpoints, since that might produce a slope not in L^AT_EX's repertoire. Instead, the slope and length of the line are specified. L^AT_EX's method of describing slope and length was chosen to make designing pictures easier, but it requires a bit of explanation.

The `\line` command produces a picture object that is a straight line, with one end of the line as its reference point. The command has the form

`\line(x,y){len}`

where the coordinate pair (x, y) specifies the slope and *len* specifies the length, in a manner I will now describe. (Figure 7.2 illustrates the following explanation with a particular example.) Let p_0 be the reference point, and suppose its coordinates are (x_0, y_0) . Starting at p_0 , move x units to the right and y units up to find the point p_1 , so p_1 has coordinates $(x_0 + x, y_0 + y)$. (Negative distances have the expected meaning: moving right a distance of -2 units means moving 2 units to the left, and moving up -2 units means moving down 2 units.) The line drawn by this command lies along the straight line through p_0 and p_1 . It starts at p_0 and goes in the direction of p_1 a distance determined as follows by *len*. If the line is not vertical ($x \neq 0$), it extends *len* units horizontally to the right or left of p_0 (depending upon whether x is positive or negative). If the line is vertical ($x = 0$), it extends *len* units above or below p_0 (depending upon whether y is positive or negative).

The *len* argument therefore specifies the line's horizontal extent, except for a vertical line, which has no horizontal extent, where it specifies the vertical




Figure 7.2: `\put (1.4,2.6){\line(3,-1){4.8}}`


distance. It equals the actual length of the line only for horizontal and vertical lines. The value of *len* must be nonnegative.

Since only a fixed number of slopes are available, there are only a limited number of values that x and y can assume. They must both be integers (numbers without decimal points) between -6 and $+6$, inclusive. Moreover, they can have no common divisor bigger than one. In other words, x/y must be a fraction in its simplest form, so you can't let $x = 2$ and $y = -4$; you must use $x = 1$ and $y = -2$ instead. The following are all *illegal* arguments of a `\line` command: $(1.4, 3)$, $(3, 6)$, $(0, 2)$, and $(1, 7)$.

$\text{\LaTeX}$ draws slanted (neither horizontal nor vertical) lines using a special font whose characters consist of small line segments. This means that there is a smallest slanted line that $\text{\LaTeX}$ can draw—its length is about 10 points, or $1/7$ inch. If you try to draw a smaller slanted line, $\text{\LaTeX}$ will print nothing. It also means that $\text{\LaTeX}$ must print lots of line segments to make up a long slanted line, so drawing a lot of slanted lines can take a long time and can use up a lot of $\text{\TeX}$'s memory. However, $\text{\LaTeX}$ draws a horizontal or vertical line of any length quickly, without using much memory.

Arrows

An arrow—a straight line ending in an arrowhead—is made by the `\vector` command. It works exactly like the `\line` command.



The tip of the arrowhead lies on the endpoint of the line opposite the reference point. This makes any normal-length arrow point away from the reference point. However, for an arrow of length zero, both endpoints lie on the reference point, so the tip of the arrow is at the reference point.

$\text{\LaTeX}$ can't draw arrows with as many different slopes as it can draw lines. The pair of integers specifying the slope in a `\vector` command must lie between -4 and $+4$, inclusive; as with the `\line` command, they must have no common divisor.

Stacks

The `\shortstack` command produces a box containing a single column of text with the reference point at its lower-left corner. Its argument contains the text, rows being separated by a `\\` command. The `\shortstack` command is much like a one-column `tabular` environment (Section 3.6.2), but the space between rows is designed for a vertical column of text in a picture. The default alignment

is to center each row in the column, but an optional positioning argument of `l` (left) or `r` (right) aligns the text on the indicated edge.

Gnats
and
gnus
(1, 7) ↗

May
break
my
(3, 7) ↗

Sh
o
e
s
(5, 7) ↗

```
\put(1,7){\shortstack{Gnats\\ and \\ gnus}}
\put(3,7){\shortstack[r]{May\\ break \\my}}
\put(5,7){\shortstack[l]{Sh\\o\\e\\s}}
```

Unlike an ordinary `tabular` environment, rows are not evenly spaced. You can change the inter-row spacing by using either the `\shortstack` command's optional argument (Section C.1.6) or a strut (Section 6.4.3). The `\shortstack` command is an ordinary box-making command that can be used anywhere, but it seldom appears outside a `picture` environment.

Circles

The `\circle` command draws a circle of the indicated diameter, with the center of the circle as reference point, and the `\circle*` command draws a disk (a circle with the center filled in). $\text{\LaTeX}$ has only a fixed collection of circles and disks; the `\circle` and `\circle*` commands choose the one whose diameter is closest to the specified diameter.




```
\put(20,0){\circle{20}}
\put(20,0){\vector(0,1){10}}
\put(50,0){\circle*{5}}
```

On my computer, the largest circle that $\text{\LaTeX}$ can draw has a diameter of 40 points (a little more than 1/2 inch) and the largest disk has a diameter of 15 points (about .2 inch). Consult the *Local Guide* to find out what size circles and disks are available on your computer.

Ovals and Rounded Corners


An oval is a rectangle with rounded corners—that is, a rectangle whose corners are replaced by quarter circles. It is generated with the `\oval` command, whose argument specifies the width and height, the reference point being the center of the oval. $\text{\LaTeX}$ draws the oval with corners as round as possible, using quarter circles with the largest possible radius.



```
\put(1.1,-4){\oval(8,3.1)}
```

Giving an optional argument to the `\oval` command causes $\text{\LaTeX}$ to draw only half or a quarter of the complete oval. The argument is one or two of the letters `l` (left), `r` (right), `t` (top), and `b` (bottom), a one-letter argument specifying

a half oval and a two-letter argument specifying a quarter oval. The size and reference point are determined as if the complete oval were being drawn; the optional argument serves only to suppress the unwanted part.




Joining a quarter oval to straight lines produces a rounded corner. It takes a bit of calculating to figure out where to `\put` the quarter oval.




Framing

The `\framebox` command puts a frame of a specified size around an object. It is often convenient to let the size of the object determine the size of the frame. The `\fbox` command described in Section 6.4.3 does this, but it puts extra space around the object that you may not want in a picture. The `\frame` command works very much like `\fbox` except it doesn't add any extra space.




7.1.3 Curves

The `\qbezier` command takes three points as arguments and draws a quadratic Bezier curve with those as its control points. A quadratic Bezier curve with control points P_1 , P_2 , P_3 is a curve from P_1 to P_3 such that the line from P_1 to P_2 is tangent to the curve at P_1 , and the line from P_3 to P_2 is tangent to the curve at P_3 .




For two curves (or a curve and a straight line) to join smoothly, they must have the same tangent at the point where they meet. Bezier control points therefore provide a convenient way of specifying a curve.

$\text{\LaTeX}$ draws curves by drawing lots of individual points. (This does not apply to the `pict2e` package's enhanced version.) Each point takes time to draw and takes memory space, so $\text{\LaTeX}$ does not draw a completely smooth curve. The `\qbeziermax` command specifies the maximum number of points $\text{\LaTeX}$ will normally plot for a single `\qbezier` command. (It can be changed with `\renewcommand`.) However, an optional argument to `\qbezier` allows you to tell $\text{\LaTeX}$ exactly how many points to plot.




7.1.4 Grids

The `graphpap` package defines the `graphpaper` command, which draws a numbered coordinate grid. The command's first argument specifies the coordinates of the lower-left corner of the grid, and its second argument specifies the grid's width and height.




The grid normally consists of one line every 10 units, but an optional first argument allows you to specify a different spacing.



The arguments of `\graphpaper` can contain only integers.

7.1.5 Reusing Objects

The `\savebox` command described in Section 6.4.3 is similar to `\makebox` except that, instead of being drawn, the box is saved in the indicated storage bin. Like `\makebox`, the `\savebox` command has a form in which the size of the box is indicated by a coordinate pair, with positioning determined by an optional argument.



The storage bin `\toy` in this example must be defined with `\newsavebox`. A `\savebox` command can be used inside a `picture` environment to save an object that appears several times in that picture, or outside to save an object that appears in more than one picture. Remember that `\savebox` is a declaration with the normal scoping rules.

It can take $\text{\LaTeX}$ a long time to draw a picture, especially if it contains slanted lines, so it's a good idea to use `\savebox` whenever an object appears in different pictures or in different places within the same picture. However, a saved box also uses memory, so a picture should be saved no longer than necessary. The space used by a saved box is reclaimed upon leaving the scope of the `\savebox` declaration. You can also use a command like `\sbox{\toy}{}{}`, which destroys the contents of storage bin `\toy` and reclaims its space.

7.1.6 Repeated Patterns

Pictures often contain repeated patterns formed by regularly spaced copies of the same object. Instead of using a sequence of `\put` commands, such a pattern


can be drawn with a `\multiput` command. For any coordinate pairs (x, y) and $(\Delta x, \Delta y)$, the command

```
\multiput(x,y)(\Delta x,\Delta y){17}{object}
```

puts 17 copies of *object* in the picture, starting at position (x, y) and stepping the position by $(\Delta x, \Delta y)$ units each time. It is equivalent to the 17 commands

```
\put(x,y){object}
\put(x+\Delta x,y+\Delta y){object}
\put(x+2\Delta x,y+2\Delta y){object}
...
\put(x+16\Delta x,y+16\Delta y){object}
```

as illustrated by the following example:



```
\multiput(3,2.4)(5.2,-1.3){4}{\circle*{.3}}
```

You can make a two-dimensional pattern by using a `picture` environment containing another `\multiput` in the argument of a `\multiput` command. However, `\multiput` typesets the object anew for each copy it makes, so it is much more efficient to make a two-dimensional pattern by saving a one-dimensional pattern made with `\multiput` in a storage bin, then repeating it with another `\multiput`. Saving the object in a bin can also save processing time for a one-dimensional pattern. However, patterns with too many repetitions in all may cause $\text{\TeX}$ to run out of memory.

7.1.7 Some Hints on Drawing Pictures

As you gain experience with the `picture` environment, you'll develop your own techniques for designing pictures. Here are a few hints to get you started.

If you use a small unit length, such as the default value of 1 point, you will seldom need decimals.

It can take quite a bit of trial and error to get a picture right. Use a screen previewer, and run $\text{\LaTeX}$ on a file containing just the picture.

Make a coordinate grid with the `\graphpaper` command, and use it for placing objects.

If you are not afraid of math, you will find that a few simple calculations can save a lot of trial and error—especially when drawing slanted lines and arrows.

It's a good idea to break a complicated picture into "subpictures". The subpicture is drawn in a separate `picture` environment inside a `\put` argument, as in

```
\put(13,14.2){\begin{picture}(10,7) ... \end{picture}}
```

This permits easy repositioning of the subpicture and allows you to work in terms of local coordinates relative to the subpicture's origin instead of calculating the position of every picture component with respect to a single origin. You can also magnify or reduce just the subpicture by changing the value of `\unitlength` with a `\setlength` command in the `\put` command's argument—but don't leave any space after the `\setlength` command.

A small mistake in a picture-drawing command can produce strange results. It's usually simple to track down such an error, so don't panic when a picture turns out all wrong. If you find that some part of the picture is incorrectly positioned by a small amount, check for stray spaces in the argument of the `\put` command. Remember that this argument is typeset in LR mode, so a space before or after an object produces space in the output.

7.2 The graphics Package

The `graphics` package defines commands for performing geometric transformations and including graphics prepared with other computer programs. The geometric transformations are scaling, rotation, and reflection. These transformations may be applied to any text including ordinary letters and words, but they are usually applied to pictures made with the `picture` environment and included graphics. This package requires support from the device driver; see the remarks at the beginning of this chapter.

The package provides two scaling commands, `\scalebox` and `\resizebox`. The `\scalebox` command allows you to enlarge or reduce any text by a constant scale factor.

great big gnat

regular gnat

tiny gnat

```
\scalebox{2}{great big gnat}
```

```
regular gnat
```

```
\scalebox{.5}{tiny gnat}
```

An optional second argument specifies a separate vertical scale factor.

tall skinny gnat

```
\scalebox{.75}[2]{tall skinny gnat}
```

The `\resizebox` allows you to scale text to a desired size. Its two arguments specify the width and height of the box that it produces. Using `!` for either argument maintains the aspect ratio of the text.

fat gnat

fat gnat

```
\resizebox{5cm}{.4cm}{fat gnat}
```

```
\resizebox{2cm}{!}{fat gnat}
```

Both `\scalebox` and `\resizebox` typeset their text argument in LR mode. They produce a box whose reference point is the same as the reference point of the original unscaled box.

The `\rotatebox` command rotates text by a specified angle. In the following examples, the sizes and reference points of boxes are shown.

  `gnu \rotatebox{30}{gnu}`

The `\rotatebox` command typesets its text argument in LR mode. It produces a box whose reference point is at the same height as the rotated reference point of the original text.

   `gnu
\rotatebox{180}{gnu}
\rotatebox{270}{gnu}`

The `\reflectbox` command typesets its argument in LR mode and then produces its mirror image.

  `gnu \reflectbox{gnu}`


Graphics produced by another program can be included in your document with the `\includegraphics` command. The following example assumes that the file `LA83.fun` contains a picture in a form that the device driver can handle.



`\includegraphics{LA83.fun}`

In this example, the size of the box is specified by the file `LA83.fun`. Some graphics files do not include a size specification. In that case, $\text{\LaTeX}$ will produce an error message, and you will have to specify the size yourself using optional arguments to the `\includegraphics` command. In the next example, the first

picture shows what is actually in the file `jason.eps` and the second shows the output of the `\includegraphics` command.²



```
\includegraphics*
[10mm,15mm][30mm,27mm]{jason.eps}
```

The optional arguments to `\includegraphics` override any size specification in the file itself. However, the box specified by the file (and produced by `\includegraphics` with no optional argument) might not contain the entire picture. A command such as

```
\resizebox{\textwidth}{!}
{\includegraphics[0in,0in][8in,10in]{jason.eps}}
```

will show you what is actually in the file `jason.eps`.

The `draft` option causes the `\includegraphics` command to print a box containing the name of the file rather than the contents of the file. This option is specified either by typing

```
\usepackage[draft]{graphics}
```

or by specifying the `draft` document-class option (Section 2.2.2). A final option in the `\usepackage` command counteracts the effects of a `draft` document-class option.

7.3 Color

You can produce colored text with the `\textcolor` command or the corresponding `\color` declaration. (To keep the cost of this book down, colors are indicated by shades of gray.)

CECI N'EST PAS UNE PIPE ROUGE.

```
... UNE \textcolor{red}{PIPE} ROUGE.
```

CECI N'EST PAS UNE PIPE NOIRE.

```
\color{red}
... UNE {\color{black} PIPE} NOIRE.
```

²Without the `*` after `\includegraphics`, the entire picture would be printed, although TeX would leave only enough space for the small rectangle.

The `\colorbox` command typesets its argument in LR mode on a rectangular background of a specified color.

UNE PIPE ROUGE

```
\colorbox{red}{UNE PIPE ROUGE}
```

The command `\fcolorbox{blue}{red}{UNE...}` puts a blue border around the red rectangle.

A `\pagecolor{green}` declaration causes the background of the entire page to be green. It is a global declaration that applies to the current page and all subsequent pages, until countermanded by another `\pagecolor` command.

The following colors are predefined: **black**, **white**, **red**, **green**, **blue**, **yellow**, **cyan**, and **magenta**. The `\definecolor` command allows you to define your own colors in terms of a *color model*. In the **rgb** color model, a color is specified by three numbers, ranging from 0 to 1, that represent the amounts of red, green, and blue light required to produce it. For example, magenta is produced by mixing equal amounts of red and blue light, so it is defined by

```
\definecolor{magenta}{rgb}{1,0,1}
```

A darker shade of magenta is defined by

```
\definecolor{darkmagenta}{rgb}{.5,0,.5}
```

In the **gray** color model, a shade of gray is specified by a single number ranging from 0 (black) to 1 (white).

A dark gray box.

```
\definecolor{dark}{gray}{.5}
\colorbox{dark}{A dark gray box.}
```

A light gray box.

```
\definecolor{light}{gray}{.75}
\colorbox{light}{A light gray box.}
```

L^AT_EX also supports the **cm_yk** model, popular with (human) printers, in which a color is specified by values of cyan, magenta, yellow, and black ranging from 0 to 1. Other color models may be available on your computer, including ones in which a color is specified by a name. Check your *Local Guide*.

After L^AT_EX 2_ε is released, there may be a period when some drivers will not handle color commands properly. Check your output carefully, especially when the scope of a color declaration spans pages—for example if the declaration appears in a footnote that is split across pages.

CHAPTER 8

Errors



Section 2.3 describes first aid for handling errors; it explains how to deal with simple errors. This chapter is for use when you encounter an error or warning message that you don't understand. The following section tells how to locate the error; the remaining sections explain the meaning of specific error and warning messages.

As you saw in Section 2.3, an error can confuse L^AT_EX and cause it to produce spurious error messages when processing subsequent text that is perfectly all right. Such spurious errors are not discussed here. When T_EX writes a page of output, it has usually recovered from the effects of any previous errors, so the next error message probably indicates a real error. The following section explains how to tell when T_EX has written an output page.

8.1 Finding the Error

As described in Section 2.3, an error message includes an error indicator stating what T_EX thinks the problem is, and an error locator that shows how much of your input file T_EX had read when it found the error. Most of the time, the line printed in the error locator displays an obvious error in the input. Typing H can also provide useful information. If you don't see what's wrong, look up the error message in the following sections to find its probable cause. If you still don't see what's wrong, the first thing to do is locate exactly where the error occurred.

The error locator starts with a line number such as 1.14, meaning that the error was found while L^AT_EX was processing the fourteenth line from the beginning of the file. If your input is all on a single file, then the error locator unambiguously identifies where T_EX thinks the problem is. However, if you're using the commands of Section 4.4 to split your input into several files, then you also must know what file the error is in. Whenever T_EX starts processing a file, it prints on your terminal (and on the log file) a "(" followed by the file name, and it prints a ")" when it finishes processing the file. For example, the terminal output

```
... (myfile.tex [1] [2] [3] (part1.tex [4] [5]) (part2.tex [6] [7]
! Undefined control sequence.
1.249 \today
?
```

tells you that the error (a misspelled `\today` command) is on line 249 of the file `part2.tex`, which was included by an `\input` or `\include` command contained in the file `myfile.tex`. T_EX had completely processed the file `part1.tex`, which was also read by a command in `myfile.tex`.

The error locator tells you how much of the input file T_EX had processed before it discovered the error; the last command that T_EX processed is usually the source of the problem. There is one important exception; but before discussing it, a digression is in order.

Logically, typesetting can be viewed as a two-step process: first the document is typeset on one continuous scroll that unrolls vertically, then the scroll is cut into individual pages to which headings and page numbers are added. (Since a 50-yard scroll of metal type is somewhat unwieldy, printers partition the logical scroll into convenient lengths called galleys.) Instead of first producing the entire scroll and then cutting it into pages, $\text{\TeX}$ does both steps together, alternately putting output on the scroll with one hand and cutting off a page with the other. It usually puts text on the scroll one paragraph unit (Section 6.2.1) at a time. After each paragraph unit, it checks whether there's enough for a page. If so, it cuts off the page, adds the heading and page number, and writes the page on the `dvi` file. This way, $\text{\TeX}$ doesn't have to keep much more than one page of text in the computer's memory at a time.

Whenever $\text{\TeX}$ writes a page on its output file, it prints the page number on the terminal, enclosed in square brackets. Thus, any message that appears on the terminal after $\text{\TeX}$ prints [27] and before it prints [28] was generated between the time $\text{\TeX}$ wrote output pages 27 and 28. Whatever generated the message probably appeared in the text printed on page 28. However, it might also be in the text that was left on the scroll when $\text{\TeX}$ cut off page 28, putting it in the first paragraph of page 29. Most of $\text{\LaTeX}$'s warning messages are generated by $\text{\TeX}$'s scroll-making hand. It reports that a problem is on page 28 if it is detected between the time $\text{\TeX}$ writes pages 27 and 28, so the problem could actually appear at the top of page 29.

Now, let's get back to locating an error. Most errors are discovered while $\text{\TeX}$ is producing the scroll, but some errors, which I will call *outputting* errors, are detected while it is cutting off a page. $\text{\TeX}$ identifies an outputting error by printing `<output>` on the terminal at the beginning of a line somewhere above the error locator. For an outputting error, the error locator shows how far $\text{\TeX}$ got when it was producing the scroll; the actual error occurred at or before that point. An outputting error is usually caused by a fragile command in a moving argument.

An error can occur while $\text{\LaTeX}$ is processing the `\begin{document}` or `\end{document}` command, when it reads the auxiliary files it has written. You can tell that this has happened because the output on your terminal shows that $\text{\TeX}$ is reading a file with the extension `aux`. Such an error means that there is bad information on the auxiliary file. An error while processing the `\begin{document}` was caused by an error the last time you ran $\text{\LaTeX}$. An error while processing the `\end{document}` is usually caused by a fragile command in a moving argument.

An error that occurs while $\text{\LaTeX}$ is processing a `toc`, `lof`, or `lot` file means that there is an error in a table of contents, list of figures, or list of tables entry. This error was caused by an error in a `\caption` or sectioning command—perhaps a fragile command in the argument—the previous time $\text{\LaTeX}$ was run on the file.

When the terminal output doesn't quickly lead you to the source of the error, look at the printed output (on your screen previewer). If $\text{\LaTeX}$ reaches the end of your input or is stopped with a `\stop` command, the printed output will contain everything it has put on the scroll, and the location of the error will probably be obvious. If you stopped $\text{\LaTeX}$ by typing an `X`, then it will not print what was left on the scroll after the last full page was written out. Since the error probably occurred in this leftover text, the output will just narrow the possible location of the error.

If you still can't find the error, your next step is to find the smallest piece of your input file that produces the error. Start by eliminating everything between the `\begin{document}` and the last page or so of output. Then keep cutting the input in half, throwing away the part that does not cause the error. This should quickly lead to the source of the problem.

When all else fails, consult your *Local Guide* to find a $\text{\LaTeX}$ expert near you.

8.2 $\text{\LaTeX}$'s Error Messages

Here is an alphabetical list of most of $\text{\LaTeX}$'s error indicators (with the initial “! $\text{\LaTeX}$ Error:” omitted), together with their causes. Not listed are indicators for errors caused by a bad document class, some errors for which typing `H` provides a clear explanation, and many errors produced only when a particular package is used.

Bad `\line` or `\vector` argument.

A `\line` or `\vector` command specified a negative length or an illegal slope. Look up the constraints on these commands in Section 7.1.

Bad math environment delimiter.

$\text{\LaTeX}$ has found either a math-mode-starting command such as `\[` or `\(` when it is already in math mode, or else a math-mode-ending command such as `\)` or `\]` while in LR or paragraph mode. The problem is caused by either unmatched math mode delimiters or unbalanced braces.

`\begin{...}` on input line ... ended by `\end{...}`.

$\text{\LaTeX}$ has found an `\end` command that doesn't match the corresponding `\begin` command. You probably misspelled the environment name in the `\end` command, have an extra `\begin`, or else forgot an `\end`.

Can be used only in preamble.

$\text{\LaTeX}$ has encountered, after the `\begin{document}`, a command that should appear only in the preamble, such as `\usepackage`, `\nofiles`, `\includeonly`, or `\makeindex`. The error is also caused by an extra `\begin{document}` command.

Cannot determine size of graphic in ... (no BoundingBox).

An `\includegraphics` command with no optional arguments read a file that does not specify the size of the box to be produced (graphics package only).

Command ... already defined.

You are using `\newcommand`, `\newenvironment`, `\newlength`, `\newsavebox`, or `\newtheorem` to define a command or environment name that is already defined, or `\newcounter` to define a counter that already exists. (Defining an environment named `gnu` automatically defines the command `\gnu`.) You'll have to choose a new name or, in the case of `\newcommand` or `\newenvironment`, switch to the `\renew...` command.

Command ... invalid in math mode.

The indicated command is not permitted in math mode but was used there.

Counter too large.

Some object that is numbered with letters or with footnote symbols has received too large a number. You're probably either making a very long enumerated list or resetting counter values.

Environment ... undefined.

L^AT_EX has encountered a `\begin` command for a nonexistent environment. You probably misspelled the environment name. This error can be corrected on the spot by typing an `I` followed by the correct command, ending with a *return*. (This does not change the input file.)

File ... not found.

L^AT_EX is trying to read a file that doesn't exist. If the missing file has the extension `tex`, then it is trying to `\input` or `\include` a nonexistent file; if it has the extension `cls`, then you have specified a nonexistent document class; if it has the extension `sty`, then you have specified a nonexistent package. L^AT_EX is waiting for you either to type another file name followed by *return*, or to type *return* to continue without reading any file.

Illegal character in array arg.

There is an illegal character in the argument of an `array` or `tabular` environment, or in the second argument of a `\multicolumn` command.

`\include` cannot be nested.

Your document `\include`'s a file containing an `\include` command.

Lonely `\item`--perhaps a missing list environment.

An `\item` command appears outside any list environment.

Missing `\begin{document}`.

L^AT_EX produced printed output before encountering a `\begin{document}` command. Either you forgot the `\begin{document}` command or there is something wrong in the preamble. The problem may be a stray character or an error in a declaration—for example, omitting the braces around an argument or forgetting the `\` in a command name.

Missing p-arg in array arg.

There is a `p` that is not followed by an expression in braces in the argument of an `array` or `tabular` environment, or in the second argument of a `\multicolumn` command.

Missing @-exp in array arg.

There is an `@` character not followed by an `@`-expression in the argument of an `array` or `tabular` environment, or in the second argument of a `\multicolumn` command.

No counter ‘...’ defined.

You have specified a nonexistent counter in a `\setcounter` or `\addtocounter` command, or in an optional argument to a `\newcounter` or `\newtheorem` command. You probably mistyped the counter name. However, if the error occurred while a file with the extension `aux` is being read, then you probably used a `\newcounter` command in an `\include`’d file.

No `\title` given.

A `\maketitle` command is not preceded by a `\title` command.

Not in outer par mode.

You had a `figure` or `table` environment or a `\marginpar` command in `math` mode or inside a `parbox`.

Option clash for package ...

The same package was loaded twice with different options. The package might have been loaded by another package.

`\pushtabs` and `\poptabs` don’t match.

L^AT_EX found a `\poptabs` with no matching `\pushtabs`, or has come to the `\end{tabbing}` command with one or more unmatched `\pushtabs` commands.

Something’s wrong--perhaps a missing `\item`.

There are many possible causes, including an omitted `\item` command in a list-making environment and a missing argument of a `thebibliography` environment.

Tab overflow.

A `\=` command has exceeded the maximum number of tab stops that L^AT_EX permits.

There's no line here to end.

A `\newline` or `\\` command appears between paragraphs, where it makes no sense. If you are trying to “leave a blank line”, use a `\vspace` command (Section 6.4.2).

This file needs format ... but this is ...

The document uses a document class or package that is not compatible with the version of L^AT_EX you are running. If you are using only standard files, then there is something wrong with the installation of L^AT_EX on your computer.

This may be a LaTeX bug.

L^AT_EX has become thoroughly confused. This is probably due to a previously detected error, but it is possible that you have discovered an error in L^AT_EX itself. If this is the first error message produced by the input file and you can't find anything wrong, save the file and contact the person listed in your *Local Guide*.

Too deeply nested.

There are too many list-making environments nested within one another. How many levels of nesting are permitted may depend upon what computer you are using, but at least four levels are provided, which should be enough.

Too many columns in eqnarray environment.

An `eqnarray` environment contains three `&` column separators without an intervening `\\` command.

Too many unprocessed floats.

While this error can result from having too many `\marginpar` commands on a page, a more likely cause is forcing L^AT_EX to save more figures and tables than it has room for. When typesetting its continuous scroll, L^AT_EX saves figures and tables separately and inserts them as it cuts off pages. This error occurs when L^AT_EX is forced to save too many `figure` and/or `table` environments. A likely cause is a logjam—a figure or table that cannot be printed, causing others to pile up behind it, since L^AT_EX will not print figures or tables out of order. The jam can be started by a figure or table that won't fit where its optional placement argument (Section C.9.1) says it must go. See the discussion of L^AT_EX's figure-placement algorithm in Section C.9.1.

Undefined color ‘...’.

The indicated color name is used without having been defined by a `\definecolor` command (color package only).

Undefined color model ‘...’.

A `\definecolor` command specifies an unknown color model (color package only).

Undefined tab position.

A `\>`, `\+`, `\-`, or `\<` command is trying to go to a nonexistent tab position—one not defined by a `\=` command.

Unknown graphics extension ...

The `graphics` package’s `\includegraphics` command uses the file’s extension to determine what kind of program produced the file. This error occurs when the file name does not have an extension known to the package. Consult the *Local Guide* to see what file extensions you can use.

Unknown option ... for ...

The `\documentclass` command or a `\usepackage` command specifies an illegal option for the class or package.

`\verb` ended by end of line.

The argument of a `\verb` command extends beyond the current line. You may have forgotten the character that ends the argument.

`\verb` illegal in command argument.

A `\verb` command appears in the argument of another command.

`\<` in mid line.

A `\<` command appears in the middle of a line in a `tabbing` environment. This command should come only at the beginning of a line.

8.3 T_EX’s Error Messages

Here is an alphabetical list of some of T_EX’s error messages and what may have caused them.

! Double subscript.

There are two subscripts in a row in a mathematical formula—something like $x_{\{2\}_{\{3\}}}$, which makes no sense. To produce x_{2_3} , type `x_{2_{\{3\}}}`.

! Double superscript.

There are two superscripts in a row in a mathematical formula—something like $x^{\{2\}^{\{3\}}}$, which makes no sense. To produce x^{2^3} , type `x^{2^{\{3\}}}`.

! Extra alignment tab has been changed to `\cr`.

There are too many separate items (column entries) in a single row of an `array` or `tabular` environment. In other words, there were too many `&`'s before the end of the row. You probably forgot the `\\` at the end of the preceding row.

! Extra `}`, or forgotten `$`.

The braces or math mode delimiters don't match properly. You probably forgot a `{`, `\[`, `\(`, or `$`.

! I can't find file '`...`'.

You probably ran L^AT_EX on a nonexistent file. This error can also occur if you omitted the braces around an `\input` command.

! Illegal parameter number in definition of `...`.

This is probably caused by a `\newcommand`, `\renewcommand`, `\providecommand`, `\newenvironment`, or `\renewenvironment` command in which a `#` is used incorrectly. A `#` character, except as part of the command name `\#`, can be used only to indicate an argument parameter, as in `#2`, which denotes the second argument. This error is also caused by nesting one of the five commands listed above inside another, or by putting a parameter like `#2` in the last argument of a `\newenvironment` or `\renewenvironment` command.

! Illegal unit of measure (pt inserted).

If you just got a

! Missing number, treated as zero.

error, then this is part of the same problem. If not, it means that L^AT_EX was expecting a length as an argument and found a number instead. The most common cause of this error is writing `0` instead of something like `0in` for a length of zero, in which case typing *return* should result in correct output. However, the error can also be caused by omitting a command argument.

! Misplaced alignment tab character `&`.

The special character `&`, which should be used only to separate items in an `array` or `tabular` environment, appeared in ordinary text. You probably meant to type `\&`, in which case typing *I\&* followed by *return* in response to the error message should produce the correct output.

! Missing control sequence inserted.

This is probably caused by a `\newcommand`, `\renewcommand`, `\newlength`, or `\newsavebox` command whose first argument is not a command name.

! Missing number, treated as zero.

This is usually caused by a $\TeX$ command expecting but not finding either a number or a length as an argument. You may have omitted an argument, or a square bracket in the text may have been mistaken for the beginning of an optional argument. This error is also caused by putting `\protect` in front of either a length command or a command such as `\value` that produces a number.

! Missing { inserted.

! Missing } inserted.

$\TeX$ has become confused. The position indicated by the error locator is probably beyond the point where the incorrect input is.

! Missing \$ inserted.

$\TeX$ probably found a command that can be used only in math mode when it wasn't in math mode. Remember that unless stated otherwise, all the commands of Section 3.3 can be used only in math mode. $\TeX$ is not in math mode when it begins processing the argument of a box-making command, even if that command is inside a math environment. This error also occurs if $\TeX$ encounters a blank line when it is in math mode.

! Not a letter.

Something appears in the argument of a `\hyphenation` command that doesn't belong there.

! Paragraph ended before ... was complete.

A blank line occurred in a command argument that shouldn't contain one. You probably forgot the right brace at the end of an argument.

! TeX capacity exceeded, sorry [...].

$\TeX$ has just run out of space and aborted its execution. Before you panic, remember that the least likely cause of this error is $\TeX$ not having the capacity to process your document. It was probably an error in your input file that caused $\TeX$ to run out of room. For example, the following command makes a circular definition, defining `\gnu` in terms of itself:

```
\newcommand{\gnu}{a \gnu} % This is wrong!
```

When $\TeX$ encounters this `\gnu` command, it will keep chasing its tail trying to figure out what `\gnu` should produce, and eventually run out of space. $\mathTeX$ seldom runs out of space on a short input file, so if running it on the last few

pages before the error indicator's position still produces the error, then there's almost certainly something wrong in the input file. An error that causes T_EX to run out of space can be hard to find; you may have to use the divide and conquer method described in Section 8.1 to locate it.

Today's computers have enough memory to provide T_EX with all the space it needs to process almost any document. However, any particular version of T_EX uses only a fixed amount of space, and the version on your computer may not be big enough to process your document. In this case, you should try to get a bigger version. Meanwhile, by understanding why T_EX ran out of space, you can reduce the space it needs for your document. The end of the error indicator tells what kind of space T_EX ran out of. The kinds of space you are most likely to run out of are listed below, with an explanation of what uses them up.

buffer size Can be caused by too long a piece of text as the argument of a sectioning, `\caption`, `\addcontentsline`, or `\addtocontents` command. This error will probably occur when the `\end{document}` is being processed, but it could happen when a `\tableofcontents`, `\listoffigures`, or `\listoftables` command is executed. To solve this problem, use a shorter optional argument. Even if you're producing a table of contents or a list of figures or tables, such a long entry won't help the reader.

exception dictionary You have used `\hyphenation` commands to give T_EX more hyphenation information than it has room for. Remove some of the less frequently used words from the `\hyphenation` commands and insert `\-` commands instead.

hash size Your input file defines too many command names and/or uses too many cross-referencing labels.

main memory size This is one kind of space that T_EX can run out of when processing a short file. There are three ways you can run T_EX out of main memory space: (1) defining a lot of very long, complicated commands, (2) making an index or glossary and having too many `\index` or `\glossary` commands on a single page, and (3) creating so complicated a page of output that T_EX can't hold all the information needed to generate it.

The solution to the first two problems is obvious: define fewer commands or use fewer `\index` and `\glossary` commands. The third problem is nastier. It can be caused by large `tabbing`, `tabular`, `array`, and `picture` environments. (In particular, `\qbezier` commands can use a lot of main memory.) T_EX's space may also be filled up with figures and tables waiting for a place to go.

To find out if you've really exceeded T_EX's capacity in this way, put a `\clearpage` command in your input file right before the place where T_EX ran out of room and try running it again. If it doesn't run out of room

with the `\clearpage` command there, then you did exceed TeX's capacity. If it still runs out of room, then there's probably an error in your file.

If TeX is really out of room, you must give it some help. Remember that TeX processes a complete paragraph before deciding whether to cut the page. Inserting a `\newpage` command in the middle of the paragraph, where TeX should break the page, may save the day by letting TeX write out the current page before processing the rest of the paragraph. (A `\pagebreak` command won't help.) If the problem is caused by accumulated figures and tables, you can try to prevent them from accumulating—either by moving them further towards the end of the document or by trying to get them to come out sooner. (See Section C.9.1 for more details.) If you are still writing the document, simply add a `\clearpage` command and forget about the problem until you're ready to produce the final version. Changes to the input file are likely to make the problem go away.

pool size You probably used too many cross-referencing labels and/or defined too many new command names. More precisely, the labels and command names that you define have too many characters, so this problem can be solved by using shorter names. However, the error can also be caused by omitting the right brace that ends the argument of either a counter command such as `\setcounter`, or a `\newenvironment` or `\newtheorem` command.

save size This occurs when commands, environments, and the scopes of declarations are nested too deeply—for example, by having the argument of a `\multiput` command contain a `picture` environment that in turn has a `\footnotesize` declaration whose scope contains a `\multiput` command containing a ...

! Text line contains an invalid character.

The input file contains some strange nonprinting character (sometimes called a control character) that it shouldn't. Instead of using a simple text editor, you may have created the file with a program that does its own formatting. Such programs usually insert strange characters into a file unless you save it as a text (or ASCII) file.

! Undefined control sequence.

TeX encountered an unknown command name. You probably misspelled the name, in which case typing I followed by the desired command name and a *return* will produce correct output. However, you still must change the input file later. If this message occurs when a LaTeX command is being processed, the command is probably in the wrong place. The error can also be caused by a missing `\documentclass` or `\usepackage` command.

! Use of ... doesn't match its definition.

If the “...” is a L^AT_EX command, then it's probably one of the picture-drawing commands described in Section 7.1, and you have used the wrong syntax for specifying an argument. If it's `\@array` that doesn't match its definition, then there is something wrong in an `@`-expression in the argument of an `array` or `tabular` environment—perhaps a fragile command that is not `\protect`'ed. The error can also be caused by an `un\protect`'ed command with an optional argument appearing in a moving argument. (The “...” may or may not be the name of the command.)

! You can't use 'macro parameter character #' in ... mode.

The special character `#` has appeared in ordinary text. You probably meant to type `\#`, in which case you can respond to the error message by typing `I\#` followed by *return* to produce the correct output.

8.4 L^AT_EX Warnings

L^AT_EX's warning messages begin with “LaTeX Warning:”. (Some begin with an indication of the class of warning—for example, “LaTeX Font Warning:”.) The most common messages are described below. Certain classes of warnings cause L^AT_EX to print an additional message at the end to indicate that a warning of that class occurred.

Citation ‘...’ on page ... undefined.

The citation key in a `\cite` command was not defined by a `\bibitem` command. See Section 4.3.

Command ... invalid in math mode.

The indicated command is not permitted in math mode but was used there. Remember that `\boldmath`, `\unboldmath`, and size-changing commands may not be used in math mode.

Float too large for page by ...

A figure or table is too tall, by the indicated length, to fit on a page. It is printed by itself on an oversize page. The length is given in points.

Font shape ‘...’ in size ... not available.

You specified a font that is not available on your computer. The next line of the message describes what font L^AT_EX is using in its place. As explained in Section 3.3.8, this message can be caused by a `\boldmath` declaration even if the font is never used.

h float specifier changed to ht
!h float specifier changed to !ht
A figure or table environment has an optional argument h or !h, but the figure or table would not fit on the current page, so it is being put on the top of a subsequent page.

Label '...' multiply defined.

Two \label or \bibitem commands have the same arguments. More precisely, they had the same arguments the preceding time that L^AT_EX processed the input.

Label(s) may have changed. Rerun to get cross-references right.
Issued after processing the entire input if the numbers printed by \cite, \ref, or \pageref commands may be wrong because the correct values have changed since the last time L^AT_EX processed the input.

Marginpar on page ... moved.

A marginal note was moved down on the page to avoid printing it on top of a previous marginal note. It will therefore not be aligned with the line of text where the \marginpar command appeared.

No \author given.

A \maketitle command is not preceded by an \author command.

Optional argument of \twocolumn too tall on page ...

The optional argument of a \twocolumn command produced a box too large to fit on a page.

Oval too small.

An \oval command specified an oval so small that L^AT_EX could not draw small enough quarter-circles to put in its corners. What L^AT_EX did draw does not look very good.

Reference '...' on page ... undefined.

The argument of a \ref or \pageref command was not defined by a \label command. See Section 4.2.

Some font shapes were not available, defaults substituted.

Issued after processing the entire input if any unavailable font was specified.

There were multiply-defined labels.

Issued after processing the entire input if any label was defined by two different \label commands.

There were undefined references or citations.

Issued after processing the entire input if a `\ref` or `\cite` was found that had no corresponding `\label` or bibliography entry.

Unused global option(s): [...].

The listed options were given to the `\documentclass` command but were not known to it or to any packages that were loaded.

You have requested release ‘...’ of LaTeX, but only release ‘...’ is available.

You are using a document class or package that requires a later release of L^AT_EX than the one you are running. You should get the latest release of L^AT_EX.

8.5 T_EX Warnings

You can identify a T_EX warning message because it is not an error message, so no ? is printed, and it does not begin with “LaTeX Warning:”. Below is a list of some of T_EX’s warnings.

Overfull \hbox ...

See Section 6.2.1.

Overfull \vbox ...

Because it couldn’t find a good place for a page break, T_EX put more on the page than it should. See Section 6.2.2 for how to deal with page-breaking problems.

Underfull \hbox ...

Check your output for extra vertical space. If you find some, it was probably caused by a problem with a `\\` or `\newline` command—for example, two `\\` commands in succession. This warning can also be caused by using the `sloppypar` environment or `\sloppy` declaration, or by inserting a `\linebreak` command.

Underfull \vbox ...

T_EX could not find a good place to break the page, so it produced a page without enough text on it. See Section 6.2.2 for how to handle page-breaking problems.

APPENDIX A

Using *MakeIndex*



A.1 How to Use *MakeIndex*

MakeIndex is a program for making an index from information generated by `\index` commands in your document. Section A.2 below explains what `\index` commands to use to produce the index entries you want. To use *MakeIndex*, you must also put the following commands in your document:

- `\usepackage{makeidx}` in the preamble (between the `\documentclass` and `\begin{document}` commands).
- `\makeindex` in the preamble.
- `\printindex` where you want the index to appear—usually right before the `\end{document}` command.

Let's suppose that the root file (Section 4.4) of your document is `myfile.tex`. You first run `LATEX` on your entire document, which causes it to generate the file `myfile.idx` containing the information from your `\index` commands. You next run *MakeIndex* by typing something like

```
makeindex myfile
```

MakeIndex reads `myfile.idx` and produces the file `myfile.ind`. *MakeIndex* will reject an entry or issue a warning when it finds an error. If it doesn't find any, you can rerun `LATEX` on your document; `LATEX` will use `myfile.ind` to produce the index. If *MakeIndex* does find errors, see Section A.3 below.

By reading the index, you may discover additional mistakes. These should be corrected by changing the appropriate `\index` commands in the document and regenerating the `ind` file. If there are problems that cannot be corrected in this way, you can always edit the `ind` file directly. However, such editing is to be avoided because it must be repeated every time you generate a new version of the index.

MakeIndex can be customized in a variety of ways to make glossaries and other kinds of indexes. See the *L^AT_EX Companion* for details.

A.2 How to Generate Index Entries

A.2.1 When, Why, What, and How to Index

The index is there to help the reader find things in your document. It should make this as easy as possible. Many authors index words, listing all the pages on which a word appears. A good writer indexes concepts—ideas, facts, people, etc. Here is an entry from a word index and the corresponding entry from a concept index. Imagine using each of them to find out if there are gnus in Tasmania. (Page 150 tells you that there aren't.)

gnu, 17, 25, 54, 62, 64, 74, 101,
103, 104, 121, 124, 125,
150, 167, 202, 250

gnu,
caged, 104, 121, 125
distribution of, 25, 54, 150, 167
gnat and, 62, 64, 103, 124, 202
indexing, 74, 150, 250
size of, 17, 25, 101, 167

With the word index, you have to look at twelve pages before reaching the right one; with the concept index, you have to look at only two.

To make an index, you must first decide what concepts should appear in it. You must then figure out under what words a reader might look to find each concept. Try to understand who your readers are and how they think about the concept. Don't just list the words that you used to describe it.

You may be tempted to generate the index as you write the document. Resist the temptation. It is virtually impossible to make a good index that way. Add `\index` commands as you write to remind yourself of what you want to index, but be prepared to modify those commands when you produce the index.

A computer can't generate the index for you, but it can help. You have to decide whether gnus are central enough to your topic to appear in the index, and if so, where to direct the reader who wants to learn about them. The computer can help by finding all occurrences of "gnu". A good way to start writing an index is by making an alphabetized list of all the distinct words that appear in your document. Consult your *Local Guide* to see if your computer has a program to generate such a list.

Most books have indexes; most technical reports don't. They should. Any nonfiction work of more than twenty or so pages that is worth reading deserves an index. With $\text{\LaTeX}$ and *MakeIndex* doing the tedious work for you, there is no good reason not to make one.

A.2.2 The Basics

The following example shows some simple `\index` commands and the index entries that they produce using *MakeIndex*. The page number refers to the page containing the text where the `\index` command appears.

Alpha, ii	Page ii: <code>\index{Alpha}</code>
alpha, viii, ix, 22	Page viii: <code>\index{alpha}</code>
alpha bet, 24	Page ix: <code>\index{alpha}</code>
Alphabet, ix	<code>\index{Alphabet}</code>
alphabet, 23	Page 22: <code>\index{alpha}</code>
alphas, 22	<code>\index{alphas}</code>
	Page 23: <code>\index{alphabet}</code>
	<code>\index{alphabet}</code>
	Page 24: <code>\index{alpha bet}</code>

The duplicate `\index{alphabet}` commands on page 23 produce only one “23” in the index.

To produce a subentry, the argument of the `\index` command should contain both the main entry and the subentry, separated by a `!` character.

gnat, 32	Page 7:	<code>\index{gnat!size of}</code>
anatomy, 35	Page 32:	<code>\index{gnat}</code>
size of, 7	Page 35:	<code>\index{gnat!anatomy}</code>
gnus		<code>\index{gnus!good}</code>
bad, 38	Page 38:	<code>\index{gnus!bad}</code>
good, 35		

You can also have subsubentries.

bites	Page 8:	<code>\index{bites!animal!gnats}</code>
animal	Page 10:	<code>\index{bites!animal!gnus}</code>
gnats, 8	Page 12:	<code>\index{bites!vegetable}</code>
gnus, 10		
vegetable, 12		

$\LaTeX$ and *MakeIndex* support only three levels of indexing; you can’t have subsubsubentries.

To specify a page range, put an `\index{...|{}}` command at the beginning of the range and an `\index{...|})}` command at the end of the range. The two “...”s must be identical.

gnat, vi–x, 22	Page vi:	<code>\index{gnat {}}</code>
gnus	Page x:	<code>\index{gnat })}</code>
bad, 22	Page 22:	<code>\index{gnat}</code>
good, 28–32		<code>\index{gnus!bad {}}</code>
		<code>\index{gnus!bad })}</code>
	Page 28:	<code>\index{gnus!good {}}</code>
	Page 30:	<code>\index{gnus!good}</code>
	Page 32:	<code>\index{gnus!good })}</code>

As the example shows, *MakeIndex* does the right thing when both ends of the range fall on the same page, and when there is an identical entry within the range.

You can add a cross-reference to another entry as follows:

at, 2	Page 2:	<code>\index{at}</code>
bat, <i>see</i> bat, at	Page 2:	<code>\index{at!bat see{bat, at}}</code>

Since the “*see*” entry does not print a page number, it doesn’t matter where the `\index{...|see{...}}` goes, but it must come after the `\begin{document}` command. You might want to put all such cross-referencing commands in one place.

If you specify an entry of the form $str_1@str_2$, the string str_1 determines the alphabetical position of the entry, while the string str_2 produces the text of the entry.

twenty, 44	Page 44: <code>\index{twenty}</code>
xx, 55	Page 46: <code>\index{twenty-one}</code>
twenty-one, 46	Page 55: <code>\index{twenty@xx}</code>

This feature is useful because the argument of the `\index` command provides the actual input string that L^AT_EX uses to generate the index entry.

alpha, 13	Page 12: <code>\index{alphas}</code>
α , 14	Page 13: <code>\index{alpha}</code>
alphas, 12	Page 14: <code>\index{alpha@\$\alpha\$}</code>
alps, 33	Page 33: <code>\index{alps@\textbf{alps}}</code>

The command `\index{${\alpha}$}` will also produce an α entry in the index, but that entry will be alphabetized as `$_alpha$`.

In some indexes, certain page numbers are specially formatted—for example, an italic page number may indicate the primary reference, and an n after a page number may denote that the item appears in a footnote. *MakeIndex* makes it easy to format an individual page number any way you want. For any string of characters str , the command `\index{...|str}` produces a page number of the form `\str{n}`. Similarly, the command `\index{...|(str}` produces a page number of the form `\str{n-m}`, or of the form `\str{n}` if the specified range includes only a single page.

gnat, 3, 4n	Preamble: <code>\newcommand{\nn}[1]{\#1n}</code>
gnu, 5, 44-46	Page 3: <code>\index{gnat emph}</code>
	Page 4: <code>\index{gnat nn}</code>
	Page 5: <code>\index{gnu}</code>
	Page 44: <code>\index{gnu emph}</code>
	Page 46: <code>\index{gnu }</code>

The “see” option is a special case of this facility, where the `\see` command is predefined by the `makeidx` package.

A.2.3 The Fine Print

The argument of an `\index` command must always have matching braces, where the brace in a `\{` or `\}` command counts. Special characters like `\` may appear in the argument only if the `\index` command is not itself contained in the argument of another command. This is most likely to be a problem when indexing items in a footnote. Even in this case, robust commands can be placed in the “@” part of an entry, as in `\index{alp@\textit{alp}}`, and fragile commands can be used if protected with the `\protect` command.

MakeIndex works as expected when all page numbers are either arabic or lowercase roman numerals; pages numbered with roman numerals are assumed to precede those numbered with arabic numerals. *MakeIndex* can also handle other types of page numbers; consult its documentation for details.

To put a `!`, `@`, or `|` character in an index entry, *quote* it by preceding the character with a `"`. More precisely, a character is said to be quoted if it follows an unquoted `"` that is not part of a `\` command. A quoted `!`, `@`, or `|` character is treated like an ordinary character rather than having its usual meaning. The `"` preceding a quoted character is deleted before the entries are alphabetized.

exclaim (!), 2	Page 2: <code>\index{exclaim ("!")}</code>
loudly, 3	Page 3: <code>\index{exclaim ("!")!loudly}</code>
für, 4	Page 4: <code>\index{fur@f\"{u}r}</code>
quote ("), 5	Page 5: <code>\index{quote (\verb+""+)}</code>

MakeIndex regards spaces as ordinary characters when alphabetizing the entries and deciding whether two entries are the same. Thus, the commands `\index{gnu}`, `\index{␣gnu}`, and `\index{gnu␣}` produce three separate entries, the first appearing near the beginning of the index, since `␣` (space) comes before any letter in *MakeIndex*'s "alphabetical" order. All three entries look the same when printed, since $\text{\LaTeX}$ ignores extra spaces in the input. However, since $\text{\LaTeX}$ regards multiple spaces as a single space, `\index{a␣space}` and `\index{a␣␣space}` produce identical output on the `idx` file, so they produce a single index entry. Since `%` is treated as an ordinary character in the argument of an `\index` command, there is no way to split the argument across lines without inserting a space into the entry.

A.3 Error Messages

MakeIndex prints out the number of lines read and written and how many errors were found. Messages to identify the errors are written on a file with extension `ilg`. There are two phases in which *MakeIndex* can produce error messages: when it is reading the `idx` file, and when it is writing the `ind` file. Each error message prints the nature of the error followed by a line number, identifying where in the file the error occurs. In the reading phase, the line number refers to the `idx` file; in the writing phase, it refers to the `ind` file. The error messages should enable you to figure out what you did wrong.

APPENDIX B

The Bibliography Database



As explained in Section 4.3.1, the `\bibliography` command specifies one or more `bib` files—bibliographic database files whose names have the extension `bib`. `BIBTEX` uses the `bib` file(s) to generate a `bbl` file that is read by `\bibliography` to make the bibliography. This appendix explains how to create `bib` files.

Once you learn to use `BIBTEX`, you will find it easier to let `BIBTEX` make your reference list than to do it yourself. Moreover, you will quickly compile a bibliographic database that eliminates almost all the work of making a bibliography. Other people may have `bib` files that you can copy, or there may be a common database that you can use. Ask your friends or check the *Local Guide* to find out what is available. However, remember that you are responsible for the accuracy of the references in your document. Even published references are notoriously unreliable; don't rely on any bibliography information that has not been carefully checked by someone you trust.

B.1 The Format of the `bib` File

B.1.1 The Entry Format

A `bib` file contains a series of entries like the following:

```
@BOOK{kn:gnus,
      AUTHOR = "Donald E. Knudson",
      TITLE  = "1966 World Gnus Almanac",
      PUBLISHER = {Permafrost Press},
      ADDRESS = {Novosibirsk} }
```

The `@BOOK` states that this is an entry of type *book*. Various entry types are described below. The `kn:gnus` is the *key*, as it appears in the argument of a `\cite` command referring to the entry.

This entry has four *fields*, named `AUTHOR`, `TITLE`, `PUBLISHER`, and `ADDRESS`. The meanings of these and other fields are described below. A field consists of the name, followed by an "=" character with optional space around it, followed by its text. The text of a field is a string of characters, with no unmatched braces, surrounded by either a pair of braces or a pair of " characters. (Unlike in `LATEX` input, `\{` and `\}` are considered to be braces with respect to brace matching.) Entry fields are separated from one another, and from the key, by commas. A comma may have optional space around it.

The outermost braces that surround the entire entry may be replaced by parentheses. As in `LATEX` input files, an end-of-line character counts as a space and one space is equivalent to one hundred. Unlike `LATEX`, `BIBTEX` ignores the case of letters in the entry type, key, and field names, so the entry above could have been typed as follows:


```
@Book(KN:Gnus, author={Donald E. Knudson} ,
      Title = "1966 World
              Gnus Almanac", ... )
```

However, the case of letters does matter to $\text{\LaTeX}$, so the key should appear exactly the same in all $\backslash\text{cite}$ commands in the $\text{\LaTeX}$ input file.

The quotes or braces can be omitted around text consisting entirely of numerals. The following two fields are equivalent:

```
Volume = "27"           Volume = 27
```

B.1.2 The Text of a Field

The text of the field is enclosed in braces or double quote characters ("). A part of the text is said to be *enclosed in braces* if it lies inside a matching pair of braces other than the ones enclosing the entire field.

Names

The text of an **author** or **editor** field represents a list of names. The bibliography style determines the format in which a name is printed—whether the first name or last name appears first, if the full first name or just the first initial is used, etc. The **bib** file entry simply tells $\text{\BibTeX}$ what the name is. You should type an author's complete name, exactly as it appears in the cited work, and let the bibliography style decide what to abbreviate.

Most names can be entered in the obvious way, either with or without a comma, as in the following examples.

```
"John Paul Jones"           "Jones, John Paul"
"Ludwig van Beethoven"      "van Beethoven, Ludwig"
```

Only the second form, with a comma, should be used for people who have last names with multiple parts that are capitalized. For example, Per Brinch Hansen's last name is Brinch Hansen, so his name should be typed with a comma:

```
"Brinch Hansen, Per"
```

If you type "Per Brinch Hansen", $\text{\BibTeX}$ will think that "Brinch" is his middle name. "van Beethoven" or "de la Madrid" pose no problem because "van" and "de la" are not capitalized.

"Juniors" present a special problem. People with "Jr." in their name generally precede it with a comma. Such a name should be entered as follows:

```
"Ford, Jr., Henry"
```

BIB_TE_X is sometimes confused by characters that are produced by L_AT_EX commands—for example, accented characters and characters produced by the commands of Section 3.2.2. It will do the right thing if you put curly braces immediately around a command that produces a character:

```
"Kurt G{\\"{o}}del"      "V. S{\\"{o}}rensen"      "J. Mart{\\"{'}{i}}"
```

If there are multiple authors or editors, their names are separated by the word `and`. A paper written by Alpher, Bethe, and Gamow has the following entry:

```
AUTHOR = "Ralph Alpher and Bethe, Hans and George Gamow"
```

An `and` separates authors' names only if it is not enclosed in braces. If an `author` or `editor` field has more names than you want to type, just end the list of names with `and others`; the standard styles convert this to the conventional "et al."

Titles

The bibliography style determines whether or not a title is capitalized; the titles of books usually are, the titles of articles usually are not. You type a title the way it should appear if it is capitalized.

```
TITLE = "The Agony and the Ecstasy"
```

You should capitalize the first word of the title, the first word after a colon, and all other words except articles and unstressed conjunctions and prepositions. BIB_TE_X will change uppercase letters to lowercase if appropriate. Uppercase letters that should not be changed are enclosed in braces. The following two titles are equivalent; the *A* of *Africa* will not be made lowercase.

```
"The Gnats and Gnus of {Africa}"
```

```
"The Gnats and Gnus of {A}frica"
```

B.1.3 Abbreviations

Instead of an ordinary text string, the text of a field can be replaced by an *abbreviation* for it. An abbreviation is a string of characters that starts with a letter and does not contain a space or any of the following ten characters:

```
" # % ' ( ) , = { }
```

The abbreviation is typed in place of the text field, with no braces or quotation marks. If `jgg1` is an abbreviation for

```
Journal of Gnats and Gnus, Series~1
```

then the following are equivalent:

```
Journal = jgg1
Journal = "Journal of Gnats and Gnus, Series~1"
```

Some abbreviations are predefined by the bibliography style. These always include the usual three-letter abbreviations for the month: `jan`, `feb`, `mar`, etc. Bibliography styles may contain abbreviations for the names of commonly referenced journals. Consult your *Local Guide* for a list of the predefined abbreviations for the bibliography styles available on your computer.

You can define your own abbreviations by putting a `@string` command in the `bib` file. The command

```
@string{jgg1 = "Journal of Gnats and Gnus, Series~1"}
```

defines `jgg1` to be the abbreviation assumed in the previous example. Parentheses can be used in place of the outermost braces in the `@string` command, and braces can be used instead of the quotation marks. The text must have matching braces.

The case of letters is ignored in an abbreviation as well as in the command name `@string`, so the command above is equivalent to

```
@STRING{JgG1 = "Journal of Gnats and Gnus, Series~1"}
```

A `@string` command can appear anywhere before or between entries in a `bib` file. However, it must come before any use of the abbreviation, so a sensible place for `@string` commands is at the beginning of the file. You can also put your abbreviations in a separate `bib` file, say `abbrev.bib`, and use the command

```
\bibliography{abbrev,...}
```

in your document. A `@string` command in a `bib` file takes precedence over a definition made by the bibliography style, so it can be used to change the definition of an abbreviation such as `Feb`.

B.1.4 Cross-References

Several cited sources may be part of a larger work—for example, different papers in the same conference proceedings. You can make a single entry for the conference proceedings, and refer to that entry in the entries for the individual papers. Fields that appear in the proceedings' entry need not be duplicated in the papers' entries. However, every required field for a paper must be either in its entry or in the referenced entry.

```

@INPROCEEDINGS(beestly-gnats,
  AUTHOR   = "Will D. Beest",
  TITLE    = "Gnats in the Gnus",
  PAGES    = "47--59",
  CROSSREF = "ope:6cpb")
...
@PROCEEDINGS(ope:6cpb,
  TITLE     = "Sixth Conference on Parasites in Bovidae",
  BOOKTITLE = "Sixth Conference on Parasites in Bovidae",
  EDITOR    = "Ann T. L. Ope",
  YEAR      = 1975)

```

The apparently redundant BOOKTITLE field in the proceedings entry is needed to provide the field of that name for the entry of each paper that cross-references it. As explained below, the TITLE field is required to produce a reference-list entry for the proceedings; $\text{BIB}_{\text{T}}\text{E}_{\text{X}}$ ignores the BOOKTITLE field when producing such an entry. The reference list made by $\text{BIB}_{\text{T}}\text{E}_{\text{X}}$ may have an entry for the proceedings that is cited by the entries for the individual papers, even if the proceedings are not explicitly cited in the original document.

A cross-referenced entry like ope:6cpb in the example must come after any entries that refer to it.

B.2 The Entries

B.2.1 Entry Types

When entering a reference in the database, the first thing to decide is what type of entry it is. No fixed classification scheme can be complete, but $\text{BIB}_{\text{T}}\text{E}_{\text{X}}$ provides enough entry types to handle almost any reference reasonably well.

References to different types of publications contain different information; a reference to a journal article might include the volume and number of the journal, which is usually not meaningful for a book. Therefore, database entries of different types have different fields. For each entry type, the fields are divided into three classes:

required Omitting the field will produce an error message and will occasionally result in a badly formatted bibliography entry. If the required information is not meaningful, you are using the wrong entry type. If the required information is meaningful but not needed—for example, because it is included in some other field—simply ignore the warning that $\text{BIB}_{\text{T}}\text{E}_{\text{X}}$ generates.

optional The field's information will be used if present, but can be omitted without causing any formatting problems. A reference should contain any information that might help the reader, so you should include the optional

field if it is applicable. (A nonstandard bibliography style might ignore an optional field when creating the reference-list entry.)

ignored The field is ignored. `BIBTEX` ignores a field that is not required or optional, so you can include any fields you want in a `bib` file entry. It's a good idea to put all relevant information about a reference in its `bib` file entry—even information that may never appear in the bibliography. For example, if you want to keep an abstract of a paper in a computer file, put it in an `abstract` field in the paper's `bib` file entry. The `bib` file is likely to be as good a place as any for the abstract, and it is possible to design a bibliography style for printing selected abstracts.

Misspelling its name will cause a field to be ignored, so check the database entry if relevant information that you think is there does not appear in the reference-list entry.

The following are all the entry types, along with their required and optional fields, that are used by the standard bibliography styles. The meanings of the individual fields are explained in the next section. A particular bibliography style may ignore some optional fields in creating the reference. Remember that, when used in the `bib` file, the entry-type name is preceded by an `@` character.

article An article from a journal or magazine. Required fields: `author`, `title`, `journal`, `year`. Optional fields: `volume`, `number`, `pages`, `month`, `note`.

book A book with an explicit publisher. Required fields: `author` or `editor`, `title`, `publisher`, `year`. Optional fields: `volume` or `number`, `series`, `address`, `edition`, `month`, `note`.

booklet A work that is printed and bound, but without a named publisher or sponsoring institution. Required field: `title`. Optional fields: `author`, `howpublished`, `address`, `month`, `year`, `note`.

conference The same as **inproceedings**, included for compatibility with older versions.

inbook A part of a book, usually untitled; it may be a chapter (or other sectional unit) and/or a range of pages. Required fields: `author` or `editor`, `title`, `chapter` and/or `pages`, `publisher`, `year`. Optional fields: `volume` or `number`, `series`, `type`, `address`, `edition`, `month`, `note`.

incollection A part of a book with its own title. Required fields: `author`, `title`, `booktitle`, `publisher`, `year`. Optional fields: `editor`, `volume` or `number`, `series`, `type`, `chapter`, `pages`, `address`, `edition`, `month`, `note`.

inproceedings An article in a conference proceedings. Required fields: `author`, `title`, `booktitle`, `year`. Optional fields: `editor`, `volume` or `number`, `series`, `pages`, `address`, `month`, `organization`, `publisher`, `note`.

- manual** Technical documentation. Required field: `title`. Optional fields: `author`, `organization`, `address`, `edition`, `month`, `year`, `note`.
- mastersthesis** A master's thesis. Required fields: `author`, `title`, `school`, `year`. Optional fields: `type`, `address`, `month`, `note`.
- misc** Use this type when nothing else fits. Required fields: none. Optional fields: `author`, `title`, `howpublished`, `month`, `year`, `note`.
- phdthesis** A Ph.D. thesis. Required fields: `author`, `title`, `school`, `year`. Optional fields: `type`, `address`, `month`, `note`.
- proceedings** The proceedings of a conference. Required fields: `title`, `year`. Optional fields: `editor`, `volume` or `number`, `series`, `address`, `month`, `organization`, `publisher`, `note`.
- techreport** A report published by a school or other institution, usually numbered within a series. Required fields: `author`, `title`, `institution`, `year`. Optional fields: `type`, `number`, `address`, `month`, `note`.
- unpublished** A document with an author and title, but not formally published. Required fields: `author`, `title`, `note`. Optional fields: `month`, `year`.

In addition to the fields listed above, each entry type also has an optional `key` field, used in some styles for alphabetizing and forming a `\bibitem` label. You should include a `key` field for any entry with no `author` or author substitute. (Depending on the entry type, an `editor` or an `organization` can substitute for an `author`.) Do not confuse the `key` field with the key that appears in the `\cite` command and at the beginning of the whole entry, after the entry type.

B.2.2 Fields

Below is a description of all the fields recognized by the standard bibliography styles. An entry can also contain other fields that are ignored by those styles.

- address** Usually the address of the `publisher` or `institution`. For major publishing houses, omit it entirely or just give the city. For small publishers, you can help the reader by giving the complete address.
- annote** An annotation. It is not used by the standard bibliography styles, but may be used by other styles that produce an annotated bibliography.
- author** The name(s) of the author(s), in the format described above.
- booktitle** The title of a book, a titled part of which is being cited. It is used only for the `incollection` and `inproceedings` entry types; use the `title` field for book entries. How to type titles is explained above.

chapter A chapter (or other sectional unit) number.

crossref The database key of the entry being cross-referenced.

edition The edition of a book—for example, “Second”. (The style will convert this to “second” if appropriate.)

editor The name(s) of editor(s), typed as indicated above. If there is also an **author** field, then the **editor** field gives the editor of the book or collection in which the reference appears.

howpublished How something strange was published.

institution The sponsoring institution of a technical report.

journal A journal name. Abbreviations may exist; see the *Local Guide*.

key Used for alphabetizing and creating a label when the **author** and **editor** fields are missing. This field should not be confused with the key that appears in the `\cite` command and at the beginning of the entry.

month The month in which the work was published or, for an unpublished work, in which it was written. Use the standard three-letter abbreviations described above.

note Any additional information that can help the reader. The first word should be capitalized.

number The number of a journal, magazine, technical report, or work in a series. An issue of a journal or magazine is usually identified by its volume and number; the organization that issues a technical report usually gives it a number; books in a named series are sometimes numbered.

organization The organization that sponsors a conference or that publishes a manual.

pages One or more page numbers or ranges of numbers, such as 42--111 or 7,41,73--97.

publisher The publisher's name.

school The name of the school where a thesis was written.

series The name of a series or set of books. When citing an entire book, the **title** field gives its title and the optional **series** field gives the name of a series or multivolume set in which the book was published.

title The work's title, typed as explained above.

type The type of a technical report—for example, “Research Note”. It is also used to specify a type of sectional unit in an inbook or incollection entry and a different type of thesis in a mastersthesis or phdthesis entry.

volume The volume of a journal or multivolume book.

year The year of publication or, for an unpublished work, the year it was written. It usually consists only of numerals, such as 1984, but it could also be something like circa 1066.

APPENDIX C

Reference Manual



This appendix describes all L^AT_EX commands and environments, including some features, anomalies, and special cases not mentioned earlier. You should look here when a command or environment does something surprising, or when you encounter a formatting problem not discussed in earlier chapters.

Command and environment descriptions are concise; material explained in an earlier chapter is sketched very briefly. The syntax of commands and environments is indicated by a *command form* such as:

```
\parbox[pos]{width}{text}
```

Everything in typewriter style, such as the `\parbox`, represents material that appears in the input file exactly as shown. The italicized parts *pos*, *width*, and *text* represent items that vary; the command's description explains their function. Arguments enclosed in square brackets [] are optional; they (and the brackets) may be omitted, so `\parbox` can also have the form

```
\parbox{width}{text}
```

The case in which an optional argument is missing is called the *default*. If a command form has two optional arguments that come one right after the other, when only one is present it is assumed to be the first one.

A number of *style parameters* are listed in this appendix. Except where stated otherwise, these parameters are length commands. A length is rigid unless it is explicitly said to be a rubber length (Section 6.4.1).

C.1 Commands and Environments

C.1.1 Command Names and Arguments

The six commands `#` `$` `&` `~` `_` `^` are the only ones with single-character names. The character `%`, while not a command, causes L^AT_EX to ignore all characters following it on the input line—including the space character that ends the line—and all space characters at the beginning of the next line. A `%` can be used to begin a comment and to start a new line without producing space in the output. However, a command name cannot be split across lines.

About two dozen commands have two-character names composed of `\` followed by a single nonletter. All other command names consist of `\` followed by one or more letters. Command names containing an `@` character can be used only in the `sty` files that implement packages (Section 6.1.4). Upper- and lowercase letters are considered to be different, so `\gamma` and `\Gamma` are different commands. Spaces are ignored after a command name of this form, except that a blank line following the command still denotes the end of a paragraph.

Commands may have mandatory and/or optional arguments. A mandatory argument is enclosed by curly braces `{` and `}` and an optional argument is enclosed by square brackets `[` and `]`. Space between arguments is ignored.

The following commands take an optional last argument:

<code>\</code>	<code>\linebreak</code>	<code>\nolinebreak</code>	<code>\newcounter</code>	<code>\twocolumn</code>
<code>\item</code>	<code>\pagebreak</code>	<code>\nopagebreak</code>	<code>\newtheorem</code>	<code>\suppressfloats</code>

If that argument is missing and the next nonspace character in the text is a `[`, then $\text{\LaTeX}$ will mistake this `[` for the beginning of an optional argument. Enclosing the `[` in braces prevents this mistake.

Enclosing text in braces can seldom cause trouble.

- `[This is an aside.]` This is the rest of the item.

```
... \begin{itemize}
    \item {[This is an aside.]} This is ...
```

A `]` within the optional argument of an `\item` command must be enclosed in braces to prevent its being mistaken for the `]` that marks the end of the argument.

`[gnu]` A large animal, found mainly in dictionaries.

`[gnat]` A small animal, found mainly in tents.

```
\begin{description}
  \item {[[gnu]]} A large animal...
  \item {[[gnat]]} A small animal...
\end{description}
```

Some commands, including `\`, have a `*-form` that is obtained by typing a `*` right after the command name. If a `*` is the first nonspace character following a command like `\`, then it should be enclosed in braces; otherwise, $\text{\LaTeX}$ will mistake the `\` and `*` for a `\*` command.

C.1.2 Environments

An environment is begun with a `\begin` command having the environment's name as the first argument. Any arguments of the environment are typed as additional arguments to the `\begin`. The environment is ended with an `\end` command having the environment's name as its only argument. If an environment has a `*-form`, the `*` is part of the environment's name, appearing in the argument of the `\begin` and `\end` commands.

C.1.3 Fragile Commands

Commands are classified as either *robust* or *fragile*. Type-style-changing commands such as `\textbf` and `\em` are robust, as are most of the math-mode commands of Section 3.3. Any command with an optional argument is fragile.

Certain command arguments are called *moving* arguments. A fragile command that appears in a moving argument must be preceded by a `\protect` command. A `\protect` applies only to the command it precedes; fragile commands appearing in its argument(s) require their own `\protect` commands. The following are all the commands and environments with moving arguments:

- Commands with an argument that may be put into a table of contents, list of figures, or list of tables: `\addcontentsline`, `\addtocontents`, `\caption`, and the sectioning commands. If an optional argument is used with a sectioning or `\caption` command, then it is this argument that is the moving one.
- Commands to print on the terminal: `\typeout` and `\typein`. The optional argument of `\typein` is not a moving argument.
- Commands to generate page headings: `\markboth` (both arguments) and `\markright`. (The sectioning commands, already listed, fall under this category too.)
- The `letter` environment (defined in the `letter` document class).
- The `\thanks` command.
- The optional argument of `\bibitem`.
- An `@` in an `array` or `tabular` environment. (Although `@` is not a command, fragile commands in an `@`-expression must be `\protect`'ed as if they were in a moving argument.)

All length commands are robust and must not be preceded by `\protect`. A `\protect` command should not be used in an argument of a `\setcounter` or `\addtocounter` command.

C.1.4 Declarations

A declaration is a command that changes the value or meaning of some command or parameter. The *scope* of a declaration begins with the declaration itself and ends with the first `}` or `\end` whose matching `{` or `\begin` occurs before the declaration. The commands `\]`, `\)`, and `$` that end a math-mode environment and the `}` or `]` that end the argument of a $\text{\LaTeX}$ command also delimit the scope of a declaration; but the `}` or `]` ending the argument of a command defined with `\newcommand`, or `\renewcommand`, or `\providecommand` does *not* delimit its scope. A declaration is in effect throughout its scope, except within the scope of a subsequent countermanding declaration.

The following declarations are *global*; their scope is not delimited by braces or environments.

<code>\newcounter</code>	<code>\pagenumbering</code>	<code>\newlength</code>	<code>\hyphenation</code>
<code>\setcounter</code>	<code>\thispagestyle</code>	<code>\newsavebox</code>	
<code>\addtocounter</code>	<code>\pagecolor</code>	<code>\newtheorem</code>	

C.1.5 Invisible Commands and Environments

A number of commands and environments are “invisible”, meaning that they do not produce any text at the point where they appear. $\TeX$ regards an invisible command or environment in the middle of a paragraph as an invisible “word”. Putting spaces or an end-of-line character both before and after an invisible word can generate two separate interword spaces, one on either side of this word, producing extra space in the output. Moreover, if the invisible word occurs at the end of a paragraph, not attached to a real word, it could appear on a line by itself, producing a blank line in the output. Invisible words caused by a command with no argument are seldom a problem, since spaces are ignored when they follow a command name that ends in a letter. Also, the following invisible commands and environments usually eliminate this extra space:¹

<code>\pagebreak</code>	<code>\nolinebreak</code>	<code>\vspace</code>	<code>\color</code>
<code>\nopagebreak</code>	<code>\label</code>	<code>\glossary</code>	<code>figure</code>
<code>\linebreak</code>	<code>\index</code>	<code>\marginpar</code>	<code>table</code>

Any other invisible command with an argument that appears inside a paragraph should be attached to an adjacent word, as should the commands and environments listed above in certain unusual situations where they can produce extra space in the output.

C.1.6 The `\` Command

`\` [*len*]

`\`*[*len*]

These commands start a new line and add an extra vertical space of length *len* above it. The default is to add no extra space. The *-form inhibits a page break before the new line. They may be used in paragraph mode and within the following commands and environments:

<code>array</code>	<code>eqnarray</code>	<code>\shortstack</code>
<code>tabular</code>	<code>tabbing</code>	<code>\author</code>

$\LaTeX$ is in paragraph mode, so a `\` can be used, in the following environments (among others):

<code>verse</code>	<code>center</code>	<code>flushleft</code>	<code>flushright</code>
--------------------	---------------------	------------------------	-------------------------

and when processing the argument of a `\title`, `\date`, or sectioning command. Do not use two `\` commands in a row in paragraph mode; instead, use an optional argument to add extra vertical space.

In the `array` and `tabular` environments, the spacing between rows is obtained by putting a strut (Section 6.4.3) on each line; a positive value of *len*

¹More precisely, spaces that follow these commands and environments are ignored if there is space in the output before the invisible word that they generate.

increases the depth of this strut. This can fail to add the expected amount of extra space if an object in the row extends further below the line than the default strut.

The `\` and `\*` commands are fragile.

C.2 The Structure of the Document

A document consists of the following parts.

prepended files

A possibly empty sequence of `filecontents` environments (Section 4.7).

preamble

Begins with a `\documentclass` command. It may contain `\usepackage` commands, declarations that apply to the entire document, and command and environment definitions.

`\begin{document}`

text of the document

`\end{document}`

C.3 Sentences and Paragraphs

C.3.1 Making Sentences

The following commands and characters are for use mainly in paragraph and LR mode. They are robust.

quotes

' Apostrophe. `'text'` Single quotes. `''text''` Double quotes.

dashes

- Intra-word. -- Number-range. --- Punctuation.

spacing

`\`, Produces a small space; use it between a double and a single quote.

`\_` Produces an interword space.

`~` Produces an interword space where no line break can occur.

`\@` Causes an “end-of-sentence” space after punctuation when typed before the punctuation character. Needed only if the character preceding the punctuation character is not a lowercase letter or a number.

`\frenchspacing` Suppresses extra space after punctuation, even when `\@` is used. Fragile.

`\nonfrenchspacing` Reverses the effect of `\frenchspacing`. Fragile.

special characters

<code>\$</code>	<code>\\$</code>	<code>%</code>	<code>\%</code>	<code>{</code>	<code>\{</code>	<code>-</code>	<code>_</code>
<code>&</code>	<code>\&</code>	<code>#</code>	<code>\#</code>	<code>}</code>	<code>\}</code>		

(These commands can be used in math mode.) See Sections 3.2 and 3.3.2 for commands to make other symbols.

logos

`\LaTeX` Produces L^AT_EX logo. `\TeX` Produces T_EX logo.

`\today` Generates the current date, in the following format: May 18, 1994.

`\emph{text}` Emphasizes *text*, usually by printing it in italic type.

`\mbox{text}` Typesets *text* in LR mode inside a box, which prevents it from being broken across lines. It can be used in math mode. (See Section 6.4.3.)

C.3.2 Making Paragraphs

A paragraph is ended by one or more completely blank lines—lines not containing even a `%`. A blank line should not appear where a new paragraph cannot be started, such as in math mode or in the argument of a sectioning command.

`\noindent` When used at the beginning of the paragraph, it suppresses the paragraph indentation. It has no effect when used in the middle of a paragraph. Robust.

`\indent` Produces a horizontal space whose width equals the width of the paragraph indentation. It is used to add a paragraph indentation where one would otherwise be suppressed. Robust.

`\par` Equivalent to a blank line; often used to make command and environment definitions easier to read. Robust.

Style Parameters

`\textwidth` Normal width of text on the page. Should be changed only in the preamble.

`\linewidth` Width of lines in the current environment; equals `\textwidth` except when inside a displayed-paragraph environment such as `quote` or `itemize`. Its value should not be changed with the length-setting commands.

`\parindent` Width of the indentation at the beginning of a paragraph. Its value is set to zero in a `parbox`. Its value may be changed anywhere.

`\baselineskip` The minimum space from the bottom of one line to the bottom of the next line in a paragraph. (The space between individual lines may be greater if they contain tall objects.) Its value is set by a type-size-changing command (Section 6.7.1). The value used for the entire paragraph unit (Section 6.2.1) is the one in effect at the blank line or command that ends the paragraph unit. Its value may be changed anywhere.

`\baselinestretch` A decimal number (such as 2 or 1.5). Its default value is 1 and is changed with `\renewcommand`. The value of `\baselineskip` is set by `\begin{document}` and by each type-size-changing command to its default value times `\baselinestretch`. You can produce a “double-spaced” version of the document for copy editing by setting `\baselinestretch` to 2, but it will be ugly and hard to read. Any other changes to the interline spacing should be part of the complete document design, best done by a competent typographic designer.

`\parskip` The extra vertical space inserted before a paragraph. It is a rubber length that usually has a natural length of zero. Its value may be changed anywhere, but should be a stretchable length when a `\flushbottom` declaration (Section 6.1.2) is in effect.

C.3.3 Footnotes

`\footnote[num]{text}`

Produces a footnote with *text* as its text and *num* as its number. The *num* argument is a positive integer, even when footnotes are “numbered” with letters or other symbols; if it is missing, then the `footnote` counter is stepped and its value used as the footnote number. This command may be used only in paragraph mode to produce ordinary footnotes. It should not be used inside a box except within a `minipage` environment, in which case it may be used in LR or math mode as well as paragraph mode and the footnote appears at the bottom of the box ended by the next `\end{minipage}`. This may be the wrong place for it if there are nested `minipage` environments. Fragile.

`\footnotemark[num]`

Used in conjunction with `\footnotetext` to footnote text where a `\footnote` command cannot be used. It produces a footnote mark (the footnote number that appears in the running text), but it does not produce a footnote. See Figure C.1 for an example of its use. It steps the `footnote` counter if the optional argument is missing. It may be used in any mode. Fragile.

It was Gnats¹² and Gnus¹³ as we trekked
through Africa in the blazing noontime heat.

⋮

¹²Small insects.

¹³Large mammals.

```
It was \fbox{Gnats\footnotemark\ and
        Gnus\footnotemark}%
\addtocounter{footnote}{-1}\footnotetext
{Small insects.}\addtocounter{footnote}{1}%
\footnotetext{Large mammals.} as we ...
```

Figure C.1: Making footnotes without the `\footnote` command.

`\footnotetext[num]{text}`

Used in conjunction with `\footnotemark` to footnote text where the `\footnote` command cannot be used. See Figure C.1 for an example. It produces a footnote, just like the corresponding `\footnote` command, except that no footnote mark is generated and the footnote counter is not stepped. Fragile.

Style Parameters

`\footnotesep` The height of a strut placed at the beginning of every footnote to produce the vertical space between footnotes. It may be changed anywhere; the value used is the one in effect when the `\footnote` or `\footnotetext` command is processed.

`\footnoterule` A command that draws the line separating the footnotes from the main text. It is used by L^AT_EX in paragraph mode, between paragraphs (in T_EX's inner vertical mode). The output it generates must take zero vertical space, so negative space should be used to compensate for the space occupied by the rule. It can be redefined anywhere with `\renewcommand`; the definition used is the one in effect when T_EX produces the page of output.

C.3.4 Accents and Special Symbols

Commands for making accents in normal text are listed in Table 3.1 on page 38; commands for making accents in math formulas are listed in Table 3.11 on page 50. See Section C.10.1 for commands used in a `tabbing` environment to produce the accents normally made with `\=`, `\'`, and `\``.

Non-English symbols are made with commands listed in Table 3.2 on page 39. The following commands for making additional special symbols can also be used in any mode:

†	<code>\dag</code>	§	<code>\S</code>	©	<code>\copyright</code>
‡	<code>\ddag</code>	¶	<code>\P</code>	£	<code>\pounds</code>

Section 3.3.2 gives many commands for generating symbols in mathematical formulas.

C.4 Sectioning and Table of Contents

The use of the following commands for producing section headings and table of contents entries is illustrated in Figure C.2.

C.4.1 Sectioning Commands

```
sec_cmd[toc_entry]{heading}
sec_cmd*{heading}
```

Commands to begin a sectional unit. The `*`-form suppresses the section number, does not increment the counter, does not affect the running head, and produces no table of contents entry. The `secnumdepth` counter, described below, determines which sectional units are numbered.

sec_cmd One of the following:

<code>\part</code>	<code>\section</code>	<code>\subsubsection</code>	<code>\subparagraph</code>
<code>\chapter</code>	<code>\subsection</code>	<code>\paragraph</code>	

Each sectional unit should be contained in the next higher-level unit, except that `\part` is optional. The `article` document class does not have a `\chapter` command.

toc_entry Produces the table of contents entry and may be used for the running head (Section 6.1.2). It is a moving argument. If it is missing, the *heading* argument is used for these purposes.

heading Produces the section heading. If the *toc_entry* argument is missing, then it is a moving argument that provides the table of contents entry and may be used for the running head (Section 6.1.2).

Gnats and Gnus Forever

From insects embedded in amber and fossils...

In the table of contents:

```
Gnats . . . . . 37
      ↑ 2 ex
2.2x Gnus . . . . . 37
2.3  Gnats and Gnus on Gneiss . . . . 37
```

In the text (on page 37):

2.3 Insects and Ungulates on ...

```
\subsection*{Gnats and Gnus Forever}
```

```
From insects embedded in amber and ...
```

```
\addcontentsline{toc}{subsection}{Gnats}
\addtocontents{toc}{\protect\vspace{2ex}}
```

```
\addcontentsline{toc}{subsection}{\protect
\numberline{2.2x}{Gnus}}
```

```
\subsection[Gnats and Gnus on Gneiss]%
{Insects and Ungulates on Metamorphic Rock}
```

Figure C.2: Sectioning and table of contents commands.

C.4.2 The Appendix

`\appendix`

A declaration that changes the way sectional units are numbered. In the standard `article` document class, appendix sections are numbered “A”, “B”, etc. In the `report` and `book` classes, appendix chapters are numbered “A”, “B”, etc., and the chapter number is printed in the heading as “Appendix A”, “Appendix B”, etc. The `\appendix` command generates no text and does not affect the numbering of parts.

C.4.3 Table of Contents

`\tableofcontents`

`\listoffigures`

`\listoftables`

Generate a table of contents, list of figures, and list of tables, respectively. These commands cause L^AT_EX to write the necessary information on a file having the same first name as the root file and the following extension:

<i>command:</i>	<code>\tableofcontents</code>	<code>\listoffigures</code>	<code>\listoftables</code>
<i>extension:</i>	<code>toc</code>	<code>lof</code>	<code>lot</code>

A table of contents or a list of figures or tables compiled from the information on the current version of this file is printed at the point where the command appears.

Table of contents entries are produced by the sectioning commands, and list of figures or tables entries are produced by a `\caption` command in a `figure` or `table` environment (Section 3.5.1). The two commands described below also produce entries.

`\addcontentsline{file}{sec_unit}{entry}`

Adds an entry to the specified list or table.

file The extension of the file on which information is to be written: `toc` (table of contents), `lof` (list of figures), or `lot` (list of tables).

sec_unit Controls the formatting of the entry. It should be one of the following, depending upon the value of the *file* argument:

- `toc`: the name of the sectional unit, such as `part` or `subsection`
- `lof`: `figure`
- `lot`: `table`

There is no `\` in this argument.

entry The text of the entry. It is a moving argument. To produce a line with a sectional-unit or figure or table number, *entry* should be of the form

```
\protect\numberline{sec_num}{heading}
```

where *sec_num* is the number and *heading* is the heading.

```
\addtocontents{file}{text}
```

Adds text (or formatting commands) directly to the file that generates the table of contents or list of figures or tables.

file The extension of the file on which information is to be written: *toc* (table of contents), *lof* (list of figures), or *lot* (list of tables).

text The information to be written. It is a moving argument.

C.4.4 Style Parameters

Parameters control which sectional units are numbered and which are listed in the table of contents. Each sectional unit has a *level number*. In all document classes, sections have level number 1, subsections have level number 2, etc. In the **article** document class, parts have level number 0; in the **report** and **book** classes, chapters have level number 0 and parts have level number -1.

The following two counters (Section 6.3) are provided; they can be set in the preamble.

secnumdepth The level number of the least significant sectional unit with numbered headings. A value of 2 means that subsections are numbered but subsubsections are not.

tocdepth The level number of the least significant sectional unit listed in the table of contents.

C.5 Classes, Packages, and Page Styles

C.5.1 Document Class

```
\documentclass[options]{class}
```

Specifies the document class and options.

class The document class. The standard classes are: **article**, **report**, **book**, **letter** (for letters), and **slides** (for slides).

options A list of one or more options, separated by commas—with no spaces. The options recognized by the standard document classes are listed below. Alternatives, at most one of which should appear, are separated by the symbol “|”.

10pt | **11pt** | **12pt** Chooses the normal (default) type size of the document. The default is **10pt**, which selects ten-point type. (These options are not recognized by the **slides** class.)

letterpaper | **legalpaper** | **executivepaper** | **a4paper** | **a5paper** | **b5paper**
Causes the output to be formatted for the appropriate paper size:

letter	8.5in × 11in	A4	210mm × 297mm
legal	8.5in × 14in	A5	148mm × 210mm
executive	7.25in × 10.5in	B5	176mm × 250mm

The default is **letterpaper**.

landscape Causes the output to be formatted for landscape (sideways) printing on the selected paper size. This option effectively interchanges the width and height dimensions of the paper size.

final | **draft** If T_EX has trouble finding good places to break lines, it can produce lines that extend past the right margin (“overfull hboxes”). The **draft** option causes such lines to be marked by black boxes in the output. The **final** option, which does not mark these lines, is the default.

oneside | **twoside** Formats the output for printing on one side or both sides of a page. The default is **oneside**, except that it is **twoside** for the **book** class. (The **twoside** option cannot be used with the **slides** document class.)

openright | **openany** Specifies that chapters must begin on a right-hand page (**openright**) or may begin on any page (**openany**). These options apply only to the **report** class (whose default is **openany**) and the **book** class (whose default is **openright**).

onecolumn | **twocolumn** Specifies one-column or two-column pages. The default is **onecolumn**. (The **twocolumn** option cannot be used with the **letter** or **slides** class.)

notitlepage | **titlepage** The **titlepage** option causes the **\maketitle** command to make a separate title page and the **abstract** environment to put the abstract on a separate page. The default is **titlepage** for all classes except **article**, for which it is **notitlepage**. (These options are not recognized by the **letter** class.)

openbib Causes the bibliography (Section 4.3) to be formatted in open style. (This option is not recognized by the **letter** and **slides** classes.)

leqno Puts formula numbers on the left side in **equation** and **eqnarray** environments.

fleqn Left-aligns displayed formulas.

Putting an option in the `\documentclass` command effectively adds that option to any package (loaded with a `\usepackage` command) that recognizes it. L^AT_EX issues a warning message if a document-class option is recognized neither by the document class nor by any loaded package.

Style Parameters

`\bibindent` Width of the extra indentation of succeeding lines in a bibliography block with the `openbib` style option.

`\columnsep` The width of the space between columns of text in `twocolumn` style.

`\columnseprule` The width of a vertical line placed between columns of text in `twocolumn` style. Its default value is zero, producing an invisible line.

`\mathindent` The amount that formulas are indented from the left margin in the `fleqn` document-class option.

C.5.2 Packages

`\usepackage[options]{pkgs}`

pkgs A list of packages to be loaded. The standard packages include:

`alltt` Defines the `alltt` environment; see Section C.6.4.

`amstex` Defines many commands for mathematical formulas. It is described in the *L^AT_EX Companion*.

`babel` For documents in one or more languages other than English; see the *L^AT_EX Companion*.

`color` For producing colors, using special device-driver support. A device driver is specified as an option; the *Local Guide* should list the default driver for your computer. See Section 7.3.

`graphics` For geometrical transformations of text and including graphics prepared by other programs. It requires special device-driver support. A device driver is specified as an option; the *Local Guide* should list the default driver for your computer. See Section 7.2.

`graphpap` Defines the `\graphpaper` command for use in the `picture` environment (Section 7.1.4).

`ifthen` Defines simple programming-language constructs (Section C.8.5).

`latexsym` Defines some special mathematical symbols; see Section 3.3.2.

`makeidx` Defines commands for use with *MakeIndex* (Appendix A).

pict2e Defines enhanced versions of the `picture` environment commands that remove restrictions on line slope, circle radius, and line thickness.

showidx Causes `\index` command arguments to be printed on the page where they occur; see Section 4.5.1.

options A list of options, which are provided to all the specified packages. They must be legal options for all the packages.

C.5.3 Page Styles

An output page consists of a *head*, a *body*, and a *foot*. Style parameters determine their dimensions; the page style specifies the contents of the head and foot. Left-hand and right-hand pages have different parameters. In two-sided style, even-numbered pages are left-hand and odd-numbered pages are right-hand; in one-sided style, all pages are right-hand. All commands described in this section are fragile.

`\pagestyle{style}`

A declaration, with normal scoping rules, that specifies the current page style. The style used for a page is the one in effect when TeX “cuts the scroll” (page 135). Standard *style* options are:

plain The head is empty, the foot has only a page number. It is the default page style.

empty The head and foot are both empty.

headings The head contains information determined by the document class (usually a sectional-unit heading) and the page number; the foot is empty.

myheadings Same as **headings**, except head information (but not the page number) is specified by `\markboth` and `\markright` commands, described below.

`\thispagestyle`

Same as `\pagestyle` except it applies only to the current page (the next one to be “cut from the scroll”). It is a global declaration (Section C.1.4).

`\markright{right_head}`

`\markboth{left_head}{right_head}`

These commands specify the following heading information for the **headings** and **myheadings** page styles:

left-hand page Specified by *left.head* argument of the last `\markboth` before the end of the page.

right-hand page Specified by *right.head* argument of the first `\markright` or `\markboth` on the page, or if there is none, by the last one before the beginning of the page.

Both *right.head* and *left.head* are moving arguments. In the `headings` page style, sectioning commands set the page headings with the `\markboth` and `\markright` commands as follows:

Printing Style	Command	Document Class	
		<u>book, report</u>	<u>article</u>
two-sided	<code>\markboth^a</code>	<code>\chapter</code>	<code>\section</code>
	<code>\markright</code>	<code>\section</code>	<code>\subsection</code>
one-sided	<code>\markright</code>	<code>\chapter</code>	<code>\section</code>

^aSpecifies an empty right head.

These commands are overridden as follows:

`\markboth` Put a `\markboth` command right after the sectioning command.

`\markright` Put a `\markright` command immediately before and after the sectioning command, but omit the first one if the sectional unit starts a new page.

The right head information is always null for the first page of a document. If this is a problem, generate a blank first page with the `titlepage` environment.

`\pagenumbering{num_style}`

Specifies the style of page numbers and sets the value of the `page` counter to 1. It is a global declaration (Section C.1.4). Possible values of *num_style* are:

`arabic` Arabic numerals.

`roman` Lowercase roman numerals.

`Roman` Uppercase roman numerals.

`alph` Lowercase letters.

`Alph` Uppercase letters.

The `\pagenumbering` command redefines `\thepage` to be `\num_style{page}`.

`\twocolumn[text]`

Starts a new page by executing `\clearpage` (Section 6.2.2) and begins typesetting in two-column format. If the *text* argument is present, it is typeset in a double-column-wide parbox at the top of the new page. Fragile.

`\onecolumn`

Starts a new page by executing `\clearpage` (Section 6.2.2) and begins typesetting in single-column format. Fragile.

Style Parameters

Most of the parameters controlling the page style are shown in Figure C.3, where the outer rectangle represents the physical page. These parameters are all rigid lengths. They are normally changed only in the preamble. Anomalies may occur if they are changed in the middle of the document. Odd-numbered pages use `\oddsidemargin` and even-numbered pages use `\evensidemargin`. Not shown in the figure is the parameter `\topskip`, the minimum distance from the top of the body to the reference point of the first line of text. It acts like `\baselineskip` for the first line of a page.

C.5.4 The Title Page and Abstract

`\maketitle`

Generates a title. With the `notitlepage` document-class option (the default for the `article` class), it puts the title at the top of a new page and issues a `\thispagestyle{plain}` command. With the `titlepage` option (the default for other classes), it puts the title on a separate page, using the `titlepage` environment. Information used to produce the title is obtained from the following declarations; an example of their use is given in Figure C.4. It's best to put these declarations in the preamble.

`\title{text}` Declares *text* to be the title. You may want to use `\\` to tell $\text{\LaTeX}$ where to start a new line in a long title.

`\author{names}` Declares the author(s), where *names* is a list of authors separated by `\and` commands. Use `\\` to separate lines within a single author's entry—for example, to give the author's institution or address.

`\date{text}` Declares *text* to be the document's date. With no `\date` command, the current date is used.

The arguments of these three commands may include the following command:

`\thanks{text}` Produces a footnote to the title. The *text* is a moving argument. Can be used for an acknowledgment of support, an author's address, etc. The footnote marker is regarded as having zero width, which is appropriate when it comes at the end of a line; if the marker comes in the middle of a line, add extra space with `\_` after the `\thanks` command.




Figure C.3: Page style parameters.

Gnu Veldt Cuisine

G. Picking*
Acme Kitchen Products

R. Dillo
Cordon Puce School†

24 July 1984
Revised 5 January 1985

:

`\title{Gnu Veldt Cuisine}`

`\author{G. Picking\thanks{Supported
by a grant from the GSF.} \\
Acme Kitchen Products`

`\and
R. Dillo \\ Cordon Puce
School\thanks{On leave during 1985.}}`

`\date{24 July 1984 \\
Revised 5 January 1985}`

`...`

`\maketitle`

*Supported by a grant from the GSF.

†On leave during 1985.

Figure C.4: An example title.

`\begin{abstract} text \end{abstract}`

Generates an abstract, with *text* as its contents, right where the environment occurs. The abstract is placed on a page by itself when the `titlepage` document-class option (the default for the `report` class; see Section 6.1.1) is in effect. This environment is not defined in the `book` document class.

`\begin{titlepage} text \end{titlepage}`

Produces a title page with the `empty` page style and resets the number of the following page to one. You are completely responsible for formatting the contents of this page.

C.6 Displayed Paragraphs

The output produced by a displayed-paragraph environment starts on a new line, as does the output produced by the text following it. In addition to the environments described in this section, the `tabbing`, `center`, `flushleft`, and `flushright` environments and the environments defined by `\newtheorem` (Section 3.4.3) are also displayed-paragraph environments.

The text following a displayed-paragraph environment begins a new paragraph if there is a blank line after the `\end` command. However, even with no blank line, the following text may have a paragraph indentation if a right brace or `\end` command comes between it and the environment's `\end` command. This anomalous indentation is eliminated with a `\noindent` command (Section C.3.2).

Anomalous extra vertical space may be added after a displayed-paragraph environment that ends with a displayed equation (one made with the `displaymath`,

equation, or `eqnarray` environment). This space can be removed by adding a negative vertical space with a `\vspace` command (Section 6.4.2). You can determine how much space to remove by trial and error.

All displayed-paragraph environments are implemented with the `list` or `trivlist` environment. These environments and the relevant formatting parameters are described in Section C.6.3 below.

C.6.1 Quotations and Verse

```
\begin{quote}  text  \end{quote}
```

For a short quotation or a sequence of short quotations separated by blank lines.

```
\begin{quotation}  text  \end{quotation}
```

For a multiparagraph quotation.

```
\begin{verse}  text  \end{verse}
```

For poetry. Lines within a stanza are separated by `\\` commands and stanzas are separated by one or more blank lines.

C.6.2 List-Making Environments

```
\begin{itemize}      item_list  \end{itemize}
```

```
\begin{enumerate}   item_list  \end{enumerate}
```

```
\begin{description} item_list  \end{description}
```

The *item_list* consists of a sequence of items, each one begun with an `\item` command (see below). Numbering in an `enumerate` environment is controlled by the counter `enumi`, `enumii`, `enumiii`, or `enumiv`, depending upon its nesting level within other `enumerate` environments. The printed value of this counter is declared to be the current `\ref` value (Section C.11.2).

The default labels of an `itemize` environment are produced by the command `\labelitemi`, `\labelitemii`, `\labelitemiii`, or `\labelitemiv`, depending upon its nesting level within other `itemize` environments. The “tick marks” produced by the `itemize` environment may be changed by redefining these commands with `\renewcommand`.

If an item of a `description` environment begins with a displayed-paragraph environment, the item label may overprint the first line of that environment. If this happens, the item should begin with an `\mbox{}` command to cause the environment to start on a new line.

```
\item[label]
```

Starts a new item and produces its label. The item label is generated by the *label* argument if present; otherwise the default label is used. In `itemize` and

`enumerate`, the label is typeset flush right a fixed distance from the item's left margin. In `enumerate`, the optional argument suppresses the incrementing of the enumeration counter. The default label is null in the `description` environment. The `\item` command is fragile.

C.6.3 The `list` and `trivlist` Environments

```
\begin{list}{default_label}{decls} item_list \end{list}
```

Produces a list of labeled items.

item_list The text of the items. Each item is begun with an `\item` command (Section C.6.2).

default_label The label generated by an `\item` command with no optional argument.

decls A sequence of declarations that can be used to change any of the following parameters that control formatting in the `list` environment. (See also Figure 6.3 on page 113.)

`\topsep` The amount of extra vertical space (in addition to `\parskip`) inserted between the preceding text and the first list item, and between the last item and the following text. It is a rubber length.

`\partopsep` The extra vertical space (in addition to `\topsep + \parskip`) inserted, if the environment is preceded by a blank line, between the preceding text and the first list item and between the last item and the following text. It is a rubber length.

`\itemsep` The amount of extra vertical space (in addition to `\parsep`) inserted between successive list items. It is a rubber length.

`\parsep` The amount of vertical space between paragraphs within an item. It is the value to which `\parskip` is set within the list. It is a rubber length.

`\leftmargin` The horizontal distance between the left margin of the enclosing environment and the left margin of the list. It must be nonnegative. In the standard document classes, it is set to `\leftmargini`, `\leftmarginii`, ... or `\leftmarginvi`, depending on the nesting level of the `list` environment.

`\rightmargin` The horizontal distance between the right margin of the enclosing environment and the right margin of the list. It must be non-negative. Its default value is zero in the standard document classes.

`\listparindent` The amount of extra indentation added to the first line of every paragraph except the first one of an item. Its default value is zero in the standard document classes. It may have a negative value.

`\itemindent` The indentation of the first line of an item. Its default value is zero in the standard document classes. It may have a negative value.

`\labelsep` The space between the end of the box containing the label and the text of the first line of the item. It may be set to a negative length.

`\labelwidth` The normal width of the box that contains the label. It must be nonnegative. In the standard document styles, its default value is `\leftmargin... - \labelsep`, so the left edge of the label box is flush with the left margin of the enclosing environment. If the natural width of the label is greater than `\labelwidth`, then the label is typeset in a box with its natural width, so the label extends further to the right than “normal”.

`\makelabel{label}` A command that generates the label printed by the `\item` command from the *label* argument. Its default definition positions the label flush right against the right edge of its box. It may be redefined with `\renewcommand`.

In addition to declarations that set these parameters, the following declaration may appear in *decls*:

`\usecounter{ctr}` Enables the counter *ctr* (Section 6.3) to be used for numbering list items. It causes *ctr* to be initialized to zero and incremented by `\refstepcounter` when executing an `\item` command that has no optional argument, causing its value to become the current `\ref` value (Section C.11.2). It is a fragile command.

`\begin{trivlist} item_list \end{trivlist}`

Acts like a `list` environment using the current values of the list-making parameters, except with `\parsep` set to the current value of `\parskip` and the following set to zero: `\leftmargin`, `\labelwidth`, and `\itemindent`. The `trivlist` environment is normally used to define an environment consisting of a single list item, with an `\item` command appearing as part of the environment’s definition.

C.6.4 Verbatim

`\begin{verbatim} literal_text \end{verbatim}`
`\begin{verbatim*} literal_text \end{verbatim*}`

Typesets *literal_text* exactly as typed, including special characters, spaces, and line breaks, using a typewriter type style. The only text following the `\begin` command that is not treated literally is the `\end` command. The `*-form` differs only in that spaces are printed as `□` symbols.

If there is no nonspace character on the line following the `\begin` command, then *literal_text* effectively begins on the next line. There can be no space between the `\end` and the `{verbatim}` or `{verbatim*}`.

A `verbatim` or `verbatim*` environment may not appear in the argument of any command.

```
\verbchar    literal_text  char
\verb*char   literal_text  char
```

Typesets *literal_text* exactly as typed, including special characters and spaces, using a typewriter type style. There may be no space between `\verb` or `\verb*` and *char*. The `*`-form differs only in that spaces are printed as `\space` symbols.

char Any nonspace character, except it may not be a `*` for `\verb`.

literal_text Any sequence of characters not containing an end-of-line character or *char*.

A `\verb` or `\verb*` command may not appear in the argument of any other command.

```
\begin{alltt}  literal_text  \end{alltt}
```

Like the `verbatim` environment, except the three characters `\`, `{`, and `}` have their usual meanings. Thus, you can use commands like `\input` in the environment. This command is defined by the `alltt` package.

C.7 Mathematical Formulas

Unless otherwise noted, all commands described in this section can be used only in math mode. See Section 3.3.8 for an explanation of the display and text math styles.

C.7.1 Math Mode Environments

```
$          formula  $
\(<         formula  \)
\begin{math} formula  \end{math}
```

These equivalent forms produce an in-text formula by typesetting *formula* in math mode using text style. They may be used in paragraph or LR mode. The `\(` and `\)` commands are fragile; `$` is robust.

```
\ensuremath{formula}
```

Equivalent to `\(formula\)` when used in paragraph or LR mode; equivalent to *formula* when used in math mode.

```

\[ formula \]
\begin{displaymath} formula \end{displaymath}

```

These equivalent forms produce a displayed formula by typesetting *formula* in math mode using display style. They may be used only in paragraph mode. The displayed formula is centered unless the `fleqn` document-class option is used (Section 6.1.1). The commands `\[` and `\]` are fragile.

```

\begin{equation} formula \end{equation}

```

The same as `displaymath` except that an equation number is generated using the `equation` counter. The equation number is positioned flush with the right margin, unless the `leqno` document-class option is used (Section 6.1.1).

```

\begin{eqnarray} eqns \end{eqnarray}
\begin{eqnarray*} eqns \end{eqnarray*}

```

Produces a sequence of displayed formulas aligned in three columns. The *eqns* text is like the body of an `array` environment (Section 3.3.3) with argument `rc1`; it consists of a sequence of rows separated by `\\` commands, each row consisting of three columns separated by `&` characters. (However, a `\multicolumn` command may not be used.) The first and third columns are typeset in display style, the second in text style. These environments may be used only in paragraph mode.

The `eqnarray` environment produces an equation number for each row, generated from the `equation` counter and positioned as in the `equation` environment. A `\label` command anywhere within the row refers to that row's number. A `\nonumber` command suppresses the equation number for the row in which it appears. The `eqnarray*` environment produces no equation numbers.

The command `\lefteqn{formula}` prints *formula* in display math style (Section 3.3.8), but pretends that it has zero width. It is used within an `eqnarray` or `eqnarray*` environment for splitting long formulas across lines.

An overfull `\hbox` warning occurs if a formula extends beyond the prevailing margins. However, if the formula does lie within the margins, no warning is generated even if it extends far enough to overprint the equation number.

Style Parameters

`\jot` The amount of extra vertical space added between rows in an `eqnarray` or `eqnarray*` environment.

`\mathindent` The indentation from the left margin of displayed formulas in the `fleqn` document-class option.

`\abovedisplayskip` The amount of extra space left above a long displayed formula—except in the `fleqn` document-class option, where `\topsep` is

used. A long formula is one that lies closer to the left margin than does the end of the preceding line. It is a rubber length.

`\belowdisplayskip` The amount of extra space left below a long displayed formula—except in the `fleqn` document-class option, where `\topsep` is used. It is a rubber length.

`\abovedisplayshortskip` The amount of extra space left above a short displayed formula—except in the `fleqn` document-class option, which uses `\topsep`. A short formula is one that starts to the right of where the preceding line ends. It is a rubber length.

`\belowdisplayshortskip` The amount of extra space left below a short displayed formula—except in the `fleqn` document-class option, which uses `\topsep`. It is a rubber length.

C.7.2 Common Structures

`_{}{sub}` Typesets *sub* as a subscript. Robust.

`^{}{sup}` Typesets *sup* as a superscript. Robust.

`'` Produces a prime symbol (*'*). Robust.

`\frac{numer}{denom}` Generates a fraction with numerator *numer* and denominator *denom*. Robust.

`\sqrt[n]{arg}` Generates the notation for the n^{th} root of *arg*. With no optional argument, it produces the square root (no indicated root). Fragile.

ellipsis The following commands produce an ellipsis (three dots) arranged as indicated. They are all robust.

`\ldots` Horizontally at the bottom of the line (...). It may be used in paragraph and LR mode as well as math mode.

`\cdots` Horizontally at the center of the line (...).

`\vdots` Vertically ($\vdots$).

`\ddots` Diagonally ($\ddots$).

C.7.3 Mathematical Symbols

See Tables 3.3 through 3.8 on pages 41–44. The symbols in Table 3.8 are printed differently in display and text styles; in display style, subscripts and superscripts

may be positioned directly above and below the symbol. All the commands listed in those tables are robust.

Log-like functions, which are set in roman type, are listed in Table 3.9 on page 44. Subscripts appear directly below the symbol in display style for `\det`, `\gcd`, `\inf`, `\lim`, `\liminf`, `\limsup`, `\max`, `\min`, `\Pr`, and `\sup`. All log-like commands are robust. The following commands also create symbols:

`\bmod` Produces a binary *mod* symbol. Robust.

`\pmod{arg}` Produces “(mod *arg*)”. Robust.

C.7.4 Arrays

See Section C.10.2.

C.7.5 Delimiters

`\leftdelim formula \rightdelim`

Typesets *formula* and puts large delimiters around it, where *delim* is one of the delimiters in Table 3.10 on page 47 or a ‘.’ character to signify an invisible delimiter. The `\left` and `\right` commands are robust.

C.7.6 Putting One Thing Above Another

`\overline{formula}`

Typesets *formula* with a horizontal line above it. Robust.

`\underline{formula}`

Typesets *formula* with a horizontal line below it. May be used in paragraph or LR mode as well as math mode. Fragile.

accents

Table 3.11 on page 50 lists math-mode accent-making commands. They are robust, as are the following additional accenting commands:

`\widehat` Wide version of `\hat`.

`\widetilde` Wide version of `\tilde`.

`\imath` Dotless *i* for use with accents.

`\jmath` Dotless *j* for use with accents.

`\stackrel{top}{bot}`

Typesets *top* immediately above *bot*, using the same math style for *top* as if it were a superscript.

C.7.7 Spacing

The following commands produce horizontal space in math mode. They are all robust. The `\,` command may also be used in paragraph and LR mode.

<code>\,</code>	thin space	<code>\:</code>	medium space
<code>\!</code>	negative thin space	<code>\;</code>	thick space

C.7.8 Changing Style

Type Style

The following commands cause letters, numbers, and uppercase Greek letters in their argument *arg* to be typeset in the indicated style. The commands may be used only in math mode. They are robust.

<code>\mathrm{text}</code>	Roman	<code>\mathsf{text}</code>	Sans Serif
<code>\mathit{text}</code>	<i>Italic</i>	<code>\mathtt{text}</code>	Typewriter
<code>\mathbf{text}</code>	Boldface	<code>\mathcal{text}</code>	<i>CALLIGRAPHIC</i>

The argument of `\mathcal` may contain only uppercase letters.

The following two commands affect all characters in a formula. They may be used only in paragraph or LR mode. They are robust.

`\boldmath` Causes math formulas to be typeset in a bold style. It causes L^AT_EX to generate a warning if a formula could use a bold-series font that is not available, even if the font is not actually used.

`\unboldmath` Causes math formulas to be typeset in a normal (nonbold) style.

Math Style

The following declarations can appear only in math mode. They choose the type size and certain formatting parameters, including ones that control the placement of subscripts and superscripts. All are robust commands.

`\displaystyle` Default style for displayed formulas.

`\textstyle` Default style for in-text formulas and for the items in an `array` environment.

`\scriptstyle` Default style for first-level subscripts and superscripts.

`\scriptscriptstyle` Default style for higher-level subscripts and superscripts.

C.8 Definitions, Numbering, and Programming

C.8.1 Defining Commands

```
\newcommand    {cmd}[args][opt]{def}
\renewcommand  {cmd}[args][opt]{def}
\providecommand{cmd}[args][opt]{def}
```

These commands define or redefine a command. They are all fragile.

cmd A command name beginning with `\` and followed by either a sequence of letters or a single nonletter. For `\newcommand` it must not be already defined and must not begin with `\end`; for `\renewcommand` it must already be defined. The command `\providecommand` acts like `\newcommand` unless *cmd* is already defined, in which case it does nothing and the old definition is retained.

args An integer from 1 to 9 denoting the number of arguments of the command being defined. The default is for the command to have no arguments.

opt If this argument is present, then the first of the *args* arguments of *cmd* is optional and has a default value of *opt*. If this argument is absent, then all arguments of *cmd* are mandatory.

def The text to be substituted for every occurrence of *cmd*; a parameter of the form `#n` in *cmd* is replaced by the text of the *n*th argument when this substitution takes place. It may contain command- and environment-defining commands only if all commands and environments they define have no arguments.

The argument-enclosing braces of a command defined or redefined with any of these three commands do not delimit the scope of a declaration in that argument. (However, the scope may be delimited by braces that appear within *def*.) The defined command is fragile if it has an optional argument or if *def* includes a fragile command; otherwise it is robust.

C.8.2 Defining Environments

```
\newenvironment {nam}[args][opt]{begdef}{enddef}
\renewenvironment{nam}[args][opt]{begdef}{enddef}
```

These commands define or redefine an environment. They are both fragile.

nam The name of the environment; it can be any sequence of letters, numbers, and the character `*` that does not begin with `end`. For `\newenvironment`, neither an environment by that name nor the command `\nam` may already be defined. For `\renewenvironment`, the environment must already be defined.

args An integer from 1 to 9 denoting the number of arguments of the newly defined environment. The default is no arguments.

opt If this argument is present, then the first of the *args* arguments of the environment is optional and has a default value of *opt*. If this argument is absent, then all arguments of the environment are mandatory.

begdef The text substituted for every occurrence of `\begin{nam}`; a parameter of the form `#n` in *begdef* is replaced by the text of the *n*th argument of `\begin{nam}` when this substitution takes place.

enddef The text substituted for every occurrence of `\end{nam}`. It may not contain any argument parameters.

The *begdef* and *enddef* arguments may contain command- and environment-defining commands only if all commands and environments they define have no arguments. The argument-enclosing braces of an environment that was defined with `\newenvironment` or `\renewenvironment` do not delimit the scope of a declaration contained in the argument.

C.8.3 Theorem-like Environments

```
\newtheorem {env_name}{caption}[within]  
\newtheorem {env_name}[numbered_like]{caption}
```

This command defines a theorem-like environment. It is a global declaration (Section C.1.4) and is fragile.

env_name The name of the environment—a string of letters. It must not be the name of an existing environment or counter.

caption The text printed at the beginning of the environment, right before the number.

within The name of an already defined counter, usually of a sectional unit. If this argument is present, the command `\theenv_name` is defined to be

```
\thewithin.\arabic{env_name}
```

and the *env_name* counter will be reset by a `\stepcounter{within}` or `\refstepcounter{within}` command (Section C.8.4). If the *within* argument is missing, `\theenv_name` is defined to be `\arabic{env_name}`.

numbered_like The name of an already defined theorem-like environment. If this argument is present, the *env_name* environment will be numbered in the same sequence (using the same counter) as the *numbered_like* environment and will declare the current `\ref` value (Section C.11.2) to be the text generated by `\thenumbered_like`.

Unless the *numbered_like* argument is present, this command creates a counter named *env_name*, and the environment declares the current `\ref` value (Section C.11.2) to be the text generated by `\theenv_name`.

The `\newtheorem` command may have at most one optional argument. See Section C.1.1 if a `\newtheorem` without a final optional argument is followed by a `[` character.

C.8.4 Numbering

The following commands manipulate counters. There are packages that provide additional commands for performing arithmetic calculations; check the *L^AT_EX Companion*.

`\newcounter{newctr}[within]`

Defines a new counter named *newctr* that is initialized to zero, with `\thenewctr` defined to be `\arabic{newctr}`. It is a global declaration. The `\newcounter` command may not be used in an `\include`'d file (Section 4.4). Fragile.

newctr A string of letters that is not the name of an existing counter.

within The name of an already defined counter. If this argument is present, the *newctr* counter is reset to zero whenever the *within* counter is stepped by `\stepcounter` or `\refstepcounter` (see below).

`\setcounter{ctr}{num}`

Sets the value of counter *ctr* to *num*. It is a global declaration (Section C.1.4). Fragile.

`\addtocounter{ctr}{num}`

Increments the value of counter *ctr* by *num*. It is a global declaration (Section C.1.4). Fragile.

`\value{ctr}`

Produces the value of counter *ctr*. It is used mainly in the *num* argument of a `\setcounter` or `\addtocounter` command—for example, the command `\setcounter{bean}{\value{page}}` sets counter *bean* equal to the current value of the *page* counter. However, it can be used anywhere that *L^AT_EX* expects a number. The `\value` command is robust, and must never be preceded by a `\protect` command.

numbering commands

The following commands print the value of counter *ctr* in the indicated format. They are all robust.

`\arabic{ctr}` Arabic numerals.

`\roman{ctr}` Lowercase roman numerals.

`\Roman{ctr}` Uppercase roman numerals.

`\alph{ctr}` Lowercase letters. The value of *ctr* must be less than 27.

`\Alph{ctr}` Uppercase letters. The value of *ctr* must be less than 27.

`\fnsymbol{ctr}` Produces one of the nine “footnote symbols” from the following sequence: * † ‡ § ¶ || ** †† ‡‡. It may be used only in math mode. The value of *ctr* must be less than 10.

`\thectr`

A command used to print the value associated with counter *ctr*. Robust.

`\stepcounter {ctr}`

`\refstepcounter{ctr}`

Increment the value of counter *ctr* by one and reset the value of any counter numbered “within” it. For example, the `subsection` counter is numbered within the `section` counter, which, in the `report` or `book` document style, is numbered within the `chapter` counter. The `\refstepcounter` command also declares the current `\ref` value (Section C.11.2) to be the text generated by `\thectr`.

C.8.5 The `ifthen` Package

The `ifthen` package provides commands for writing simple programs with tests and loops. The use of these commands is illustrated in Figure C.5. This section may not make much sense unless you have already done some programming.

`\ifthenelse{test}{then_txt}{else_txt}`

If *test* is true, then *then_txt* is processed; if *test* is false, then *else_txt* is processed. The *then_txt* and *else_txt* arguments can be any L^AT_EX input. The *test* argument must be an expression that L^AT_EX evaluates to *true* or *false*. It can be any of the following:

*num*₁ *op* *num*₂ A numerical relation, where *op* is one of the following three characters: > = <, and *num*₁ and *num*₂ are numbers. For example, `\value{page}>17` evaluates to *true* if and only if the current value of the `page` counter is greater than 17.

`\equal{str1}{str2}` Evaluates to *true* if and only if T_EX regards *str*₁ and *str*₂ as equal. T_EX may think the two arguments are different even if they print the same—for example, `\today` and `May 1, 2001` are not equal, even on

The gcd (greatest common divisor) of m and n is printed by the following algorithm, which successively subtracts the smaller value from the larger until the two are equal.

```

a := m;  b := n;
while a ≠ b
  do if a > b then a := a - b
      else b := b - a;
print(a)

```

For example: $\text{Gcd}(54,30) = \text{gcd}(24,30) = \text{gcd}(24,6)$
 $= \text{gcd}(18,6) = \text{gcd}(12,6) = \text{gcd}(6,6) = 6$.

```

\newcounter{ca} \newcounter{cb}
\newcommand{\printgcd}[2]{%
  \setcounter{ca}{#1}\setcounter{cb}{#2}%
  Gcd(#1,#2) =
  \whiledo{\not\(\value{ca}=\value{cb}\)}%
    {\ifthenelse{\value{ca}>\value{cb}}%
      {\addtocounter{ca}{-\value{cb}}}%
      {\addtocounter{cb}{-\value{ca}}}%
      gcd(\arabic{ca},\arabic{cb}) = }%
  \arabic{ca}.}

```

... For example: `\printgcd{54}{30}`

Figure C.5: Writing programs with the `ifthen` package's commands.

May 1, 2001. T_EX will think str_1 and str_2 are equal if replacing every command by its definition makes them identical. For example, `no□\g{x}` and `no□x-gnu-x` are equal if `\g` is defined by

```
\newcommand{\g}[1]{#1-gnu-#1}
```

If you're not sure exactly what equals what, try some experiments.

`\lengthtest{len1 op len2}` A length relation, where *op* is one of the following three characters: `>`, `=`, `<`, and *len₁* and *len₂* are lengths. For example, `\lengthtest{\parindent < 1cm}` evaluates to *true* if and only if the current value of `\parindent` is less than 1 centimeter. In evaluating the relation, a rubber length is replaced by its natural length (Section 6.4.1).

`\isodd{num}` Evaluates to *true* if and only if the number *num* is odd. It is used to produce different text for left- and right-hand pages. However, the obvious `\isodd{\value{page}}` doesn't work, because the current value of the `page` counter could be 42 even though the text now being processed will wind up on page 43 (see Section 8.1). Instead, use `\label{key}` and `\isodd{\pageref{key}}` (Section C.11.2). The `page` counter does have the expected value when processing the page's head or foot.

`\boolean{nam}` Evaluates to the current value of the boolean register *nam*, where *nam* can be any sequence of letters. This register must be defined with the command `\newboolean{name}`. Its value is set by the command `\setboolean{nam}{bool}`, where *bool* is either *true* or *false*.

complex expressions A *test* can be built up from simpler expressions in the customary fashion using the boolean operators `\and`, `\or`, and `\not`, with `\(` and `\)` serving as parentheses.

```
\whiledo{test}{body}
```

Repeatedly processes *body* until *test* becomes false, where *test* is the same as for `\ifthenelse`. (Does nothing if *test* is initially false.)

C.9 Figures and Other Floating Bodies

C.9.1 Figures and Tables

```
\begin{figure}[loc]    body    \end{figure}
\begin{figure*}[loc]    body    \end{figure*}
\begin{table}[loc]      body    \end{table}
\begin{table*}[loc]     body    \end{table*}
```

These environments produce floating figures and tables. In two-column format, the ordinary forms produce single-column figures and tables and the `*`-forms produce double-column ones. The two forms are equivalent in single-column format.

The *body* is typeset in a parbox of width `\textwidth`. It may contain one or more `\caption` commands (see below). The *loc* argument contains a sequence of one to four letters, each one specifying a location where the figure or table may be placed, as follows:

- h *Here*: at the position in the text where the environment appears. (Not possible for double-column figures and tables in two-column format.)
- t *Top*: at the top of a text page.
- b *Bottom*: at the bottom of a text page. (Not possible for double-column figures or tables in two-column format.)
- p *Page of floats*: on a separate page containing no text, only figures and tables.

If the *loc* argument is missing, the default specifier is `tbp`, so the figure or table may be placed at the top or bottom of a text page or on a separate page consisting only of figures and/or tables.

The *loc* argument can also contain the character `!`, which directs $\text{\LaTeX}$ to try harder to place the figure or table at the earliest possible place in the document allowed by the rest of the argument. What “trying harder” means is explained below.

You may find that $\text{\LaTeX}$ puts a figure or table where you don’t want it. If the figure or table is printed too soon, you can either move it later in the input or use the `\suppressfloats` command described below. If it is printed too late, you can move it earlier in the input or use an optional argument with a `!` character. Occasionally, you will find that nothing seems to work. You may then think you

have discovered a bug in L^AT_EX. You almost certainly haven't. No computer program can deduce exactly where you want your figures to go. L^AT_EX's figure-placement algorithm was carefully designed to do the best it could. To solve your problem, you will have to understand why L^AT_EX puts the figure or table where it does. L^AT_EX follows the rules listed below. You will have to read these rules slowly and carefully to understand what L^AT_EX is doing. The last rule, which mentions the formatting parameters, is likely to be the key. You will have to read the descriptions of these parameters carefully to understand the rule. There are fifteen parameters, but one of the first seven is probably responsible for your problem.

Here are the rules that determine where a figure or table is put:

- It is printed at the earliest place that does not violate subsequent rules, except that an *h* (here) position takes precedence over a *t* (top) position.
- It will not be printed on an earlier page than the place in the text where the `figure` or `table` environment appears.
- A figure will not be printed before an earlier figure, and a table will not be printed before an earlier table.²
- It may appear only at a position allowed by the *loc* argument, or, if that argument is missing, by the default `tbp` specifier.
- Placement of the figure or table cannot produce an overfull page.
- The page constraints determined by the formatting parameters described below are not violated. However, if a `!` appears in the optional argument, then the constraints for text pages are ignored, and only the ones for float pages (expressed by `\floatpagefraction` and `\dblfloatpagefraction`) apply.

The last three rules are suspended when a `\clearpage`, `\cleardoublepage`, or `\end{document}` command occurs, all unprocessed figures and tables being allowed a *p* option and printed at that point.

When giving an optional *loc* argument, include enough options so these rules allow the figure or table to go somewhere, otherwise it and all subsequent figures or tables will be saved until the end of the chapter or document, probably causing T_EX to run out of space.

`\caption[lst_entry]{heading}`

Produces a numbered caption.

²However, in a two-column page style, a single-column figure can come before an earlier double-column figure, and vice versa.

lst_entry Generates the entry in the list of figures or tables. Such an entry should not contain more than a few hundred characters. If this argument is missing, the *heading* argument is used. It is a moving argument.

heading The text of the caption. It produces the list of figures or tables entry if the *lst_entry* argument is missing, in which case it is a moving argument. If this argument contains more than a few hundred characters, a shorter *lst_entry* argument should be used—even if no list of figures or tables is being produced.

A `\label` command that refers to the caption's number must go in *heading* or after the `\caption` command in the *body* of the `figure` or `table` environment. The `\caption` command can be used only in paragraph mode, but can be placed in a parbox made with a `\parbox` command or `minipage` environment (Section 6.4.3). It is fragile.

`\suppressfloats[loc]`

Prevents additional figures and tables from appearing on the current page. There are two possible *loc* arguments:

- t No more figures or tables at the top of the current page.
- b No more figures or tables at the bottom of the current page.

With no optional argument, additional figures and tables are suppressed from both the top and bottom of the current page. A `!` in the optional argument of a `figure` or `table` environment counteracts the effect of a `\suppressfloats` command for that particular figure or table.

Style Parameters

Changes made to the following parameters in the preamble apply from the first page on. Changes made afterwards take effect on the next page, not the current one. A *float* denotes either a figure or a table, and a *float page* is a page containing only floats and no text. Parameters that apply to all floats in a one-column page style apply to single-column floats in a two-column style.

topnumber A counter whose value is the maximum number of floats allowed at the top of a text page.

\topfraction The maximum fraction of the page that can be occupied by floats at the top of the page. Thus, the value `.25` specifies that as much as the top quarter of the page may be devoted to floats. It is changed with `\renewcommand`.

bottomnumber Same as **topnumber** except for the bottom of the page.

- `\bottomfraction` Same as `\topfraction` except for the bottom of the page.
- `totalnumber` A counter whose value is the maximum number of floats that can appear on a single text page, irrespective of their positions.
- `\textfraction` The minimum fraction of a text page that must be devoted to text. The other $1 - \text{\textfraction}$ fraction may be occupied by floats. It is changed with `\renewcommand`.
- `\floatpagefraction` The minimum fraction of a float page that must be occupied by floats, limiting the amount of blank space allowed on a float page. It is changed with `\renewcommand`.
- `dbltopnumber` The analog of `topnumber` for double-column floats on a two-column page.
- `\dbltopfraction` The analog of `\topfraction` for double-column floats on a two-column page.
- `\dblfloatpagefraction` The analog of `\floatpagefraction` for a float page of double-column floats.
- `\floatsep` The vertical space added between floats that appear at the top or bottom of a text page. It is a rubber length.
- `\textfloatsep` The vertical space added between the floats appearing at the top or bottom of a page and the text on that page. It is a rubber length.
- `\intextsep` The vertical space placed above and below a float that is put in the middle of the text with the `h` location option. It is a rubber length.
- `\dblfloatsep` The analog of `\floatsep` for double-width floats on a two-column page. It is a rubber length.
- `\dbltextfloatsep` The analog of `\textfloatsep` for double-width floats on a two-column page. It is a rubber length.

C.9.2 Marginal Notes

`\marginpar` [*left_text*]{*right_text*}

Produces a marginal note using *right_text* if it goes in the right margin or there is no optional argument, otherwise using *left_text*. The text is typeset in a parbox.

For two-sided, single-column printing, the default placement of marginal notes is on the outside margin—left for even-numbered pages, right for odd-numbered ones. For one-sided, single-column printing, the default placement is in the right margin. These defaults may be changed by the following declarations:

`\reversemarginpar` Causes marginal notes to be placed in the opposite margin from the default one.

`\normalmarginpar` Causes marginal notes to be placed in the default margin.

When a marginal note appears within a paragraph, its placement is determined by the declaration in effect at the blank line ending the paragraph. For two-column format, marginal notes always appear in the margin next to the column containing the note, irrespective of these declarations.

A marginal note is normally positioned so its top line is level with the line of text containing the `\marginpar` command; if the command comes between paragraphs, the note is usually level with the last line of the preceding paragraph. However, the note is moved down and a warning message printed on the terminal if this would make it overlap a previous note. Switching back and forth between reverse and normal positioning with `\reversemarginpar` and `\normalmarginpar` may inhibit this movement of marginal notes, resulting in one being overprinted on top of another.

Style Parameters

`\marginparwidth` The width of the parbox containing a marginal note.

`\marginparsep` The horizontal space between the outer margin and a marginal note.

`\marginparpush` The minimum vertical space allowed between two successive marginal notes.

C.10 Lining It Up in Columns

C.10.1 The tabbing Environment

`\begin{tabbing}` *rows* `\end{tabbing}`

This environment may be used only in paragraph mode. It produces a sequence of lines, each processed in LR mode, with alignment in columns based upon a sequence of tab stops. Tab stops are numbered 0, 1, 2, etc. Tab stop number i is said to be *set* if it is assigned a horizontal position on the page. Tab stop 0 is always set to the prevailing left margin (the left margin in effect at the beginning of the environment). If tab stop i is set, then all tab stops numbered 0 through $i - 1$ are also set. Tab stop number $i - 1$ is normally positioned to the left of tab stop number i .

The behavior of the tabbing commands is described in terms of the values of two quantities called *next_tab_stop* and *left_margin_tab*. Initially, the value of *next_tab_stop* is 1, the value of *left_margin_tab* is 0, and only tab number 0 is set. The value of *next_tab_stop* is incremented by the `\>` and `\=` commands, and

Gnat:	swatted by: men	<code>\begin{tabbing}</code>	
	cows	Armadillo: \=	<code>\kill</code>
	and gnus	Gnat: \> swatted by: \= men \+ \+ \\	
	not very filling	cows \\	
Armadillo:	not edible	and \' gnus \+ \\	
(note also the:	aardvark	not very filling \+ \\	
	albatross	Armadillo: \> not edible \\	
Gnu:	eaten by gnats	<code>\pushtabs</code>	
		(note also the: \= aardvark \\	
		\> albatross \' eton) \\	
		<code>\poptabs</code>	
		Gnu: \> eaten by \> gnats	
		<code>\end{tabbing}</code>	

Figure C.6: A `tabbing` environment example.

it is reset to the value of `left_margin_tab` by the `\\` and `\kill` commands. The following commands, all of which are fragile, may appear in *rows*; their use is illustrated in Figure C.6.

- `\=` If the value of `next_tab_stop` is *i*, then this command sets tab stop number *i*'s position to be the current position on the line and changes the value of `next_tab_stop` to *i* + 1.
- `\>` If the value of `next_tab_stop` is *i*, then this command starts the following text at tab stop *i*'s position and changes the value of `next_tab_stop` to *i* + 1.
- `\\` Starts a new line and sets the value of `next_tab_stop` equal to the value of `left_margin_tab`. See Section C.1.6 for more details.
- `\kill` Throws away the current line, keeping the effects of any tab-stop-setting commands, starts a new line, and sets the value of `next_tab_stop` to the value of `left_margin_tab`.
- `\+` Increases the value of `left_margin_tab` by one. This causes the left margin of subsequent lines to be indented one tab stop to the right, just as if a `\>` command were added to the beginning of subsequent lines. Multiple `\+` commands have the expected cumulative effect.
- `\-` Decreases the value of `left_margin_tab`, which must be positive, by one. This has the effect of canceling one preceding `\+` command, starting with the following line.
- `\<` Decreases the value of `next_tab_stop` by one. This command can be used only at the beginning of a line, where it acts to cancel the effect, on that line, of one previous `\+` command.

`\'` Used to put text flush right against the right edge of a column or against the left margin. If the value of *next.tab.stop* is *i*, then it causes everything in the current column—all text from the most recent `\>`, `\=`, `\'`, `\<`, or `\kill` command—to be positioned flush right a distance of `\tabbingsep` (a style parameter) from the position of tab stop number *i* − 1. Text following the `\'` command is placed starting at the position of tab stop number *i* − 1.

`\'` Moves all following text on the line flush against the prevailing right margin. There must be no `\>`, `\=`, or `\'` command after the `\'` and before the command that ends the output line.

`\pushtabs` Saves the current positions of all tab stops, to be restored by a subsequent `\poptabs` command. You can nest `\pushtabs` commands, but `\pushtabs` and `\poptabs` commands must come in matching pairs within a `tabbing` environment.

`\poptabs` See `\pushtabs`.

`\a...` The commands `\=`, `\'`, and `\'` usually produce accents, but are redefined to tabbing commands inside the `tabbing` environment. The commands `\a=`, `\a'`, and `\a'` produce those accents in a `tabbing` environment.

The `tabbing` environment exhibits the following anomalies:

- The scope of a declaration appearing in *rows* is ended by any of the following commands:

<code>\=</code>	<code>\></code>	<code>\+</code>	<code>\'</code>	<code>\pushtabs</code>	<code>\kill</code>
<code>\<</code>	<code>\<</code>	<code>\-</code>	<code>\'</code>	<code>\poptabs</code>	<code>\end{tabbing}</code>

No environment contained within the `tabbing` environment can contain any of these tabbing commands.

- The commands `\=`, `\'`, `\'`, and `\-` are redefined to have special meanings inside a `tabbing` environment. The ordinary `\-` command would be useless in this environment; the effects of the other three are obtained with the `\a...` command described above. These commands revert to their ordinary meanings inside a `parbox` contained within the `tabbing` environment.
- One `tabbing` environment cannot be nested within another, even if the inner one is inside a `parbox`.

Style Parameters

`\tabbingsep` See the description of the `\'` command above.

C.10.2 The array and tabular Environments

```
\begin{array}[pos]{cols}          rows \end{array}
\begin{tabular}[pos]{cols}         rows \end{tabular}
\begin{tabular*}[width][pos]{cols} rows \end{tabular*}
```

These environments produce a box (Section 6.4.3) consisting of a sequence of rows of items, aligned vertically in columns. The `array` environment can be used only in math mode, while `tabular` and `tabular*` can be used in any mode. Examples illustrating most of the features of these environments appear in Figure C.7.

width Specifies the width of the `tabular*` environment. There must be rubber space between columns that can stretch to fill out the specified width; see the `\extracolsep` command below.

pos Specifies the vertical positioning; the default is alignment on the center of the environment.

t align on top row.

b align on bottom row.

GG&A Hoofed Stock		
Year	Price	
	low	high
1971	97-245	Bad year.
72	245-245	Light trading due to a heavy winter.
73	245-2001	No gnus was very good gnus this year.

```
\begin{tabular}{|r||r@{--}l|p{1.25in}|}
\hline
\multicolumn{4}{|c|}{GG&A Hoofed Stock}
\\ \hline
\multicolumn{2}{|c|}{Price}& \\ \cline{2-3}
\multicolumn{1}{|c|}{Year}
& \multicolumn{1}{r@{\,}\vline\,}}{low}
& high & \multicolumn{1}{|c|}{Comments}
\\ \hline
1971 & 97 & 245 & Bad year. \\
72 & 245 & 245 & Light trading due to a
heavy winter. \\
73 & 245 & 2001 & No gnus was very
good gnus this year. \\
\end{tabular}
```

1.234	centaur	rite::gauche
56.7	scenter	wright::rad
8.99	cent	write::sinister

```
\begin{tabular*}{65mm}{@{}r@{.}l%
@{\extracolsep{\fill}}cr%
@{\extracolsep{0pt}::}l@{}}
\multicolumn{5}{c}{\underline{Table}} \\
1&234 & centaur & rite & gauche \\
56 & 7 & scenter & wright & rad \\
8&99 & cent & write & sinister
\end{tabular*}
```

Figure C.7: Examples of the `tabular` and `tabular*` environments.

cols Specifies the column formatting. It consists of a sequence of the following specifiers, corresponding to the sequence of columns and intercolumn material:

- l A column of left-aligned items.
- r A column of right-aligned items.
- c A column of centered items.
- | A vertical line the full height and depth of the environment.

`@{text}` This specifier is called an *@-expression*. It inserts *text* in every row, where *text* is processed in math mode in the `array` environment and in LR mode in the `tabular` and `tabular*` environments. The *text* is considered a moving argument, so any fragile command within it must be `\protect`'ed.

An *@-expression* suppresses the space L^AT_EX normally inserts between columns; any desired space between the inserted text and the adjacent items must be included in *text*. To change the space between two columns from the default to *wd*, put an `@{\hspace{wd}}` command (Section 6.4.1) between the corresponding column specifiers.

An `\extracolsep{wd}` command in an *@-expression* causes an extra space of width *wd* to appear to the left of all subsequent columns, until countermanded by another `\extracolsep` command. (However, it will not put space to the left of the first column.) Unlike ordinary intercolumn space, this extra space is not suppressed by an *@-expression*. An `\extracolsep` command can be used only in an *@-expression* in the *cols* argument. It is most commonly used to insert a `\fill` space (Section 6.4.1) in a `tabular*` environment.

`p{wd}` Produces a column with each item typeset in a parbox of width *wd*, as if it were the argument of a `\parbox[t]{wd}` command (Section 6.4.3). However, a `\\` may not appear in the item, except in the following situations: (i) inside an environment like `minipage`, `array`, or `tabular`, (ii) inside an explicit `\parbox`, or (iii) in the scope of a `\centering`, `\raggedright`, or `\raggedleft` declaration. The latter declarations must appear inside braces or an environment when used in a *p*-column element.

`*{num}{cols}` Equivalent to *num* copies of *cols*, where *num* is any positive integer and *cols* is any list of column-specifiers, which may contain another **-expression*.

An extra space, equal to half the default intercolumn space, is put before the first column unless *cols* begins with a `|` or *@-expression*, and after the last column unless *cols* ends with a `|` or *@-expression*. This space

usually causes no problem, but is easily eliminated by putting an @{} at the beginning and end of *cols*.

rows A sequence of rows separated by \\ commands (Section C.1.6). Each row is a sequence of items separated by & characters; it should contain the same number of items as specified by the *cols* argument. Each item is processed as if it were enclosed in braces, so the scope of any declaration in an item lies within that item. The following commands may appear in an item:

`\multicolumn{num}{col}{item}` Makes *item* the text of a single item spanning *num* columns, positioned as specified by *col*. If *num* is 1, then the command serves simply to override the item positioning specified by the environment argument. The *col* argument must contain exactly one l, r, or c and may contain one or more @-expressions and | characters. It replaces that part of the environment's *cols* argument corresponding to the *num* spanned columns, where the part corresponding to any column except the first begins with l, r, c, or p, so the *cols* argument |c|l@{:}lr has the four parts |c|, l@{:}, l, and r. A `\multicolumn` command must either begin the row or else immediately follow an &. It is fragile.

`\vline` When used within an l, r, or c item, it produces a vertical line extending the full height and depth of its row. An `\hfill` command (Section 6.4.2) can be used to move the line to the edge of the column. A `\vline` command can also be used in an @-expression. It is robust.

The following commands can go between rows to produce horizontal lines. They must appear either before the first row or immediately after a \\ command. A horizontal line after the last row is produced by ending the row with a \\ followed by one of these commands. (This is the only case in which a \\ command appears after the last row of an environment.) These commands are fragile.

`\hline` Draws a horizontal line extending the full width of the environment. Two `\hline` commands in succession leave a space between the lines; vertical rules produced by | characters in the *cols* argument do not appear in this space.

`\cline{col1-col2}` Draws a horizontal line across columns *col₁* through *col₂*. Two or more successive `\cline` commands draw their lines in the same vertical position. See the `\multicolumn` command above for how to determine what constitutes a column.

The following properties of these environments, although mentioned above, are often forgotten:

- These environments make a box; see Section 6.5 for environments and commands that can be used to position this box.
- The box made by these commands may have blank space before the first column and after the last column; this space can be removed with an @-expression.
- Any declaration in *rows* is within an item; its scope is contained within the item.
- An @-expression in *cols* suppresses the default intercolumn space.

Style Parameters

The following style parameters can be changed anywhere outside an `array` or `tabular` environment. They can also be changed locally within an item, but the scope of the change should be explicitly delimited by braces or an environment.

`\arraycolsep` Half the width of the default horizontal space between columns in an `array` environment.

`\tabcolsep` Half the width of the default horizontal space between columns in a `tabular` or `tabular*` environment.

`\arrayrulewidth` The width of the line created by a `|` in the *cols* argument or by an `\hline`, `\cline`, or `\vline` command.

`\doublerulesep` The width of the space between lines created by two successive `|` characters in the *cols* argument, or by two successive `\hline` commands.

`\arraystretch` Controls the spacing between rows. The normal interrow space is multiplied by `\arraystretch`, so changing it from its default value of 1 to 1.5 makes the rows 1.5 times farther apart. Its value is changed with `\renewcommand` (Section 3.4).

C.11 Moving Information Around

C.11.1 Files

L^AT_EX creates a number of ancillary files when processing a document. They all have the same first name as the root file (Section 4.4). These files are referred to, and listed below, by their extensions. A `\nofiles` command in the preamble prevents L^AT_EX from writing any of them except the `dvi` and `log` files. Knowing when and under what circumstances these files are read and written can help in locating and recovering from errors.

- aux** Used for cross-referencing and in compiling the table of contents, list of figures, and list of tables. In addition to the main **aux** file, a separate **aux** file is also written for each `\include`'d file (Section 4.4), having the same first name as that file. All **aux** files are read by the `\begin{document}` command. The `\begin{document}` command also starts writing the main **aux** file; writing of an `\include`'d file's **aux** file is begun by the `\include` command and is ended when the `\include`'d file has been completely processed. A `\nofiles` command suppresses the writing of all **aux** files. The table of contents and cross-reference information in the **aux** files can be printed by running $\text{\LaTeX}$ on the file `lablst.tex`.
- bb1** This file is written by $\text{\BibTeX}$, not by $\text{\LaTeX}$, using information on the **aux** file. It is read by the `\bibliography` command.
- dvi** This file contains $\text{\LaTeX}$'s output, in a form that is independent of any particular printer. (This printer-independence may be lost when using the `graphics`, `color`, and `pict2e` packages; see the introduction to Chapter 7.) Another program must be run to print the information on the **dvi** file. The file is always written unless $\text{\LaTeX}$ has generated no printed output.
- glo** Contains the `\glossaryentry` commands generated by `\glossary` commands. The file is written only if there is a `\makeglossary` command and no `\nofiles` command.
- idx** Contains the `\indexentry` commands generated by `\index` commands. The file is written only if there is a `\makeindex` command and no `\nofiles` command.
- ind** This file is written by *MakeIndex*, not by $\text{\LaTeX}$, using information on the **idx** file. It is read by the `\printindex` command. See Appendix A.
- lof** Read by the `\listoffigures` command to generate a list of figures; it contains the entries generated by all `\caption` commands in **figure** environments. The **lof** file is generated by the `\end{document}` command. It is written only if there is a `\listoffigures` command and no `\nofiles` command.
- log** Contains everything printed on the terminal when $\text{\LaTeX}$ is executed, plus additional information and some extra blank lines. It is always written. In some systems, this file has an extension other than **log**.
- lot** Read by the `\listoftables` command to generate a list of tables; it contains the entries generated by all `\caption` commands in **table** environments. The **lot** file is generated by the `\end{document}` command. It is written only if there is a `\listoftables` command and no `\nofiles` command.

`toc` Read by the `\tableofcontents` command to generate a table of contents; it contains the entries generated by all sectioning commands (except the `*`-forms). The `toc` file is generated by the `\end{document}` command. It is written only if there is a `\tableofcontents` command and no `\nofiles` command.

C.11.2 Cross-References

```
\label {key}
\ref {key}
\pageref{key}
```

The *key* argument is any sequence of letters, digits, and punctuation symbols; upper- and lowercase letters are regarded as different. L^AT_EX maintains a *current \ref value*, which is set with the `\refstepcounter` declaration (Section C.8.4). (This declaration is issued by the sectioning commands, by numbered environments like `equation`, and by an `\item` command in an `enumerate` environment.) The `\label` command writes an entry on the `aux` file (Section C.11.1) containing *key*, the current `\ref` value, and the number of the current page. When this `aux` file entry is read by the `\begin{document}` command (the next time L^AT_EX is run on the same input file), the `\ref` value and page number are associated with *key*, causing a `\ref{key}` or `\pageref{key}` command to produce the associated `\ref` value or page number, respectively.

The `\label` command is fragile, but it can be used in the argument of a sectioning or `\caption` command.

C.11.3 Bibliography and Citation

```
\bibliography{bib_files}
```

Used in conjunction with the BIB_TE_X program (Section 4.3.1) to produce a bibliography. The *bib_files* argument is a list of first names of bibliographic database (`bib`) files, separated by commas; these files must have the extension `bib`. The `\bibliography` command does two things: (i) it creates an entry on the `aux` file (Section C.11.1) containing *bib_files* that is read by BIB_TE_X, and (ii) it reads the `bbl` file (Section C.11.1) generated by BIB_TE_X to produce the bibliography. (The `bbl` file will contain a `thebibliography` environment.) The database files are used by BIB_TE_X to create the `bbl` file.

```
\begin{thebibliography}{widest_label} entries \end{thebibliography}
```

Produces a bibliography or source list. In the standard `article` document class, this source list is labeled “References”; in the `report` and `book` class, it is labeled “Bibliography”. See Section 6.1.4 for information on how to create a document-class option to change the reference list’s label.

widest_label Text that, when printed, is approximately as wide as the widest item label produced by the `\bibitem` commands in *entries*. It controls the formatting.

entries A list of entries, each begun by the command

```
\bibitem[label]{cite_key}
```

which generates an entry labeled by *label*. If the *label* argument is missing, a number is generated as the label, using the `enumiv` counter. The *cite_key* is any sequence of letters, numbers, and punctuation symbols not containing a comma. This command writes an entry on the `aux` file (Section C.11.1) containing *cite_key* and the item's label. When this `aux` file entry is read by the `\begin{document}` command (the next time L^AT_EX is run on the same input file), the item's label is associated with *cite_key*, causing a reference to *cite_key* by a `\cite` command to produce the associated label.

```
\cite[text]{key_list}
```

The *key_list* argument is a list of citation keys (see `\bibitem` above). This command generates an in-text citation to the references associated with the keys in *key_list* by entries on the `aux` file read by the `\begin{document}` command. It also writes *key_list* on the `aux` file, causing B_IB_TE_X to add the associated references to the bibliography (Section 4.3.1). If present, *text* is added as a remark to the citation. Fragile.

```
\nocite{key_list}
```

Produces no text, but writes *key_list*, which is a list of one or more citation keys, on the `aux` file. This causes B_IB_TE_X to add the associated references to the bibliography (Section 4.3.1). A `\nocite{*}` command causes B_IB_TE_X to add all references from the `bib` files. The `\nocite` command must appear after the `\begin{document}`. It is fragile.

C.11.4 Splitting the Input

```
\input{file_name}
```

Causes the indicated file to be read and processed, exactly as if its contents had been inserted in the current file at that point. The *file_name* may be a complete file name with extension or just a first name, in which case the file *file_name.tex* is used. If the file cannot be found, an error occurs and L^AT_EX requests another file name.

```
\include{file}
\includeonly{file_list}
```

Used for the selective inclusion of files. The *file* argument is the first name of a file, denoting the file *file.tex*, and *file_list* is a possibly empty list of first names of files separated by commas. If *file* is one of the file names in *file_list* or if there is no `\includeonly` command, then the `\include` command is equivalent to

```
\clearpage \input{file} \clearpage
```

except that if file *file.tex* does not exist, then a warning message rather than an error is produced. If *file* is not in *file_list*, the `\include` command is equivalent to `\clearpage`.

The `\includeonly` command may appear only in the preamble; an `\include` command may not appear in the preamble or in a file read by another `\include` command. Both commands are fragile.

```
\begin{filecontents}{nam} body \end{filecontents}
\begin{filecontents*}{nam} body \end{filecontents*}
```

If a file named *nam* does not exist, then one is created having *body* as its contents. If file *nam* already exists, then a warning message is printed and no file is written. The `filecontents` environment writes helpful identifying comments at the beginning of the file. These comments can cause problems if the file is used as input to a program that, unlike $\text{\LaTeX}$, does not treat lines beginning with `%` as comments. The `filecontents*` environment does not add any comments. These environments can appear only before the `\documentclass` command.

```
\listfiles
```

Causes $\text{\LaTeX}$ to print on the terminal a list of all files that it reads when processing the document, excluding ancillary files that it wrote. The command may appear only in the preamble.

C.11.5 Index and Glossary

Appendix A describes how to make an index using the *MakeIndex* program.

Producing an Index

```
\begin{theindex} text \end{theindex}
```

Produces a double-column index. Each entry is begun with either an `\item` command, a `\subitem` command, or a `\subsubitem` command.

```
\printindex
```

Defined by the *makeidx* package. This command just reads the *ind* file.

Compiling the Entries

`\makeindex` Causes the `\indexentry` entries produced by `\index` commands to be written on the `idx` file, unless a `\nofiles` declaration occurs. The `\makeindex` command may appear only in the preamble.

`\makeglossary` Causes the `\glossaryentry` entries produced by `\glossary` commands to be written on the `glo` file, unless a `\nofiles` declaration occurs. The `\makeglossary` command may appear only in the preamble.

`\index{str}` If an `idx` file is being written, then this command writes an `\indexentry{str}{pg}` entry on it, where `pg` is the page number. The `str` argument may contain any characters, including special characters, but it must have no unmatched braces, where the braces in `\{` and `\}` are included in the brace matching. The `\index` command may not appear inside another command's argument unless `str` contains only letters, digits, and punctuation characters. The command is fragile.

`\glossary{str}` If a `glo` file is being written, then this command writes a `\glossaryentry{str}{pg}` entry on it, where `str` and `pg` are the same as in the `\index` command, described above. The `\glossary` command may not appear inside another command's argument unless `str` contains only letters, digits, and punctuation characters. The command is fragile.

C.11.6 Terminal Input and Output

`\typeout{msg}`

Prints `msg` on the terminal and in the log file. Commands in `msg` that are defined with `\newcommand` or `\renewcommand` are replaced by their definitions before being printed. $\text{\LaTeX}$ commands in `msg` may produce strange results. Preceding a command name by `\protect` causes that command name to be printed.

$\text{\TeX}$'s usual rules for treating multiple spaces as a single space and ignoring spaces after a command name apply to `msg`. A `\space` command in `msg` causes a single space to be printed. The `\typeout` command is fragile; moreover, putting it in the argument of another $\text{\LaTeX}$ command may do strange things. The `msg` argument is a moving argument.

`\typein[cmd]{msg}`

Prints `msg` on the terminal, just like `\typeout{msg}`, and causes $\text{\TeX}$ to stop and wait for you to type a line of input, ending with `return`. If the `cmd` argument is missing, the typed input is processed as if it had been included in the input file in place of the `\typein` command. If the `cmd` argument is present, it must be a command name. This command name is then defined or redefined to be

the typed input. Thus, if *cmd* is not already defined, then the command acts like

```
\typeout{msg}
\newcommand{cmd}{typed input}
```

The `\typein` command is fragile; moreover, it may produce an error if it appears in the argument of a L^AT_EX command. The *msg* argument is a moving argument.

C.12 Line and Page Breaking

C.12.1 Line Breaking

```
\linebreak [num]
\nolinebreak[num]
```

The `\linebreak` command encourages and `\nolinebreak` discourages a line break, by an amount depending upon *num*, which is a digit from 0 through 4. A larger value of *num* more strongly encourages or discourages the line break; the default is equivalent to a *num* argument of 4, which either forces or completely prevents a line break. An underfull `\hbox` message is produced if a `\linebreak` command results in too much space between words on the line. Both commands are fragile.

```
\\ [len]
\\*[len]
\newline
```

These commands start a new line without justifying the current one, producing a ragged-right effect. The optional argument of `\\` adds an extra vertical space of length *len* above the new line. The `*-form` inhibits a page break right before the new line. The `\newline` command may be used only in paragraph mode and should appear within a paragraph; it produces an underfull `\hbox` warning and extra vertical space if used at the end of a paragraph, and an error when used between paragraphs. The `\\` command behaves the same way when used in paragraph mode. Both commands are fragile.

```
\-
```

Permits the line to be hyphenated (the line broken and a hyphen inserted) at that point. It inhibits hyphenation at any other point in the current word except where allowed by another `\-` command. Robust.

```
\hyphenation{words}
```

Declares allowed hyphenation points, where *words* is a list of words, separated by spaces, in which each hyphenation point is indicated by a `-` character. It is a global declaration (Section C.1.4) and is robust.

`\sloppy`
`\fussy`

Declarations that control line breaking. The `\fussy` declaration, which is the default, prevents too much space between words, but leaves words extending past the right-hand margin if no good line break is found. The `\sloppy` declaration almost always breaks lines at the right-hand margin, but may leave too much space between words, in which case TeX produces an underfull `\hbox` warning. Line breaking is controlled by the declaration in effect at the blank line or `\par` command that ends the paragraph.

`\begin{sloppypar} pars \end{sloppypar}`

Typesets *pars*, which must consist of one or more complete paragraphs, with the `\sloppy` declaration in effect.

C.12.2 Page Breaking

`\pagebreak [num]`
`\nopagebreak[num]`

The `\pagebreak` command encourages and `\nopagebreak` discourages column breaking by an amount depending upon *num*, where the entire page is a single column in a one-column page style. The *num* argument is a digit from 0 through 4, a larger value more strongly encouraging or discouraging a break; the default is equivalent to *num* having the value 4, which forces or entirely forbids a break. When used within a paragraph, these commands apply to the point immediately following the line in which they appear. When `\flushbottom` is in effect (Section 6.1.1), an underfull `\vbox` message is produced if `\pagebreak` results in too little text on the page. A `\nopagebreak` command will have no effect if another L^AT_EX command has explicitly allowed a page break to occur at that point. These commands have no effect when used in LR mode or inside a box. Both commands are fragile.

`\enlargethispage {len}`
`\enlargethispage*{len}`

These commands increase the height of the page that L^AT_EX is currently trying to produce by *len*, which must be a rigid length and may be negative. The `*`-form shrinks the vertical space on the page as much as possible, which is what you want to do when trying to squeeze a little more onto a page than TeX wants to put there. For two-sided printing, it is usually best to make facing pages the same height. These commands are fragile.

```
\newpage
\clearpage
\cleardoublepage
```

When one-column pages are being produced, these commands all end the current paragraph and the current page. Any unfilled space in the body of the page (Section 6.1.2) appears at the bottom, even with `\flushbottom` in effect (Section 6.1.1). The `\clearpage` and `\cleardoublepage` commands also cause all figures and tables that have so far appeared in the input to be printed, using one or more pages of only figures and/or tables if necessary. In a two-sided printing style, `\cleardoublepage` also makes the next page a right-hand (odd-numbered) page, producing a blank page if necessary.

When two-column text is being produced, `\newpage` ends the current column rather than the current page; `\clearpage` and `\cleardoublepage` end the page, producing a blank right-hand column if necessary. These commands should be used only in paragraph mode; they should not be used inside a parbox (Section 6.4.3). The `\newpage` and `\clearpage` commands are robust; `\cleardoublepage` is fragile.

C.13 Lengths, Spaces, and Boxes

C.13.1 Length

explicit lengths An explicit length is written as an optional sign (+ or -) followed by a decimal number (a string of digits with an optional decimal point) followed by a *dimensional unit*. The following dimensional units are recognized by TeX:

cm Centimeters.

em One em is about the width of the letter *M* in the current font.

ex One ex is about the height of the letter *x* in the current font.

in Inches.

pc Picas (1pc = 12pt).

pt Points (1in = 72.27pt).

mm Millimeters.

\fill A rubber length (Section 6.4.1) having a natural length of zero and the ability to stretch to any arbitrary (positive) length. Robust.

\stretch{*dec_num*} A rubber length having zero natural length and *dec_num* times the stretchability of `\fill`, where *dec_num* is a signed decimal number (an optional sign followed by a string of digits with an optional decimal point). Robust.

`\newlength{cmd}` Declares *cmd* to be a length command, where *cmd* is the name of a command not already defined. The value of *cmd* is initialized to zero inches. Fragile.

`\setlength{cmd}{len}` Sets the value of the length command *cmd* equal to *len*. Robust.

`\addtolength{cmd}{len}` Sets the value of the length command *cmd* equal to its current value plus *len*. Robust.

`\settowidth {cmd}{text}`

`\settoheight{cmd}{text}`

`\settodepth {cmd}{text}` Set the value of the length command *cmd* equal to the natural width, height, and depth, respectively, of the output generated when *text* is typeset in LR mode. Robust.

C.13.2 Space

`\hspace {len}`

`\hspace*{len}`

Produce a horizontal space of width *len*. The space produced by `\hspace` is removed if it falls at a line break; that produced by `\hspace*` is not. These commands are robust.

`\vspace {len}`

`\vspace*{len}`

Add a vertical space of height *len*. If the command appears in the middle of a paragraph, then the space is added after the line containing it. The space produced by `\vspace` is removed if it falls at a page break; that produced by `\vspace*` is not. These commands may be used only in paragraph mode; they are fragile.

`\bigskip`

`\medskip`

`\smallskip`

These commands are equivalent to the three commands

```
\vspace{\bigskipamount}      \vspace{\smallskipamount}
\vspace{\medskipamount}
```

where the three length commands `\bigskipamount`, `\medskipamount`, and `\smallskipamount` are style parameters. These space-producing commands can be used in the definitions of environments to provide standard amounts of vertical space. They are fragile.

`\addvspace{len}`

This command normally adds a vertical space of height *len*. However, if vertical space has already been added to the same point in the output by a previous `\addvspace` command, then this command will not add more space than needed to make the natural length of the total vertical space equal to *len*. It is used to add the extra vertical space above and below most L^AT_EX environments that start a new paragraph. It may be used only in paragraph mode between paragraphs—that is, after a blank line or `\par` command (in T_EX's vertical mode). Fragile.

`\hfill`

Equivalent to `\hspace{\fill}`.

`\vfill`

Equivalent to a blank line followed by `\vspace{\fill}`; it should be used only in paragraph mode.

C.13.3 Boxes

A *box* is an object that is treated by T_EX as a single character, so it will not be broken across lines or pages.

`\mbox{text}`

`\makebox[width][pos]{text}`

Typesets *text* in LR mode in a box. The box has the width of the typeset text except for a `\makebox` command with a *width* argument, in which case it has width *width*. In the latter case, the position of the text within the box is determined by the one-letter *pos* argument as follows:

- l Flush against left edge of box.
- r Flush against right edge of box.
- s Interword space in *text* is stretched or shrunk to try to fill the box exactly.

The default positioning is centered in the box. The `\mbox` command is robust; `\makebox` is fragile.

`\fbox{text}`

`\framebox[width][pos]{text}`

Similar to `\mbox` and `\makebox`, except that a rectangular frame is drawn around the resulting box. The `\fbox` command is robust; `\framebox` is fragile.

`\newsavebox{cmd}`

Declares *cmd*, which must be a command name that is not already defined, to be a bin for saving boxes. Fragile.

`\sbox{cmd}{text}`

`\savebox{cmd}[width][pos]{text}`

`\begin{lrbox}{cmd} text \end{lrbox}`

Typeset *text* in a box just as for `\makebox`. However, instead of printing the resulting box, they save it in bin *cmd*, which must have been declared with `\newsavebox`. In the `lrbox` environment, spaces are removed from the beginning and end of *text*. The `\sbox` command is robust; `\savebox` is fragile.

`\usebox{cmd}`

Prints the box most recently saved in bin *cmd*. Robust.

`\parbox [pos]{width}{text}`

`\begin{minipage}[pos]{width} text \end{minipage}`

They produce a *parbox*—a box of width *width* formed by typesetting *text* in paragraph mode. The vertical positioning of the box is specified by the one-letter *pos* argument as follows:

b The bottom line of the box is aligned with the current line of text.

t The top line of the box is aligned with the current line of text.

The default vertical positioning is to align the center of the box with the center of the current line of text.

The list-making environments listed in Section 6.6 and the `tabular` environment may appear in *text* with the `minipage` environment, but not with the `\parbox` command. (If *text* consists of only a `tabbing` environment, then the width of the resulting box is the actual width of the longest line rather than the *width* argument.) A `\footnote` or `\footnotetext` command appearing in *text* in a `minipage` environment produces a footnote at the bottom of the `parbox` ended by the next `\end{minipage}` command, which may be the wrong place for it when there are nested `minipage` environments. These footnote-making commands may not be used in the *text* argument of `\parbox`.

A `minipage` environment that begins with a displayed equation or with an `eqnarray` or `eqnarray*` environment will have extra vertical space at the top (except with the `fleqn` document-class option). This extra space can be removed by starting *text* with a `\vspace{-\abovedisplayskip}` command.

The `\parbox` command is fragile.

```
\rule[raise_len]{width}{hgt}
```

Generates a solid rectangle of width *width* and height *hgt*, raised a distance of *raise_len* above the bottom of the line. (A negative value of *raise_len* lowers it.) The default value of *raise_len* is zero inches. Fragile.

```
\raisebox{raise_len}[hgt][dpth]{text}
```

Creates a box by typesetting *text* in LR mode, raising it by *raise_len*, and pretending that the resulting box extends a distance of *hgt* above the bottom of the current line and a distance of *dpth* below it. If the *dpth* argument or both optional arguments are omitted, TeX uses the actual extent of the box. Fragile.

```
\width
```

```
\height
```

```
\depth
```

```
\totalheight
```

Length commands that can be used only in the *width* argument of `\makebox`, `\framebox`, and `\savebox`, and in the *raise_len*, *hgt*, and *dpth* arguments of `\raisebox`. They refer to the dimensions (width, height, depth, and height + depth) of the box obtained by typesetting the *text* argument.

Style Parameters


`\fboxrule` The width of the lines forming the box produced by `\fbox` and `\framebox`. However, the version of `\framebox` used in the `picture` environment (Section 7.1) employs the same width lines as other `picture` commands.

`\fboxsep` The amount of space left between the edge of the box and its contents by `\fbox` and `\framebox`. It does not apply to the version of `\framebox` used in the `picture` environment (Section 7.1).

C.14 Pictures and Color

C.14.1 The `picture` Environment

A *coordinate* is a decimal number—an optional sign followed by a string of digits with an optional decimal point. It represents a length in multiples of `\unitlength`. All argument names in this section that begin with *x* or *y* are coordinates.



```

\newcounter{cms}
...
\setlength{\unitlength}{1mm}
\begin{picture}(50,39)
\put(0,7){\makebox(0,0)[bl]{cm}}
\multiput(10,7)(10,0){5}{\addtocounter
    {cms}{1}\makebox(0,0)[b]{\arabic{cms}}}
\put(15,20){\circle{6}}
\put(30,20){\circle{6}}
\put(15,20){\circle*{2}}
\put(30,20){\circle*{2}}
\put(10,24){\framebox(25,8){car}}
\put(10,32){\vector(-2,1){10}}
\multiput(1,0)(1,0){49}{\line(0,1){2.5}}
\multiput(5,0)(10,0){5}{\line(0,1){3.5}}
\thicklines
\put(0,0){\line(1,0){50}}
\multiput(0,0)(10,0){6}{\line(0,1){5}}
\end{picture}

```

Figure C.8: A sample picture environment.

```

\begin{picture}(x_dimen,y_dimen)(x_offset,y_offset)
  pict_cmds
\end{picture}

```

Creates a box of width *x_dimen* and height *y_dimen*, both of which must be non-negative. The *(x_offset,y_offset)* argument is optional. If present, it specifies the coordinates of the lower-left corner of the picture; if absent, the lower-left corner has coordinates (0,0). (Like all dimensions in the **picture** environment, the lengths specified by the arguments of the **picture** environment are given in multiples of `\unitlength`.) The **picture** environment can be used anywhere that ordinary text can, including within another **picture** environment.

The *pict_cmds* are processed in picture mode—a special form of LR mode—and may contain only declarations and the following commands:

```

\put      \multiput    \qbezier    \graphpaper

```

Figure C.8 illustrates many of the picture-drawing commands described below.

Picture-Mode Commands

The following are the only commands, other than declarations, that can be used in picture mode.

`\put(x_coord,y_coord){picture_object}`

Places *picture_object* in the picture with its reference point at the position specified by coordinates (*x_coord*, *y_coord*). The *picture_object* can be arbitrary text, which is typeset in LR mode, or else one of the special picture-object commands described below. The `\put` command is fragile.

`\multiput(x_coord,y_coord)(x_incr,y_incr){num}{picture_object}`

Places *num* copies of *picture_object*, the i^{th} one positioned with its reference point having coordinates ($x_coord + [i - 1]x_incr$, $y_coord + [i - 1]y_incr$). The *picture_object* is the same as for the `\put` command above. It is typeset *num* times, so the copies need not be identical if it includes declarations. (See Figure C.8.) Fragile.

`\qbezier[num](x_coord_1,y_coord_1)(x_coord_2,y_coord_2)(x_coord_3,y_coord_3)`

Draws a quadratic Bezier curve whose control points are specified by the mandatory arguments (see Section 7.1.3). The *num* argument specifies the number of points plotted on the curve. If it is absent, a smooth curve is drawn, with the maximum number of points determined by the value of `\qbeziermax`. Use `\renewcommand` to change `\qbeziermax`:

`\renewcommand{\qbeziermax}{250}`

(With the `pict2e` package, there is no limit to the number of points plotted.)

`\graphpaper[spcing](x_coord,y_coord)(x_dimen,y_dimen)`

Defined by the `graphpap` package. It draws a coordinate grid with origin at (*x_coord*, *y_coord*), extending *x_dimen* units to the right and *y_dimen* units up. Grid lines are spaced every *spcing* units; the default value is 10. All arguments must be integers.

Picture Objects

`\makebox(x_dimen,y_dimen)[pos]{text}`

`\framebox(x_dimen,y_dimen)[pos]{text}`

`\dashbox{dash_dimen}(x_dimen,y_dimen)[pos]{text}`

Produce a box having width *x_dimen* and height *y_dimen* (in multiples of `\unitlength`) with reference point at its lower-left corner. The *text* is typeset in LR mode, positioned in the box as specified by the one- or two-letter *pos* argument as follows:

- l Horizontally positioned flush against the left edge of the box.
- r Horizontally positioned flush against the right edge of the box.

- t Vertically positioned flush against the top edge of the box.
- b Vertically positioned flush against the bottom edge of the box.

The default horizontal and vertical positioning is to center *text* in the box. The `\framebox` command also draws a rectangle showing the edges of the box, and `\dashbox` draws the rectangle with dashed lines, composed of dashes and spaces of length *dash_dimen* (in multiples of `\unitlength`), where *dash_dimen* is a positive decimal number. For best results, *x_dimen* and *y_dimen* should be integral multiples of *dash_dimen*. The thickness of the lines drawn by `\framebox` and `\dashbox` equals the width of the lines produced by other picture commands; it is not determined by `\fbboxrule`. All three commands are fragile.

`\line (h_slope,v_slope){dimen}`
`\vector(h_slope,v_slope){dimen}`

Draw a line having its reference point at the beginning and its slope determined by (h_slope, v_slope) , where *h_slope* and *v_slope* are positive or negative integers of magnitude at most 6 for `\line` and at most 4 for `\vector`, with no common divisors except ± 1 . (These restrictions are eliminated by the `pict2e` package.) In addition, `\vector` draws an arrowhead at the opposite end of the line from the reference point. The horizontal extent of the line is *dimen* (in multiples of `\unitlength`) unless *h_slope* is zero, in which case *dimen* is the (vertical) length of the line. However, a line that is neither horizontal nor vertical may not be drawn unless *dimen* times `\unitlength` is at least 10 points (1/7 inch). (This does not apply when the `pict2e` package is loaded.) The `\vector` command always draws the arrowhead. Both commands are fragile.

`\shortstack[pos]{col}`

The *pos* argument must be either *l*, *r*, or *c*, the default being equivalent to *c*. This command produces the same result as

`\begin{tabular}[b]{b}{pos} col \end{tabular}`

(Section 3.6.2) except that no space is left on either side of the resulting box and there is usually less interrow space. The reference point is at the left edge of the box, level with the reference point of the bottom line. Fragile.

`\circle {diam}`
`\circle*{diam}`

Draw a (hollow) circle and a disk (filled circle), respectively, with diameter as close as possible to *diam* times `\unitlength` and reference point in the center of the circle. The largest circle L^AT_EX can draw has a diameter of 40 points (about 1/2 inch) and the largest disk has a diameter of 15 points (about .2 inch). (With the `pict2e` package, any size circle or disk can be drawn.) Both commands are fragile.

`\oval[rad](x_dimen,y_dimen)[part]`

Draws an oval inscribed in a rectangle of width *x_dimen* and height *y_dimen*, its corners made with quarter circles of the largest possible radius less than or equal to *rad*. An explicit *rad* argument can be used only with the `pict2e` package; the default value is the radius of the largest quarter-circle L^AT_EX can draw without the `pict2e` package. The *part* argument consists of one or two of the following letters to specify a half or quarter oval: `l` (left), `r` (right), `t` (top), `b` (bottom). The default is to draw the entire oval. The reference point is the center of the (complete) oval. Fragile.

`\frame{picture_object}`

Puts a rectangular frame around *picture_object*. The reference point is the bottom left corner of the frame. No extra space is put between the frame and *picture_object*. Fragile.

Picture Declarations

The following declarations can appear anywhere in the document, including in picture mode. They obey the normal scope rules.

`\savebox{cmd}(x_dimen,y_dimen)[pos]{text}`

Same as the corresponding `\makebox` command, except the resulting box is saved in the bin *cmd*, which must be defined with `\newsavebox` (Section 6.4.3). Fragile.

`\thinlines`

`\thicklines`

They select one of the two standard thicknesses of lines and circles in the `picture` environment. The default is `\thinlines`. Robust.

`\linethickness{len}`

Declares the thickness of lines in a `picture` environment to be *len*, which must be a positive length. With the `pict2e` package, it applies to all lines; otherwise, it applies only to horizontal and vertical lines and does not affect the thickness of slanted lines and circles, or of the quarter circles drawn by `\oval` to form the corners of an oval.

C.14.2 The graphics Package

The following commands are provided by the `graphics` package. They are all fragile. This package requires special support from the device driver.

`\scalebox{h_scale}[v_scale]{text}`

Produces a box by typesetting *text* in LR mode and scaling it horizontally by a factor of *h_scale* and vertically by a factor of *v_scale*. The default value of *v_scale* is *h_scale*.

`\resizebox {width}{ht}{text}`

`\resizebox*{width}{ht}{text}`

Produce a box of width *width* and height *ht* by typesetting *text* in LR mode and scaling it horizontally and vertically to fit. In the ***-form, *ht* specifies the height + depth. If either argument is *!*, then the corresponding dimension is the one that maintains the aspect ratio of *text*.

`\rotatebox{ang}{text}`

Produces a box formed by typesetting *text* in LR mode and rotating it counterclockwise through an angle of *ang* degrees. The box is the smallest one containing the rotated box; its reference point is at the same height as that of the rotated box.

`\reflectbox{text}`

Produces a box by typesetting *text* in LR mode and reflecting it about a vertical line.

`\includegraphics [x_len1,y_len1] [x_len2,y_len2]{file_name}`

`\includegraphics*{x_len1,y_len1] [x_len2,y_len2]{file_name}`

Produces a box containing the graphic material in the file named *file_name*. With no optional arguments, the reference point and size of the box are specified by the file. The optional arguments specify a box of width $x_len_2 - x_len_1$ and height $y_len_2 - y_len_1$ whose reference point is shifted a distance of x_len_1 to the right and y_len_1 up from the lower-left corner of the contents of the file. Specifying only one optional argument is the same as giving a first optional argument of `[0pt,0pt]`. The ***-form clips the material by removing everything outside the specified box; the normal form does not.

C.14.3 The color Package

The following commands are provided by the `color` package. They are all fragile. This package requires special support from the device driver.

`\definecolor{clr}{mdl}{val}`

Defines *clr*, which may be any sequence of letters and numbers, to be the name of the color specified by the color model *mdl* and color value *val*. L^AT_EX's standard color models are:

gray A color value is a number from 0 to 1 that specifies a shade of gray, where 0 is black.

rgb A color value is a list of three numbers from 0 to 1, separated by commas, that describe intensities of red, green, and blue light.

cmk A color value is a list of four numbers from 0 to 1, separated by commas, that specify amounts of cyan, magenta, yellow, and black ink.

Other color models may also be supported. The package predefines the following color names: **black**, **white**, **red**, **green**, **blue**, **yellow**, **cyan**, and **magenta**. All other color names must be defined before they are used.

`\color{clr}`

Declares *clr* to be the current text color. It obeys the normal scoping rules.

`\textcolor{clr}{text}`

Equivalent to `{\color{clr} text}`.

`\colorbox{bkgd_clr}{text}`

Produces a box by typesetting *text* in LR mode on a background of color *bkgd_clr*. The box includes a border of width `\fboxsep`.

`\fcolorbox{line_clr}{bkgd_clr}{text}`

Like `\colorbox`, except it also puts a line of width `\fboxrule` and color *line_clr* around the box.

`\pagecolor{clr}`

Declares *clr* to be the page's background color. It is a global declaration.

C.15 Font Selection

A font is a size and style of type. A text font is selected by specifying the size and style. There are also special symbol fonts that are selected implicitly by math-mode commands. It is possible to select a font that is not available, in which case L^AT_EX types a warning and substitutes a similar font.

C.15.1 Changing the Type Style

A type style is specified by three separate components: shape, series, and family. Changing one component does not affect the others. These components are changed by the following declarations, which obey the normal scope rules:

<code>\mdseries</code>	Medium Series	<code>\upshape</code>	Upright Shape
<code>\bfseries</code>	Boldface Series	<code>\itshape</code>	<i>Italic Shape</i>
<code>\rmfamily</code>	Roman Family	<code>\slshape</code>	<i>Slanted Shape</i>
<code>\sffamily</code>	Sans Serif Family	<code>\scshape</code>	SMALL CAPS SHAPE
<code>\ttfamily</code>	Typewriter Family	<code>\normalfont</code>	Normal Style

The `\normalfont` declaration sets series, family, and shape to that of the document's main text font.

Each of these declarations has a corresponding command `\text...{text}` that typesets *text* in the scope of the declaration. The commands and their corresponding declarations are:

<code>\textmd{text}</code>	<code>\mdseries</code>	<code>\textup{text}</code>	<code>\upshape</code>
<code>\textbf{text}</code>	<code>\bfseries</code>	<code>\textit{text}</code>	<code>\itshape</code>
<code>\textrm{text}</code>	<code>\rmfamily</code>	<code>\textsl{text}</code>	<code>\slshape</code>
<code>\textsf{text}</code>	<code>\sffamily</code>	<code>\textsc{text}</code>	<code>\scshape</code>
<code>\texttt{text}</code>	<code>\ttfamily</code>	<code>\textnormal{text}</code>	<code>\normalfont</code>

Words typeset in typewriter style will not be hyphenated except where permitted by `\-` commands.

None of these commands or declarations can be used in math mode. They are all robust.

C.15.2 Changing the Type Size

The following declarations select a type size, but leave the type style unaffected. They are listed in nondecreasing size; in some document-class options, two different size declarations may have the same effect.

<code>\tiny</code>	<code>\small</code>	<code>\large</code>	<code>\huge</code>
<code>\scriptsize</code>	<code>\normalsize</code>	<code>\Large</code>	<code>\Huge</code>
<code>\footnotesize</code>		<code>\LARGE</code>	

These commands may not be used in math mode; they are all fragile.

C.15.3 Special Symbols

Special symbols can be obtained from special fonts. The *L^AT_EX Companion* explains how to get L^AT_EX to use such a font.

`\symbol{num}`

Chooses the symbol with number *num* from the current font. Octal (base 8) and hexadecimal (base 16) numbers are preceded by ' and ", respectively. Robust.

APPENDIX D

What's New



This appendix lists most of the differences between L^AT_EX 2.09, the original version of L^AT_EX, and the current version, L^AT_EX 2_ε.

Document Styles and Style Options

Documents prepared for L^AT_EX 2_ε begin with a `\documentclass` command (Section 2.2.2). L^AT_EX 2_ε realizes it is processing a L^AT_EX 2.09 input file and enters *compatibility mode* when it encounters a L^AT_EX 2.09 `\documentstyle` command. Most L^AT_EX 2.09 input files will work with L^AT_EX 2_ε. However, an error may occur if L^AT_EX 2_ε reads an auxiliary file produced by L^AT_EX 2.09, so it's a good idea to delete such files before running L^AT_EX 2_ε.

The document styles of L^AT_EX 2.09 have become document classes. SL^AT_EX has been eliminated; slides are produced using the `slides` document class. Standard document-style options that controlled formatting, such as `twoside`, have become document-class options, and are specified as optional arguments to the `\documentclass` command. Other document-style options have become packages, loaded with the `\usepackage` command (Section 2.2.2). Most nonstandard document-style options will work as L^AT_EX 2_ε packages.

Type Styles and Sizes

The L^AT_EX 2.09 commands for changing type style, such as `\tt`, will still work more or less the same as before. The major difference is that `\sc` and `\sl` can no longer be used in math mode (except when L^AT_EX 2_ε is in compatibility mode). However, instead of using these commands, you should switch to the more rational commands described in Sections 3.1 and 3.3.8 for changing type style. The new commands treat the different aspects of type style separately—for example, allowing you easily to specify bold sans serif type. The commands for changing type size are the same, but they no longer change the type style (except in compatibility mode). The `\boldmath` command now works better (Section 3.3.8).

Pictures and Color

The `picture` environment has been enhanced by the addition of the `\qbezier` command for drawing curves (Section 7.1.3). The `pict2e` package also removes many restrictions on `picture` environment commands, such as limitations on the slopes of lines and arrows. The `graphics` package allows you to insert pictures produced by other programs (Section 7.2). It also defines commands for scaling and rotating text and pictures. The `color` package defines commands for producing colored text (Section 7.3).

Other New Features

You can now define a command or environment that has an optional argument. The `\ensuremath` command is useful for defining a command that can appear in or out of math mode. See Section 3.4.

Control of the placement of floats (figures and tables) has been enhanced with a new float-location option `!` that encourages $\text{\LaTeX}$ to print the float as soon as possible, and with the `\suppressfloats` command to prevent additional floats on the current page.

When sending your document electronically, you can bundle other files along with your input file using the `filecontents` environment (Section 4.7).

Analogues of the `\settowidth` command have been added for determining the dimensions of text other than the width (Section 6.4.1). In the length arguments of various box-making commands, it is now possible to refer to the dimensions of the text argument using commands such as `\width` (Section C.13.3).

The `ifthen` package defines commands for writing simple programs (Section C.8.5).

The `\enlargethispage` command has been added to help in correcting bad page breaks (Section 6.2.2). The `\samepage` command still works, but is now of little use.

A few commands and options have been added to the `book` document class (Section 5.1).

APPENDIX E

Using Plain T_EX Commands



L^AT_EX is implemented as a T_EX “macro package”—a series of predefined T_EX commands. Plain T_EX is the standard version of T_EX, consisting of “raw” T_EX plus the `plain` macro package. You can use Plain T_EX commands to do some things that you can’t with standard L^AT_EX commands. However, before using Plain T_EX, check the *L^AT_EX Companion* to see if there is a package that does what you want.

Most Plain T_EX commands can be used in L^AT_EX, but only with care. L^AT_EX is designed so its commands fit together as a single system. Many compromises have been made to ensure that a command will work properly when used in any reasonable way with other L^AT_EX commands. A L^AT_EX command may not work properly when used with Plain T_EX commands not described in this book.

There is no easy way to tell whether a Plain T_EX command will cause trouble, except by trying it. A general rule is not to combine a L^AT_EX command or environment with Plain T_EX commands that might modify parameters it uses. For example, don’t use a Plain T_EX command such as `\hangindent` that modifies T_EX’s paragraph-making parameters inside one of L^AT_EX’s list-making environments.

You should not modify any parameters that are used by L^AT_EX’s `\output` routine, except as specified in this book. In particular, you should forget about most of Chapter 15 of *The T_EXbook*. However, L^AT_EX does obey all of T_EX’s conventions for the allocation of registers, so you can define your own counts, boxes, etc., with ordinary T_EX commands.

Listed below are all the Plain T_EX commands whose definitions have been eliminated or changed in L^AT_EX. Not listed are L^AT_EX commands that approximate the corresponding Plain T_EX versions, and some “internal” commands whose names contain @ characters.

Tabbing Commands

The following commands are made obsolete by L^AT_EX’s `tabbing` environment:

<code>\tabs</code>	<code>\tabsdone</code>	<code>\settabs</code>	<code>\+</code>
<code>\tabset</code>	<code>\cleartabs</code>	<code>\tabalign</code>	

Output, Footnotes, and Figures

The following commands that require Plain T_EX’s output routine are obsolete. They have been replaced by L^AT_EX’s footnote-making commands and its `figure` and `table` environments.

<code>\pageno</code>	<code>\nopagenumbers</code>	<code>\makeheadline</code>	<code>\topins</code>
<code>\headline</code>	<code>\advancepageno</code>	<code>\makefootline</code>	<code>\topinsert</code>
<code>\footline</code>	<code>\pagebody</code>	<code>\dosupereject</code>	<code>\midinsert</code>
<code>\normalbottom</code>	<code>\plainoutput</code>	<code>\footstrut</code>	<code>\pageinsert</code>
<code>\folio</code>	<code>\pagecontents</code>	<code>\vfootnote</code>	<code>\endinsert</code>

Font-Selecting Commands

The following Plain $\text{\TeX}$ commands are not defined in $\text{\LaTeX}$:

$\text{\fivei}$	$\text{\fivebf}$	$\text{\sevensy}$
$\text{\fiverm}$	$\text{\seveni}$	$\text{\teni}$
$\text{\fivesy}$	$\text{\sevenbf}$	$\text{\oldstyle}$

Aligned Equations

The following Plain $\text{\TeX}$ commands have been made obsolete by the `eqnarray` and `eqnarray*` environments:

$\text{\eqalign}$	$\text{\eqalignno}$	$\text{\leqalignno}$
-------------------	---------------------	----------------------

Miscellaneous

Plain $\text{\TeX}$'s `$$` does not work properly; it has been replaced by the $\text{\LaTeX}$ commands `\[` and `\]`. Plain $\text{\TeX}$'s `\beginsection` command has been replaced by $\text{\LaTeX}$'s sectioning commands; its `\end` and `\bye` commands have been replaced by `\end{document}`. The Plain $\text{\TeX}$ commands `\centering` and `\line` have had their names usurped by $\text{\LaTeX}$ commands, and the syntax of the `\input` command has been changed to conform to $\text{\LaTeX}$ conventions. Most functions performed by Plain $\text{\TeX}$'s `\line` command can be achieved by the `center`, `flushleft`, and `flushright` environments. The `\magnification` command of Plain $\text{\TeX}$ has no counterpart in $\text{\LaTeX}$. Magnification of the output can often be done by the program that prints the `dvi` file.

Bibliography

- [1] Theodore M. Bernstein. *The Careful Writer: A Modern Guide to English Usage*. Atheneum, New York, 1965.
- [2] *The Chicago Manual of Style*. University of Chicago Press, fourteenth edition, 1993.
- [3] Michel Goossens, Frank Mittelbach, and Alexander Samarin. *The L^AT_EX Companion*. Addison-Wesley, Reading, Massachusetts, 1994.
- [4] Donald E. Knuth. *The T_EXbook*. Addison-Wesley, Reading, Massachusetts, 1994.
- [5] N. E. Steenrod, P. R. Halmos, M. M. Schiffer, and J. A. Dieudonné. *How to Write Mathematics*. American Mathematical Society, London, 1983.
- [6] William Strunk, Jr. and E. B. White. *The Elements of Style*. Macmillan, New York, third edition, 1979.
- [7] Mary-Claire van Leunen. *A Handbook for Scholars*. Oxford University Press, New York, Oxford, revised edition, 1992.
- [8] *Words Into Type*. Prentice-Hall, Englewood Cliffs, New Jersey, third edition, 1974.

Index

`\` (space character), 13, 32
 ignored in math mode, 36, 50
 in LR mode, 36
 printing, 64
`\` (interword space), 14, 16, 32, 33, 51,
 170
 used with `\thanks`, 181
`#` (hash mark), 12, 32, 166
 in definition, 54, 56, 192, 193
 misplaced, 141, 145
 printing, 15, 171
`\#` (`#`), 15, 39, 171
`$` (dollar sign), 12, 32, 166
 delimiting formula, 18, 33, 39, 187
 delimits scope of declaration, 168
 missing, 142
 not fragile, 22
 printing, 15, 171
 unmatched, 141
`\$` (`$`), 15, 39, 171
`$$` (`TeX` command), 233
`%` (percent sign), 12, 19, 32, 166
 for ending line without adding space,
 33, 109
 in `\index` argument, 154
 printing, 15, 171
`\%` (`%`), 15, 39, 171
`&` (ampersand), 12, 32, 166
 in `array` or `tabular` environment, 45,
 206
 misplaced, 141
 printing, 15, 171
 too many in row, 141
`\&` (`&`), 15, 39, 171
`~` (tilde), 12, 17, 32, 33, 166, 170
 used with `\ref` and `\pageref`, 68
`\^` (`^` accent), 38

`_` (underscore), 12, 32, 166
 for subscript, 18, 33, 40, 189
 printing, 15, 171
`\_` (`_`), 15, 39, 171
`^` (circumflex), 12, 32, 166
 for superscript, 18, 33, 40, 189
`\^` (`^` accent), 38
`\` (backslash), 12, 16, 32, 166
`\\` (new line), 25–26, 34, 169–170, 213
 [after, 26
 * after, 167
 after last row of `array` or `tabular`,
 62, 206
 bad use of, 147
 between paragraphs, 139
 in `\address` argument, 84
 in `array` environment, 45, 169
 in `\author` argument, 169
 in `center` environment, 111, 169
 in `eqnarray` environment, 47, 169
 in `flushleft` environment, 169
 in `flushright` environment, 169
 in `p` column of `array` or `tabular`, 205
 in paragraph mode, 96, 213
 in `\shortstack` argument, 169
 in `\signature` argument, 84
 in `tabbing` environment, 61, 169, 202
 in `tabular` environment, 62, 169
 in `\title` argument, 181
 in `verse` environment, 169, 184
 is fragile, 33
 missing, 141
 optional argument of, 167
 two in a row, 169
`\\*` (new line), *see* `\\`
`{` (left brace), 12, 32
 enclosing argument, 33, 166

Index Order

`\` (space)
`#`
`$`
`%`
`&`
`~` (tilde)
`_` (underscore)
`^` (circumflex)
`\` (backslash)
`{`
`}`
`.` (period)
`:` (colon)
`;` (semicolon)
`,` (comma)
`?`
`!`
`'` (left quote)
`'` (right quote)
`(`
`)`
`[`
`]`
`-` (dash)
`/` (slash)
`*`
`@`
`+`
`=`
`|` (vertical line)
`<`
`>`
`"` (double quote)
`0 ... 1`
`A a B ... z`

Index Order

- (space)
- #
- \$
- %
- &
- ~ (tilde)
- _ (underscore)
- ^ (circumflex)
- \ (backslash)
- {
- }
- . (period)
- :
- ;
- ,
- ?
- !
- ' (left quote)
- ' (right quote)
- (
-)
- [
-]
- (dash)
- / (slash)
- *
- @
- +
- =
- | (vertical line)
- <
- >
- " (double quote)
- 0 ... 1
- A a B ... z
- in bib file, 158
- in \index argument, 75
- missing, 142
- printing, 15, 171
- scope delimited by, 27–28
- \{ ({), 15, 39, 47, 171
 - in bib file, 156
 - in \index argument, 212
- } (right brace), 12, 32
 - enclosing argument, 33, 166
 - in bib file, 158
 - in \index argument, 75
 - missing, 142
 - printing, 15, 171
 - scope delimited by, 27–28, 168
 - unmatched, 141
- \} (}), 15, 39, 47, 171
 - in bib file, 156
 - in \index argument, 212
- . (period), 12, 32, 33
 - invisible delimiter, 47
 - ..., *see* ellipsis
- \. (' accent), 38
- :
- ;
- \: (medium space), 51, 191
- ;
- \; (thick space), 51, 191
- ,
- not allowed in citation key, 69
- \, (thin space), 14, 33, 51, 170, 191
- ? (question mark), 12, 32, 33
 - in error message, 29
- ? ' (i), 39
- From, 32
- ! (exclamation point), 12, 32, 33
 - in error message, 29
 - in figure or table argument, 197
 - in \index argument, 152
 - in \resizebox argument, 129, 224
- ! ' (i), 39
- \! (negative thin space), 51, 191
- !h float specifier changed, 146
- ' (left quote), 12, 13, 32, 33, 170
- \' (' accent or tabbing command), 38, 203
 - in parbox, 203
- ' (right quote), 12, 13, 32, 33, 170
 - in formula, 18, 189
 - period before, 15
 - specifying octal number, 226
- \' (' accent or tabbing command), 38, 203
 - in parbox, 203
- ((left parenthesis), 12, 32
 - delimiter, 47
 - in terminal output, 134
- \((begin formula), 18, 33, 39, 187
 - in ifthen package expression, 196
 - in math mode error, 136
 - is fragile, 22, 33
-) (right parenthesis), 12, 32
 - delimiter, 47
 - in terminal output, 134
 - period before, 15
- \) (end formula), 18, 33, 187
 - delimits scope of declaration, 168
 - in ifthen package expression, 196
 - is fragile, 22, 33
 - not in math mode error, 136
- [(left bracket), 12, 32, 33, 166
 - ambiguous, 25
 - delimiter, 47
 - printed on terminal, 135
- \[(begin displayed formula), 26, 34, 39, 188
 - in math mode error, 136
 - is fragile, 33
-] (right bracket), 12, 32, 33, 166
 - ambiguous, 25
 - delimiter, 47
 - delimiting optional argument, 168
 - in \item argument, 167
 - printed on terminal, 135
- \] (end displayed formula), 26, 34, 39, 188
 - delimits scope of declaration, 168
 - is fragile, 33
 - not in math mode error, 136
- (dash or minus), 12, 14, 32, 33, 170
 - in overfull \hbox message, 93
 - space around, 48
 - unary, 48
- (number-range dash), 14, 33, 170

- (punctuation dash), 14, 33, 170
- \- (hyphenation or tabbing command), 93, 202, 213
 - error in, 140
 - in parbox, 203
 - in `tabbing` environment, 203
 - instead of `\hyphenation`, 143
 - needed in typewriter style, 226
- / (slash), 12, 32
 - delimiter, 47
 - quotient symbol, 40, 51
- * (asterisk), 12, 32, 167
 - acts like optional argument, 26
 - after command name, 26
 - argument to `\nocite`, 70
 - in array or tabular argument, 205
 - written on terminal, 30
- *-expression, 205
- *-form
 - of command, 26, 33, 167
 - of environment, 167
 - of sectioning command, 174
- @ (at sign), 12, 32
 - command name with, 91, 166
 - in `\index` argument, 153
 - regarded as letter in `sty` file, 91
- \@, 14, 33, 170
- @-expression, 205
 - error in, 145
 - fragile command in, 168
 - missing, 138
- \@array, 145
- \@chapter, 92
- \@makechapterhead, 92
- \@schapter, 92
- @string, 159
- + (plus), 12, 32
 - space around, 48
 - unary, 48
- \+ (tabbing command), 202
 - error in, 140
 - in Plain TeX, 232
- = (equals), 12, 32
 - in `bib` file, 156
 - in `ifthen` package expression, 195
 - in `\lengthtest` expression, 196
- \= (˘ accent or tabbing command), 38, 61, 201, 202
 - in parbox, 203
 - too many, 139
- | (vertical line), 12, 32
 - delimiter, 47
 - in array or tabular argument, 62, 205
- || in array or tabular argument, 207
- < (less than), 12, 32
 - in `ifthen` package expression, 195
 - in `\lengthtest` expression, 196
- \< (tabbing command), 202
 - error in, 140
- > (greater than), 12, 32
 - in `ifthen` package expression, 195
 - in `\lengthtest` expression, 196
- \> (tabbing command), 61, 201, 202
 - error in, 140
- " (double quote), 12
 - in `bib` file, 156
 - in index entry, 154
 - specifying hexadecimal number, 226
- \" (˘ accent), 38
- 0 (zero), 12
 - incorrect use as length, 99, 141
- 1 (one), 12
- 10pt document-class option, 177
- 11pt document-class option, 19, 115, 177
- 12pt document-class option, 19, 115, 177
- 2.09, 2
- 2ε, 2
- \a˘ (˘ accent in `tabbing` environment), 203
- \a˘ (˘ accent in `tabbing` environment), 203
- \a= (˘ accent in `tabbing` environment), 203
- A4 paper size, 177
- a4paper document-class option, 177
- A5 paper size, 177
- a5paper document-class option, 177
- \AA (Å), 39
- \aa (ä), 39
- abbreviation, 14
 - in `bib` file, 158–159

Index Order

- (space)
- #
- \$
- %
- &
- ~ (tilde)
- _ (underscore)
- ˘ (circumflex)
- \ (backslash)
- {
- }
- . (period)
- :
- ;
- ,
- ?
- !
- ‘ (left quote)
- ’ (right quote)
- (
-)
- [
-]
- (dash)
- / (slash)
- *
- @
- +
- =
- | (vertical line)
- <
- >
- " (double quote)
- 0 ... 1
- A a B ... z

- abbrv bibliography style, 70
- `\abovedisplayshortskip`, 189
- `\abovedisplayskip`, 188
- abstract, 90, 181–183
 - not in book document class, 183
 - on separate page, 88, 177
- abstract environment, 90, 183
 - effect of `titlepage` option, 88
- accent, 38
 - dotless i and j for, 38, 50, 190
 - in bib file, 158
 - in `tabbing` environment, 203
 - math mode, 49–50, 190
 - not available in typewriter style, 38
 - wide math, 49
- acknowledgment of support, 181
- `\acute` (‘math accent), 50
- `\addcontentsline`, 175
 - argument too long, 143
 - moving argument of, 168
- address field (in bib file), 162
- `\address`, 84
- `\addtime`, 83
- `\addtocontents`, 67, 176
 - argument too long, 143
 - moving argument of, 168
- `\addtocounter`, 98, 194
 - error in, 138
 - `\protect` not used in argument of, 168
 - scope of, 98, 168
- `\addtolength`, 101, 216
- `\addvspace`, 217
- `\advancepageno` (T_EX command), 232
- `\AE` (Æ), 39
- `\ae` (æ), 39
- `\aleph` (ℵ), 43
- aligning
 - formulas on left, 88, 177
 - in columns, 60–63, 201–207
- alignment tab error, 141
- `alltt` environment, 187
- `alltt` package, 178, 187
- `\Alph`, 98, 195
- `\alph`, 98, 195
- alpha bibliography style, 70
- `\alpha` (α), 41
- alphabetic page numbers, 180
- `\amalg` (II), 42
- ambiguous [or], 25
- American Mathematical Society, 52
- ampersand, *see* &
- `amstex` package, 52, 178
- and separating names in bib file field, 158
- `\and`, 21, 34, 181
 - in `ifthen` package expression, 196
- and others, 158
- `\angle` (∠), 43
- annotate field (in bib file), 162
- apostrophe, 14, 170
- appendix, 22, 175
- `\appendix`, 22, 175
- `\approx` (≈), 43
- arabic page numbers, 89, 180
- `\arabic`, 98, 195
- `\arccos` (arccos), 44
- `\arcsin` (arcsin), 44
- `\arctan` (arctan), 44
- `\arg` (arg), 44
- argument (of command), 16, 33, 166–167
 - braces enclosing, 33, 55, 166
 - coordinate pair as, 119
 - mandatory, 166
 - missing, 142
 - in thebibliography environment, 138
 - moving, *see* moving argument
 - of picture command, 119
 - omitted, 141
 - optional, *see* optional argument
 - positioning, 205, 217–218, 221–222
 - processed multiple times, 110
 - scope of declaration in, 27, 168
 - `\verb` in, 140
- array, 45–46
- array environment, 45–46, 204–207
 - `\` in, 45, 169
 - box made by, 103
 - error in, 137, 138, 141, 145
 - extra space around, 205
 - illegal character in argument, 137
 - interrow space in, 169
 - large, 143
 - making symbol with, 42

- scope of declaration in, 45
- strut in, 169
- versus `tabular`, 46, 60, 62
- `\arraycolsep`, 207
- `\arrayrulewidth`, 207
- `\arraystretch`, 207
- arrow
 - accent, *see* `\vec`
 - in formula, 53
 - in margin, 59
 - in picture, 123, 222
 - symbols, 43
 - zero-length, 123
- arrowhead, 123
- article bibliography entry type, 161
- article document class, 19, 176
 - appendix in, 175
 - `\chapter` not defined in, 21, 174
 - default page style, 89
 - `thebibliography` environment in, 209
 - used in examples, 21
- ASCII file, 144
- assumption, 56
- `\ast` (*), 42
- `\asymp` ($\asymp$), 43
- at sign, *see* @
- author, 20
- author field (in `bib` file), 162
- author's address in title, 181
- `\author`, 20, 34, 181
 - `\` in argument, 169
 - missing, 146
- authors, multiple, 21
- aux file, 208
 - entry generated by `\label`, 209
 - entry written by `\cite` and `\nocite`, 210
 - error when reading, 135, 138
- auxiliary file, error reading, 135, 228
- axiom, 56
- b** (bottom)
 - float specifier, 197
 - oval-part argument, 124, 223
 - positioning argument, 46, 105, 121, 218, 222
- `\b` ($_$ accent), 38
- B5 paper size, 177
- `b5paper` document-class option, 177
- `babel` package, 38, 94, 178
- back matter (of a book), 80
- `\backmatter`, 80
- backslash, 12, 16, 32, 166
- `\backslash` ($\backslash$), 43, 47
- backspace, 51, 101
- bar over a symbol, 49
- `\bar` ($\bar$ math accent), 50
- `\baselineskip`, 100, 172
- `\baselinestretch`, 172
- `\batchmode`, 30
- `bbl` file, 71, 156, 208
 - read by `\bibliography`, 209
- `\begin`, 23, 167
 - delimits scope of declaration, 27–28
 - is fragile, 22, 33
 - of nonexistent environment, 137
 - unmatched, 136
- `\begin{document}`, 19, 170
 - aux file read by, 208
 - error while processing, 135
 - extra, 136
 - missing, 138
- `\beginsection` (TeX command), 233
- `\belowdisplayshortskip`, 189
- `\belowdisplayskip`, 189
- `\beta` (β), 41
- Bezier curve, 125–126, 221
- `\bfseries`, 37, 226
- `bib` file, 70, 155–164
 - abbreviations in, 158–159
 - entry, 156
 - keeping data in, 161
 - specified by `\bibliography`, 156, 209
- `\bibindent`, 178
- `\bibitem`, 71, 210
 - moving argument of, 72, 168
- bibliographic database, *see* `bib` file
- bibliography, 69–72, 209–210
 - open format, 71, 177
 - produced by `thebibliography` environment, 209
 - style, 70–71
- `\bibliography`, 70, 209
 - `bbl` file read by, 208

- specifies `bib` files, 156
- `\bibliographystyle`, 70
- `BIBTEX`, 69–71, 155–164
 - `bb1` file written by, 208
 - producing bibliography with, 209
- big delimiter, 46
- `\bigcap` ($\cap$), 44
- `\bigcirc` ($\bigcirc$), 42
- `\bigcup` ($\cup$), 44
- `\bigodot` ($\odot$), 44
- `\bigoplus` ($\oplus$), 44
- `\bigotimes` ($\otimes$), 44
- `\bigskip`, 216
- `\bigskipamount`, 216
- `\bigsqcup` ($\sqcup$), 44
- `\bigtriangledown` (∇), 42
- `\bigtriangleup` ($\triangle$), 42
- `\biguplus` ($\uplus$), 44
- `\bigvee` ($\vee$), 44
- `\bigwedge` ($\wedge$), 44
- black, 132, 225
- blank line, 13, 33
 - above or below environment, 23
 - before displayed formula, 26
 - in formula, 142, 171
 - in input, 166
 - in sectioning command, 171
 - `\par` equivalent to, 171
 - paragraph-ending, 95, 166, 171
- blank page, 97
 - made by `\cleardoublepage`, 215
 - with `\titlepage` environment, 180
- blob of ink, rectangular, 106
- blue, 132, 225
- `\bmod`, 44, 190
- body, page, 89, 179
 - height of, 100
- boldface type series, 37, 226
 - in math mode, 51, 191
- `\boldmath`, 51, 191
 - font warning caused by, 52, 145
- book, 80
- book bibliography entry type, 161
- book document class, 80, 176
 - appendix in, 175
 - no abstract in, 183
 - `thebibliography` environment in, 209
- booklet bibliography entry type, 161
- `booktitle` field (in `bib` file), 162
- boolean register, 196
- `\boolean`, 196
- `\bot` ($\perp$), 43
- bottom of line, 107
- `\bottomfraction`, 200
- bottomnumber counter, 199
- `\bowtie` ($\bowtie$), 43
- box, 103–108, 217
 - dashed, 121, 222
 - declaration local to, 103
 - dimensions of, 103
 - displaying, 104
 - framed, 104, 217
 - in `picture` environment, 222
 - in formula, 103
 - LR, 103–104, 107
 - rule, 103, 106
 - saving, 107, 127, 218
 - typeset in paragraph mode, 104
 - with specified width, 104
 - zero-width, 121
- `\Box` ($\square$), 43
- boxes, 217–219
 - formatting with, 108–111
- brace, curly, 12
 - enclosing command argument, 33, 55, 166
 - error caused by unbalanced, 136
 - horizontal, 49
 - in `bib` file, 158
 - in `\index` argument, 75, 153
 - missing, 142
 - removed from first argument of `\newcommand`, 92
- bracket, square, 12
 - enclosing optional argument, 20, 166
 - mistaken for optional argument, 142
 - printed on terminal, 135
- break, line, 93–96, 213–214
 - interword space without, 17, 170
 - permitting, 95
 - preventing, 17, 95, 171
 - with `\`, 26
- break, page, 96–97, 214–215
 - bad, 147

- in tabbing environment, 60
- `\breve` ($\sim$ math accent), 50
- Brinch Hansen, Per, 157
- buffer size, 143
- bug, L^AT_EX, 139
- `\bullet` ($\bullet$), 42
- Bush, George, 24
- `\bye` (T_EX command), 233
-
- c (center) positioning argument, 45, 205
- `\c` (, accent), 38
- calligraphic letter, 42
- calligraphic type style, 51, 191
- `\cap` ($\cap$), 42
- capacity exceeded, 142–144
- caps, small, 37, 226
- caption
 - cross-reference to, 68
 - figure or table, 58
 - multiple, 59
- `\caption`, 58, 198
 - argument too long, 143
 - fragile command in, 135
 - in parbox, 199
 - `\label` in argument, 209
 - list of figures or tables entry, 175, 208
 - moving argument of, 58, 168
 - precedes `\label`, 68
- case of letters
 - in command name, 16, 32
 - in key, 68, 69
- catching errors with text editor, 32
- `\cc`, 85
- `\cdot` ($\cdot$), 42
- `\cdots` ($\cdots$), 40, 189
- center environment, 111
 - `\in`, 111, 169
 - as displayed paragraph, 183
 - as list, 112
 - displaying a box with, 104
 - in title page, 90
 - tabular environment in, 63
- center line of formula, 46
- centered
 - array column, 45
 - ellipsis, 40, 189
- centering a figure or table, 112
-
- `\centering`, 112
 - in p column, 205
 - T_EX command, 233
- centimeter (cm), 99, 215
- chapter, in separate file, 74
- chapter counter, 97
- chapter field (in bib file), 163
- `\chapter`, 21, 174
 - changes current page style, 89
 - in front and back matter of a book, 80
 - not in article document class, 174
 - uses `\clearpage`, 97
- character
 - code, 116
 - control, 144
 - end of line, 12
 - illegal, in array or tabular, 137
 - input, 32
 - invalid, 144
 - invisible, 12, 32
 - nonprinting, 144
 - punctuation, 12, 32
 - in key, 68
 - space, *see* space character
 - special, *see* special character
- `\check` ($\sim$ math accent), 50
- chgsam.tex file, 9
- `\chi` (χ), 41
- `\circ` ($\circ$), 42
- circle, 124, 222
- `\circle`, 124, 222
- `\circle*`, 124, 222
- circular reference, 263
- citation, 69–72, 209–210
 - key, 69, 71, 156
 - undefined, 145, 147
- `\cite`, 69, 210
 - wrong number printed by, 146
- class, document, 19–20
 - nonexistent, 137
- classes.dtx file, 92
- `\cleardoublepage`, 97, 215
 - figures and tables output by, 198
- `\clearpage`, 97, 215
 - checking capacity exceeded error, 143
 - figures and tables output by, 198
 - used by `\chapter`, 97

- used by `\include`, 97
 - used by `\onecolumn`, 181
 - used by `\twocolumn`, 180
- `\cleartabs` (T_EX command), 232
- `\cline`, 62, 206
- clipping, 224
- clock document-class option, 83
- `\closing`, 85
- `cls` (class) file, missing, 137
- `\clubsuit` ($\clubsuit$), 43
- cm (centimeter), 99, 215
- cm_YK color model, 132, 225
- code, character, 116
- colon, *see* :
- color, 131–132
 - background, 132
 - model, 132, 224
 - undefined, 140
 - undefined, 140
 - value, 224
- color package, 131–132, 178, 224–225
- `\color`, 131, 225
- `\colorbox`, 132, 225
- column
 - aligning text in, 60–63, 201–207
 - of text in picture, 123
- `\columnsep`, 178
- `\columnseprule`, 178
- comma (,), 12, 32
 - not allowed in citation key, 69
- command, 32–33, 166–170
 - *-form of, 26, 33, 167
 - adding to table of contents, etc., 176
 - argument, *see* argument
 - definition, 7, 53–55, 192
 - # in, 54
 - in preamble, 55
 - space character in, 54
 - with optional argument, 192
 - with `\typein`, 212
 - environment made from, 108
 - form, 166
 - fragile, 22, 25, 26, 33, 167–168
 - in $\mathcal{O}$ -expression, 168
 - invisible, 169
 - length, 99
 - defining, 101
 - not preceded by `\protect`, 168
 - name, 16, 32, 166–167
 - * after, 26
 - already used error, 137
 - beginning with `\end`, 55
 - case of letters in, 16, 32
 - correcting misspelled, 144
 - ending with space or end of line, 16
 - misspelled, 31
 - one-character, 166
 - with $\mathcal{O}$, 91, 166
 - names, too many, 143, 144
 - nested too deeply, 144
 - nesting, 16
 - parameter, 54, 192
 - picture, argument of, 119
 - Plain T_EX, 231–233
 - preloaded, 91
 - printing on terminal, 212
 - redefining, 55
 - robust, 22, 167
 - sectioning, *see* sectioning command
 - spacing, 170
 - text-generating, 15
 - with two optional arguments, 166
- commas, ellipsis between, 40
- comment, 19, 166
 - printed on terminal, 76
- common errors, 31
- compatibility mode, 228
- compressed bibliography style, 71
- Computer Modern font, 115
- computer program, formatting, 60
- concept index, 150
- concepts versus notation, 31
- `\cong` ($\cong$), 43
- conjecture, 56
- contents, table of, 66–67, 175–176
 - adding commands to, 67
- control character, 144
- control sequence error, 142, 144
- coordinate, 118, 219
 - geometry, 118
 - grid, 126–127
 - local, 129
 - pair, 118
 - as argument, 119

- `\coprod` ($\coprod$), 44
- copy editing, double-spacing for, 172
- `\copyright` ($\copyright$), 39, 173
- corner, rounded, 124–125
- `\cos` (cos), 44
- `\cosh` (cosh), 44
- `\cot` (cot), 44
- `\coth` (coth), 44
- counter, 97–99
 - command, error in, 144
 - created by `\newtheorem`, 97
 - creating a new, 99
 - for theorem-like environment, 97, 193
 - list, 114
 - reset by `\stepcounter` and `\refstepcounter`, 194
 - too large, 137
 - value of, 98, 194
- cross-reference, 66–69, 209
 - in bib file, 159–160
 - in index, 152
 - information, printing, 208
 - labels, too many, 143, 144
 - to page number, 68
 - use of aux file for, 208
- `crossref` field (in bib file), 163
- `\csc` (csc), 44
- `\cup` ($\cup$), 42
- curly brace, *see* brace, curly
- curve, Bezier, 125–126, 221
- customizing style, 91–93
- cyan, 132, 225
- `\d` ($\d$ accent), 38
- `\dag` ($\dagger$), 39, 173
- `\dagger` ($\dagger$), 42
- dash, 14, 33, 170
 - intraword, 14, 170
 - number-range, 14
 - punctuation, 14
- `\dashbox`, 121, 221
- dashed box, 121, 222
- `\dashv` ($\dashv$), 43
- data, keeping in bib file, 161
- database, bibliographic, *see* bib file
- date, 20
 - generating with `\today`, 15, 171
 - in title, 20
 - in title page, 90
 - on letter, 86
- `\date`, 20, 34, 181
 - `\in`, 169
- `\dblfloatpagefraction`, 200
- `\dblfloatsep`, 200
- `\dbltextfloatsep`, 200
- `\dbltopfraction`, 200
- `dbltopnumber` counter, 200
- `\ddag` ($\ddagger$), 39, 173
- `\ddagger` ($\ddagger$), 42
- `\ddot` ($\ddot$ math accent), 50
- `\ddots` ($\ddots$), 41, 189
- declaration, 27–28, 33, 168
 - color, 131, 225
 - global, 168
 - local to a box, 103
 - picture, 223
 - scope of, *see* scope
 - type-size changing, 115
- declarations, file of, 73
- `\def` ($\TeX$ command), 92, 93
- default
 - argument, 166
 - page style, 179
 - type size, 115
- `\definecolor`, 132, 224
- defined, multiply, 146
- definition
 - command, *see* command
 - environment, *see* environment
 - recursive, 54
 - use doesn't match, 145
- `\deg` (deg), 44
- delimiter, 46–47, 190
 - bad, 136
 - unmatched math mode, 141
- `\Delta` (Δ), 41
- `\delta` (δ), 41
- depth
 - changing apparent, 107
 - of a box, 103
- `\depth`, 219
- description environment, 24–25, 34, 184
 - as list, 112

- item label overprinting text in, 184
 - used for glossary, 76
- design
 - logical, 7
 - typographic, 91
 - visual, 7, 88
- designer, typographic, 5
- `\det` (det), 44
 - subscript of, 190
- determinant, 45
- device driver, 118
- device-independent file, *see* `dvi` file
- diacritical mark, *see* accent
- diagonal ellipsis, 40, 189
- `\Diamond` ($\diamond$), 43
- `\diamond` ($\diamond$), 42
- `\diamondsuit` ($\diamond$), 43
- dictionary, exception, 143
- differential, 50
- digit, 12, 32
- `\dim` (dim), 44
- dimen (TeX term), 100
- dimensional unit, 215
- disk (filled circle), 124, 222
- diskette, sending document on, 77
- display math style, 52, 188, 191
- displayed
 - formula, 26, 34, 39
 - blank line before, 26
 - math style for, 52, 191
 - multiline, 47–49
 - numbered, 39
 - space above and below, 107, 183, 188, 189, 218
 - paragraph, 183–187
 - quotation, 23, 34
 - text, 23–26
- displaying a box, 104
- `\displaymath` environment, 26, 34, 39, 188
 - anomalous vertical space after, 183
 - displaying a box with, 104
 - size of symbols in, 42
- `\displaystyle`, 52, 191
- distance, *see* length
- `\div` ($\div$), 42
- document
 - class, 19–20, 176–178
 - nonexistent, 137
 - multilanguage, 38
 - non-English, 38
 - structure of, 170
 - style (L^AT_EX 2.09), 228
- `document` environment, 34
- document-class option, 19, 88, 176
 - unused, 147
- document-style option (L^AT_EX 2.09), 228
- `\documentclass`, 19, 34, 170, 176–178
 - in `\input` file, 73
 - missing, 144
 - unused option, 147
- `\documentstyle` (L^AT_EX 2.09 command), 228
- `\dosupereject` (TeX command), 232
- `\dot` ($\dot{}$ math accent), 50
- `\doteq` ($\doteq$), 43
- `\dotfill`, 102
- dotless i and j, 38, 50, 190
- dots, space-filling, 102
- double quote, 13, 170
- double spacing, 172
- double sub- or superscript error, 140, 141
- double-column, *see* two-column
- `\doublerulesep`, 207
- `\Downarrow` ($\Downarrow$), 43, 47
- `\downarrow` ($\downarrow$), 43, 47
- `draft` document-class option, 93, 177
- `draft` package option, 131
- drawing curves, 125–126
- drawing pictures, 118–129
- driver, device, 118
- `dtx` file, 92
- `dvi` (device-independent) file, 6, 208
 - page written to, 135
- e-mail
 - sending document by, 77
 - sending file by, 32
- editing, copy, double-spacing for, 172
- edition field (in bib file), 163
- editor field (in bib file), 163
- `11pt` document-class option, 19
- eleven-point type, 19, 115

- `\ell` (ℓ), 43
- ellipsis, 15, 33, 40–41, 189
- `em` (unit of length), 99, 215
- `\em`, 27
- `\emph` (emphasis), 16, 33, 171
 - in slides, 81
- emphasis, 16, 33, 171
- empty `\mbox`, 97
- empty page style, 89, 179
 - for title page, 90
- `\emptyset` ($\emptyset$), 43
- `\encl`, 85
- end of line
 - character, 12
 - ending command name with, 16
 - space character at, 19
- end of paragraph, 13, 166, 171
- end of sentence, 13
- end of word, 13
- `\end`, 23, 167
 - delimits scope of declaration, 27–28, 168
 - is fragile, 22, 33
 - $\TeX$ command, 233
 - unmatched, 136
- `\end{document}`, 19, 170
 - error while processing, 135, 143
 - figures and tables output by, 198
 - `lof` file written by, 208
 - `lot` file written by, 208
 - missing, 30
 - `toc` file written by, 209
- `\end{verbatim}`, no space allowed in, 64
- `\end...`, defining, 55
- `\endinsert` ($\TeX$ command), 232
- `\enlargethispage`, 214
- `\enlargethispage*`, 96, 214
- `\ensuremath`, 53, 187
- `enter` key, 12
- entry
 - `bib` file, 156
 - field, bibliography, 156, 160–164
 - index, 75
 - type, bibliography, 156, 160–162
- `enumerate` environment, 24–25, 34, 184
 - as list, 112
 - counters, 97
 - suppressing advance of, 185
 - cross-reference to item number, 68
- enumerated list, long, 137
- `enumi ... enumiv` counters, 97, 184
- environment, 23, 33, 167
 - $*$ -form of, 167
 - `\begin` of nonexistent, 137
 - blank line above or below, 23
 - defining in terms of a command, 108
 - definition, 55–56, 192–193
 - with optional argument, 193
 - invisible, 169
 - list-making, 24–25, 112–115
 - made from declaration, 27, 33
 - math mode, 187–189
 - nested too deeply, 144
 - paragraph-making, 183–187
 - parameter, 56, 193
 - redefining, 56
 - theorem-like, 56–57, 193–194
 - as displayed paragraph, 183
 - cross-reference to, 68
 - undefined, 137
- `\epsilon` (ϵ), 41
- `\eqalign` ($\TeX$ command), 233
- `\eqalignno` ($\TeX$ command), 233
- `eqnarray` environment, 47, 188
 - `\` in, 169
 - anomalous vertical space after, 184
 - cross-reference to equation number, 68
 - formula numbers in, 88
 - in `leqno` document-class option, 177
 - space between rows in, 188
 - too many columns, 139
- `eqnarray*` environment, 48, 188
- `\equal`, 195
- equation counter, 97, 188
- equation environment, 26, 34, 39, 188
 - anomalous vertical space after, 184
 - cross-reference to number, 68
 - formula numbers in, 88
 - in `leqno` document-class option, 177
- `\equiv` ($\equiv$), 43
- error, 133–147
 - catching with text editor, 32
 - common, 31

- finding, 134–136
- in cross-referencing file, 66
- indicator, 29, 134
- L^AT_EX versus T_EX, 29
- locator, 29, 134, 135
- message, 29–30
 - L^AT_EX, 136–140
 - MakeIndex*, 154
 - T_EX, 140–145
- outputting, 135
- T_EX versus L^AT_EX, 29
- typographic, 91
- errsam.tex** file, 28
- et al., 158
- η , 41
- `\evensidemargin`, 181, 182
- ex (unit of length), 99, 215
- exception dictionary, 143
- exclamation point, *see* !
- executive paper size, 177
- executivepaper** document-class option, 177
- `\exists`, 43
- `\exp` (exp), 44
- extension, file, 12
- `\extracolsep`, 205
- face example, 108–110
- `\face`, 108–110
- family of type, 36, *see* type
- fat, making things, 129
- `\fbox`, 104, 125, 217
 - width of line, 219
- `\fboxrule`, 219
 - not used in picture commands, 222
 - used by `\fcolorbox`, 225
- `\fboxsep`, 219
 - used by `\colorbox`, 225
- `\fcolorbox`, 132, 225
- field, bibliography entry, 156, 160–164
- figure, 58–59, 197–200
 - centering, 112
 - in two-column format, 197
 - placement of, *see* float
 - too tall, 145
 - vertical space in, 58
- figure** counter, 97
- figure** environment, 58–59, 197
 - in parbox, 138
 - misplaced, 138
 - parbox made by, 104
 - space around, 169
 - too many, 139
- figure*** environment, 197
- figures, list of, 67, 175–176
 - generated from `lof` file, 208
- file, 207–209
 - ASCII, 144
 - auxiliary, error when reading, 135, 228
 - bibliographic database, *see* **bib** file
 - chapter in separate, 74
 - cross-referencing, 66
 - device-independent, *see* **dvi** file
 - extension, 12
 - `\include'd`, 73
 - input, *see* input
 - inserting, 72
 - name, 12
 - needs format error, 139
 - nonexistent, 137, 141
 - not found error, 137
 - of declarations, 73
 - prepended, 170
 - root, 72
 - sample input, 2, 8
 - sending by e-mail, 32
 - text, 12, 144
- filecontents** environment, 77, 170, 211
- filecontents*** environment, 211
- files, listing ones used, 77
- files, multiple input, 72–74
- `\fill`, 100, 102, 215
 - in **tabular*** environment, 205
- final** document-class option, 177
- final** package option, 131
- finding an error, 134–136
- first name of file, 12
- first page, right head for, 180
- `\fivebf` (T_EX command), 233
- `\fivei` (T_EX command), 233
- `\fiverm` (T_EX command), 233
- `\fivesy` (T_EX command), 233
- `\flat` (b), 43

- `fleqn` document-class option, 88, 177,
 - 188, 189
 - indentation in, 178, 188
- `float`, 58–59, 199
 - page, 199
 - made by `\clearpage`, 97
 - placement of, 59, 197
 - specifier, 197
 - too tall, 145
- `\floatpagefraction`, 200
- floats, too many, 139
- `\floatsep`, 200
- floppy disk, *see* diskette
- flush left
 - array column, 45
 - text, 111
- flush right
 - array column, 45
 - text, 111
 - in `tabbing` environment, 203
- `\flushbottom`, 88
 - bad page break with, 96
 - ignored by `\newpage`, 97
 - `\parskip` value for, 172
 - space between paragraphs, 100
- `flushleft` environment, 111
 - `\l` in, 169
 - as displayed paragraph, 183
 - as list, 112
- `flushright` environment, 111
 - `\l` in, 169
 - as displayed paragraph, 183
 - as list, 112
- `\fnsymbol`, 195
- `\folio` (T_EX command), 232
- font, 115–116, 225–226
 - Computer Modern, 115
 - for slides, 81
 - length dependent on, 99
 - selecting in Plain T_EX, 233
 - shape not available, 145, 146
 - special, 116
 - warning caused by `\boldmath`, 52, 145
- foot, page, 89, 179
- `\footline` (T_EX command), 232
- footnote, 17, 172–173
 - colors in, when split across pages, 132
 - example of difficult, 173
 - in `minipage` environment, 105, 218
 - in `parbox`, 105
 - line above, 173
 - mark, 172
 - symbols, 195
 - too many, 137
 - type size in, 116
- footnote counter, 97
 - for `minipage` environment, 97
- `\footnote`, 17, 33, 172
 - in `minipage` environment, 105, 218
 - is fragile, 22, 33
- `\footnotemark`, 172
 - for footnote in `parbox`, 105
- `\footnoterule`, 173
- `\footnotesep`, 173
- `\footnotesize`, 115, 226
- `\footnotetext`, 173
 - for footnote in `parbox`, 105
 - in `minipage` environment, 218
- `\footskip`, 182
- `\footstrut` (T_EX command), 232
- `\forall`, 43
- foreign language, *see* non-English language
- forests, preserving, 6
- form, command, 166
- format
 - open bibliography, 177
 - this file needs, 139
 - two-column, 20, 59, 88, 180, 197
- formatting the input file, 31
- formatting, visual, 64
 - for slides, 81
- formula, math, 18, 33, 39–53, 187–191
 - aligning on left, 88, 177
 - arrow in, 53
 - blank line not allowed in, 142, 171
 - bold subformula of, 52
 - box in, 103
 - center line of, 46
 - changing type size in, 116
 - complicated, 52
 - delimiter in, 190
 - displayed, *see* displayed formula

- formatting with `picture` environment, 52
- lines in, 53
- logical structure of, 50
- `\mbox` in, 38, 39
- multiline, 47–49
- number on left, 177
- numbered, 39
- overprinting of number, 188
- space character in, 18, 50
- space in, 50–51
- splitting across lines, 188
- using `graphics` package for, 53
- vertical space in, 106
- visual formatting of, 49, 52
- `\frac`, 40, 189
- fraction, 40, 189
- fragile command, 22, 25, 26, 33, 167–168
 - in @-expression, 168
 - in moving argument, 135
 - protecting, 22
- `\frame`, 125, 223
- `\framebox`, 104, 125, 217
 - in `picture` environment, 120, 221
 - use of `\width`, `\height`, `\depth`, and `\totalheight` in, 219
 - width of line, 219
- framed box, 104, 217
 - in `picture` environment, 222
- framing, 125
- `\frenchspacing`, 171
- `From`, line beginning with, 32
- `zFrom`, 32
- front matter (of a book), 80
- `\frontmatter`, 80
- `\frown` ($\smile$), 43
- function, log-like, 44–45, 190
- `\fussy`, 95, 214
- galley, 135
- `\Gamma` (Γ), 41
- `\gamma` (γ), 41
- `\gcd` ($\gcd$), 44
 - subscript of, 190
- geometric transformation, 129
- geometry, coordinate, 118
- `\geq` ($\geq$), 43
- `\gg` ($\gg$), 43
- Gilkerson, Ellen, iii, xv, 130
- `glo` (glossary) file, 75, 208
 - suppressed by `\nofiles`, 212
 - written by `\makeglossary`, 212
- global declaration, 168
- global option, unused, 147
- glossary, 74–76, 211–212
- `\glossary`, 75, 212
 - `glo` file entry written by, 208
 - space around, 169
 - too many on page, 143
- `\glossaryentry`, 75, 208, 212
- gnomonically, 93
- gnu, 37
- Goossens, Michel, xv, 2
- Gordon, Peter, xvi
- graphic, determining size of, 137
- `graphics` package, 129–131, 178, 223–224
 - making figures with, 58
 - making formulas with, 53
- graphics, unknown extension, 140
- `graphpap` package, 126, 178, 221
- `\graphpaper`, 126–127, 221
- `\grave` ($\grave{\hspace{0.1em}}$ math accent), 50
- gray color model, 132, 225
- Greek letter, 41
- green, 132, 225
- grid, coordinate, 126–127
- `h` float specifier, 197
 - changed, 146
- `\H` ($\H$ accent), 38
- half oval, 124
- hash size, 143
- `\hat` ($\hat{\hspace{0.1em}}$ math accent), 50
- `\hbar` ($\hbar$), 43
- `\hbox`, overfull, 30, 93, 147
 - marked with `draft` option, 93
- `\hbox`, underfull, 95, 147
- head, of arrow, 123
- head, page, 89, 179
 - in two-sided printing, 89
 - set by sectioning command, 22, 90, 174
- `\headheight`, 182

- heading, *see* head
- headings page style, 89, 179, 180
- \headline (T_EX command), 232
- \headsep, 182
- \heartsuit (♥), 43
- height
 - changing apparent, 107
 - of a box, 103
 - of page body, 100, 214
- \height, 219
- Helvetica, *see* sans serif type family
- hexadecimal character code, 116
- \hfill, 102, 217
 - in marginal note, 59
 - positioning item label with, 114
 - used with \vline, 206
- \hline, 62, 206
- \hom (hom), 44
- \hookleftarrow (↩), 43
- \hookrightarrow (↪), 43
- horizontal
 - brace, 49
 - line
 - drawn with \rule, 106
 - in array or tabular environment, 62, 206
 - space-filling, 102
 - mode, 36
 - positioning of text, 121
 - space, 101
 - around array or tabular environment, 205
 - in formula, 51, 191
- howpublished field (in bib file), 163
- \hrulefill, 102
- \hspace, 101, 216
 - rubber length in, 102
- \hspace*, 102, 216
- \Huge, 115, 226
- \huge, 115, 226
- hyphen, 14
 - inserted by T_EX, 17
- hyphenation, 93
 - correcting error in, 94
 - of non-English words, 94
 - permitting with \-, 213
 - suppressed in typewriter style, 226
- \hyphenation, 94, 213
 - \- instead of, 143
 - error in, 142
 - exceeding capacity with, 143
 - scope of, 168
- i, dotless (for accents), 38, 43, 50, 190
- \i (i), 38
- idx (index) file, 74, 150, 208
 - suppressed by \nofiles, 212
 - written by \makeindex, 212
- ifthen package, 178, 195–196
- \ifthenelse, 195
- ignored bibliography field, 161
- ignoring input, 19
- illegal
 - character in array argument, 137
 - parameter number, 141
 - unit of measure, 141
- \Im (ℑ), 43
- \imath (i), 43, 50, 190
- in (inch), 99, 215
- \in (∈), 43
- in-text formula, 39
- inbook bibliography entry type, 161
- inch (in), 99, 215
- \include, 73, 211
 - cannot be nested, 137
 - numbering with, 74
 - of nonexistent file, 137
 - sending files read by, 77
 - uses \clearpage, 97
- \include'd file, 73
 - \newcounter in, 138
- \includegraphics, 130, 224
 - cannot determine size of error, 137
- \includegraphics*, 224
- \includeonly, 73, 211
 - entered from terminal, 76
 - entering arguments with \typein, 74
 - misplaced, 136
- incollection bibliography entry type, 161
- ind file, 150, 208
 - read by \printindex, 211
- \indent, 171
- indentation, in fleqn option, 178

- indentation, paragraph, *see* paragraph
- index, 30, 74–76, 150–154, 211–212
- `\index`, 74, 212
 - curly brace in argument, 75
 - `idx` file entry written by, 208
 - in command argument, 153
 - space around, 169
 - special character in argument, 75
 - too many on page, 143
- `\indexentry`, 75, 212
 - on `idx` file, 208
- `\indexspace`, 75
- indicator, error, 29, 134
- `\inf` (∞), 44
 - subscript of, 190
- infinite loop, 252
- infinitely stretchable length, 100, 102, 215
- information, moving, 65–77, 207–209
- `\infty` (∞), 43
- ink, rectangular blob of, 106
- `inproceedings` bibliography entry type, 161
- input
 - character, 32
 - file, 12
 - displaying logical structure, 53
 - formatting, 31
 - page of, 13
 - files, multiple, 72–74
 - finding error in, 134
 - from terminal, 76–77, 212–213
 - ignoring, 19
 - processing part of, 73–74
 - sample, 2, 8
- `\input`, 72, 210
 - braces missing from argument, 141
 - differs from Plain $\TeX$ version, 233
 - of nonexistent file, 137
 - sending files read by, 77
- inserting a file, 72
- institution field (in `bib` file), 163
- `\int` ($\int$), 44, 51
- integral sign, space around, 51
- interaction, 76–77
- intercolumn space, 178
 - in array or tabular environment, 205
- interword space
 - in array or tabular environment, 169, 207
 - in `eqnarray` environment, 188
 - in `\shortstack`, 124
- interword space, 14, 170
 - before or after `\hspace` command, 101
 - in math mode, 51
 - produced by invisible command, 169
 - too much with `\sloppy`, 214
 - without line break, 17, 170
- `\intertextsep`, 200
- intraword dash, 14, 170
- invalid character error, 144
- invisible
 - character, 12, 32
 - command, 169
 - delimiter, 47
 - environment, 169
 - term made with `\mbox`, 48
 - text, 82, 97
- `\iota` (ι), 41
- `\isodd`, 196
- italic type shape, 16, 37, 226
 - in math mode, 51, 191
 - used for emphasis, 171
- `\item`, 24–25, 34, 184
 - [following, 25
 - in index, 211
 - in `theindex` environment, 75
 - in `trivlist` environment, 115
 - is fragile, 33
 - lonely, 137
 - missing, 138
 - optional argument of, 25, 167
 - outside list environment, 137
 - `\ref` value set by, 209
- item, label, 24–25, 184
 - extra-wide, 114
 - positioning with `\hfill`, 114
- `\itemindent`, 113, 186
 - in `trivlist` environment, 115
- `itemize` environment, 24–25, 34, 184
 - as list, 112
 - default labels of, 184
- `\itemsep`, 113, 185
- `\itshape`, 37, 226

- j, dotless (for accents), 38, 43, 50, 190
- `\j` (j), 38
- `\jmath` (j), 43, 50, 190
- `\Join` ($\Join$), 43
- `\jot`, 188
- journal field (in bib file), 163
- Jr., 157
- justifying lines, 95, 100
-
- `\kappa` (κ), 41
- `\ker` (ker), 44
- Kernighan, Brian, 7
- key
 - citation, 69, 71, 156
 - cross-reference, 67
 - enter*, 12
 - return*, 12
- key field (in bib file), 162, 163
- keyboard, *see* terminal
- keys, listing, 69
- `\kill`, 61, 202
- Knuth, Donald Ervin, xvi, 5, 115
-
- 1 (left)
 - oval-part argument, 124, 223
 - positioning argument, 45, 217, 221
 - in array or tabular argument, 205
 - of `\makebox`, 104, 121
 - of `\shortstack`, 124
- 1 (letter el), 12
- `\L` (L), 39
- `\l` (l), 39
- label
 - item, 24–25, 184
 - extra-wide, 114
 - positioning with `\hfill`, 114
 - mailing, 86
 - multiply-defined, 146
 - produced by `\cite`, 210
 - source, 69
- `\label`, 67, 209
 - in `\caption` argument, 209
 - in `\eqnarray` environment, 188
 - in figure or table environment, 68
 - missing, 146
 - preceded by `\caption`, 68
 - similar to `\bibitem`, 71
 - space around, 169
- `\labelitemi` ... `\labelitemiv` counters, 184
- labels may have changed warning, 146
- labels, cross-reference, too many, 143, 144
- `\labelsep`, 113, 186
- `\labelwidth`, 113, 186
 - in `trivlist` environment, 115
- `lablst.tex` file, 69, 208
- `\Lambda` (Λ), 41
- `\lambda` (λ), 41
- Lamport, Jason, 131
- Lamport, Leslie, 131
- landscape document-class option, 177
- landscape printing, 177
- `\angle` ($\angle$), 47
- language, non-English, 38, 94
- `\LARGE`, 115, 226
- `\Large`, 115, 226
- `\large`, 115, 226
- L^AT_EX**
 - bug, 139
 - distinguished from T_EX, 5
 - error message, 136–140
 - error versus T_EX error, 29
 - logo, 5, 15, 33, 171
 - pronunciation of, 5
 - running on part of document, 31, 73–74
 - running unattended, 30
 - stopping, 30, 136
 - version, 2
 - warning message, 135, 145–147
- L^AT_EX Companion, The, 2
- L^AT_EX**, 15, 33, 171
- L^AT_EX 2.09 versus L^AT_EX 2_ε, 2, 228–229
- L^AT_EX 2_ε, xv, 2, 118, 132
- latexsym package, 42, 178
- law (mathematical), 56
- `\lceil` ($\lceil$), 47
- `\ldots`, 15, 33
- `\ldots` (...), 40, 189
- `\leadsto` ($\leadsto$), 43
- leaving math mode, 36
- left margin, prevailing, 201
- `left_margin_tab`, 201

- `\left`, 47, 190
- left, flush, *see* flush
- left-hand page, 179
- left-to-right mode, *see* LR mode
- `\Leftarrow` ($\Leftarrow$), 43
- `\leftarrow` ($\leftarrow$), 43
- `\lefteqn`, 48, 188
- `\lefteye`, 109
- `\leftharpoondown` ($\leftharpoondown$), 43
- `\leftharpoonup` ($\leftharpoonup$), 43
- `\leftmargin`, 113, 185
 - in `trivlist` environment, 115
- `\leftmargini` ... `\leftmarginvi`, 185
- `\Leftrightarrow` ($\Leftrightarrow$), 43
- `\leftrightarrow` ($\leftrightarrow$), 43
- legal paper size, 177
- `legalpaper` document-class option, 177
- lemma, 56
- length, 99–101, 215–216
 - command, 99
 - defining, 101
 - not preceded by `\protect`, 168
 - font-dependent, 99
 - infinitely stretchable, 100, 215
 - natural, 100
 - of line in picture, 122
 - parameter, 100
 - rigid, 100
 - rubber, 100
 - in `\hspace` or `\vspace`, 102
 - in `\lengthtest` expression, 196
 - infinitely stretchable, 102
 - unit (in `picture` environment), 118
 - unit of, 215
 - zero, 99
- `\lengthtest`, 196
- `\leq` ($\leq$), 43
- `\leqalignno` (T_EX command), 233
- `leqno` document-class option, 88, 177, 188
- letter, 32
 - case of, 68, 69
 - for mailing, 84–86
 - Greek, 41
 - lowercase, 12
 - not a, 142
 - script, 42
 - uppercase, 12
- `letter` document class, 84–86, 176
 - `\parskip` in, 100
- letter environment
 - moving argument of, 168
- `letter` environment, 85
- letter paper size, 177
- `letterpaper` document-class option, 177
- level number of sectional unit, 176
- `\lfloor` ($\lfloor$), 47
- `\lg` ($\lg$), 44
- `\lhd` ($\lhd$), 42
- `\lim` ($\lim$), 44
 - subscript of, 190
- `\liminf` ($\liminf$), 44
 - subscript of, 190
- `\limsup` ($\limsup$), 44
 - subscript of, 190
- line
 - blank, *see* blank line
 - bottom of, 107
 - break, *see* break, line
 - horizontal, *see* horizontal
 - in formula, 53
 - in picture, 122–123
 - thickness of, 118
 - justifying, 95, 100
 - none to end error, 139
 - slanted, minimum size of, 123
 - space at beginning or end of, 102
 - vertical, *see* vertical
 - width, *see* width
- `\line`, 122, 222
 - error in, 136
 - T_EX command, 233
- `\linebreak`, 95, 213
 - optional argument of, 167
 - space around, 169
 - warning caused by, 147
- lines, distance between, 100
- `\linethickness`, 223
- `\linewidth`, 171
- lining up, *see* aligning
- list, 24–25, 34
 - counter, defining, 114
 - long enumerated, 137
 - margins of nested, 114

- of figures or tables, 67, 175–176, 208
 - adding an entry, 175
 - adding commands to, 67, 176
 - error in, 135
 - source, 70
- `list` environment, 112–114, 185
 - style parameters for, 185
- list-making environment, 24–25, 112–115
 - defining, 114
 - in parbox, 105, 218
 - nested too deeply, 139
 - primitive, 112
- `\listfiles`, 77, 211
- listing keys, 69
- `\listoffigures`, 67, 175–176
 - error when processing, 143
 - lof file read by, 208
- `\listoftables`, 67, 175–176
 - error when processing, 143
 - lot file read by, 208
- `\listparindent`, 113, 185
- `\ll` ($\ll$), 43
- `\ln` (ln), 44
- local coordinates, 129
- Local Guide, 2, 6, 8, 12, 20, 28, 30, 69, 71, 77, 86, 88, 91–93, 115, 116, 118, 124, 132, 136, 139, 140, 151, 156, 159, 163, 178
- locator, error, 29, 134, 135
- lof (list of figures) file, 67, 175, 208
 - editing, 67
 - error in, 135
- log file, 28, 76, 208
- `\log` (log), 44, 51
- log-like function, 44–45, 190
- logical design, 7
- logical structure, 6, 88
 - displaying in input file, 53
 - of formula, 50
 - repeated, 53
- logo, L^AT_EX, 5, 15, 33, 171
- logo, T_EX, 5, 15, 33, 171
- lonely `\item`, 137
- `\Longleftarrow` ($\Longleftarrow$), 43
- `\longleftarrow` ($\longleftrightarrow$), 43
- `\Longlefterightarrow` ($\Longleftrightarrow$), 43
- `\longlefterightarrow` ($\longleftrightarrow$), 43
- `\longmapsto` ($\mapsto$), 43
- `\Longrightarrow` ($\Rightarrow$), 43
- `\longrightarrow` ($\rightarrow$), 43
- lot (list of tables) file, 67, 175, 208
 - editing, 67
 - error in, 135
- low ellipsis, 40, 189
- lowercase letter, 12
- lowering text, 107
- LR box, 103–104, 107
- LR mode, 36, 39
 - in `tabbing` environment, 201
 - space character in, 36
 - `tabular` item processed in, 62
- lrbox environment, 108, 218
- macho T_EX programmer, 92
- macro parameter character error, 145
- magenta, 132, 225
- magnification of output, 233
- `\magnification` (T_EX command), 233
- magnifying a picture, 118
- Magritte, René, 131
- mailing label, 86
- main matter (of a book), 80
- main memory size, 143
- `\mainmatter`, 80
- `\makebox`, 104, 217
 - in picture environment, 120, 221
 - use of `\width`, `\height`, `\depth`, and `\totalheight` in, 219
- `\makefootline` (T_EX command), 232
- `\makeglossary`, 75, 212
 - glo file produced by, 208
- `\makeheadline` (T_EX command), 232
- makeidx package, 150
 - defines `\printindex`, 211
- MakeIndex*, 74, 150–154
 - ind file written by, 208
- `\makeindex`, 74, 150, 212
 - idx file produced by, 208
 - misplaced, 136
- `\makelabel`, 186
- `\makelabels`, 86
- `\maketitle`, 20, 34, 90, 181
 - effect of `titlepage` option, 88
 - not preceded by `\author`, 146

- not preceded by `\title`, 138
- mandatory argument, 166
- manual bibliography entry type, 162
- `\mapsto` ($\mapsto$), 43
- margin
 - arrow in, 59
 - changing in `\tabbing` environment, 202
 - determined by `\textwidth` and `\textheight`, 100
 - of nested lists, 114
 - prevailing, 201, 203
- marginal note, 59–60, 200–201
 - `\hfill` in, 59
 - moved, 146
 - overprinting of, 201
- marginpar moved warning, 59, 146
- `\marginpar`, 59–60, 200
 - incorrectly placed, 146
 - space around, 169
 - too many on page, 139
- `\marginparpush`, 201
- `\marginparsep`, 182, 201
- `\marginparwidth`, 182, 201
- mark, footnote, 172
- `\markboth`, 89, 90, 179
 - moving argument of, 90, 168
 - with `myheadings` page style, 179
- `\markright`, 89, 90, 179
 - moving argument of, 90, 168
 - with `myheadings` page style, 179
- `masterstthesis` bibliography entry type, 162
- `math`
 - formula, *see* formula, `math`
 - mode, 36, 39
 - accent in, *see* accent
 - bad command in, 137, 145
 - blank line not allowed in, 142, 171
 - defining commands for use in, 53
 - environment, 187–189
 - leaving, 36
 - space character ignored in, 36, 50
 - style, 52, 191
 - display, 52, 188, 191
 - for sub- and superscripts, 52, 191
 - of `array` environment item, 191
 - text, 52, 187, 191
 - symbol, 41–45
 - variable-sized, 42, 52
- `math` environment, 18, 39, 187
- `\mathbf`, 51, 191
- `\mathcal`, 42, 51, 191
- mathematical, *see* `math`
- `\mathindent`, 178, 188
- `\mathit`, 51, 191
- `\mathrm`, 51, 191
- `\mathsf`, 51, 191
- `\mathtt`, 51, 191
- matrix, 45
- `\max` (`max`), 44
 - subscript of, 190
- `\mbox`, 17, 33, 104, 171, 217
 - bold subformula in, 52
 - empty, 97
 - for changing type size in formula, 116
 - how it works, 36, 103
 - in formula, 38, 39
 - invisible term made with, 48
- `\mdseries`, 37, 226
- medium space, 51, 191
- medium type series, 37, 226
- `\medskip`, 216
- `\medskipamount`, 216
- memory size, 143
- message
 - $\LaTeX$ error, 136–140
 - $\LaTeX$ warning, 145–147
 - page number in, 135
 - MakeIndex* error, 154
 - printing on terminal, 76
 - $\TeX$ error, 140–145
 - $\TeX$ warning, 30, 147
- `\mho` (Ω), 43
- `\mid` ($|$), 43
- `\midinsert` ($\TeX$ command), 232
- millimeter (`mm`), 99, 215
- `\min` (`min`), 44
 - subscript of, 190
- `minipage` environment, 104, 105, 218
 - footnote counter for, 97
 - footnote in, 172
 - in `p` column of `array` or `tabular` environment, 205
 - nested, 106

- tabbing environment in, 106
- versus `\parbox`, 105
- minus sign, 14
- mirror image, 130
- misc bibliography entry type, 162
- misplaced
 - `#`, 141, 145
 - `&`, 141
 - alignment tab, 141
 - figure environment, 138
 - `\includeonly`, 136
 - `\makeindex`, 136
 - `\marginpar`, 138
 - `\nofiles`, 136
 - table environment, 138
 - `\usepackage`, 136
- missing
 - `$` error, 142
 - `\`, 141
 - `{` error, 142
 - `}` error, 142
 - @-expression, 138
 - argument, 138, 142
 - `\begin{document}` error, 138
 - brace, 142
 - control sequence error, 142
 - `\documentclass`, 144
 - `\end{document}`, 30
 - `\item`, 138
 - `\label`, 146
 - number error, 142
 - p-arg error, 138
 - `\usepackage`, 144
- misspelled command name, 31
 - correcting, 144
- Mittelbach, Frank, xv, 2
- mm (millimeter), 99, 215
- mod, 44, 190
- mode, 36
 - compatibility, 228
 - horizontal, 36
 - left-to-right, *see* LR mode
 - LR, *see* LR mode
 - math, *see* math
 - paragraph, *see* paragraph
 - picture, 120, 220–221
 - vertical, 36
- model, color, 132, 224
 - undefined, 140
- `\models (=)`, 43
- modulo, 44, 190
- month field (in `bib` file), 163
- moved marginal note, 146
- moving argument, 22, 33, 167
 - fragile command in, 135
 - of @-expression, 205
 - of `\bibitem`, 72
 - of `\caption`, 58
 - of letter environment, 85
 - of `\markboth` and `\markright`, 90
 - of `\typein` and `\typeout`, 77, 212, 213
- moving information around, 65–77,
207–209
- `\mp (±)`, 42
- mpfootnote counter, 97
- `\mu (μ)`, 41
- `\multicolumn`, 62, 206
 - error in, 137, 138
 - not allowed in `eqnarray`, 188
- multilanguage document, 38
- multiline formula, 47–49
- multiple
 - authors, 21
 - captions, 59
 - column item, 62, 206
 - input files, 72–74
 - finding error in, 134
 - names in `bib` file field, 158
- multiply-defined label warning, 146
- `\multiput`, 127–128, 221
- myheadings page style, 89, 179
- `\nabla (∇)`, 43
- name
 - command, *see* command
 - in `bib` file field, 157–158
 - of file, 12
- named theorem, 57
- names, multiple, in `bib` file field, 158
- natural length, 100
- `\natural (ℎ)`, 43
- `\nearrow (↗)`, 43
- `\neg (¬)`, 43
- negative thin space, 51, 191

- `\neq` ($\neq$), 43
- nested
 - commands, 16
 - lists, margins of, 114
 - `minipage` environments, 106
 - too deeply, 139, 144
- nesting depth error, 139
- `\newboolean`, 196
- `\newcommand`, 53, 168, 192
 - braces removed from, 92
 - error in, 137, 141, 142
- `\newcounter`, 99, 194
 - error in, 137, 138
 - in included file, 138
 - optional argument of, 167
 - scope of, 168
- `\newenvironment`, 55–56, 114, 192
 - error in, 137, 141, 144
- `\newlength`, 101, 216
 - error in, 137, 142
 - scope of, 168
- `\newline`, 95, 213
 - bad use of, 147
 - error in, 139
- `\newpage`, 97, 215
 - in two-column format, 97
- `\newsavebox`, 107, 218
 - error in, 137, 142
 - scope of, 168
- newt, 68
- `\newtheorem`, 56, 193
 - counter created by, 97
 - cross-reference to environment defined by, 68
 - environment defined by, 183
 - error in, 137, 138, 144
 - optional argument of, 167
 - scope of, 168
- `next_tab_stop`, 201
- `\ni` ($\ni$), 43
- Nixon, Richard, 24
- no counter error, 138
- `\nocite`, 70, 210
- `\nofiles`, 207
 - misplaced, 136
 - suppresses `glo` file, 212
 - suppresses `idx` file, 212
 - used when editing `toc` file, 67
- `\noindent`, 171, 183
- `\nolinebreak`, 95, 213
 - optional argument of, 167
 - space around, 169
- non-English symbol, 38–39
 - in `bib` file, 158
- nonexistent
 - document class, 137
 - environment, 137
 - file, 141
 - package, 137
- `\nonfrenchspacing`, 171
- nonmath symbol, 38–39
- nonprinting character, 144
- `\nonumber`, 48, 188
- `\nopagebreak`, 96, 214
 - optional argument of, 167
 - space around, 169
- `\nopagenumbers` (T_EX command), 232
- `\normalbottom` (T_EX command), 232
- `\normalfont`, 226
- `\normalmarginpar`, 201
- `\normalsize`, 115, 226
- `\not`, 42
 - in `ifthen` package expression, 196
- notation, 53
 - versus concepts, 31
- note environment, 83
- note field (in `bib` file), 163
- note, marginal, 59–60, 200–201
- `\notin` ($\notin$), 43
- `\notitlepage` document-class option, 177
- `\nu` (ν), 41
- number
 - alphabetic, 195
 - arabic, 195
 - assigning key to, 67
 - formula, 88
 - printed at left, 177
 - suppressing in `eqnarray`, 48
 - illegal parameter, 141
 - missing, 142
 - page, *see* page
 - roman, 195
 - wrong, 146
- number field (in `bib` file), 163

- number-range dash, 14, 170
- numbered displayed formula, 39
- numbering, 97–99, 194–195
 - commands, `\the...`, 98
 - page, 98
 - sectional units, 176
 - style, 98
 - with `\include`, 74
 - within sectional unit, 57
- `\numberline`, 176
- `\narrow` (`\`), 43
- O (letter oh), 12
- `\O` ($\mathcal{O}$), 39
- `\o` ($\mathcal{o}$), 39
- object, floating, 58
- object, picture, 120, 221–223
- octal character code, 116
- `\oddsidemargin`, 181, 182
- `\odot` ($\odot$), 42
- `\OE` ($\mathfrak{E}$), 39
- `\oe` ($\mathfrak{e}$), 39
- `\oint` ($\oint$), 44
- `\oldstyle` (T_EX command), 233
- `\Omega` (Ω), 41
- `\omega` (ω), 41
- omicron ($\mathcal{o}$), 41
- `\ominus` ($\ominus$), 42
- omitted argument, error caused by, 141
- one (1), 12
- one-column format, 181
- one-sided printing, marginal notes in, 59
- onecolumn document-class option, 177
- `\onecolumn`, 88, 181
- oneside document-class option, 177
- only in preamble error, 136
- `\onlynotes`, 84
- `\onlyslides`, 83
- open bibliography format, 71, 177
- openany document-class option, 80, 177
- openbib document-class option, 71, 177
- `\opening`, 85
- openright document-class option, 80, 177
- `\oplus` ($\oplus$), 42
- option
 - clash error, 138
 - document-class, 176
 - document-style (L^AT_EX 2.09), 228
 - unknown, 140
- optional argument, 20, 166
 - [or] in, 25
 - default, 166
 - defining a command with, 192
 - defining an environment with, 193
 - of `array` environment, 46
 - of `\item`, 25
 - of `\marginpar`, 59
 - of sectioning command, 174
 - of `\twocolumn` too tall, 146
 - square bracket mistaken for, 142
 - square brackets enclosing, 20, 33, 166
- optional arguments, command with two, 166
- optional bibliography field, 160
- `\or`, 196
- organization field (in bib file), 163
- origin, 118
- `\oslash` ($\oslash$), 42
- `\otimes` ($\otimes$), 42
- outerpar mode, not in, 138
- output
 - line, space at beginning or end of, 102
 - printing, 6, 208
 - routine, Plain T_EX, 232
 - to terminal, 76–77, 212–213
- `<output>` printed on terminal, 135
- `\output` routine, 232
- outputting error, 135
- oval, 124–125, 223
 - too small, 146
- `\oval`, 124–125, 223
- oval-part argument, 124
- `\overbrace`, 49
- overfull `\hbox`
 - marked with `draft` option, 93
 - message, 30, 93, 147
- overfull `\vbox` message, 147
- overlay environment, 82
- `\overline`, 49, 190
- overlining, 49, 190
- overprinting
 - of equation number, 188
 - of marginal notes, 201

- overriding item position in `tabular` environment, 63
- p**
 - float specifier, 197
 - in `array` or `tabular` argument, 205
 - `\P` (§), 39, 173
 - `p`-arg missing error, 138
 - package, 2, 20, 178–179
 - creating your own, 91
 - loaded twice, 138
 - nonexistent, 137
 - page
 - blank, 97
 - made by `\cleardoublepage`, 215
 - with `titlepage` environment, 180
 - body, 89, 179
 - height of, 100, 214
 - break, *see* break, page
 - color of, 132
 - first, right head for, 180
 - float, 199
 - made by `\clearpage`, 97
 - foot, 89, 179
 - head, 89, 179
 - in `twoside` option, 90
 - set by sectioning command, 90, 174
 - input file, 13
 - last, output by `\stop`, 136
 - left-hand, 179, 196
 - number, 98
 - alphabetic, 180
 - arabic, 89, 180
 - cross-reference to, 68
 - in warning message, 135
 - indexing different styles, 154
 - printed on terminal, 135
 - roman, 89, 180
 - style of, 180
 - one-column, 181
 - positioning relative to, 111
 - range, in index, 152
 - right-hand, 179, 196
 - starting on, 97
 - space at top or bottom, 102
 - squeezing extra text on, 96, 214
 - starting a new, 215
 - style, 89–90, 179–182
 - default, 89, 179
 - title, *see* title
 - too many `\index` or `\glossary` commands on, 143
 - too many `\marginpar` commands on, 139
 - two-column, 20, 88, 180
 - width of text on, 100
 - `page` counter, 97, 98
 - current value of, 196
 - set by `\pagenumbering`, 180
 - `\pagebody` (T_EX command), 232
 - `\pagebreak`, 96, 214
 - in two-column format, 97
 - optional argument of, 167
 - space around, 169
 - `\pagecolor`, 132, 225
 - scope of, 168
 - `\pagecontents` (T_EX command), 232
 - `\pageheight`, 182
 - `\pageinsert` (T_EX command), 232
 - `\pageno` (T_EX command), 232
 - `\pagenumbering`, 89, 180
 - scope of, 168
 - `\pageref`, 68, 209
 - ~ used with, 68
 - undefined, 146
 - used with `\isodd`, 196
 - wrong number printed by, 146
 - `pages` field (in `bib` file), 163
 - pages, how T_EX makes, 135
 - `\pagestyle`, 89, 179
 - after `\chapter`, 89
 - scope of, 89
 - `\pagewidth`, 182
 - paper size, 177
 - `\par`, 171
 - paragraph, 13, 171
 - bad end of, 142
 - beginning of, 183
 - displayed, 183–187
 - end of, 13, 166, 171
 - in picture, 104
 - in table item, 104
 - indentation, 171
 - anomalous, 183

- removing with `\noindent`, 183
- width of, 99, 172
- mode, 36
 - `\` in, 96
 - box made in, 103
 - box typeset in, 104
 - center environment in, 111
 - figure or table body processed in, 58
 - marginal note processed in, 59
- new, 33
- unit, 94
- paragraph counter, 97
- `\paragraph`, 21, 174
- paragraph-making environment, 105, 183–187
- paragraphs
 - `\` between, 139
 - space between, 100, 172
- `\parallel` (`\|`), 43
- parameter
 - length, 100
 - number error, 141
 - of command, 54, 192
 - of environment, 56, 193
 - style, 166
- parbox, 104–106, 218
 - `\caption` in, 199
 - figure or table environment in, 138
 - in array or tabular column, 205
 - in tabbing environment, 203
 - list-making environment in, 105, 218
 - marginal note typeset in, 200
 - paragraph-making environment in, 105
 - `\parindent` set to zero in, 172
 - positioning with `\raisebox`, 105
 - tabbing environment in, 105
 - tabular environment in, 218
- `\parbox`, 104, 218
 - versus `minipage` environment, 105
- parenthesis, 12, 15
- `\parindent`, 99, 100, 172
 - equals zero in parbox, 105
 - in list environment, 114
- `\parsep`, 113, 185
- `\parskip`, 100, 172
 - in letter document class, 100
 - in list environment, 114, 185
- part counter, 97
- part of input, processing, 31, 73–74
- `\part`, 21, 22, 174
- `\partial` (∂), 43
- `\partopsep`, 113, 185
 - when added, 114
- pasting, 58
- pattern, repeated, 127–128
- pc (pica), 215
- period, 33
 - space after, 14–15
- `\perp` ($\perp$), 43
- phdthesis bibliography entry type, 162
- `\Phi` (Φ), 41
- `\phi` (ϕ), 41
- `\Pi` (Π), 41
- `\pi` (π), 41
- pica (pc), 215
- pict2e package, 118, 179, 221–223
- picture, 118–129
 - command, argument of, 119
 - declaration, 223
 - in float, 58
 - line thickness in, 118
 - magnifying, 118
 - mode, 120, 220–221
 - object, 120, 221–223
 - paragraph in, 104
 - reducing, 118
- picture environment, 118–129, 219–223
 - box made by, 103
 - example, 220
 - formatting formula with, 52
 - large, 143
 - making figures with, 58
 - reusing, 107
 - zero-width box in, 121
- placement
 - of figures and tables, 59, 197
 - of marginal note, 59–60
 - of `\protect`, incorrect, 142
 - of tabular environment, 63
- plain bibliography style, 70
- plain page style, 89, 179
- Plain T_EX, 231–233
- `\plainoutput` (T_EX command), 232

- `\pm` ($\pm$), 42
- `\pmod`, 44, 190
- poetry, 25–26, 34, 184
- point (unit of length), 93, 99, 215
- point, reference, 103, 221
- pool size, 144
- `\poptabs`, 203
 - unmatched, 138
- position, specifying by coordinate, 118
- positioning
 - argument, 45–46, 104–105, 121, 124
 - of item label, 114
 - of parbox with `\raisebox`, 105
 - of text, 121, 217, 219
 - relative to a fixed point on page, 111
 - relative to a line of text, 110
 - text in picture, 121
 - vertical, *see* vertical
- `\pounds` (£), 39, 173
- `\Pr` (Pr), 44
 - subscript of, 190
- preamble, 19, 34, 170
 - command definition in, 55
 - error in, 138
 - `\hyphenation` command in, 94
 - `\makeindex` in, 74
 - only in error, 136
 - visual design commands in, 88
- `\prec` ($\prec$), 43
- `\preceq` ($\preceq$), 43
- preloaded command, 91
- preparing input file, 12
- prepended file, 170
- previewer, screen, 6
- prime symbol, 18, 189
- `\prime` ($\prime$), 43
- primitive list-making environment, 112
- principle, 56
- `\printindex`, 150, 211
 - ind file read by, 208
- printing
 - aux file information, 208
 - counter values, 98
 - landscape, 177
 - L^AT_EX output, 6, 208
 - one-column, 181
 - one-sided, marginal notes in, 59
 - slides and notes separately, 83
 - two-column, 20, 180
 - two-sided, 19, 177
 - increasing page height in, 214
 - marginal notes in, 59
- proceedings bibliography entry type, 162
- `\prod` ($\prod$), 44
- program, formatting a, 60
- programming in L^AT_EX, 195
- pronunciation of L^AT_EX and T_EX, 5
- proposition, 56
- `\propto` ($\propto$), 43
- `\protect`, 22, 33, 167
 - in @-expression, 205
 - in `\caption` argument, 58
 - in `\index` argument, 153
 - in `\typeout` argument, 212
 - incorrect placement of, 142
 - not before length command, 100, 168
 - not in `\addtocounter` or `\setcounter` argument, 168
 - not used with `\value`, 194
- protecting a fragile command, 22
- `\providecommand`, 168, 192
 - error in, 141
- `\ps`, 86
- `\Psi` (Ψ), 41
- `\psi` (ψ), 41
- pt (point), 99, 215
- publisher field (in bib file), 163
- punctuation character, 12, 32
 - in key, 68, 69
- punctuation dash, 14, 170
- punctuation, space after, 14–15, 170, 171
- `\pushtabs`, 203
 - unmatched, 138
- `\put`, 120, 221
 - sequence replaced by `\multiput`, 127
 - space in argument, 129
- `\qbezier`, 125–126, 221
 - T_EX space used by, 143
- `\qbeziermax`, 126, 221
- quarter oval, 124
- question mark (?), *see* ?

- quotation environment, 24, 34, 184
 - as list, 112
- quotation marks, 13–14, 33, 170
- quotation, displayed, 23, 34
- quote
 - double, 13, 170
 - left (‘), 12, 13, 32, 33, 170
 - right (’), 12, 13, 15, 32, 33
 - in formula, 18
 - single, 13, 170
- quote environment, 23–24, 34, 184
 - as list, 112
- quotient symbol (/), 51
- quoting character in index entry, 154
- r (right)
 - oval-part argument, 124, 223
 - positioning argument, 45, 217, 221
 - in `array` or `tabular` argument, 205
 - of `\makebox`, 104, 121
 - of `\shortstack`, 124
- ragged right, 111
- `\raggedbottom`, 88
 - bad page break with, 96
- `\raggedleft`, 112
 - in p column, 205
- `\raggedright`, 112
 - in p column, 205
- `\raisebox`, 107, 219
 - positioning parbox with, 105
 - use of optional arguments, 109
 - use of `\width`, `\height`, `\depth`, and `\totalheight` in, 219
- raising text, 107
- `\rangle` (}), 47
- `\rceil` (⌈), 47
- `\Re` ($\mathbb{R}$), 43
- reading auxiliary file, error when, 135, 228
- reclaiming saved box’s space, 127
- rectangular blob of ink, 106
- recursive definition, 54
- red, 132, 225
- redefining a command, 55, 168, 192
 - with `\typein`, 212
- redefining an environment, 56, 192
- reducing a picture, 118
- `\ref`, 67, 209
 - ~ used with, 68
 - similar to `\cite`, 71
 - undefined, 146
 - value, 209
 - in `enumerate` environment, 184
 - in list environment, 186
 - in theorem-like environment, 193, 194
 - set by `\refstepcounter`, 195
 - wrong number printed by, 146
- reference point, 103, 221
 - of picture object, 120
- reference undefined warning, 146, 147
- reference, circular, 243
- `\reflectbox`, 130, 224
- reflection, 130
- `\refstepcounter`, 195
 - `\ref` value set by, 209
 - resets counter, 194
- register, boolean, 196
- Reid, Brian, 7
- remark in citation, 210
- `\renewcommand`, 55, 168, 192
 - error in, 141, 142
- `\renewenvironment`, 56, 192
 - error in, 141
- repeated logical structure, 53
- repeated pattern in picture, 127–128
- report document class, 19, 176
 - appendix in, 175
 - default page style, 89
 - `thebibliography` environment in, 209
 - `titlepage` option the default, 88
- `report.cls` file, 92
- required bibliography field, 160
- `\resizebox`, 129–130, 224
- `\resizebox*`, 224
- `return` key, 12
- reusing a picture environment, 107
- `\reversemarginpar`, 201
- `\rfloor` (⌋), 47
- rgb color model, 132, 225
- `\rhd` (⋗), 42
- `\rho` (ρ), 41
- right head for first page, 180
- right margin, prevailing, 203

- `\right`, 47, 190
- right, flush, *see* flush right
- right-hand page, 179
 - starting on, 97
- `\Rightarrow` ($\Rightarrow$), 43
- `\rightharpoonrightarrow` ($\rightarrow$), 43
- `\rightharpoonrightarrowdown` ($\rightarrow$), 43
- `\rightharpoonrightarrowup` ($\rightarrow$), 43
- `\rightleftharpoons` ($\Leftrightarrow$), 43
- `\rightmargin`, 113, 185
 - in `trivlist` environment, 115
- rigid length, 100
- `\rmfamily`, 37, 226
- robust command, 22, 167
- roman page numbers, 89, 180
- roman type family, 37, 226
 - in math mode, 51, 191
 - in slides document class, 81
- `\Roman`, 98, 195
- `\roman`, 98, 195
- Romanian, 94
- root file, 72
- root, square, 40, 189
 - space around, 51
- `\rotatebox`, 130, 224
- `\rotatebox*`, 224
- rotation, 130
- rounded corner, 124–125
- rubber length, 100
 - in `\hspace` or `\vspace`, 102
 - in `\lengthtest` expression, 196
 - infinitely stretchable, 102, 215
- rule (mathematical), 56
- rule box, 103, 106
- `\rule`, 106, 219
 - horizontal line drawn with, 106
 - vertical line drawn with, 106
- running head, *see* head
- running L^AT_EX
 - on part of document, 31, 73–74
 - unattended, 30
- s positioning argument, 217
- `\S` (§), 39, 173
- Samarin, Alexander, 2
- `\samepage` (L^AT_EX 2.09 command), 229
- sample input, 2, 8
- `sample2e.tex` file, 3, 8, 19, 28, 93
- sans serif type family, 37, 226
 - in math mode, 51, 191
- save size, 144
- `\savebox`, 107, 218, 223
 - in picture environment, 120, 127
 - use of `\width`, `\height`, `\depth`, and `\totalheight` in, 219
- saving a box, 107–108, 127, 218
- saving typing, 54
- `\sbox`, 108, 218
- `\scalebox`, 129–130, 224
- scaling, 129
- school field (in bib file), 163
- scope of declaration, 27–28, 168
 - in argument of user-defined command or environment, 55, 56, 192
 - in `array` environment, 45
 - in `tabbing` environment, 61, 203
 - nested too deeply, 144
 - within command argument, 193
- screen output, *see* terminal
- screen previewer, 6
- script letter, 42
- script math style, 52, 191
- scriptscript math style, 52, 191
- `\scriptscriptstyle`, 52, 191
- `\scriptsize`, 115, 226
- `\scriptstyle`, 52, 191
- scroll, the, 135
- `\scshape`, 37, 226
- `\searrow` ($\searrow$), 43
- `\sec` (sec), 44
- `secnumdepth` counter, 174, 176
- section counter, 97
- section numbering, 176
- section structure, 21
- `\section`, 21, 174
- sectional unit, 21
 - cross-reference to, 67
 - in different document classes, 21, 22
 - level number of, 176
 - numbering of, 174
 - numbering within, 57
- sectioning command, 21–22, 174–176
 - `\` in, 169
 - *-form of, 174

- argument too long, 143
- blank line not allowed in, 171
- examples, 174
- fragile command in, 135
- in front and back matter of a book, 80
- `\label` in argument, 209
- moving argument of, 168
- optional argument of, 174
- page heading set by, 90, 174
- table of contents entry, 22, 174, 209
- “see” index entry, 152
- `\see`, 153
- sending a document, 77
- sentence, 13
- series** field (in **bib** file), 163
- series of type, *see* type
- `\setboolean`, 196
- `\setcounter`, 98, 194
 - error in, 138, 144
 - `\protect` not used in argument of, 168
 - scope of, 98, 168
- `\setlength`, 101, 216
- `\setminus` (`\`), 42
- `\settabs` (T_EX command), 232
- `\settime`, 83
- setting tab stops, 61
- `\settodepth`, 101, 216
- `\settoheight`, 101, 216
- `\settowidth`, 101, 216
- `\sevenbf` (T_EX command), 233
- `\seveni` (T_EX command), 233
- `\sevetsy` (T_EX command), 233
- `\sffamily`, 37, 226
- shape of type, 36
- `\sharp` (`#`), 43
- `\shortstack`, 123–124, 222
 - `\` in argument, 169
- showidx** package, 75, 179
- `\Sigma` (Σ), 41
- `\sigma` (σ), 41
- sign, minus, 14
- `\signature`, 84
- `\sim` ($\sim$), 43
- `\simeq` ($\simeq$), 43
- simulating typed text, 63–64
- `\sin` ($\sin$), 44
- single quote, 12, 13, 170
- single-column format, 181
- `\sinh` ($\sinh$), 44
- size
 - buffer, 143
 - hash, 143
 - main memory, 143
 - of paper, 177
 - of type, *see* type
 - pool, 144
 - save, 144
- skinny, making things, 129
- skip (T_EX term), 100
- slanted line, minimum size of, 123
- slanted type shape, 37, 226
- slash through symbol, 42
- slide** environment, 81
- slides, 80–84, 228
- slides** document class, 80–84, 176
- SL_TE_X, 228
- slope of line in picture, 122
- `\sloppy`, 94, 214
 - causes underfull `\hbox` message, 147
- sloppypar** environment, 94, 214
 - causes underfull `\hbox` message, 147
- `\slshape`, 37, 226
- small caps type shape, 37, 226
- `\small`, 115, 226
- small2e.tex** file, 2
- `\smallskip`, 216
- `\smallskipamount`, 216
- `\smile` ($\smile$), 43
- source list, 69, 70, 209
- source, bibliographic, 69
- source2e.tex** file, 91
- space, 216–217
 - above displayed formula, 107, 188, 189
 - after punctuation, 14–15, 170, 171
 - after tabbing command, 61
 - around + and –, 48
 - around `\hspace` command, 101
 - around integral sign, 51
 - around square root, 51
 - at beginning or end of output line, 102
 - at top or bottom of page, 102
 - avoiding unwanted, 98, 109
 - below displayed formula, 107, 189
 - between paragraphs, 100, 172

- character, 13
 - at end of line, 19
 - ignored in math mode, 36
 - in command definition, 54
 - in formula, 18
 - in LR mode, 36
 - in `\put` argument, 129
 - in `\typeout` or `\typein` argument, 212
 - multiple, 13, 154
 - not allowed after `\verb` command, 64
 - not allowed in `\end{verbatim}`, 64
 - ending command name with, 16
 - ending line without adding, 33
 - horizontal, *see* horizontal space
 - ignored after command name, 16
 - in array, 45
 - in formula, 50–51
 - intercolumn, *see* intercolumn space
 - interrow, *see* interrow space
 - interword, *see* interword space
 - medium, 51, 191
 - negative thin, 51, 191
 - thick, 51, 191
 - thin, 14, 33, 51, 170, 191
 - vertical, *see* vertical space
- `\space`, 212
- space-filling dots, 102
- space-filling horizontal line, 102
- spacing, 101–103
 - command, 170
 - double, 172
- `\spadesuit` ($\spadesuit$), 43
- special character, 12, 32, 171
 - in `\index` argument, 75, 153
 - in `verbatim` environment, 64
 - used incorrectly, 31
- special font, 116
- special symbol, 38–39, 226
- `\sqcap` ($\sqcap$), 42
- `\sqcup` ($\sqcup$), 42
- `\sqrt` ($\sqrt{}$), 40, 51, 189
- `\sqsubset` ($\sqsubset$), 43
- `\sqsubseteq` ($\sqsubseteq$), 43
- `\sqsupset` ($\sqsupset$), 43
- `\sqsupseteq` ($\sqsupseteq$), 43
- square bracket, 12
 - enclosing optional argument, 20, 33, 166
 - mistaken for optional argument, 142
- square root, 40, 189
 - space around, 51
- `\ss` ($\ss$), 39
- stack, 123–124
- stacking symbols, 50
- `\stackrel`, 50, 191
 - making symbol with, 42
- `\star` ($\star$), 42
- `\stepcounter`, 195
 - resets counter, 194
- `\stop`, 30
 - last page produced by, 136
- stopping L^AT_EX, 30, 136
- storage bin, 107, 127
- `\stretch`, 215
- stretchable length, *see* rubber length
- structure
 - logical, 6, 88
 - of document, 170
 - section, 21
 - theorem-like, 56–57
- strut, 106
 - example of use, 110
 - in array and `tabular` environments, 169
- stupidity, in Unix, 32
- `sty` (package) file, 91, 166
 - @ regarded as letter in, 91
 - missing, 137
- style
 - bibliography, 70–71
 - customizing, 91–93
 - math, *see* math
 - numbering, 98
 - page, *see* page
 - parameter, 166
 - type, *see* type
- subentry, index, 75
- `\subitem`, 75, 211
- subparagraph counter, 97
- `\subparagraph`, 21, 174
- subpicture, 128

- subscript, 18, 33, 40, 189
 - double, error, 140
 - math style for, 52, 191
 - of log-like function, 190
 - size of type in, 52, 116
- subsection counter, 97
- `\subsection`, 21, 174
- `\subset` ($\subset$), 43
- `\subseteq` ($\subseteq$), 43
- substituted type style, 37
- subsubentry, index, 75
- `\subsubitem`, 75, 211
- subsubsection counter, 97
- `\subsubsection`, 21, 174
- `\succ` ($\succ$), 43
- `\succeq` ($\succeq$), 43
- `\sum` ($\sum$), 44
- sundial, 94
- `\sup` (sup), 44
 - subscript of, 190
- superscript, 18, 33, 40, 189
 - double, error, 140
 - math style for, 52, 191
 - size of type in, 52, 116
- support, acknowledgment of, 181
- `\suppressfloats`, 199
 - optional argument of, 167
- `\supset` ($\supset$), 43
- `\supseteq` ($\supseteq$), 43
- `\surd` ($\surd$), 43
- `\swarrow` ($\swarrow$), 43
- symbol
 - bar over, 49
 - bold, 51
 - footnote, 195
 - too many, 137
 - making with `array` environment, 42
 - making with `\stackrel`, 42
 - math, 41–45
 - non-English, 38–39
 - in `bib` file, 158
 - nonmath, 38–39
 - not in typewriter style, 38
 - not provided by $\text{\LaTeX}$, 116
 - slash through, 42
 - special, 38–39, 226
 - stacking, 50
 - variable-sized, 42, 52
- `\symbol`, 116, 226
- `t` (top)
 - float specifier, 197
 - oval-part argument, 124, 223
 - positioning argument, 46, 105, 121, 218, 222
- `\t` ($\tilde{}$ accent), 38
- tab overflow error, 139
- tab stop, 61, 201
 - too many, 139
 - undefined, 140
- tab, alignment, error, 141
- `\tabalign` ($\text{\TeX}$ command), 232
- tabbing command
 - Plain $\text{\TeX}$, 232
 - space after, 61
- tabbing environment, 60–62, 201–203
 - `\in`, 169
 - as displayed paragraph, 183
 - example, 202
 - in `minipage` environment, 106, 218
 - in `parbox`, 105
 - large, 143
 - redefinition of commands in, 203
 - scope of declaration in, 61
 - used instead of `verbatim`, 64
 - versus `tabular`, 60
- `\tabbingsep`, 203
- `\tabcolsep`, 207
- table, 58–59, 197–200
 - centering, 112
 - in two-column format, 197
 - item, paragraph in, 104
 - made with `tabular` environment, 58
 - of contents, 66–67, 175–176
 - adding an entry, 175
 - adding commands to, 67, 176
 - depth, 176
 - entry made by sectioning
 - command, 22, 174
 - error in, 135
 - example, 174
 - generated from `toc` file, 209
 - placement of, *see* float
 - too tall, 145

- table counter, 97
- table environment, 58–59, 197
 - in parbox, 138
 - misplaced, 138
 - parbox made by, 104
 - space around, 169
 - too many, 139
- table* environment, 197
- \tableofcontents, 66, 175–176
 - error when processing, 143
 - toc file read by, 209
- tables, list of, 67, 175–176
- \tabs (T_EX command), 232
- \tabdone (T_EX command), 232
- \tabset (T_EX command), 232
- tabular environment, 62–63, 204–207
 - \ in, 169
 - box made by, 103
 - error in, 137, 138, 141, 145
 - example, 204
 - extra space around, 205
 - footnoting item of, 105
 - illegal character in argument, 137
 - in parbox, 218
 - interrow space in, 169
 - large, 143
 - making tables with, 58
 - strut in, 169
 - versus array, 46, 60
 - versus tabbing, 60
- tabular* environment, 204–207
- \tan (tan), 44
- \tanh (tanh), 44
- \tau (τ), 41
- techreport bibliography entry type, 162
- ten-point type, 19, 115
- \teni (T_EX command), 233
- term, invisible, 48
- terminal, 28
 - defining command from, 76
 - input, 76–77, 212–213
 - message, spaces in, 212
 - output, 76–77, 212–213
 - written on log file, 208
 - printing command on, 212
- T_EX, 5, 231–233
 - distinguished from L^AT_EX, 5
 - error message, 140–145
 - error versus L^AT_EX error, 29
 - logo, 5, 15, 33, 171
 - pronunciation of, 5
 - warning message, 147
- \TeX, 15, 33, 171
- text
 - editor, 12, 32
 - emphasized, 16, 171
 - file, 12, 144
 - invisible, 82, 97
 - math style, 52, 187
 - positioning of, 107, 121
 - typed, simulating, 63–64
- text-generating command, 15
- \textbf, 37, 226
- \textcolor, 131, 225
 - used for invisible text in slide, 82
- \textfloatsep, 200
- \textfraction, 200
- \textheight, 100, 182
- \textit, 37, 226
- \textmd, 37, 226
- \textnormal, 226
- \textrm, 37, 226
- \textsc, 37, 226
- \textsf, 37, 226
- \textsl, 37, 226
- \textstyle, 52, 191
 - used with \stackrel, 50
- \texttt, 37, 226
- \textup, 37, 226
- \textwidth, 100, 171, 182
- \thanks, 181
 - moving argument of, 168
- \the... numbering commands, 98, 195
- thebibliography environment, 71–72, 209
 - as list, 112
 - missing argument in, 138
- theindex environment, 75–76, 211
 - \item in, 75
- theorem, 56
 - named, 57
- theorem-like environment, 56–57, 193–194
 - as displayed paragraph, 183

- as list, 112
- counter for, 97, 193
- cross-reference to, 68
- theorem-like structure, 56–57
- `\the page` redefined by `\pagenumbering`, 180
- `\Theta` (Θ), 41
- `\theta` (θ), 41
- thick space, 51, 191
- `\thicklines`, 119, 223
- thickness, *see* width
- thin space, 14, 33, 51, 170, 191
- thin, making things, 129
- `\thinlines`, 118, 223
- `\thispagestyle`, 89–90, 179
 - scope of, 168
- tick marks, 184
- tilde ($\sim$), 12, 17, 32
- `\tilde` ($\sim$ math accent), 50
- time, printing on notes, 83
- `\times` ($\times$), 42
- `\tiny`, 115, 226
- title, 20–21
 - acknowledgment of support in, 181
 - author's address in, 181
 - date in, 20
 - example, 183
 - in bib file, 158
 - page, 20–21, 88, 90, 177, 181–183
- title field (in bib file), 163
- `\title`, 20, 34, 181
 - `\` in, 169
 - not given error, 138
- `\titlepage` document-class option, 88, 90, 177
- `\titlepage` environment, 90, 183
 - making blank page with, 180
- toc (table of contents) file, 66, 67, 175, 209
 - editing, 67
 - error in, 135
- `\tocdepth` counter, 176
- `\today`, 15, 33, 171
 - in title page, 90
 - redefining in letters, 86
- `\top` ($\top$), 43
- `\topfraction`, 199
- `\topins` (TeX command), 232
- `\topinsert` (TeX command), 232
- `\topmargin`, 182
- topnumber counter, 199
- `\topsep`, 113, 185
 - in fleqn option, 188, 189
- `\topskip`, 181
- `\totalheight`, 219
- totalnumber counter, 200
- Trahsion des Images, La, 131
- transformation, geometric, 129
- `\triangle` ($\triangle$), 43
- `\triangleleft` ($\triangleleft$), 42
- `\triangleright` ($\triangleright$), 42
- trivlist environment, 112, 115, 186
- Truman, Harry, 24
- `\ttfamily`, 37, 226
- 12pt document-class option, 19
- twelve-point type, 19, 115
- two-column format, 20, 88, 180
 - `\cleardoublepage` in, 97
 - `\clearpage` in, 97
 - figures and tables in, 197
 - marginal notes in, 59
 - `\newpage` in, 97
 - `\pagebreak` in, 97
- two-sided printing, 19, 177
 - increasing page height in, 214
 - marginal notes in, 59
 - page heading in, 89
- `\twocolumn` document-class option, 20, 177
 - marginal notes in, 59
- `\twocolumn`, 88, 180
 - optional argument of, 167
 - optional argument too tall, 146
- `\twoside` document-class option, 19, 177
 - default in book class, 80
 - evens page bottoms, 88
 - marginal notes in, 59
 - page heading in, 90
- type
 - bibliography entry, 156, 160–162
 - eleven-point, 19, 115
 - family, 36
 - roman, 37, 51, 191, 226
 - sans serif, 37, 51, 191, 226

- typewriter, 37, 51, 191, 226
- font, *see* font
- series, 36
 - boldface, 37, 51, 191, 226
 - medium, 37, 226
- shape, 36
 - italic, 37, 51, 191, 226
 - slanted, 37, 226
 - small caps, 37, 226
 - upright, 37, 226
- size, 226
 - changing, 115–116
 - default, 115
 - in footnote, 116
 - of sub- and superscripts, 52, 116
- style, 36–37, 225–226
 - calligraphic, 51, 191
 - in math mode, 51–52, 191
 - substituted, 37
 - unavailable, 37, 116
- ten-point, 19, 115
- twelve-point, 19, 115
- type field (in bib file), 164
- typed text, simulating, 63–64
- `\typein`, 76, 212
 - moving argument of, 77, 168
 - of `\includeonly`, 74
- `\typeout`, 76, 212
 - moving argument of, 77, 168
- typesetter, 6
- typewriter type family, 37, 226
 - in math mode, 51, 191
 - no accents or symbols in, 38
- typewriter, simulating, 63–64
- typing, saving, 54
- typographic
 - design, 91
 - designer, 5
 - error, 91
- `\u` ($\sim$ accent), 38
- unary + and –, 48
- unavailable type style, 37, 116
- unbalanced braces, error caused by, 136
- `\unboldmath`, 191
- undefined
 - citation, 145, 147
 - color, 140
 - color model, 140
 - control sequence error, 144
 - environment error, 137
 - `\pageref`, 146
 - `\ref`, 146
 - reference, 146, 147
 - tab position, 140
- `\underbrace`, 49
- underfull `\hbox` message, 95, 147
 - caused by `\\` and `\newline`, 213
 - caused by `\linebreak`, 147, 213
 - caused by `\sloppy`, 147, 214
 - caused by `\sloppypar`, 147
- underfull `\vbox` message, 147
 - caused by `\pagebreak`, 214
- `\underline`, 49, 190
- underlining, 49, 190
- unit
 - length, 118
 - of length, 215
 - of measure, illegal, 141
 - paragraph, 94
 - sectional, *see* sectional unit
- `\unitlength`, 118, 219
 - for subpictures, 129
- Unix, e-mail in, 32
- Unix, stupidity in, 32
- unknown graphics extension, 140
- unknown option, 140
- `\unlhd` ($\triangleleft$), 42
- unmatched
 - `$` (dollar sign), 141
 - `}`, 141
 - `\begin`, 136
 - brace, 31
 - `\end`, 136
 - math mode delimiter, 141
 - `\poptabs`, 138
 - `\pushtabs`, 138
- unpublished bibliography entry type, 162
- `\unrhd` ($\triangleright$), 42
- unsrt bibliography style, 70
- `\Uparrow` ($\Uparrow$), 43, 47
- `\uparrow` ($\Uparrow$), 43, 47
- `\Updownarrow` ($\Updownarrow$), 43, 47

- `\updownarrow` ($\updownarrow$), 43, 47
- `\uplus` ($\uplus$), 42
- uppercase letter, 12
- upright type shape, 37, 226
- `\upshape`, 37, 226
- `\Upsilon` (Υ), 41
- `\upsilon` (υ), 41
- use doesn't match definition error, 145
- `\usebox`, 107, 218
- `\usecounter`, 114, 186
- `\usepackage`, 20, 34, 170, 178–179
 - misplaced, 136
 - missing, 144
 - option obtained from `\documentclass` command, 178
 - redundant, 138
- user-defined command or environment,
 - scope in argument of, 55, 56, 192
- `\v` ($\sim$ accent), 38
- value of counter, 194
- `\value`, 194
 - in `ifthen` package expression, 195
- van Leunen, Mary-Claire, 8
- `\varepsilon` (ε), 41
- variable-sized math symbol, 42, 52
- variant Greek letters, 41
- `\varphi` (φ), 41
- `\varpi` (ϖ), 41
- `\varrho` (ϱ), 41
- `\varsigma` (ς), 41
- `\vartheta` (ϑ), 41
- `\vbox`, overfull, 147
- `\vbox`, underfull, 147, 214
- `\vdash` ($\vdash$), 43
- `\vdots` ($\vdots$), 41, 189
- `\vec` ($\sim$ math accent), 50
- `\vector`, 123, 222
 - error in, 136
- `\vee` ($\vee$), 42
- `\verb`, 64, 187
 - in argument of a command, 140
 - text ended by end of line, 140
- `\verb*`, 64, 187
- `verbatim` environment, 63–64, 186
- `verbatim*` environment, 64, 186
- `verse` environment, 25–26, 34, 184
 - `\` in, 169
 - as list, 112
- version, of $\text{\LaTeX}$, 2, 228–229
- `\Vert` ($\|$), 43, 47
- `\vert` ($|$), 47
- vertical
 - alignment, 46, 60–63, 201–207
 - ellipsis, 40, 189
 - line
 - drawn with `\rule`, 106
 - in `tabular` environment, 62
 - mode, 36
 - positioning
 - of `array` environment, 46
 - of array item, 46
 - of text, 107, 121, 219
 - space, 102
 - above displayed formula, 188, 189, 218
 - adding, 106, 216
 - at top or bottom of page, 102
 - below displayed formula, 183, 189
 - in math formula, 106
- `\vfill`, 102
- `\vfootnote` ($\text{\TeX}$ command), 232
- visual design, 7, 88
 - of marginal notes, 60
- visual formatting, 64
 - for slides, 81
 - of formula, 49, 52
 - with boxes, 108–111
- visual property, 37
- `\vline`, 206
- volume field (in `bib` file), 164
- `\vspace`, 102, 216
 - in figure, 58
 - removing space with, 184
 - rubber length in, 102
 - space around, 169
 - using strut instead, 106
- `\vspace*`, 102, 216
- warning message, 30
 - $\text{\LaTeX}$, 145–147
 - $\text{\TeX}$, 147
- `\wedge` ($\wedge$), 42

- `\whiledo`, 197
- white, 132, 225
- wide math accent, 49
- `\widehat` ($\hat{}$ math accent), 49, 190
- `\widetilde` ($\tilde{}$ math accent), 49, 190
- width
 - box with specified, 104
 - of a box, 103
 - of line, 91, 171
 - for `\fbox` and `\framebox`, 219
 - in `array` or `tabular` environment, 207
 - in picture, 118, 223
 - of paragraph indentation, 99
 - of text on page, 100, 171
- `\width`, 219
- Wiles, Andrew, 57
- window, 28
- word, 13
 - index, 150
- `\wp` ($\wp$), 43
- `\wr` ($\wr$), 42
- writing, 8
- wrong number printed by `\cite`,
`\pageref`, and `\ref`, 146
- WYSIWYG, 7
- `\Xi` (Ξ), 41
- `\xi` (ξ), 41
- year field (in bib file), 164
- yellow, 132, 225
- zero (0), 12
- zero length, 99
- zero-length arrow, 123
- zero-width box, 121
- `\zeta` (ζ), 41

Sentences and Paragraphs

quotes single '...' double "..."

dashes intra-word - number range: --
punctuation: ---

spacing small \, inter-word _ unbreak-
able ~ sentence-ending period \@.

special characters \$ \\$ & \& % \%

\# { \{ } \} - _

emphasis \emph{...}

unbreakable text \mbox{...}

footnotes \footnote{...}

date \today

Type Style

\textrm{...} Rom \textsc{...} CAPS
\textit{...} Ital \texttt{...} Type
\textbf{...} Bold \textsf{...} SSrf
\textsl{...} Slan

\boldmath use bold math symbols

in math mode

\mathrm{...} Rom \mathtt{...} Type
\mathit{...} Ital \mathsf{...} SSrf
\mathbf{...} Bold \mathcal{...} CAL

Type Size

\tiny \small \large \huge
\scriptsize \normalsize \Large \Huge
\footnotesize \LARGE

Accents and Symbols

ò \~{o} õ \v{o} q \c{o}
ó \^{'o} ô \={o} õ \H{o} q \d{o}
ô \^~{o} ô \. {o} õ \t{oo} q \b{o}
ö \"{o} ö \u{o}

† \dag § \S © \copyright
‡ \ddag ¶ \P £ \pounds

Sectioning and Table of Contents

\part \section \paragraph
\chapter \subsection \subparagraph
\subsubsection

\appendix start appendix

\tableofcontents make table of contents

Mathematical Formulas

\$. . \$ or \(\dots\) in-text formula
\[...\] displayed formula
\begin{equation} ... \end{equation}
numbered equation
\begin{eqnarray} ... \end{eqnarray}
numbered equations, like 3-column array en-
vironment; \nonumber omits one equation
number, eqnarray* omits all

_ {...} subscript
^ {...} superscript
' prime (')

\frac{n}{d} print fraction $\frac{n}{d}$
\sqrt[n]{arg} print $\sqrt[n]{arg}$
ellipsis \ldots \cdots \vdots
symbols see Tables 3.4–3.8 (pp. 42–44)
Greek letters α \alpha ... Ω \Omega
delimiters \left or \right followed by delim-
iter from Table 3.10 (p. 47)
\overline{exp} print $\overline{exp}$
space thin \, medium \: thick \; neg-
ative thin \!

Displayed Paragraphs

\begin{quote} ... \end{quote}
short displayed quotation
\begin{quotation} ... \end{quotation}
long displayed quotation
\begin{center} ... \end{center}
centered lines, separated by \\
\begin{verse} ... \end{verse}
\\ between lines, blank line between stanzas
\begin{verbatim} ... \end{verbatim}
in typewriter font exactly as formatted

Lists

Begin each item with \item or \item[label]
\begin{itemize} ... \end{itemize}
“ticked” items
\begin{enumerate} ... \end{enumerate}
numbered items
\begin{description} ... \end{description}
labeled items

Document Class, Packages, Styles

\documentclass[options]{class}

style article report book
slides letter (for letters)

options 11pt titlepage twoside leqno
12pt twocolumn a4paper fleqn

\usepackage[options]{pkg}

pkg amstex color latexsym
babel graphics makeidx

\pagestyle{style} style of head and foot:
plain empty headings myheadings

\pagenumbering{style} style of page numbers:
arabic roman alph Roman Alph

Title Page and Abstract

\maketitle make title with information declared
by \title, \author, and [optional] \date
\begin{titlepage} ... \end{titlepage}
do-it-yourself title page
\begin{abstract} ... \end{abstract}
make abstract

Cross-Reference

\label{key} assign current counter value to key
\ref{key} print value assigned to key

Bibliography and Citation

\bibliography{...} make bibliography and tell
BIBTEX names of bib files
\begin{thebibliography}{lbl} ... \end{...}
make bibliography; lbl is widest entry label
\bibitem[lbl]{key} begin bibliography entry for
citation key [with lbl as label]
\cite[note]{keys} cite reference(s) keys [with
added note]

Splitting the Input

\input{file} read specified file
\include{file} read specified file unless excluded
by \includeonly
\includeonly{files} exclude any file not in files
\begin{filecontents}{file} contents \end{...}
write contents on specified file

Line Breaking

`\linebreak` force a line break

`\[len]` start new line and leave *len* vertical space

`\-` permit hyphenation

`\begin{sloppypar} ... \end{sloppypar}`
allow loose lines in paragraphs

`\sloppy` allow loose lines

Page Breaking

`\pagebreak` force a page break

`\enlargethispage*{ht}` squeezes extra *ht* of text on current page.

`\newpage` start a new page

`\clearpage` print all figures and tables and start a new page

Boxes

`\mbox{...}`

`\makebox[wd][pos]{...}`
make box of width *wd*; *pos* puts text at left (l), right (r), or center (default)

`\fbox{text}`

`\framebox[wd][pos]{text}`
same as `\mbox` or `\makebox` but draws frame around box

`\newsavebox{cmd}` defines *cmd* to be a bin for saving boxes

`\sbox{cmd}{text}`

`\savebox{cmd}[wd][pos]{text}`
same as `\mbox` or `\makebox` but saves box in bin *cmd*

`\usebox{cmd}` print box saved in bin *cmd*

`\begin{minipage}[pos]{wd} ... \end{...}`
make parbox of width *wd*, aligned by *pos* at top (t), bottom (b), or center (default) line

`\parbox[pos]{wd}{...}` same as `minipage` for small text, no displayed environments

Space

`\hspace{len}` make *len* horizontal space; *-form works even at beginning of line

`\hfill` make infinitely stretchable horizontal space

`\vspace{len}` leave *len* vertical space; *-form works even at beginning of page

Length

units cm em ex in pc pt mm

`\newlength{cmd}` define *cmd* to be a length

`\setlength{cmd}{len}` set length *cmd* to *len*

`\addtolength{cmd}{len}` add *len* to length *cmd*

Pictures

`\begin{picture}(x,y)(x',y') ... \end{...}`
x × *y* picture [lower-left corner at (*x'*, *y'*)]

`\put(x,y){...}` put object at point (*x*, *y*)

`\multiput(x,y)(Δx,Δy){n}{...}`
make *n* copies of object with first at (*x*, *y*) and others offset by (*Δx*, *Δy*)

`\makebox(x,y)[pos]{...}` make *x* × *y* box; *pos* puts object at top (t), bottom (b), left (l), right (r), and/or centered (default); `\framebox` and `\savebox` have analogs

`\dashbox{d}(x,y)[pos]{...}` like `\makebox` but puts dashed lines of length *d* around box

`\line(h,v){l}` line of slope *v/h* and horizontal extent *l* (length *l* if *h* = 0), $0 \leq h, v \leq 6$

`\vector(h,v){l}` same as `\line` but draws arrowhead; $0 \leq h, v \leq 4$

`\shortstack[pos]{...}`
like `\begin{tabular}[pos] ...`

`\circle{d}` draw circle of diameter *d*; *-form draws solid disk

`\oval(x,y)[part]` draw *x* × *y* [partial] oval

`\frame{...}` draw frame around object

line thickness `\thinlines` or `\thicklines`

graphics and color Packages

`\scalebox{fac}{...}` scale by factor of *fac*

`\resizebox[wd]{ht}{...}` scale to *wd* × *ht*

`\rotatebox{ang}{...}` rotate by *ang* degrees

`\includegraphics{file}` insert graphics from file

`\definecolor{clr}{mdl}{val}` define color *clr* using color model *mdl*

`\color{clr}` set current color to *clr*

`\textcolor{clr}{...}` typeset in color *clr*

`\colorbox{clr}{...}` typeset on colored box

`\pagecolor{clr}` set background color of page

Figures and Tables

`\begin{figure} ... \end{figure}`
make floating figure

`\begin{table} ... \end{table}`
make floating table

`\caption{...}` make figure or table caption

tabbing Environment

Rows separated by `\\`; columns determined by:

`\=` set tab stop

`\>` go to next tab stop

`\kill` throw away line

array and tabular Environments

`\begin{array}[pos]{cols} ... \end{array}`

`\begin{tabular}[pos]{cols} ... \end{tabular}`
use `array` for formulas, `tabular` for text; items separated by `&` and rows by `\\`; *pos* aligns with top (t), bottom (b), or center (default); *cols* entries format columns:

l left-justified column

r right-justified column

c centered column

| vertical rule

@{...} text or space between columns

*{n}{...} equivalent to *n* copies of ...

`\multicolumn{n}{col}{...}` span next *n* columns with *col* format

`\hline` draw horizontal line between rows

`\cline{i-j}` horizontal line across columns *i-j*

Definitions

`\newcommand{cmd}[n][opt]{...}` define command *cmd* [with *n* arguments] [first optional]

`\newenvironment{nam}[n]{beg}{end}`
define environment *nam* [with *n* arguments]

`\newtheorem{nam}{cap}` define a theorem-like environment *nam* captioned by *cap*

Numbering

`\setcounter{ctr}{n}` set counter *ctr* to *n*

`\addtocounter{ctr}{n}` add *n* to counter *ctr*

**A Document Preparation System
Second Edition****Leslie Lamport***Digital Equipment Corporation*

L^AT_EX is a software system for typesetting documents. Because it is especially good for technical documents and is available for almost any computer system, L^AT_EX has become a *lingua franca* of the scientific world. Researchers, educators, and students in universities, as well as scientists in industry, use L^AT_EX to produce professionally formatted papers, proposals, and books. They also use L^AT_EX input to communicate information electronically to their colleagues around the world.


With the release of L^AT_EX 2_ε, the new standard version, L^AT_EX has become even more powerful. Among its new features are an improved method for handling different styles of type, and commands for including graphics and producing colors. L^AT_EX 2_ε makes available to *all* L^AT_EX users valuable enhancements to the software that have been developed over the years by users in many different places to satisfy a variety of needs.

This book, written by the original architect and implementer of L^AT_EX, is both the user's guide and the reference manual for the software. It has been updated to reflect the changes in the new release. The book begins with instructions for formatting simpler text, and progressively describes commands and techniques for handling larger and more complicated documents. A separate chapter explains how to deal with errors. An added appendix describes what is new and different in L^AT_EX 2_ε. Other additions to the second edition include:

- Descriptions of new commands for inserting pictures prepared with other programs and for producing colored output;
- New sections on how to make books and slides;
- Instructions for making an index with the *MakeIndex* program, and an updated guide to preparing a bibliography with the BIB_TE_X program;
- A section on how to send your L^AT_EX documents electronically.

Users new to L^AT_EX will find here a book that has earned worldwide praise as a model for clear, concise, and practical documentation. Experienced users will want to update their L^AT_EX library. Although most standard L^AT_EX input files will work with L^AT_EX 2_ε, to take advantage of the new features, a few L^AT_EX 2_ε conventions must first be learned. For users who want an advanced guide to L^AT_EX 2_ε and to more than 150 packages that can now be used at any site to provide additional features, a useful companion to this book is *The L^AT_EX Companion*, by Goossens, Mittelbach, and Samarin (also published by Addison-Wesley).

Leslie Lamport is a computer scientist well known for his contributions to concurrent computing, as well as for creating the L^AT_EX typesetting system in 1985. He now works at the Systems Research Center of Digital Equipment Corporation. He received a Ph.D. in mathematics from Brandeis University.



9 780201 529838

ISBN 0-201-52983-1

**ADDISON-WESLEY PUBLISHING COMPANY**