# The Elements of Typographic Style

version 3.0

# Robert Bringhurst



# TYPOGRAPHIC STYLE

version 3.0

# Robert Bringhurst

d HARTLEY & MARKS, Publishers

Copyright © 1992, 1996, 2004 by Robert Bringhurst

Version 3.0 ¶ 5 4 3 2 1

All rights reserved. No part of this book may be reproduced in any form or by any means without permission from the publisher (or in the case of photocopying in Canada, without a licence from *Access Copyright*, the Canadian Copyright Licensing Agency). Critics are welcome, of course, to quote brief passages by way of criticism and review.

HARTLEY & MARKS, PUBLISHERS

- PO Box 147
  Point Roberts, wa 98281
- 3661 West Broadway
  Vancouver, BC V 6R 2B8
  Canada

Designed & assembled in Canada; printed & bound in China.

 $\infty$ 

Library of Congress Cataloguing in Publication Data:

Bringhurst, Robert.

The elements of typographic style / Robert Bringhurst. – 3rd ed. p. cm.

Includes bibliographical references and index.

ISBN 0-88179-205-5 -ISBN 0-88179-206-3 (pbk.)

- Graphic design (Typography)
- 2. Type and type-founding.
- 3. Book design.
- 1. Title.

Z246.B74 2004 686.2'24 – dc22

2004053913

National Library of Canada Cataloguing in Publication Data

Bringhurst, Robert, 1946-

The elements of typographic style / Robert Bringhurst. – 3rd ed., expanded and rev.

Includes bibliographical references and index.

ISBN 0-88179-205-5 (bound) – ISBN 0-88179-206-3 (pbk.)

- 1. Layout (Printing)
- 2. Type and type-founding.
- 3. Book design.
- 4. Printing Specimens.
- 1. Title.

Z246.B74 2004 686.2'24 C2004-902010-2 for my colleagues & friends

in the worlds of letters:


writers & editors,


type designers, typographers,

printers & publishers,

shepherding words and books

on their lethal and innocent ways





## CONTENTS

	Foreword 9
	Historical Synopsis 12
1	The Grand Design 17
2	Rhythm & Proportion 25
3	Harmony & Counterpoint 45
4	Structural Forms & Devices 61
5	Analphabetic Symbols 75
6	Choosing & Combining Type 93
7	Historical Interlude 119
8	Shaping the Page 143
9	The State of the Art 179
10	Grooming the Font 198
11	Prowling the Specimen Books 209
	APPENDIX A: The Working Alphabet 288
	APPENDIX B: Glossary of Characters 301
	APPENDIX C: Glossary of Terms 321
	APPENDIX D: Type Designers 333
	APPENDIX E: Typefoundries 346
	Further Reading 357
	Afterword to the Third Edition 365
	Index 367

- Everything written symbols can say has already passed by. They are like tracks left by animals. That is why the masters of meditation refuse to accept that writings are final. The aim is to reach true being by means of those tracks, those letters, those signs but reality itself is not a sign, and it leaves no tracks. It doesn't come to us by way of letters or words. We can go toward it, by following those words and letters back to what they came from. But so long as we are preoccupied with symbols, theories and opinions, we will fail to reach the principle.
- But when we give up symbols and opinions, aren't we left in the utter nothingness of being?
  - Yes.

KIMURA KYŪHO, Kenjutsu Fushigi Hen [On the Mysteries of Swordsmanship], 1768

A true revelation, it seems to me, will only emerge from stubborn concentration on a solitary problem. I am not in league with inventors or adventurers, nor with travelers to exotic destinations. The surest – also the quickest – way to awake the sense of wonder in ourselves is to look intently, undeterred, at a single object. Suddenly, miraculously, it will reveal itself as something we have never seen before.

CESARE PAVESE, Dialoghi con Leucò, 1947

There are many books about typography, and some of them are models of the art they teach. But when I set myself to compile a simple list of working principles, one of the benchmarks I first thought of was William Strunk and E.B. White's small masterpiece, *The Elements of Style*. Brevity, however, is the essence of Strunk & White's manual of literary technique. This book is longer than theirs, and for that there is a cause.

Typography makes at least two kinds of sense, if it makes any sense at all. It makes visual sense and historical sense. The visual side of typography is always on display, and materials for the study of its visual form are many and widespread. The history of letterforms and their usage is visible too, to those with access to manuscripts, inscriptions and old books, but from others it is largely hidden. This book has therefore grown into something more than a short manual of typographic etiquette. It is the fruit of a lot of long walks in the wilderness of letters: in part a pocket field guide to the living wonders that are found there, and in part a meditation on the ecological principles, survival techniques and ethics that apply. The principles of typography as I understand them are not a set of dead conventions but the tribal customs of the magic forest, where ancient voices speak from all directions and new ones move to unremembered forms.

One question, nevertheless, has been often in my mind. When all right-thinking human beings are struggling to remember that other men and women are free to be different, and free to become more different still, how can one honestly write a rulebook? What reason and authority exist for these commandments, suggestions and instructions? Surely typographers, like others, ought to be at liberty to follow or to blaze the trails they choose.

Typography thrives as a shared concern – and there are no paths at all where there are no shared desires and directions. A typographer determined to forge new routes must move, like other solitary travelers, through uninhabited country and against the grain of the land, crossing common thoroughfares in the silence before dawn. The subject of this book is not typographic solitude, but the old, well-traveled roads at the core of the tradition: paths that each of us is free to follow or not, and to enter and leave when we choose – if only we know the paths are there

and have a sense of where they lead. That freedom is denied us if the tradition is concealed or left for dead. Originality is everywhere, but much originality is blocked if the way back to earlier discoveries is cut or overgrown.

Foreword

If you use this book as a guide, by all means leave the road when you wish. That is precisely the use of a road: to reach individually chosen points of departure. By all means break the rules, and break them beautifully, deliberately and well. That is one of the ends for which they exist.

Letterforms change constantly yet differ very little, because they are alive. The principles of typographic clarity have also scarcely altered since the second half of the fifteenth century, when the first books were printed in roman type. Indeed, most of the principles of legibility and design explored in this book were known and used by Egyptian scribes writing hieratic script with reed pens on papyrus in 1000 BC. Samples of their work sit now in museums in Cairo, London and New York, still lively, subtle and perfectly legible thirty centuries after they were made.

Writing systems vary, but a good page is not hard to learn to recognize, whether it comes from Táng Dynasty China, the Egyptian New Kingdom or Renaissance Italy. The principles that unite these distant schools of design are based on the structure and scale of the human body – the eye, the hand and the forearm in particular – and on the invisible but no less real, no less demanding and no less sensuous anatomy of the human mind. I don't like to call these principles universals, because they are largely unique to our species. Dogs and ants, for example, read and write by more chemical means. But the underlying principles of typography are, at any rate, stable enough to weather any number of human fashions and fads.

It is true that typographers' tools are presently changing with considerable force and speed, but this is not a manual in the use of any particular typesetting system or medium. I suppose that most readers of this book will set most of their type in digital form, using computers, but I have no preconceptions about which brands of computers, or which versions of which proprietary software, they may use. The essential elements of style have more to do with the goals typographers set for themselves than with the mutable eccentricities of their tools. Typography itself, in other words, is far more device-independent than PostScript, which is the computer language used to render these particular letters, and the design of these pages, into typographic code. If I have

succeeded in my task, this book should be as useful to artists and antiquarians setting foundry metal by hand and pulling proofs on a flat-bed press, as to those who check their work on a screen or laser printer, then ship it to high-resolution digital output devices by optical disk or long-distance telephone line.

Typography is the craft of endowing human language with a durable visual form, and thus with an independent existence. Its heartwood is calligraphy – the dance, on a tiny stage, of the living, speaking hand – and its roots reach into living soil, though its branches may be hung each year with new machines. So long as the root lives, typography remains a source of true delight, true knowledge, true surprise.

true
and
one

Foreword

As a craft, typography shares a long common boundary and many common concerns with writing and editing on the one side and with graphic design on the other; yet typography itself belongs to neither. This book in its turn is neither a manual of editorial style nor a textbook on design, though it overlaps with both of these concerns. The perspective throughout is first and foremost typographic – and I hope the book will be useful for that very reason to those whose work or interests may be centered in adjacent fields.

This book owes much to the conversation and example, over the years, of several friends and master craftsmen – Kay Amert, Stan Bevington, Crispin Elsted, Glenn Goluska, Peter Koch, Vic Marks, George Payerle and others – and to the practice of two artists and exemplars: the late Adrian Wilson, and Hermann Zapf. Artists and scholars around the world have shared their knowledge freely. James Mosley, his staff and his successors at the St Bride Printing Library, London, have been particularly helpful. I am grateful to them all.

I have many others to thank as well for their contributions to the second and now the third edition of the book. Their names appear in the afterword, page 365.

R.B.

# abpfoe: abpfoe

Historical Synopsis

aperture: the opening in letters such as a, c, e, s

RENAISSANCE (15th & 16th centuries): modulated stroke; humanist [oblique] axis; crisp, pen-formed terminals; large *aperture*; italic equal to and independent of roman.



These charts show first and foremost the axis of the stroke, which is the axis of the pen that makes the letter. It is often very different from the axis of the lettershape itself. A pen that points northwest can make an upright letter or a letter that slopes to the northeast.

BAROQUE (17th century): modulated stroke; variable axis; modeled serifs and terminals; moderate aperture; italic subsidiary to roman and closely linked with it. A secondary vertical axis often develops in Baroque letters – but the *primary* axis of the penstroke is normally oblique.



Historical Synopsis

# abpfor

NEOCLASSICAL (18th century): modulated stroke; rationalist [vertical] axis; refined, *adnate* serifs; *lachrymal* terminals; moderate aperture; italic fully subjugated to roman.

adnate · flowing into the stem; lachrymal: tear-drop shaped




ROMANTIC (18th & 19th centuries): hypermodulated stroke; intensified rationalist axis; abrupt, thin serifs; round terminals; small aperture; fully subjugated italic. In Neoclassical and Romantic letters alike, the *primary* axis is usually vertical and the *secondary* axis oblique.



Historical Synopsis



REALIST (19th & early 20th centuries): unmodulated stroke; implied vertical axis; small aperture; serifs absent or abrupt and of equal weight with main strokes; italic absent or replaced by sloped roman.



GEOMETRIC MODERNIST (20th century): unmodulated stroke; bowls often circular (no axis); moderate aperture; serifs absent or of equal weight with main strokes; italic absent or replaced by sloped roman. The modeling, however, is often much more subtle than it first appears.

# abpfoe-

Historical Synopsis

# abpfoe

LYRICAL MODERNIST (20th century): rediscovery of Renaissance form: modulated stroke; humanist axis; pen-formed serifs and terminals; large aperture; italic partially liberated from roman.



POSTMODERNIST (late 20th & early 21st century): frequent parody of Neoclassical, Romantic or Baroque form: rationalist or variable axis; sharply modeled serifs and terminals; moderate aperture. (There are many kinds of Postmodernist letter. This is one example.)

rigo Habraam numera 1 a mosaica lege(septim r)sed naturali fuit ratio idit enim Habraam dec m quoq3 gentium patr is oés gentes hoc uidelic m est: cuius ille iustitiæ us est: qui post multas imum omnium diuine o nascerétur tradidit: ue gnum: uel ut hoc quas suos imitari conaret: au um nobis modo est. Po

Roman type cut in 1469 by Nicolas Jenson, a French typographer working in Venice. The original is approximately 16 pt. The type is shown here as Jenson printed it, but at twice actual size. This is the ancestor of the type (Bruce Rogers's Centaur) shown at the top of page 12.

### 1.1 FIRST PRINCIPLES

### 1.1.1 Typography exists to honor content.

Like oratory, music, dance, calligraphy – like anything that lends its grace to language – typography is an art that can be deliberately misused. It is a craft by which the meanings of a text (or its absence of meaning) can be clarified, honored and shared, or knowingly disguised.

In a world rife with unsolicited messages, typography must often draw attention to itself before it will be read. Yet in order to be read, it must relinquish the attention it has drawn. Typography with anything to say therefore aspires to a kind of statuesque transparency. Its other traditional goal is durability: not immunity to change, but a clear superiority to fashion. Typography at its best is a visual form of language linking timelessness and time.

One of the principles of durable typography is always legibility; another is something more than legibility: some earned or unearned interest that gives its living energy to the page. It takes various forms and goes by various names, including serenity, liveliness, laughter, grace and joy.

These principles apply, in different ways, to the typography of business cards, instruction sheets and postage stamps, as well as to editions of religious scriptures, literary classics and other books that aspire to join their ranks. Within limits, the same principles apply even to stock market reports, airline schedules, milk cartons, classified ads. But laughter, grace and joy, like legibility itself, all feed on meaning, which the writer, the words and the subject, not the typographer, must generally provide.

In 1770, a bill was introduced in the English Parliament with the following provisions:

... all women of whatever age, rank, profession, or degree, whether virgins, maids, or widows, that shall ... impose upon, seduce, and betray into matrimony, any of His Majesty's subjects, by the scents, paints, cosmetic washes, artificial teeth, false hair, Spanish wool, iron stays, hoops, high heeled shoes [or] bolstered hips shall incur

1

the penalty of the law in force against witchcraft ... and ... the marriage, upon conviction, shall stand null and void.

First Principles The function of typography, as I understand it, is neither to further the power of witches nor to bolster the defences of those, like this unfortunate parliamentarian, who live in terror of being tempted and deceived. The satisfactions of the craft come from elucidating, and perhaps even ennobling, the text, not from deluding the unwary reader by applying scents, paints and iron stays to empty prose. But humble texts, such as classified ads or the telephone directory, may profit as much as anything else from a good typographical bath and a change of clothes. And many a book, like many a warrior or dancer or priest of either sex, may look well with some paint on its face, or indeed with a bone in its nose.

### 1.1.2 Letters have a life and dignity of their own.

Letterforms that honor and elucidate what humans see and say deserve to be honored in their turn. Well-chosen words deserve well-chosen letters; these in their turn deserve to be set with affection, intelligence, knowledge and skill. Typography is a link, and it ought, as a matter of honor, courtesy and pure delight, to be as strong as the others in the chain.

Writing begins with the making of footprints, the leaving of signs. Like speaking, it is a perfectly natural act which humans have carried to complex extremes. The typographer's task has always been to add a somewhat unnatural edge, a protective shell of artificial order, to the power of the writing hand. The tools have altered over the centuries, and the exact degree of unnaturalness desired has varied from place to place and time to time, but the character of the essential transformation between manuscript and type has scarcely changed.

The original purpose of type was simply copying. The job of the typographer was to imitate the scribal hand in a form that permitted exact and fast replication. Dozens, then hundreds, then thousands of copies were printed in less time than a scribe would need to finish one. This excuse for setting texts in type has disappeared. In the age of photolithography, digital scanning and offset printing, it is as easy to print directly from handwritten copy as from text that is typographically composed. Yet the typographer's

18

task is little changed. It is still to give the illusion of superhuman speed and stamina – and of superhuman patience and precision – to the writing hand.

Typography is just that: idealized writing. Writers themselves now rarely have the calligraphic skill of earlier scribes, but they evoke countless versions of ideal script by their varying voices and literary styles. To these blind and often invisible visions, the typographer must respond in visible terms.

The Grand Design

In a badly designed book, the letters mill and stand like starving horses in a field. In a book designed by rote, they sit like stale bread and mutton on the page. In a well-made book, where designer, compositor and printer have all done their jobs, no matter how many thousands of lines and pages they must occupy, the letters are alive. They dance in their seats. Sometimes they rise and dance in the margins and aisles.

Simple as it may sound, the task of creative non-interference with letters is a rewarding and difficult calling. In ideal conditions, it is all that typographers are really asked to do – and it is enough.

### 1.1.3 There is a style beyond style.

Literary style, says Walter Benjamin, "is the power to move freely in the length and breadth of linguistic thinking without slipping into banality." Typographic style, in this large and intelligent sense of the word, does not mean any particular style – my style or your style, or Neoclassical or Baroque style – but the power to move freely through the whole domain of typography, and to function at every step in a way that is graceful and vital instead of banal. It means typography that can walk familiar ground without sliding into platitudes, typography that responds to new conditions with innovative solutions, and typography that does not vex the reader with its own originality in a self-conscious search for praise.

Typography is to literature as musical performance is to composition: an essential act of interpretation, full of endless opportunities for insight or obtuseness. Much typography is far removed from literature, for language has many uses, including packaging and propaganda. Like music, it can be used to manipulate behavior and emotions. But this is not where typographers, musicians or other human beings show us their finest side. Typography at its best is a slow performing art, worthy of the

From part 2 of Benjamin's essay on Karl Kraus, in Illuminationen (Frankfurt, 1955). There is an English translation in Walter Benjamin, Reflections, ed. Peter Demetz (New York, 1978). same informed appreciation that we sometimes give to musical performances, and capable of giving similar nourishment and pleasure in return.

First Principles The same alphabets and page designs can be used for a biography of Mohandas Gandhi and for a manual on the use and deployment of biological weapons. Writing can be used both for love letters and for hate mail, and love letters themselves can be used for manipulation and extortion as well as to bring delight to body and soul. Evidently there is nothing inherently noble and trustworthy in the written or printed word. Yet generations of men and women have turned to writing and printing to house and share their deepest hopes, perceptions, dreams and fears. It is to them, not to the extortionist – nor to the opportunist or the profiteer – that the typographer must answer.

### 1.2 TACTICS

## 1.2.1 Read the text before designing it.

The typographer's one essential task is to interpret and communicate the text. Its tone, its tempo, its logical structure, its physical size, all determine the possibilities of its typographic form. The typographer is to the text as the theatrical director to the script, or the musician to the score.

# 1.2.2 Discover the outer logic of the typography in the inner logic of the text.

A novel often purports to be a seamless river of words from beginning to end, or a series of unnamed scenes. Research papers, textbooks, cookbooks and other works of nonfiction rarely look so smooth. They are often layered with chapter heads, section heads, subheads, block quotations, footnotes, endnotes, lists and illustrative examples. Such features may be obscure in the manuscript, even if they are clear in the author's mind. For the sake of the reader, each requires its own typographic identity and form. Every layer and level of the text must be consistent, distinct, yet (usually) harmonious in form.

The first task of the typographer is therefore to read and understand the text; the second task is to analyze and map it. Only then can typographic interpretation begin.

If the text has many layers or sections, it may need not only

heads and subheads but running heads as well, reappearing on every page or two-page spread, to remind readers which intellectual neighborhood they happen to be visiting.

Novels seldom need such signposts, but they often require typographic markers of other kinds. Peter Matthiessen's novel Far Tortuga (New York, 1975; designed by Kenneth Miyamoto) uses two sizes of type, three different margins, free-floating block paragraphs and other typographic devices to separate thought, speech and action. Ken Kesey's novel Sometimes a Great Notion (New York, 1964) seems to flow like conventional prose, yet it shifts repeatedly in mid-sentence between roman and italic to distinguish what characters say to each other from what they say in silence to themselves.

The Grand Design

In poetry and drama, a larger typographic palette is sometimes required. Some of Douglass Parker's translations from classical Greek and Dennis Tedlock's translations from Zuni use roman, italic, bold, small caps and full caps in various sizes to emulate the dynamic markings of music. Robert Massin's typographic performances of Eugène Ionesco's plays use intersecting lines of type, stretched and melted letters, inkblots, pictograms, and a separate typeface for each person in the play. In the works of other artists such as Guillaume Apollinaire and Guy Davenport, boundaries between author and designer sometimes vanish. Writing merges with typography, and the text becomes its own illustration.

Aristophanes, Four Comedies (Ann Arbor, Michigan, 1969), Dennis Tedlock, Finding the Center (New York, 1972); Eugène Ionesco. La Cantatrice chauve (Paris, 1964), and Délire à deux (Paris, 1966). There are samples of Massin's work in Typographia n.s 11 (1965).

See for example

The typographer must analyze and reveal the inner order of the text, as a musician must reveal the inner order of the music he performs. But the reader, like the listener, should in retrospect be able to close her eyes and see what lies inside the words she has been reading. The typographic performance must reveal, not replace, the inner composition. Typographers, like other artists and craftsmen – musicians, composers and authors as well – must as a rule do their work and disappear.

1.2.3 Make the visible relationship between the text and other elements (photographs, captions, tables, diagrams, notes) a reflection of their real relationship.

If the text is tied to other elements, where do they belong? If there are notes, do they go at the side of the page, the foot of the page, the end of the chapter, the end of the book? If there are photographs or other illustrations, should they be embedded in the text or should they form a special section of their own? And if the photographs have captions or credits or labels, should these sit close beside the photographs or should they be separately housed?

Tactics

If there is more than one text – as in countless publications issued in Canada, Switzerland, Belgium and other multilingual countries – how will the separate but equal texts be arrayed? Will they run side by side to emphasize their equality (and perhaps to share in a single set of illustrations), or will they be printed back-to-back, to emphasize their distinctness?

No matter what their relation to the text, photos or maps must sometimes be grouped apart from it because they require a separate paper or different inks. If this is the case, what typographic cross-references will be required?

These and similar questions, which confront the working typographer on a daily basis, must be answered case by case. The typographic page is a map of the mind; it is frequently also a map of the social order from which it comes. And for better or for worse, minds and social orders change.

1.2.4 Choose a typeface or a group of faces that will honor and elucidate the character of the text.

 $\frac{a \cdot a}{a \cdot a \cdot a}$   $\frac{a \cdot a \cdot a}{a \cdot a \cdot a}$   $\frac{a \cdot a \cdot a}{a \cdot a \cdot a}$ 

aa

a a

This is the beginning, middle and end of the practice of typography: choose and use the type with sensitivity and intelligence. Aspects of this principle are explored throughout this book and considered in detail in chapters 6, 7 and 11.

Letterforms have tone, timbre, character, just as words and sentences do. The moment a text and a typeface are chosen, two streams of thought, two rhythmical systems, two sets of habits, or if you like, two personalities, intersect. They need not live together contentedly forever, but they must not as a rule collide.

The root metaphor of typesetting is that the alphabet (or in Chinese, the entire lexicon) is a system of interchangeable parts. The word *form* can be surgically revised, instead of rewritten, to become the word *farm* or *firm* or *fort* or *fork* or *from*, or with a little more trouble, to become the word *pineapple*. The old compositor's typecase is a partitioned wooden tray holding hundreds of such interchangeable bits of information. These subsemantic particles, these bits – called *sorts* by letterpress printers – are letters cast on standardized bodies of metal, waiting to be assembled into meaningful combinations, then dispersed and reassembled in a

different form. The compositor's typecase is one of the primary ancestors of the computer – and it is no surprise that while typesetting was one of the last crafts to be mechanized, it was one of the first to be computerized.

But the bits of information handled by typographers differ in one essential respect from the computer programmer's bits. Whether the type is set in hard metal by hand, or in softer metal by machine, or in digital form with a computer, every comma, every parenthesis, every *e*, and in context, even every empty space, has style as well as bald symbolic value. Letters are microscopic works of art as well as useful symbols. They mean what they are as well as what they say.

The Grand Design

Typography is the art and craft of handling these doubly meaningful bits of information. A good typographer handles them in intelligent, coherent, sensitive ways. When the type is poorly chosen, what the words say linguistically and what the letters imply visually are disharmonious, dishonest, out of tune.

1.2.5 Shape the page and frame the textblock so that it honors and reveals every element, every relationship between elements, and every logical nuance of the text.

Selecting the shape of the page and placing the type upon it is much like framing and hanging a painting. A cubist painting in an eighteenth-century gilded frame, or a seventeenth-century still-life in a slim chrome box, will look no sillier than a nineteenth-century text from England set in types that come from seventeenth-century France, asymmetrically positioned on a German Modernist page.

If the text is long or the space is short, or if the elements are many, multiple columns may be required. If illustrations and text march side by side, does one take precedence over the other? And does the order or degree of prominence change? Does the text suggest perpetual symmetry, perpetual asymmetry, or something in between?

Again, does the text suggest the continuous unruffled flow of justified prose, or the continued flirtation with order and chaos evoked by flush-left ragged-right composition? (The running heads and sidenotes on the recto (righthand) pages of this book are set flush left, ragged right. On the verso (lefthand) pages, they are ragged left. Leftward-reading alphabets, like Arabic and Hebrew, are perfectly at home in ragged-left text, but with

rightward-reading alphabets like Latin, Greek or Thai, ragged-left setting emphasizes the end, not the beginning, of the line. This makes it a poor choice for extended composition.)

Shaping the page goes hand in hand with choosing the type, and both are permanent typographical preoccupations. The subject of page shapes and proportions is addressed in greater detail in chapter 8.

**Tactics** 

1.2.6 Give full typographic attention even to incidental details.

Some of what a typographer must set, like some of what any musician must play, is simply passage work. Even an edition of Plato or Shakespeare will contain a certain amount of routine text: page numbers, scene numbers, textual notes, the copyright claim, the publisher's name and address, and the hyperbole on the jacket, not to mention the passage work or background writing that is implicit in the text itself. But just as a good musician can make a heart-wrenching ballad from a few banal words and a trivial tune, so the typographer can make poignant and lovely typography from bibliographical paraphernalia and textual chaff. The ability to do so rests on respect for the text as a whole, and on respect for the letters themselves.

Perhaps the principle should read: Give full typographic attention *especially* to incidental details.

### 1.3 SUMMARY

There are always exceptions, always excuses for stunts and surprises. But perhaps we can agree that, as a rule, typography should perform these services for the reader:

- invite the reader into the text:
- reveal the tenor and meaning of the text;
- clarify the structure and the order of the text;
- link the text with other existing elements;
- induce a state of energetic repose, which is the ideal condition for reading.

While serving the reader in this way, typography, like a musical performance or a theatrical production, should serve two other ends. It should honor the text for its own sake – always assuming that the text is worth a typographer's trouble – and it should honor and contribute to its own tradition: that of typography itself.

# 2.1 HORIZONTAL MOTION

An ancient metaphor: thought is a thread, and the raconteur is a spinner of yarns – but the true storyteller, the poet, is a weaver. The scribes made this old and audible abstraction into a new and visible fact. After long practice, their work took on such an even, flexible texture that they called the written page a *textus*, which means cloth.

The typesetting device, whether it happens to be a computer or a composing stick, functions like a loom. And the typographer, like the scribe, normally aims to weave the text as evenly as possible. Good letterforms are designed to give a lively, even texture, but careless spacing of letters, lines and words can tear this fabric apart.

Another ancient metaphor: the density of texture in a written or typeset page is called its *color*. This has nothing to do with red or green ink; it refers only to the darkness or blackness of the letterforms in mass. Once the demands of legibility and logical order are satisfied, *evenness of color* is the typographer's normal aim. And color depends on four things: the design of the type, the spacing between the letters, the spacing between the words, and the spacing between the lines. None is independent of the others.

2.1.1 Define the word space to suit the size and natural letterfit of the font.

Type is normally measured in picas and points (explained in detail on pages 328–329), but horizontal spacing is measured in *ems*, and the em is a sliding measure. One em is a distance equal to the type size. In 6 point type, an em is 6 points; in 12 pt type it is 12 points, and in 60 pt type it is 60 points. Thus a one-em space is *proportionately* the same in any size.

 12 pt em	18 pt em	24 pt em	36 pt em

2

Typesetting machines generally divide the em into units. Ems of 18, 36 or 54 units, for example, are commonly found in the older machines. In newer devices, the em is generally a thousand units. Typographers are more likely to divide the em into simple fractions: half an em, a third of an em, and so on, knowing that the unit value of these fractions will vary from one machine to the next. Half an em is called an *en*.

Horizontal Motion

If text is set ragged right, the word space (the space between words) can be fixed and unchanging. If the text is justified (set flush left and right, like the text in this book), that space must usually be elastic. In either case, the size of the ideal word space varies from one circumstance to another, depending on factors such as letterfit, type color, and size. A loosely fitted or bold face will need a larger interval between the words. At larger sizes, when letterfit is tightened, the spacing of words can be tightened as well. For a normal text face in a normal text size, a typical value for the word space is a quarter of an em, which can be written M/4. (A quarter of an em is typically about the same as, or slightly more than, the set-width of the letter t.)

Language has some effect on the word space as well. In highly inflected languages, such as Latin, most word boundaries are marked by grammatical tags, and a smaller space is therefore sufficient. In English and other uninflected languages, good word spacing makes the difference between a line that has to be deciphered and a line that can be efficiently read.

If the text is justified, a reasonable *minimum* word space is a fifth of an em (M/5), and M/4 is a good average to aim for. A reasonable maximum in justified text is M/2. If it can be held to M/3, so much the better. But for loosely fitted faces, or text set in a small size, M/3 is often a better average to aim for, and a better minimum is M/4. In a line of widely letterspaced capitals, a word space of M/2 or more may be required.

## 2.1.2 Choose a comfortable measure.

Anything from 45 to 75 characters is widely regarded as a satisfactory length of line for a single-column page set in a serifed text face in a text size. The 66-character line (counting both letters and spaces) is widely regarded as ideal. For multiple-column work, a better average is 40 to 50 characters.

If the type is well set and printed, lines of 85 or 90 characters will pose no problem in discontinuous texts, such as bibliogra-



For example, the word space native to the font used here is 227 units wide, or 227 thousandths of an em. The typesetting software is instructed to allow, in the main text, a minimum word space of 85%. That is 193 units: just under a fifth of an em. The maximum word space is set to 150%, which is 340 units: just over a third of

an em.

phies, or, with generous leading, in footnotes. But even with generous leading, a line that averages more than 75 or 80 characters is likely to be too long for continuous reading.

A reasonable working minimum for justified text in English is the 40-character line. Shorter lines may compose perfectly well with sufficient luck and patience, but in the long run, justified lines averaging less than 38 or 40 characters will lead to white acne or pig bristles: a rash of erratic and splotchy word spaces or an epidemic of hyphenation. When the line is short, the text should be set ragged right. In large doses, even ragged-right composition may look anorexic if the line falls below 30 characters, but in small and isolated patches – ragged marginal notes, for example – the minimum line (if the language is English) can be as little as 12 or 15 characters.

ut in
nple
little
llude
plest
one
abet
are
er of
no pt
ngth,
less,

These line lengths are in every case averages, and they include empty spaces and punctuation as well as letters. The simplest way of computing them is with a copyfitting table like the one on page 29. Measure the length of the basic lowercase alphabet – abcdefghijklmnopqrstuvwxyz – in any face and size you are considering, and the table will tell you the average number of characters to expect on a given line. In most text faces, the 10 pt roman alphabet will run between 120 and 140 points in length, but a 10 pt italic alphabet might be 100 points long or even less, while a 10 pt bold might run to 160. The 12 pt alphabet is, of course, about 1.2 times the length of the 10 pt alphabet – but not exactly so unless it is generated from the same master design and the letterfit is unchanged.

On a conventional book page, the measure, or length of line, is usually around 30 times the size of the type, but lines as little as 20 or as much as 40 times the type size fall within the expectable range. If, for example, the type size is 10 pt, the measure might be around  $30 \times 10 = 300$  pt, which is 300/12 = 25 picas. A typical lowercase alphabet length for a 10 pt text font is 128 pt, and the copyfitting table tells us that such a font set to a 25-pica measure will yield roughly 65 characters per line.

# 2.1.3 Set ragged if ragged setting suits the text and the page.

In justified text, there is always a trade-off between evenness of spacing and frequency of hyphenation. The best available compromise will depend on the nature of the text as well as on the specifics of the design. Good compositors like to avoid consecu-

When the counters of the letterforms themselves, not just the spaces between words, are elastic, justification can be carried to greater extremes See pp 190–192

tive hyphenated line-ends, but frequent hyphens are better than sloppy spacing, and ragged setting is better yet.

Narrow measures – which make good justification extremely difficult – are commonly used when the text is set in multiple columns. Setting ragged right under these conditions will lighten the page and decrease its stiffness, as well as preventing an outbreak of hyphenation.

Horizontal Motion

Many unserifed faces look best when set ragged no matter what the length of the measure. And monospaced fonts, which are common on typewriters, always look better set ragged, in standard typewriter style. A typewriter (or a computer-driven printer of similar quality) that justifies its lines in imitation of typesetting is a presumptuous, uneducated machine, mimicking the outward form instead of the inner truth of typography.

When setting ragged text with a computer, take a moment to refine your software's understanding of what constitutes an honest rag. Software is often predisposed to invoke a minimum as well as a maximum line. If permitted to do so, it will hyphenate words and adjust the word spaces regardless of whether it is ragging or justifying the text. Ragged setting with these parameters tends to produce an orderly ripple down the righthand side, making the text look like a neatly pinched piecrust. If that is what you want, fine; but it may not be. Unless the measure is excruciatingly narrow, you may prefer the greater variations of a hard rag. This means fixed word spaces, no minimum line, no letterspacing, and no hyphenation beyond what is inherent in the text. In a hard rag, hyphenated linebreaks may occur in words like selfconsciousness, which are hyphenated anyway, but they cannot occur without manual intervention in words like hyphenation or pseudosophisticated, which aren't.

# 2.1.4 Use a single word space between sentences.

In the nineteenth century, which was a dark and inflationary age in typography and type design, many compositors were encouraged to stuff extra space between sentences. Generations of twentieth-century typists were then taught to do the same, by hitting the spacebar twice after every period. Your typing as well as your typesetting will benefit from unlearning this quaint Victorian habit. As a general rule, no more than a single space is required

12 14 16 18 20 22 24 26 28 30 34 36 

Read down. in the left column: lowercase alphabet length in points. Read across, in the top row: line length in picas.

after a period, a colon or any other mark of punctuation. Larger spaces (e.g., en spaces) are *themselves* punctuation.

The rule is sometimes altered, however, when setting classical Latin and Greek, romanized Sanskrit, phonetics or other kinds of texts in which sentences begin with lowercase letters. In the absence of a capital, a full *en space* (M/2) between sentences may be welcome.

Horizontal Motion

2.1.5 Add little or no space within strings of initials.

Names such as W.B. Yeats and J.C.L. Prillwitz need hair spaces, thin spaces or no spaces at all after the intermediary periods. A normal word space follows the *last* period in the string.

2.1.6 Letterspace all strings of capitals and small caps, and all long strings of digits.

Acronyms such as CIA and PLO are frequent in some texts. So are abbreviations such as CE and BCE or AD and BC. The normal value for letterspacing these sequences of small or full caps is 5% to 10% of the type size. If your software sees the em as 1000 PostScript units, that means 50 to 100 units of letterspacing.

With digital fonts, it is a simple matter to assign extra width to all small capitals, so that letterspacing occurs automatically. The width values of full caps are normally based on the assumption that they will be used in conjunction with the lower case, but letterspacing can still be automated through the use of kerning tables (see pages 33–34).

In titles and headings, extra letterspacing is often desirable. Justified lines of letterspaced capitals are generally set by inserting a normal word space (M/5 to M/4) between letters. This corresponds to letterspacing of 20% to 25% of the type size. But the extra space between letters will also require more space between lines. A Renaissance typographer setting a multi-line head in letterspaced text-size capitals would normally set blanks between the lines: the hand compositor's equivalent of the keyboard operator's extra hard return, or double spacing.

There is no generalized optimum value for letterspacing capitals in titles or display lines. The effective letterspacing of caps in good classical inscriptions and later manuscripts ranges from 5% to 100% of the nominal type size. The quantity of space is far less important than its balance. Sequences like LA or AVA

may need no extra space at all, while sequences like NN and HIH beg to be pried open.

## WAVADOPATTIMMILTL

## WAVADOPATTIMMILTL

Letterspaced caps, above; kerned but unletterspaced, below.

Rhythm and Proportion

Many typographers like to letterspace all strings of numbers as well. Spacing is essential for rapid reading of long, fundamentally meaningless strings, such as serial numbers, and it is helpful even for shorter strings such as phone numbers and dates. Numbers set in pairs need not be letterspaced; strings of three or more may need a little air. This is the rationale behind the old European habit of setting phone numbers in the form oo oo oo instead of ooo-oooo.

### 2.1.7 Don't letterspace the lower case without a reason.

A man who would letterspace lower case would steal sheep, Frederic Goudy liked to say. If this wisdom needs updating, it is chiefly to add that a woman who would letterspace lower case would steal sheep as well.

Nevertheless, like every rule, this one extends only as far as its rationale. The reason for not letterspacing lower case is that it hampers legibility. But there are some lowercase alphabets to which this principle doesn't apply.

Headings set in exaggeratedly letterspaced, condensed, unserifed capitals are now a hallmark, if not a cliché, of postmodern typography. In this context, secondary display can be set perfectly well in more modestly letterspaced, condensed, unserifed lower case. Moderate letterspacing can make a face such as lowercase Univers bold condensed more legible rather than less. Inessential ligatures are, of course, omitted from letterspaced text.

# wharves and wharfingers

Lowercase Univers bold condensed, letterspaced 10%.

It would be possible, in fact, to make a detailed chart of lowercase letterforms, plotting their inherent resistance to letterspacing. Horizontal Motion Near the top of the list (most unsuitable for letterspacing) would be Renaissance italics, such as Arrighi, whose structure strongly implies an actual linkage between one letter and the next. A little farther along would be Renaissance romans. Still farther along, we would find faces like Syntax, which echo the forms of Renaissance roman but lack the serifs. Around the middle of the list, we would find other unserifed faces, such as Helvetica, in which nothing more than wishful thinking bonds the letters to each other. Bold condensed sanserifs would appear at the bottom of the list. Letterspacing will always sabotage a Renaissance roman or italic. But when we come to the other extreme, the faces with no calligraphic flow, letterspacing of lowercase letters can sometimes be of genuine benefit.

Because it isolates the individual elements, letterspacing has a role to play where words have ceased to matter and letters are what count. Where letters function one by one (as in acronyms, web-site and e-mail addresses) letterspacing is likely to help, no matter whether the letters are caps, small caps or lower case.

daß daß Outside the domain of roman and italic type, the letterspacing of text has other traditional functions. Blackletter faces have, as a rule, no companion italic or bold, and no small caps. The simplest methods of emphasis available are underlining and letterspacing. The former was the usual method of the scribes, but letterspacing is easier for letterpress printers. In digitial typography, however, underlining is just as easy as letterspacing and sometimes does less damage to the page.

ЖИ *Ж*И In Cyrillic, the difference between lower case and small caps is more subtle than in the Latin or Greek alphabets, but small caps are nonetheless important to skilled Cyrillic typographers. In former days, when Cyrillic cursive type was scarce and small caps almost nonexistent, Cyrillic was routinely set like fraktur, with letterspaced upright (roman) lower case where the small caps and the cursive (italic) would have been. Improved Cyrillic types have made that practice obsolete.

# 2.1.8 Kern consistently and modestly or not at all.

Inconsistencies in letterfit are inescapable, given the forms of the Latin alphabet, and small irregularities are after all essential to the legibility of roman type. *Kerning* – altering the space between selected pairs of letters – can increase consistency of spacing in a word like Washington or Toronto, where the combinations Wa

and To are kerned. But names like Wisconsin, Tübingen, Tbilisi and Los Alamos, as well as common words like The and This, remain more or less immune to alteration.

Hand compositors rarely kern text sizes, because their kerning pairs must be manually fitted, one at a time. Computerized typesetting makes extensive kerning easy, but judgment is still required, and the computer does not make good judgment any easier to come by. Too little kerning is preferable to too much, and inconsistent kerning is worse than none.

In digital type, as in foundry type, each letter has a standard

and Proportion

Rhythm

width of its own. But computerized typesetting systems can modify these widths in many ways. Digital fonts are generally kerned through the use of *kerning tables*, which can specify a reduction or increase in spacing for every possible pair of letters, numbers or symbols. By this means, space can be automatically added to combinations like HH and removed from combinations like Ty. Prefabricated kerning tables are now routine components of well-made digital fonts, but they still sometimes require extensive editing to suit individual styles and requirements. If you use an automatic kerning program, test it thoroughly before trusting its decisions, and take the time to repair its inevitable shortcomings.

There is more about kerning tables on pp 203–207.

Kerning tables generally subtract space from combinations such as Av, Aw, Ay, 'A, 'A, L', and all combinations in which the first element is T, V, W or Y and the second element is anything other than b, h, k or l. Not all such combinations occur in English, but a good kerning table will accommodate names such as Tchaikovsky, Tmolos, Tsimshian, Vázquez, Chateau d'Yquem and Ysaÿe.

Top

Töpf

Especially at larger sizes, it is common to kern combinations involving commas and periods, such as r, / r. / v, / v. / w, / w. / y, / y. But use care in kerning combinations such as F. / P. / T. / V. Capitals need their space, and some combinations are easy to misread. P.F. Didot may be misread as R E Didot if too enthusiastically kerned.

(f")

w, f'

Numbers are often omitted from kerning tables, but numbers often need more kerning than letters do. Most fonts, both metal and digital, are equipped with *tabular figures* – figures that all have identical set-width, so columns of typeset figures will align. If you are forced to use such a font, heavy kerning will be required. A

good text font will give you *proportional figures* instead. A digital font in the OpenType format may offer you four choices: proportional and tabular lining (titling) figures, and proportional and tabular old-style (text) figures. No matter how the figures are cut, when used in text, they are likely to need some kerning, to each other and to the en dash.

Horizontal Motion

# 1740-1900 1740-1900

Unkerned Sabon numerals, left, and well-kerned numerals, right

Whatever kerning you do, make sure it does not result in collisions with diacritics. Wolf can be kerned more than Wölfflin in many faces, and Tennyson more than Tête-à-tête. Also beware the composite effect of sequential kerns. The apostrophes in L'Hôtel and D'Artagnan can be brought up fairly close, but in L'Anse aux Meadows, two close kerns in a row will produce a collision.

A kerning table written expressly for one language will need subtle alteration before it can do justice to another. In English, for example, it is normal to kern the combinations 'd'm'r's't, which appear in common contractions. In French, 'a' a' e' e' e' e' e' o' o are kerned instead, because these appear in elisions. In Native American texts, apostrophes can appear in many other contexts. For Spanish, one kerns the combinations '¿ and "¿. For German, a careful typographer will take space out of the combinations ,T "T ,V "V "W "W and may add some space to "J and "J.

The letter *c* is not a full-fledged member of the German alphabet, and in former times it was always restricted, in German, to the ligatures *ch* and *ck*. English-speaking readers often find these combinations kerned too close for comfort in German-made fonts – or they find the right sidebearing of the *c* too close-cut to begin with. In fonts from the Netherlands, unusually tight kerning is common in the sequence *ij* instead.

Binomial kerning tables are powerful and useful typographic tools, but they eliminate neither the need nor the pleasure of making final adjustments by hand. Names like T.V.R. Murti and T.R.V. Murti, for example, pose microscopic typographic problems that no binomial kerning table can solve. Fonts with polynomial kerning tables – able to kern a given pair of letters in different ways according to context – have existed for a decade and may someday be the norm. For now, they are a rarity.

'S

a'a

ું.

ck

ij

2.1.9 Don't alter the widths or shapes of letters without cause.

Type design is an art practiced by few and mastered by fewer – but font-editing software makes it possible for anyone to alter in a moment the widths and shapes of letters to which an artist may have devoted decades of study, years of inspiration and a rare concentration of skill. The power to destroy such a type designer's work should be used with caution. And arbitrarily condensing or expanding letterforms is the poorest of all methods for fitting uneditable copy into unalterable space.

Rhythm and Proportion

In many fonts, the exclamation mark, question mark, semicolon and colon need a wider left sidebearing than manufacturers have given them, but the width of any character should be altered for one purpose only: to improve the set of the type.

Typographic letters are made legible not only by their forms and by the color of the ink that prints them but also by the sculpted empty space between and around them. When type is cast and set by hand, that space is physically defined by blocks of metal. When the type is reduced to a *face*, photographically or digitally stored, the letter still has a room of its own, defined by its stated body height and width, but it is a virtual room. In the world of digital type, it is very easy for a designer or compositor with no regard for letters to squish them into cattle trains and ship them to the slaughter.



# letterfit letterfit

When letters are maltreated in this way, their reserve of legibility is sapped. They can do little in their turn except shortchange and brutalize the reader.

2.1.10 Don't stretch the space until it breaks.

Lists, such as contents pages and recipes, are opportunities to build architectural structures in which the space between the elements both separates and binds. The two favorite ways of destroying such an opportunity are setting great chasms of space that the eye cannot leap without help from the hand, and setting unenlightening rows of dots (*dot leaders*, they are called) that force the eye to walk the width of the page like a prisoner being escorted back to its cell.

The following examples show two among many ways of han-

dling a list. Splitting titles and numbers apart, setting one flush left and the other flush right, with or without dot leaders, would only muffle the information:

Introduction 7
Chapter 1 The Sex of Centaurs 11
Chapter 2 Poliphilo's Dream 43

Horizontal Motion

Prologue · page 5
Points of Possible Agreement · page 9
Irreconcilable Differences · page 11
Conclusion · page 163
Index · page 164

### 2.2 VERTICAL MOTION

2.2.1 Choose a basic leading that suits the typeface, text and measure.

Time is divisible into any number of increments. So is space. But for working purposes, time in music is divided into a few proportional intervals: halves, quarters, eighths, sixteenths and so on. And time in most music is measured. Add a quarter note to a bar whose time is already accounted for and, somewhere nearby, the equivalent of that quarter note must come out. Phrasing and rhythm can move in and out of phase – as they do in the singing of Billie Holiday and the trumpet solos of Miles Davis – but the force of blues phrasing and syncopation vanishes if the beat is actually lost.

Space in typography is like time in music. It is infinitely divisible, but a few proportional intervals can be much more useful than a limitless choice of arbitrary quantities.

The metering of horizontal space is accomplished almost unconsciously in typography. You choose and prepare a font, and you choose a measure (the width of the column). When you set the type, the measure fills with the varied rhythm of repeating letter shapes, which are music to the eye.

Vertical space is metered in a different way. You must choose not only the overall measure – the depth of the column or page – but also a basic rhythmical unit. This unit is the leading, which is the distance from one baseline to the next.

Eleven-point type *set solid* is described as 11/11. The theoretical face of the type is 11 points high (from the top of d to the bottom of p, if the type is full on the body), and the distance from the baseline of line one to the baseline of line two is also 11 points. Add two points of lead (interlinear space), and the type is set 11/13. The type size has not changed, but the distance from baseline to baseline has increased to 13 points, and the type has more room to breathe.

Rhythm and Proportion

The text of the book you are reading, to take an example, is set  $10/12 \times 21$ . This means that the type size is 10 pt, the added lead is 2 pt, giving a total leading of 12 pt, and the line length is 21 picas.

A short burst of advertising copy or a title might be set with negative leading (18/15, for example), so long as the ascenders and descenders don't collide:

# this is an example of negative leading

Continuous text is very rarely set with negative leading, and only a few text faces read well when set solid. Most text requires positive leading. Settings such as 9/11, 10/12, 11/13 and 12/15 are routine. Longer measures need more lead than short ones. Dark faces need more lead than light ones. Large-bodied faces need more lead than smaller-bodied ones. Faces like Bauer Bodoni, with substantial color and a rigid vertical axis, need much more lead than faces like Bembo, whose color is light and whose axis is based on the writing hand. And unserifed faces often need more lead (or a shorter line) than their serifed counterparts.

Extra leading is also generally welcome where the text is thickened by superscripts, subscripts, mathematical expressions, or the frequent use of full capitals. A text in German would ideally have a little more lead than the same text in Latin or French, purely because of the increased frequency of capitals.

# 2.2.2 Add and delete vertical space in measured intervals.

For the same reason that the tempo must not change arbitrarily in music, leading must not change arbitrarily in type.

Pages and columns are set most often to uniform depth, but ragged depths are better in some situations. A collection of short

brj erf brj

Bauer Bodoni and Bembo, both set 40/42. texts, such as catalogue entries, set in multiple-column pages, is likely to look better and read more easily if the text is not sawed into columns of uniform depth. A collection of short poems is bound to generate pages of varying depth as well – and so much the better.

Vertical Motion Continuous prose offers no such excuse for variation. It is therefore usually set in pages of uniform depth, designed in symmetrical pairs. The lines and blocks of text on facing pages in this format should align, and the lines on the front and back of the leaf (the recto and verso pages) should align as well. Typographers check their reproduction proofs by holding them up to the light in pairs, to see that the text and crop marks match from page to page. Press proofs are checked in the same way, by holding them up to the light to see that textblocks *back each other up* when the sheet is printed on both sides.

Headings, subheads, block quotations, footnotes, illustrations, captions and other intrusions into the text create syncopations and variations against the base rhythm of regularly leaded lines. These variations can and should add life to the page, but the main text should also return after each variation precisely on beat and in phase. This means that the total amount of vertical space consumed by each departure from the main text should be an even multiple of the basic leading. If the main text runs 11/13, intrusions to the text should equal some multiple of 13 points: 26, 39, 52, 65, 78, 91, 104 and so on.

Subheads in this book are leaded in the simplest possible way, with a *white line* (that is, in keyboard terms, a hard return) before and after. They could just as well be leaded asymmetrically, with more space above than below, so long as the total additional lead is equivalent to an even number of text lines.

If you happen to be setting a text 11/13, subhead possibilities include the following:

- subheads in 11/13 small caps, with 13 pt above the head and 13 pt below;
- subheads in 11/13 bold u&lc (upper and lower case), with 8 pt above the head and 5 pt below, since 8 + 5 = 13;
- subheads in 11/13 caps with 26 pt above and 13 pt below;
- one-line subheads in 14/13 italic u&lc, with 16 pt above the head and 10 pt below. (The negative leading is merely to minimize coding in this case. If the heads are one line long, no cramping will occur.)

### 2.2.3 Don't suffocate the page.

Most books now printed in the Latin alphabet carry from 30 to 45 lines per page. The average length of line in most of those books is 60 to 66 characters. In English and the Romance languages, a word is typically assumed to average five letters plus a space. Ten or eleven such words fit on a line of 60 to 66 characters, and the page, if it is full, holds from 300 to 500 words.

Rhythm and Proportion

Outside these conventional boundaries lie many interesting typographic problems. If the text deserves the honor, a handsome page can be made with very few words. A page with 17 lines of 36 characters each, as an example, will carry only 100 words. At the other extreme, a page with 45 lines of 70 characters each will carry 525 words. If you want more than 500 words to the page, it is time to consider multiple columns. A two-column book page will comfortably carry 750 words. If it must, it can carry a thousand.

However empty or full it may be, the page must breathe, and in a book – that is, in a long text fit for the reader to live in – the page must breathe in both directions. The longer the line, the more space necessary between lines. Two columns of short lines are therefore more compact than a single column of long lines.

### 2.3 BLOCKS & PARAGRAPHS

# 2.3.1 Set opening paragraphs flush left.

The function of a paragraph indent is to mark a pause, setting the paragraph apart from what precedes it. If a paragraph is preceded by a title or subhead, the indent is superfluous and can therefore be omitted, as it is here.

2.3.2 In continuous text, mark all paragraphs after the first with an indent of at least one en.

Typography like other arts, from cooking to choreography, involves a balance between the familiar and the unfamiliar, the dependably consistent and the unforeseen. Typographers generally take pleasure in the unpredictable length of the paragraph while accepting the simple and reassuring consistency of the paragraph indent. The prose paragraph and its verse counterpart, the stanza, are basic units of linguistic thought and literary style. The typographer must articulate them enough to make them clear, yet not

so strongly that the form instead of the content steals the show. If the units of thought, or the boundaries between thoughts, look more important than the thoughts themselves, the typographer has failed.

Ornaments can be placed in the paragraph indents, but few texts actually profit from ornamentation.

Blocks and Paragraphs Paragraphs can also be marked, as this one is, by drop lines, but dropline paragraphs grow tiresome in long texts. They also increase the labor of revisions and corrections. ¶ Pilcrows, boxes and bullets can be used to mark the breaks in a stream of continuous text, sometimes with excellent results. This format is more economical of space than conventional indented paragraphs, but again, extra labor and expense may arise with emendations and corrections.

Outdented paragraphs and indented paragraphs are the two most obvious possibilities that remain. And outdented paragraphs bring with them other possibilities, such as the use of enlarged marginal letters.

All these variants, and others, have their uses, but the plainest, most unmistakable yet unobtrusive way of marking paragraphs is the simple indent: a white square.

How much indent is enough? The most common paragraph indent is one em. Another standard value is *one lead*. If your text is set 11/13, the indent would then be either 11 pt (one em) or 13 pt (one lead). One en (half an em) is the practical minimum.

Where the line is long and margins are ample, an indent of 1½ or 2 ems may look more luxurious than one em, but paragraph indents larger than three ems are generally counterproductive. Short last lines followed by new lines with large indents produce a tattered page.

Block paragraphs open flush left and are separated vertically from their neighbors by extra lead, usually a white line. Block paragraphs are common in business letters and memos, and because they suggest precision, crispness and speed, they can be useful in short documents of other kinds. In longer sequences, they may seem soulless and uninviting.

# 2.3.3 Add extra lead before and after block quotations.

Block quotations (like the one on pp 17–18 of this book) can be distinguished from the main text in many ways. For instance: by

a change of face (usually from roman to italic), by a change in size (as from 11 pt down to 10 pt or 9 pt), or by indention.

Combinations of these methods are often used, but one device is enough. If your paragraph indent is modest, you may for consistency's sake want to use the same indent for quotations. And even if your block quotations are set in a size smaller than normal text, you may want to leave the leading unchanged. If the main text runs 10/12, the block quotations might run 10/12 italic or 9/12 roman. If you prefer greater density or are eager to save space, you might set them 9/11 or 9/10½.

Rhythm and Proportion

However the block quotations are set, there must be a visible distinction between main text and quotation, and again between the quotation and subsequent text. This usually means a white line or half-line at the beginning and end of the block. But if the leading within the block quotation differs from the leading of the main text, these blanks before and after the quotation must be elastic. They afford the only opportunity for bringing the text back into phase.

Suppose your main text is 11/13 and a five-line block quotation set 10/12 intervenes. The depth of the quotation is  $5 \times 12 = 60$ . This must be bulked up to a multiple of 13 to bring the text back into phase. The nearest multiple of 13 is  $5 \times 13 = 65$ . The remaining space is 65 - 60 = 5, and 5/2 = 2.5, which is not enough. Adding 2.5 points before and after the quotation will not give adequate separation. The next multiple of 13 is  $6 \times 13 = 78$ , which is better: 78 - 60 = 18, and 18/2 = 9. Add 9 pt lead before and after the quotation, and the text will realign.

## 2.3.4 Indent or center verse quotations.

Verse is usually set flush left and ragged right, and verse quotations within prose should not be deprived of their chosen form. But to distinguish verse quotations from surrounding prose, they should be indented or centered on the longest line. Centering is preferable when the prose measure is substantially longer than the verse line. The following passage, for example, is centered on the first and longest line.

God guard me from those thoughts men think In the mind alone; He that sings a lasting song Thinks in a marrow bone.

William Butler Yeats, "A Prayer for Old Age." Blocks and Paragraphs Suppose your main text is set on a 24-pica measure and you have decided to set verse quotations in italic at the text size. Suppose that the longest line in your quotation measures 269 points. The indent for this quotation might be computed as follows:  $24 \times 12 = 288$  pt, which is the full prose measure, and 288 - 269 = 19 pt, which is the difference between the measure and the longest verse line. The theoretically perfect left indent for the verse quotation is 19/2 = 9.5 pt. But if another indent close to 9.5 pt is already in use, either for block quotations in prose, or as a paragraph indent, then the verse quotation might just as well be indented to match.

Suppose however that the longest line in the verse is 128 points. The measure, again, is 288 points, and 288 - 128 = 160. Half of 160 is 80 points. No other indent in the vicinity of 80 points is likely to be in use. The verse quotation would then be indented by precisely that amount.

### 2.4 ETIQUETTE OF HYPHENATION & PAGINATION

The rules listed below are traditional craft practice for the setting of justified text. Except for the last rule, they are all programmable, but the operation of these rules necessarily affects the spacing of words and thus the texture and color of the page. If decisions are left to the software, they should be checked by a trained eye – and no typesetting software should be permitted to compress, expand or letterspace the text automatically and arbitrarily as a means of fitting the copy. Copyfitting problems should be solved by creative design, not fobbed off on the reader and the text nor cast like pearls before machines.

For a brief discussion of software justification engines, which now do most of the work, see \$9.4, page 190.

2.4.1 At hyphenated line-ends, leave at least two characters behind and take at least three forward.

Fi-nally is conventionally acceptable line-end hyphenation, but final-ly is not, because it takes too little of the word ahead to the next line.

2.4.2 Avoid leaving the stub-end of a hyphenated word, or any word shorter than four letters, as the last line of a paragraph.

- 2.4.3 Avoid more than three consecutive hyphenated lines.
- 2.4.4 Hyphenate proper names only as a last resort unless they occur with the frequency of common nouns.
- 2.4.5 Hyphenate according to the conventions of the language.

In English we hyphenate *cab-ri-o-let* but in French *ca-brio-let*. The old German rule which hyphenated *Glockenspiel* as *Glok-kenspiel* was changed by law in 1998, but when *össze* is broken in Hungarian, it still turns into *ösz-sze*. In Spanish the double consonants *ll* and *rr* are never divided. (The only permissible hyphenation in the phrase *arroz con pollo* is thus *arroz con po-llo*.) The conventions of each language are a part of its typographic heritage and should normally be followed, even when setting single foreign words or brief quotations.

2.4.6 Link short numerical and mathematical expressions with hard spaces.

All you may see on the keyboard is a space bar, but typographers use several invisible characters: the word space, fixed spaces of various sizes (em space, en space, thin space, figure space, etc) and a hard space or no-break space. The hard space will stretch, like a normal word space, when the line is justified, but it will not convert to a linebreak. Hard spaces are useful for preventing linebreaks within phrases such as  $6.2 \, mm$ ,  $3 \, in.$ ,  $4 \times 4$ , or in phrases like page 3 and chapter 5.

When it is necessary to break longer algebraic or numerical expressions, such as a + b = c, the break should come at the equal sign or another clear logical pause.

- 2.4.7 Avoid beginning more than two consecutive lines with the same word.
- 2.4.8 Never begin a page with the last line of a multi-line paragraph.

The typographic terminology is telling. Isolated lines created when paragraphs *begin* on the *last* line of a page are known as *orphans*. They have no past, but they do have a future, and they

Hart's Rules for Compositors (39th ed, 1983) includes a good, brief guide to hyphenation and punctuation rules for several European languages. Its fat successor, Ritter's Oxford Guide to Style (2002) is more thorough but much less handy. It is always worthwhile, however, to consult a style manual written in and for the language at issue - e.g., for French, the Lexique des règles typographiques en usage à l'imprimerie nationale (Paris, 1990).

need not trouble the typographer. The stub-ends left when paragraphs *end* on the *first* line of a page are called *widows*. They have a past but not a future, and they look foreshortened and forlorn. It is the custom – in most, if not in all, the world's typographic cultures – to give them one additional line for company. This rule is applied in close conjunction with the next.

Etiquette of Hyphenation and Pagination

2.4.9 Balance facing pages by moving single lines.

Pages with more than two columns often look best with the columns set to varying depths. This is the vertical equivalent of ragged-right composition. Where there are only one or two main text columns per page, paired columns and facing pages (except at the end of a chapter or section) are usually set to a uniform depth.

Balance facing pages not by adding extra lead or puffing up the word space, but by exporting or importing single lines to and from the preceding or following spreads. The same technique is used to avoid widows, and to extend or shorten any chapters that would otherwise end with a meager few lines on the final page. But this balancing should be performed with a gentle hand. In the end, no spread of continuous text should have to run more than a single line short or a single line long.

2.4.10 Avoid hyphenated breaks where the text is interrupted.

Style books sometimes insist that both parts of a hyphenated word must occur on the same page: in other words, that the last line on a page must never end with a hyphen. But turning the page is not, in itself, an interruption of the reading process. It is far more important to avoid breaking words in those locations where the reader is likely to be distracted by other information. That is, whenever a map, a chart, a photograph, a pull-quote, a sidebar or other interruption intervenes.

2.4.11 Abandon any and all rules of hyphenation and pagination that fail to serve the needs of the text.

3.1 SIZE

## 3.1.1 Don't compose without a scale.

The simplest scale is a single note, and sticking with a single note draws more attention to other parameters, such as rhythm and inflection. The early Renaissance typographers set each book in a single font – that is, one face in one size – supplemented by hand-drawn or specially engraved large initial letters for the openings of chapters. Their pages show what sensuous evenness of texture and variety of rhythm can be attained with a single font of type: very much greater than on a typewriter, where letters have, more often than not, a single width and a single stroke-weight as well as a single size.

In the sixteenth century, a series of common sizes developed among European typographers, and the series survived with little change and few additions for 400 years. In the early days, the sizes had names rather than numbers, but measured in points, the traditional series is this:

This is the typographic equivalent of the diatonic scale. But modern equipment makes it possible to set, in addition to these sizes, all the sharps and flats and microtonal intervals between. Twenty-point, 22-point, 23-point, and 10½-point type are all available for the asking. The designer can now choose a new scale or tone-row for every piece of work.

These new resources are useful, but rarely all at once. Use the old familiar scale, or use new scales of your own devising, but limit yourself, at first, to a modest set of distinct and related intervals. Start with one size and work slowly from there. In time, the scales you choose, like the faces you choose, will become recognizable features of personal style.

3

of the many older names for type sizes: 6 pt: nonpareil 7 pt:minion 8 pt: brevier or small text 9 pt: bourgeois or galliard 10 pt:long primer or garamond 11 pt:small pica or philosophy 12 pt:pica 14 pt: english or augustin 18 pt: great primer

A few examples

### 3.2 NUMERALS, CAPITALS & SMALL CAPS

3.2.1 Use titling figures with full caps, and text figures in all other circumstances.

Numerals, Capitals and Small Caps So the date is 23 August 1832; it could be 3:00 AM in Apartment 6-B, 213-A Beacon Street; it is 27° C or 81° F; the price is \$47,000 USD or £28,200; the postal codes are NL 1034 WR Amsterdam, SF 00170 Helsinki 17, Honolulu 96814, London WC1 2NN, New Delhi 110 003, Toronto M5S 2G5, and Dublin 2.

## BUT IT IS 1832 AND 81° IN FULL CAPITALS.

1 T T E 0 T V A 9 •

The arabic numerals of Latin script are derived from the Indian numerals of Arabic script (above) Arabic numerals – known in Arabic as Indian numerals, arqām hindiyya, because the Arabs obtained them from India – entered the scribal tradition of Europe in the thirteenth century. Before that (and for many purposes afterward) European scribes used roman numerals, written in capitals when they occurred in the midst of other capitals, and in lowercase in the midst of lowercase letters. Typographers have naturally inherited this custom of setting roman numerals so that they harmonize with the words:

Number xiii lowercase AND XIII UPPERCASE

AND THE NUMBER XIII IN SMALL CAPITALS

and the roman numeral xiii in italic

When arabic numerals joined the roman alphabet, they too were given both lowercase and uppercase forms. Typographers call the former text figures, hanging figures, lowercase figures, or old-style figures (OSF for short) and make a point of using them whenever the surrounding text is set in lowercase letters or small caps. The alternative forms are called titling figures, ranging figures or lining figures, because they range or align with one another and with the upper case.

Text 1234567890 figures
TITLING 1234567890 FIGURES
FIGURES 1234567890 WITH SMALL CAPS

Italic text 1234567890 figures

Text figures were the common form in European typography between 1540 and 1800. But in the mid-eighteenth century, when European shopkeepers and merchants were apt to write more numbers than letters, handwritten numerals developed proportions of their own. These quite literally middle-class figures entered the realm of typography in 1788, when a British punchcutter named Richard Austin cut a font of three-quarter-height lining figures for the founder John Bell.

Harmony and Counterpoint

# Bell letters and 1234567890 figures in roman and 1234567890 in italic

In the nineteenth century, which was not a great age for typography, founders stretched these figures up to cap height, and titling figures became the norm in commercial typography. Renaissance letterforms were revived in the early twentieth century, and text figures found their way back into books. But in news and advertising work, titling figures remained routine. In the 1960s, phototypesetting machines with their truncated fonts once again made text figures difficult to find. The better digital foundries now offer a wide selection of fonts with text figures and small caps. These are often sold separately and involve extra expense, but they are essential to good typography. It is better to have one good face with all its parts, including text figures and small caps, than fifty faces without.

It is true that text figures are rarely useful in classified ads, but they are useful for setting almost everything else, including good magazine and newspaper copy. They are basic parts of typographic speech, and they are a sign of civilization: a sign that dollars are not really twice as important as ideas, and numbers are not afraid to consort on an equal footing with words.

It is also true that a number of excellent text faces, both serifed and unserifed, were originally issued without text figures. Examples include Adrian Frutiger's Méridien, Eric Gill's Gill Sans, Paul Renner's Futura, Hans Eduard Meier's Syntax, Hermann Zapf's Comenius and Optima, and Gudrun Zapf-von Hesse's Carmina. In several of these cases, text figures were part of the original conception or even the finished design but were scuttled by the foundry. Many such missing components have belatedly been issued in digital form. With any text face that is missing text figures, it is reasonable to enquire whether commercial intimidation or, in effect, commercial censorship may not have played a role.

Numerals, Capitals and Small Caps During most of the nineteenth and twentieth centuries, lining figures were widely known as 'modern' and text figures as 'old-style.' Modernism was preached as a sacred duty, and numbers, in a sense, were actually deified. Modernism is nothing if not complex, but its gospel was radical simplicity. Many efforts were made to reduce the Latin alphabet back to a single case. (The telegraph and teletype, with their unicameral alphabets, are also products of that time.) These efforts failed to make much headway where letters were concerned. With numbers, the campaign had considerable success. Typewriters soon came to have letters in both upper and lower case but numbers in upper case alone. And from typewriters have come computer keyboards.

Typographic civilization seems, nonetheless, determined to proceed. Text figures are again a normal part of type design – and have thus been retroactively supplied for faces that were earlier denied them. However common it may be, the use of titling figures in running text is illiterate: it spurns the truth of letters.

3.2.2 For abbreviations and acronyms in the midst of normal text, use spaced small caps.

This is a good rule for just about everything except two-letter geographical acronyms and acronyms that stand for personal names. Thus: 3:00 AM, 3:00 PM, the ninth century CE, 450 BC to AD 450, the OAS and NATO; World War II or WWII; but JFK and Fr J.A.S. O'Brien, OMI; HMS *Hypothesis* and USS *Ticonderoga*; Washington, DC, and Mexico, DF; J.S. Bach's Prelude and Fugue in Bb minor, BWV 867.

Many typographers prefer to use small caps for postal abbreviations (San Francisco, CA 94119), and for geographical acronyms longer than two letters. Thus, the USA, or in Spanish, *los EEUU*, and Sydney, NSW. But the need for consistency intervenes when long and short abbreviations fall together. From the viewpoint of the typographer, small caps are preferable in faces with fine features and small x-height, full caps in faces with large x-height and robust form.

Genuine small caps are not simply shrunken versions of the full caps. They differ from large caps in stroke weight, letterfit, and internal proportions as well as in height. Any good set of small caps is designed as such from the ground up. Thickening, shrinking and squashing the full caps with digital modification routines will only produce a parody.

Sloped small capitals – ABCDEFG – have been designed and cut for relatively few faces in the history of type design. They can be faked with digital machinery, by sloping the roman small caps, but it is better to choose a face (such as this one, Robert Slimbach's Minion) which includes them, or to live without. Sloped (italic) text figures, on the other hand, are part of the basic requirement and are available for most good text fonts.

Harmony and Counterpoint

# 3.2.3 Refer typographic disputes to the higher courts of speech and thinking.

Type is idealized writing, and its normal function is to record idealized speech. Acronyms such as CD and TV or USA and UFO are set in caps because that is the way we pronounce them. Acronyms like UNESCO, ASCII and FORTRAN, which are pronounced not as letters but as words, are in the process of becoming precisely that. When a writer accepts them fully into her speech and urges readers to do likewise, it is time for the typographer to accept them into the common speech of typography by setting them in lower case: Unesco, Ascii (or ascii) and Fortran. Other acronymic words, such as *laser* and *radar*, have long since traveled the same road.

Logograms pose a more difficult question. An increasing number of persons and institutions, from e.e. cummings to WordPerfect, now come to the typographer in search of special treatment. In earlier days it was kings and deities whose agents demanded that their names be written in a larger size or set in a specially ornate typeface; now it is business firms and mass-market products demanding an extra helping of capitals, or a proprietary face, and poets pleading, by contrast, to be left entirely in the vernacular lower case. But type is visible speech, in which gods and men, saints and sinners, poets and business executives are treated fundamentally alike. Typographers, in keeping with the virtue of their trade, honor the stewardship of *texts* and implicitly oppose private ownership of *words*.

Logotypes and logograms push typography in the direction of hieroglyphics, which tend to be looked at rather than read. They also push it toward the realm of candy and drugs, which tend to provoke dependent responses, and away from the realm of food, which tends to promote autonomous being. Good typography is like bread: ready to be admired, appraised and dissected before it is consumed.

3.3.1 Use the ligatures required by the font, and the characters required by the language, in which you are setting type.

In most roman faces the letter f reaches into the space beyond it. In most italics, the f reaches into the space on both sides. Typographers call these overlaps kerns. Only a few kerns, like those in the arm of the f and the tail of the j, are implicit in a normal typefont, while others, like the overlap in the combination To, are optional refinements, independent of the letterforms.

Reaching into the space in front of it, the arm of the f will collide with certain letters – b, f, h, i, j, k, l – and with question marks, quotation marks or parentheses, if these are in its way.

Most of the early European fonts were designed primarily for setting Latin, in which the sequences fb, fh, fj, fk do not occur, but the sequences ff, fi, fl, ffl, ffl are frequent. The same set of ligatures was once sufficient for English, and these five ligatures are standard in traditional roman and italic fonts. As the craft of typography spread through Europe, new regional ligatures were added. An fj and æ were needed in Norway and Denmark for words such as *fjeld* and *fjord* and *nær*. In France an æ, and in Germany an ß (*eszett* or double-s) were required, along with accented and umlauted vowels. Double letters which are read as one – *ll* in Spanish, *ij* in Dutch, and *ch* in German, for example – were cast as single sorts for regional markets. An ffj was needed in Iceland. New individual letters were added, like the Polish ł, the Spanish ñ, and the Danish and Norwegian ø. Purely decorative ligatures were added to many fonts as well.

English continues to absorb and create new words – fjord, gaffhook, halfback, hors d'œuvre – that call for ligatures beyond the Latin list. As an international language, English must also accommodate names like Youngfox, al-Hajji and Asdzáá Yolgai. These sometimes make demands on the roman alphabet which earlier designers didn't foresee. In the digital world, some of these compound characters and ligatures can, in effect, take care of themselves. In text work, there is no burning need for a specially crafted fb or fh ligature when the digital forms can be cleanly superimposed, but in display work, such ligatures can be crucial. Recent type designers, alive to these polylingual demands on the alphabet, have often simplified the problem further by designing faces in which no sequence of letters involves a collision.



ل + I → لا



The lâm-alif ligature above is from Nabih Jaroudi's Yakout Arabic. The pitau, chi-rho and mu-alpha-iota ligatures below are from Matthew Carter's Wilson Greek.



 $\pi + \tau \rightarrow \pi$ 

X+9 → H

 $\mu + \alpha + \iota$   $\rightarrow \mu \alpha \mu$ 

# ææ as &b &t ff ffi ffl fi fl fr ÿ is ll q<sub>8</sub> \$t f&b fb fi fl fb ff f\$ fl fl fl fæ us Æ Œ æ æ æ ß ß ff fi fl ffi ffl ffi ffl &t &t &t fh fi fl fl fb fi fl ff

Top two lines: Ligatures from an italic font cut in the 1650s by Christoffel van Dijck. Lower two lines: Ligatures from Adobe Caslon, a digital face by Carol Twombly, after William Caslon, dating from about 1750. These are Baroque typefaces. As such, they include a set of ligatures with f and a second set formed with the long s (f,f). Long s and its ligatures were normal in European typography until late in the eighteenth century, though fonts designed to do without them were cut as early as the 1640s.

Separation of the letters f and i is sometimes crucial. In Turkish, i with a dot and i without – or in capitals,  $\dot{I}$  and I – are two different letters. To set Turkish well, you need a face whose f is designed so it does not disguise the difference.

This does not do away with the question of the five Latin ligatures. Older typefaces – Bembo, Garamond, Caslon, Baskerville and other distinguished creations – are, thankfully, still with us, in metal and in digital revivals. Many new faces also perpetuate the spirit of these earlier designs. These faces are routinely supplied with the five basic ligatures because they require them. And for digital typographers, software is available that will automatically insert them.



Bembo, set with ligatures (above) and without (below)

If your software is inserting ligatures automatically, take a moment to verify two things: (1) that the software is inserting all the ligatures you want *and* none that you do not want; (2) that all these ligatures are staying where they're put.

Harmony and Counterpoint

St Th

M

Decorative ligatures such as st and Th are now deservedly rare. The ligature fffl is rarer, but it has been cut for at least one typeface (Jonathan Hoefler's Requiem italic) and can be used in at least two words: German Sauerstoffflasche (oxygen bottle) and Sauerstoffflaschenspüler (oxygen bottle washer).

ff

Th

Good OpenType digital fonts usually include the five Latin ligatures (ff, ffi, ffl, fi, fl), and many include the two Scandinavian ligatures (ffi, fi). There may also be a set of ornamentals and archaics (ct, sp, st, Th; fi, fk, fl, ffi, ffl, etc) – and sometimes there are more of these special-purpose ligatures (quaints, as typographers call them) in italic than in roman. Where such a feast of ligatures is present, they are usually divided into classes: basic and discretionary. If your software is conversant with OpenType fonts, it can be told to use the ligatures from either class or from both. But the classes are not always well defined. For now at least, fonts in the 'Adobe Originals' series all have the Th ligature misclassified as basic, not discretionary. Unless you edit the font to fix this error, you cannot get fi, fj, ff and ffi without getting Th also. If you want the Th ligature, this is fine. But Th has a different pedigree than fi and its brethren. Stylistically, it belongs to a different register. These two registers can certainly be paired; they should not be arbitrarily blurred together.

Some software that inserts ligs automatically will also strip them out again as soon as the type is letterspaced. If you let such software justify a text by adding space between the letters, you may find ligatures present in one line and missing in the next. The solution for this is twofold: (1) good software and (2) intelligent justification. Ligatures should go where they are needed and then stay no matter what.

3.3.2 If you wish to avoid ligatures altogether, restrict yourself to faces that don't require them.

It is quite possible to avoid the use of ligatures completely and still set beautiful type. All that is required is a face with non-kerning roman and italic f – and some of the finest twentieth-century faces have been deliberately equipped with just this feature. Aldus, Melior, Mendoza, Palatino, Sabon, Trajanus and Trump Mediäval, for example, all set handsomely without ligatures. Full or partial ligatures do exist for these faces, and the ligatures may add a touch

# fi fi fi fi fi fi fi

Ligatured and unligatured combinations in Sabon (left) and Trump Mediäval (right). In faces such as these, f-ligatures are optional – and in most such faces, only a partial set of ligatures exists.

of refinement – but when ligatures are omitted from these faces, no unsightly collisions occur.

The choice is wider still among sanserifs. Ligatures are important to the design of Eric Gill's Gill Sans, Ronald Arnholm's Legacy Sans, Martin Majoor's Scala Sans and Seria Sans but irrelevant to many unserifed faces. (Dummy ligatures, consisting of separate letters, are usually present on digital versions of those fonts, but using these dummies has no visible effect.)

Harmony and Counterpoint

### 3.4 TRIBAL ALLIANCES & FAMILIES

3.4.1 To the marriage of type and text, both parties bring their cultural presumptions, dreams and family obligations. Accept them.

Each text, each manuscript (and naturally, each language and each alphabet) has its own requirements and expectations. Some types are more adaptable than others in meeting these demands. But typefaces too have their individual habits and presumptions. Many of them, for instance, are rich with historical and regional connections – a subject pursued at greater length in chapter 7. For the moment, consider just the sociology of typefaces. What kinds of families and alliances do they form?

The union of uppercase and lowercase roman letters – in which the upper case has seniority but the lower case has the power – has held firm for twelve centuries. This constitutional monarchy of the alphabet is one of the most durable of European cultural institutions.

Ornamental initials, small caps and arabic figures were early additions to the roman union. Italics were a separate tribe at first, refusing to associate with roman lower case, but forming an alliance of their own with roman (not italic) capitals and small caps. Sloped caps developed only in the sixteenth century. Roman, italic and small caps formed an enlarged tribal alliance at that time, and most text families continue to include them.

Bold and condensed faces became a fashion in the nineteenth century, partially displacing italics and small caps. Bold weights and titling figures have been added retroactively to many earlier faces (Bembo and Centaur for example), though they lack any historical justification. Older text faces, converted from metal to digital form, are usually available in two fundamentally different versions. The better digital foundries supply authentic reconstruc-


Aa
BbB
ccC
Dd
EeEe
Ff

	Primary:	roman lower case	1.1
	Secondary:	Roman Upper Case	2.1
		ROMAN SMALL CAPS	2.2
		roman text figures: 123	2.3
		italic lower case	2.4
Tribal	Tertiary:	True Italic (Cursive) Upper Case & Swash	3.1
Alliances	·	italic text figures: 123	3.2
and		SLOPED SMALL CAPS	3.3
Families		Roman Titling Figures: 123	3.4
		bold lower case	3.5
	Quaternary:	False Italic (Sloped) Upper Case	4.1
	•	<b>Bold Upper Case</b>	4.2
		BOLD SMALL CAPS	4.3
		bold text figures: 123	4.4
		bold italic lower case	4.5
	Quintary:	Italic Titling Figures: 123	5.1
		Bold False Italic (Sloped) Upper Case	5.2
		bold italic text figures: 123	5.3
		<b>Bold Titling Figures: 123</b>	5.4
	Sextary:	Bold Italic Titling Figures: 123	6.1

tions; others supply the fonts without small caps, text figures and other essential components, and usually burden them instead with an inauthentic bold.

Among recent text faces, two basic family structures are now common. The simplified model consists only of roman, italic and titling figures, in a range of weights – light, medium, bold and black, for example. The more elaborate family structure includes small caps and text figures, though these are sometimes present only in the lighter weights.

A family with all these elements forms a hierarchical series, based not on historical seniority but on general adaptability and frequency of use. And the series works the way it does not so much from force of custom as from the force of physiology. The monumentality of the capitals, the loudness of the bold face, the calligraphic flow and (most of the time) slope of italic, stand out effectively against a peaceful, largely perpendicular, roman ground. Reverse the order and the text not only looks peculiar, it causes the reader physical strain.



The chart at left is a grammatical road map of a conventional large family of type. (The heavy rules show the extent of the basic nuclear family.) The typographer can move directly along any of the lines - e.g., from roman lower case to bold lower case or to small or full caps. A sudden shift from roman lower case to bold caps or sloped caps short-circuits the conventions of typographic grammar.

Fonts in each of these categories are called into use, through a surprisingly complex grammar of editorial and typographic rules, by fonts in the category above. The typographer can intervene in this process at will, and alter it to any degree. But good type is good because it has natural strength and beauty. The best results come, as a rule, from finding the best type for the work and then guiding it with the gentlest possible hand.

The standard North American reference on the editorial tradition is the *Chicago Manual of Style*, now in its 15th edition (2003).

# 3.4.2 Don't use a font you don't need.

The marriage of type and text requires courtesy to the in-laws, but it does not mean that all of them ought to move in, nor even that all must come to visit.

Boldface roman type did not exist until the nineteenth century. Bold italic is even more recent. Generations of good typographers were quite content without such variations. Font manufacturers nevertheless now often sell these extra weights as part of a basic package, thereby encouraging typographers – begin-

ners especially – to use bold roman and italic whether they need them or not.

Bold and semibold faces do have their value. They can be used, for instance, to flag items in a list, to set titles and subheads u&lc in small sizes, to mark the opening of the text on a complex page, or to thicken the texture of lines that will be printed in pale ink or as dropouts (negative images) in a colored field. Sparingly used, they can effectively emphasize numbers or words, such as the headwords, keywords and definition numbers in a dictionary. They can also be used (as they often are) to shout at readers, putting them on edge and driving them away; or to destroy the historical integrity of a typeface designed before boldface roman was born; or to create unintentional anachronisms, something like adding a steam engine or a fax machine to the stage set for *King Lear*.

Tribal Alliances and Families

3.4.3 Use sloped romans sparingly and artificially sloped romans more sparingly still.

It is true that most romans are upright and most italics slope to the right – but flow, not slope, is what really differentiates the two. Italics have a more cursive structure than romans, which is to say that italic is closer to longhand or continuous script. Italic serifs are usually *transitive*; they are direct entry and exit strokes, depicting the pen's arrival from the previous letter and its departure for the next. Roman serifs, by contrast, are generally *reflexive*. They show the pen doubling back onto itself, emphasizing the end of the stroke. Italic serifs therefore tend to slope at a natural writing angle, tracing the path from one letter to another. Roman serifs, especially at the baseline, tend to be level, tying the letters not to each other but to an invisible common line.

Some italics are more cursive than others; so are some romans. But any given italic is routinely more cursive than the roman with which it is paired.

# e e l l m m u u

Baskerville roman and italic. Baskerville has less calligraphic flow than most earlier typefaces, but the italic serifs are, like their predecessors, transitive and oblique, showing the path of the pen from letter to letter. The roman serifs are reflexive and level, tying letters to a common line.

Early italic fonts had only modest slope and were designed to be used with upright roman capitals. There are some beautiful fifteenth-century manuscript italics with no slope whatsoever, and some excellent typographic versions, old and new, that slope as little as 2° or 3°. Yet others slope as much as 25°.

Italic and roman lived quite separate lives until the middle of the sixteenth century. Before that date, books were set in either roman or italic, but not in both. In the late Renaissance, typographers began to use the two for different features in the same book. Typically, roman was used for the main text and italic for the preface, headnotes, sidenotes and for verse or block quotations. The custom of combining italic and roman in the same line, using italic to emphasize individual words and mark specific classes of information, developed in the sixteenth century and flowered in the seventeenth. Baroque typographers liked the extra activity this mixing of fonts gave to the page, and the convention proved so useful to editors and authors that no subsequent change of typographic taste has ever driven it entirely away. Modulation between roman and italic is now a basic and routine typographic technique, much the same as modulation in music between major and minor keys. (The system of linked major and minor keys in music is, of course, another Baroque invention.)

Since the seventeenth century, many attempts have been made to curb the cursive, fluid nature of italic and to refashion it on the roman model. Many so-called italics designed in the last two hundred years are actually not italics at all, but sloped romans – otherwise known as *obliques*. And many are hybrids between the two.

As lowercase italic letterforms mutated toward sloped roman, their proportions changed as well. Most italics (though not all) are 5% to 10% narrower than their roman counterparts. But most sloped romans (unless designed by Eric Gill) are as wide or wider than their upright roman companions.

Renaissance italics were designed for continuous reading, and modern italics based on similar principles tend to have similar virtues. Baroque and Neoclassical italics were designed to serve as secondary faces only, and are best left in that role. Sloped romans, as a general rule, are even more devotedly subsidiary faces. They have been with us for ten centuries or more, but have rarely succeeded in rising above the status of calligraphic stunts or short-term perturbations of the upright roman.

Harmony and Counterpoint

In addition to families consisting of upright and sloped roman, there are now several families consisting of upright (or nearly upright) and sloped italic. Hermann Zapf's Zapf Chancery (ITC, 1979) is an example. The 'roman' is an italic with a slope of 4°; the 'italic' is also an italic, but with swash caps and a slope of 14°. Another example is Eaglefeather Informal (see p 271), in which the 'roman' is an italic with a slope of o° and the 'italic' is in essence the same design with a slope of 10°.

adefmpru adefmpru	[19 pt]
2 adefmpru <i>adefmpru</i>	[18 pt]
3 adefmpru adefmpru	[24 pt]
4 adefmpru <i>adefmpru</i>	[18 pt]
5 adefmpru adefmpru	[21 pt]

Tribal Alliances and Families

1 Adrian Frutiger's Méridien roman and *italic*; 2 Lucida Sans roman and *italic*, by Kris Holmes & Charles Bigelow; 3 Perpetua roman and its *italic* – actually a hybridized sloped roman – by Eric Gill; 4 Univers roman and its *oblique* (a pure sloped roman), by Adrian Frutiger; 5 Romulus roman and *oblique* (again a pure sloped roman), by Jan van Krimpen.

Typesetting software is capable of distorting letters in many different ways: condensing, expanding, outlining, shadowing, sloping, and so on. If the only difference between a roman and its companion font were slope, the roman font alone would be enough for the computer. Sloped versions could be generated at will. But italic is not sloped roman, and even a good sloped roman is more than simply roman with a slope.

Direct electronic sloping of letterforms changes the weight of vertical and sloped strokes, while the weight of the horizontal strokes remains the same. Strokes that run northwest-southeast in the parent form – like the right leg of the A or the upper right and lower left corners of the O – are rotated toward the vertical when the letter is given a slope. Rotation toward the vertical causes these strokes to thicken. But strokes running northeast-southwest, like the left leg of the A, and the other corners of the O, are rotated farther away from the vertical. Rotation away from the vertical thins them down. Stroke curvature is altered in this translation process as well. The natural inclinations of a calligrapher drawing a sloped roman differ from what is convenient for the machine. Even 'italic' capitals – which nowadays are rarely anything except sloped roman – require individual shaping and editing to reach a durable form.

Through the collaborative efforts of calligraphers, typographers and engineers, software for the design and editing of typographic letterforms continues to improve. As it does, it continues

to mimic more and more closely those subtle and primitive tools that lie at the root of all typography: the stick, the brush, the chisel and the broadnib pen. Rules for transforming roman into good sloped roman forms, instead of into parodies, can surely be derived through close analysis of what the best scribes do. When parts of the procedure can be stated with mechanical precision, they can also be entrusted to machines. But rules for translating roman into *italic* cannot be stated clearly because no such rules exist. The two kinds of letterform have different genealogies, like apples and bananas. They form a common heritage and share an evolutionary source, yet neither one is a direct modification of the other.

Harmony and Counterpoint

# AAAOOO

Adobe Caslon roman, the same roman sloped electronically, and the true 'italic' capitals as drawn. Caslon italics have an average slope of 20°.

# aaa ooo

Palatino roman, the same roman sloped electronically, and the genuine italic, whose average slope is 9°.

# $\mathcal{A} \in \mathcal{M} \mathcal{R} \mathcal{S} \mathcal{T} \mathcal{Y}$

True italic capitals: the swash forms from Robert Slimbach's Minion italic. It is the structure, not the slope, of the letters that marks them as italic.

Once in a while, nevertheless, a typographer will pine for a sloped version of a font such as Haas Clarendon or André Gürtler's Egyptian 505, for which no italic, nor even a sloped roman, has been drawn. On such occasions, a sloped roman generated by computer may suffice as a temporary solution. But the slope should be modest (perhaps 10° maximum), because less slope yields less distortion.

### 3.5.1 Change one parameter at a time.

Contrast

When your text is set in a 12 pt medium roman, it should not be necessary to set the heads or titles in 24 pt bold italic capitals. If boldface appeals to you, begin by trying the bold weight of the text face, u&lc, in the text size. As alternatives, try u&lc italic, or letterspaced small caps, or letterspaced full caps in the text weight and size. If you want a larger size, experiment first with a larger size of the text face, u&lc in the text weight. For a balanced page, the weight should decrease slightly, not increase, as the size increases.

### 3.5.2 Don't clutter the foreground.

When boldface is used to emphasize words, it is usually best to leave the punctuation in the background, which is to say, in the basic text font. It is the words, not the punctuation, that merit emphasis in a sequence such as the following:

... on the islands of Lombok, Bali, Flores, Timor and Sulawesi, the same textiles ...

But if the same names are emphasized by setting them in italic rather than bold, there is no advantage in leaving the punctuation in roman. With italic text, italic punctuation normally gives better letterfit and thus looks less obtrusive:

... on the islands of *Lombok*, *Bali*, *Flores*, *Timor* and *Sulawesi*, the same textiles ...

If spaced small caps are used for emphasis – changing the stature and form of the letters instead of their weight or slope, and thereby minimizing the surface disturbance on the page – the question of punctuation does not arise. The punctuation used with small caps is (except for question and exclamation marks) usually the same as roman punctuation; it is only necessary to check it for accurate spacing:

... on the islands of LOMBOK, BALI, FLORES, TIMOR and SULAWESI, the same textiles ...

#### 4.1 OPENINGS

4.1.1 Make the title page a symbol of the dignity and presence of the text.

If the text has immense reserve and dignity, the title page should have these properties as well – and if the text is devoid of dignity, the title page should in honesty be the same.

Think of the blank page as alpine meadow, or as the purity of undifferentiated being. The typographer enters this space and must change it. The reader will enter it later, to see what the typographer has done. The underlying truth of the blank page must be infringed, but it must never altogether disappear – and whatever displaces it might well aim to be as lively and peaceful as it is. It is not enough, when building a title page, merely to unload some big, prefabricated letters into the center of the space, nor to dig a few holes in the silence with typographic heavy machinery and then move on. Big type, even huge type, can be beautiful and useful. But poise is usually far more important than size – and poise consists primarily of emptiness. Typographically, poise is made of white space. Many fine title pages consist of a modest line or two near the top, and a line or two near the bottom, with little or nothing more than taut, balanced white space in between.

# 4.1.2 Don't permit the titles to oppress the text.

In books, spaced capitals of the text size and weight are often perfectly adequate for titles. At the other extreme, there is a fine magazine design by Bradbury Thompson, in which the title, the single word BOOM, is set in gigantic bold condensed caps that fill the entire two-page spread. The text is set in a tall narrow column *inside the stem* of the big B. The title has swallowed the text – yet the text has been reborn, alive and talkative, like Jonah from the whale.

Most unsuccessful attempts at titling fall between these two extremes, and their problem is often that the title throws its weight around, unbalancing and discoloring the page. If the title is set in a larger size than the text, it is often best to set it u&lc in a light

4

For examples of Thompson's work, see Bradbury Thompson, The Art of Graphic Design (1988) titling font or a lightened version of the text font. Inline capitals (like the Castellar initials on pages 64 and 160) are another device that typographers have used since the fifteenth century to get large size without excessive weight.

Openings

There are other ways of creating large letters of light weight, but some of these are printerly instead of typographic. First of all, if the budget permits, the typographer can design the work to be printed in two or even in twenty different colors. An inexpensive alternative is the same one your monochrome desktop printer uses to render that colorful file: screening the type: breaking up the solid image with an electronic filter. (Note however that screened text always looks different on screen than on paper.)

# 10 20 30 40 50 60 70 80 90 100

Screened text. The numbers indicate the percentage of ink coverage permitted by the screen.

4.1.3 Set titles and openings in a form that contributes to the overall design.

Renaissance books, with their long titles and ample margins, generally left no extra space at the heads of chapters. In modern books, where the titles are shorter and the margins have been eaten by inflationary pressure, a third of a page sometimes lies vacant just to celebrate the fact that the chapter begins. But space alone is not enough to achieve the sense of richness and celebration, nor is absence of space necessarily a sign of typographic poverty.

Narrow row houses flush with the street are found not only in urban slums but in the loveliest of the old Italian hill towns and Mediterranean villages. A page full of letters presents the same possibilities. It can lapse into a typographic slum, or grow into a model of architectural grace, skilled engineering and simple economy. Broad suburban lawns and wide typographical front yards can also be uninspiringly empty or welcoming and graceful. They can display real treasure, including the treasure of empty

space, or they can be filled with souvenirs of wishful thinking. Neoclassical birdbaths and effigies of liveried slaves, stable boys and faded pink flamingoes all have counterparts in the typographic world.

# 4.1.4 Mark each beginning and resumption of the text.

The simplest way of beginning any block of prose is to start from the margin, flush left, as this paragraph does. On a peaceful page, where the text is announced by a head or subhead, this is enough. But if the text, or a new section of text, begins at the top of a page with no heading to mark it, a little fanfare will probably be required. The same is true if the opening page is busy. If there is a chapter title, an epigraph, a sidenote, and a photograph and caption, the opening of the text will need a banner, a ten-gallon hat or a bright red dress to draw the eye.

Fleurons (typographic ornaments) are often used to flag text openings, and are often printed in red, the typographer's habitual second color. The opening phrase, or entire first line, can also be set in small caps or in bold u&lc. Another excellent method of marking the start of the text, inherited from ancient scribal practice, is a large initial capital: a versal or lettrine. Versals can be treated in many ways. Indented or centered, they can stick up from the text. Flush left, they can be nested into the text (typographers call these drop caps, as opposed to elevated or stick-up caps). If there is room, they can hang in the left margin. They can be set in the same face as the text or in something outlandishly different. In scribal and typographic tradition alike, where the budget permits, versals too are generally red or another color in preference to black.

Elevated caps are easier to set well from a keyboard, but drop caps have closer links with the scribal and letterpress tradition. And the tooling and fitting of drop caps is something typographers do for fun, to test their skill and visual intuition. It is common practice to set the first word or phrase after the versal in caps, small caps or boldface, as a bridge between versal and normal text. Examples are shown on the following page.

In English, if the initial letter is A, I or O, a question can arise: is the initial letter itself a word? The answer to this question must come in the spacing of the text in relation to the versal. If the first word of the text is *Ahead*, for example, excessive space betwen the initial A and the rest of the word is bound to cause confusion.

Structural Forms and Devices

Ba

\$

عد

Õ

8

**\*** 

Openings

sculetur me osculo oris sui; quia meliora sunt ubera tua vino, ¶ fragantia unguentis optimis. Oleum effusum nomen tuum; ideo adolescentulae dilexerunt te.

RAHE ME, post te curremus in odorem unguentorum tuorum. Introduxit me rex in cellaria sua; exsultabimus et laetabimur in te, memores uberum tuorum super vinum. Recti diligunt te.

formosa, filiae Ierusalem, sicut tabernacula Cedar, sicut pelles Salomonis. Nolite me considerare quod fusca sim, quia decoloravit me sol. Filii matris meae pugnaverunt contra me....»

"ADIURO VOS, filiae Ierusalem, per capreas cervosque camporum, ne suscitetis, neque evigilare faciatis dilectam, quoadusque ipsa velit."

ecce iste venit, saliens in montibus, transiliens colles. ¶ Similis est dilectus meus capreae, hinnuloque cervorum. En ipse stat post parietem nostrum, respiciens per fenestras, prospiciens per cancellos. En dilectus meus loquitur mihi.

Surge, propera, amica mea, columba mea, formosa mea, et veni. Iam enim hiems transiit; imber abiit, et recessit. Flores apparuerunt in terra nostra....

quomodo inquinabo illos? ¶ Dilectus meus misit manum suam per foramen, et venter meus intremuit ad tactum eius. ¶ Surrexit ut aperirem dilecto meo; manus meae stillaverunt myrrham, et digiti mei pleni myrrha probatissima. Pessulum ostii mei....

Passages from the Song of Songs, set in Aldus 10/12 × 10 RR. Elevated cap: Castellar 54 pt. Drop caps: Aldus 42 pt, mortised line by line.

4.1.5 If the text begins with a quotation, include the initial quotation mark.

Quotation marks have a long scribal history as editorial signs added after the fact to other people's texts, but they did not come into routine typographic use until late in the sixteenth century. Then, because they interfered with established habits for positioning large initials, they were commonly omitted from the open-

ings of texts. Some style books still prescribe this concession to convenience as a fixed procedural rule. But digital typography makes it simple to control the size and placement of the opening quotation mark, whether or not the text begins with a versal. For the reader's sake, it should be there.

#### 4.2 HEADINGS & SUBHEADS

4.2.1 Set headings in a form that contributes to the style of the whole.

Structural Forms and Devices

Headings can take many forms, but one of the first choices to make is whether they will be symmetrical or asymmetrical. Symmetrical heads, which are centered on the measure, are known to typographers as *crossheads*. Asymmetrical heads usually take the form of *left sideheads*, which is to say they are set flush left, or modestly indented or outdented from the left. *Right sideheads* work well in certain contexts, but more often as main heads than as subheads. A short, one-line head set flush right needs substantial size or weight to prevent the reader from missing it altogether.

These principles are reversed, of course, when setting leftward-reading alphabets such as Arabic and Hebrew.

One way to make heads prominent without making them large is to set them entirely in the margin, like the running heads (in typographic terms, they are *running shoulderheads*) used throughout this book.

4.2.2 Use as many levels of headings as you need: no more and no fewer.

As a rule it is best to choose a predominantly symmetrical or asymmetrical form for subheads. Mixing the two haphazardly leads to stylistic as well as logical confusion. But the number of levels available can be slightly increased, if necessary, by judicious combinations. If symmetrical heads are added to a basically asymmetrical series, or vice versa, it is usually better to put the visiting foreigners at the top or bottom of the hierarchical pile. Two six-level series of subheads are shown, by way of example, on the following pages.

In marking copy for typesetting, the various levels of subheads are generally given letters rather than names: A-heads, B-heads, C-heads, and so on. Using this terminology, the heads on the following pages run from A through F.

# 

Headings and Subheads If A MAN walk in the woods for love of them half of each day, he is in danger of being regarded as a loafer; but if he spends his whole day as a speculator, shearing off those woods and making earth bald before her time, he is esteemed an industrious and enterprising citizen.

### MAIN CROSSHEAD

The ways by which you may get money almost without exception lead downward. To have done anything by which you earned money *merely* is to have been truly idle or worse.... If you would get money as a writer or lecurer, you must be popular, which is to go down perpendicularly....

### Heavy Crosshead

In proportion as our inward life fails, we go more constantly and desperately to the post office. You may depend on it, that the poor fellow who walks away with the greatest number of letters ... has not heard from himself this long while.

#### MEDIUM CROSSHEAD

If do not know but it is too much to read one newspaper a week. I have tried it recently, and for so long it seems to me that I have not dwelt in my native region. The sun, the clouds, the snow, the trees say not so much to me....

# Light Crosshead

We You cannot serve two masters. It requires more than a day's devotion to know and to possess the wealth of a day.... Really to see the sun rise or go down every day, so to relate ourselves to a universal fact, would preserve us sane forever.

hypethral: from Greek ἐν ὑπαίθρω, 'in the open air' RUN-IN SIDEHEAD Shall the mind be a public arena...? Or shall it be a quarter of heaven itself, an hypethral temple, consecrated to the service of the gods?

# Main Section Title

₩ IF I AM TO BE a thoroughfare, I prefer that it be of the mountain brooks, the Parnassian streams, and not the town sewers.... I believe that the mind can be permanently profaned by attending to trivial things, so that all our thoughts shall be tinged with triviality.

Structural Forms and Devices

### MAIN CROSSHEAD

Our very intellect shall be macadamized, as it were: its foundation broken into fragments for the wheels of travel to roll over; and if you would know what will make the most durable pavement, surpassing rolled stones, spruce blocks, and asphaltum, you have only to look into some of our minds....

### 8 ORNAMENTED CROSSHEAD 8

Read not the Times. Read the Eternities.... Even the facts of science may dust the mind by their dryness, unless they are in a sense effaced each morning, or rather rendered fertile by the dews of fresh and living truth.

### INDENTED SIDEHEAD

Knowledge does not come to us by details, but in flashes of light from heaven. Yes, every thought that passes through the mind helps to wear and tear it, and to deepen the ruts, which, as in the streets of Pompeii, evince how much it has been used.

# Secondary Indented Sidehead

When we want culture more than potatoes, and illumination more than sugar-plums, then the great resources of a world are taxed and drawn out, and the result, or staple production, is not slaves, nor operatives, but ... saints, poets, philosophers....

Run-in Sidehead In short, as a snowdrift is formed where there is a lull in the wind, so, one would say, where there is a lull of truth, an institution springs up....

The texts on this and the facing page are excerpts from HENRY DAVID THOREAU'S "Life Without Principle," c. 1854, first published in 1863. The type on the facing page is Adobe Caslon  $10/12 \times 21$ , and on this page, recut Monotype Centaur & Arrighi  $11/12 \times 21$ .

## 4.3.1 If the text includes notes, choose the optimum form.

Notes

If notes are used for subordinate details, it is right that they be set in a smaller size than the main text. But the academic habit of relegating notes to the foot of the page or the end of the book is a mirror of Victorian social and domestic practice, in which the kitchen was kept out of sight and the servants were kept below stairs. If the notes are permitted to move around in the margins – as they were in Renaissance books – they can be present where needed and at the same time enrich the life of the page.

Footnotes are the very emblem of fussiness, but they have their uses. If they are short and infrequent, they can be made economical of space, easy to find when wanted and, when not wanted, easy to ignore. Long footnotes are inevitably a distraction: tedious to read and wearying to look at. Footnotes that extend to a second page (as some long footnotes are bound to do) are an abject failure of design.

Endnotes can be just as economical of space, less trouble to design and less expensive to set, and they can comfortably run to any length. They also leave the text page clean except for a peppering of superscripts. They do, however, require the serious reader to use two bookmarks and to read with both hands as well as both eyes, swapping back and forth between the popular and the persnickety parts of the text.

Sidenotes give more life and variety to the page and are the easiest of all to find and read. If carefully designed, they need not enlarge either the page or the cost of printing it.

Footnotes rarely need to be larger than 8 or 9 pt. Endnotes are typically set in small text sizes: 9 or 10 pt. Sidenotes can be set in anything up to the same size as the main text, depending on their frequency and importance, and on the overall format of the page.

# 4.3.2 Check the weight and spacing of superscripts.

If they are not too frequent, sidenotes can be set with no superscripts at all (as in this book), or with the same symbol (normally an asterisk) constantly reused, even when several notes appear on a single page. For endnotes, superscript numbers are standard. For footnotes, symbols can be used if the notes are few. (The traditional order is \* † ‡ §  $\parallel$  ¶. But beyond the asterisk, dagger and double dagger, this order is not familiar to most readers, and never was.) Numbers are more transparent, and their order is much less easy to confuse.

Many fonts include sets of superscript numbers, but these are not always of satisfactory size and design. Text numerals set at a reduced size and elevated baseline are sometimes the best or only choice. Establishing the best size, weight and spacing for superscripts will, however, require some care. In many faces, smaller numbers in semibold look better than larger numbers of regular weight. And the smaller the superscripts are, the more likely they are to need increased character space.

Structural Forms and Devices

Superscripts frequently come at the ends of phrases or sentences. If they are high above the line, they can be kerned over a comma or period, but this may endanger readability, especially if the text is set in a modest size.

4.3.3 Use superscripts in the text but full-size numbers in the notes themselves.

In the main text, superscript numbers are used to indicate notes because superscript numbers minimize interruption. They are typographic asides: small because that is an expression of their relative importance, and raised for two reasons: to keep them out of the flow of the main text, and to make them easier to find. In the note itself, the number is not an aside but a target. Therefore the number in the note should be full size.<sup>1</sup>

a¹ b 1. Ba

To make them easy to find, the numbers of footnotes or endnotes can be hung to the left (like the marginal numbers on the following two pages and the footnote number below). Punctuation, apart from empty space, is not normally needed between the number and text of the note.

4.3.4 Avoid ambiguity in the numbering and placement of endnotes.

Readers should never be forced to hunt for the endnotes. As a rule, this means the endnotes should not appear in small clumps

This footnote is flagged by a superscript in the text, but the note itself is introduced by an outdented figure of the same size used for the text of the note. The main text on this page is set  $10/12 \times 21$ , and the note is 8/11.

at the end of each chapter. It is better to place them together at the end of the book. Wherever possible, they should also be numbered sequentially from the beginning to end of the book, and the notes themselves should be designed so the numbers are readily visible. If the notes are numbered anew for each section or chapter or essay, running heads will be needed along with the notes to point the way. If the running heads accompanying the notes say, for instance, "Notes to Pages 44–62," readers will know their way. But if the running heads say something like "Notes to Chapter 5," then chapter 5 must be identified as such by running heads of its own.

Notes

#### 4.4 TABLES & LISTS

4.4.1 Edit tables with the same attention given to text, and set them as text to be read.

For graphic alternatives to typographic tables, see Edward R. Tufte, The Visual Display of Quantitative Information (2nd ed., 2001) and Envisioning Information (1990).

Tables are notoriously time-consuming to typeset, but the problems posed are often editorial as much as typographic. If the table is not planned in a readable form to begin with, the typographer can render it readable only by rewriting or redesigning it from scratch.

Tables, like text, go awry when approached on a purely technical basis. Good typographic answers are not elicited by asking questions such as "How can I cram this number of characters into that amount of space?"

If the table is approached as merely one more form of text, which must be made both good to read and good to look at, several principles will be clear:

- 1 All text should be horizontal, or in rare cases oblique. Setting column heads vertically as a space-saving measure is quite feasible if the text is in Japanese or Chinese, but not if it is written in the Latin alphabet.
- 2 Letterforms too small or too condensed for comfortable reading are not part of the solution.
- 3 There should be a minimum amount of furniture (rules, boxes, dots and other guiderails for traveling through typographic space) and a maximum amount of information.
- 4 Rules, tint blocks or other guides and dividers, where they are necessary at all, should run in the predominant reading direction: vertically in the case of lists, indices and some numerical tables, and horizontally otherwise.

- 5 A rule located at the edge of a table, separating the first or final column from the adjacent empty space, ordinarily serves no function.
- 6 A table, like any other text in multiple columns, must contain within itself an adequate amount of white space.

## 4.4.2 Avoid overpunctuating lists.

A list is an inherently spatial and numerical arrangement. Speakers reciting lists often enumerate on their fingers, and lists set in type often call for equivalent typographic gestures. This means that the list should be clarified as much as possible through spatial positioning and pointing, usually done with bullets, dashes or numerals. (Examples occur on these two pages and throughout this book.) If the numbers are made visible either through position (e.g., by hanging them in the margin) or through prominence (e.g., by setting them in a contrasting face), additional punctuation – extra periods, parentheses or the like – should rarely be required.

Dot leaders (lines of dots leading the eye from one word or number to another) are rarely beneficial in tables.

4.4.3 Set lists and columns of figures to align flush right or on the decimal.

The numerals in many fonts are all of equal width, though there is sometimes an alternative, narrower form of the numeral one. This fitted one is generally used when setting figures in the midst of text, while the unfitted one (of standard numeral width) is often used when setting figures in columns. The font itself or the composition software will also include a figure space – a fixed blank space corresponding to the width of a standard, unkerned numeral. This makes it a simple matter to compose lists and columns of figures in rigorous mechanical alignment.

If you use proportionally fitted numerals (always the best choice for text), or kern the numeral permutations in a font with tabular figures, the individual figures will not align in columns or lists, but *columns* of figures can still be aligned. For much tabular matter (e.g., the first table overleaf) this is sufficient. If notes are required in a table with flush-right columns, the superscripts should be hung to the right (as in column 3, line 2 of the first example overleaf) so they will not disrupt the alignment.

Structural Forms and Devices

8	98	998	9.75
9	99	999*	10
10	100	1000	10.25
11	101	1001	10.5

Above: aligning columns of nonaligning figures, with a hanging asterisk. Below: columns in mixed alignment.

Tables and Lists

Aster 2:3 
$$24 \times 36$$
 0.667  $a = 2b$   
Valerian 271:20  $813 \times 60$  13.550  $6a = c$ 

4.4.4 For text and numerals alike, choose harmonious and legible tabular alignments.

Simple tables and lists of paired items, like the sample tables of contents on page 36, are often best aligned against each other, the left column flush right and the right column flush left. Financial statements and other numerical tables usually follow the opposite pattern: a column of words, on the left, aligns flush left, while the subsequent columns of numbers all align flush right or on the decimal. Any repeating character – a dimension sign or equal sign, for instance – is potentially of use in tabular alignment. But many columns with many different alignments can generate overall visual chaos. Occasionally it is better, in such cases, to set all columns or most columns either flush right or flush left, for the sake of general clarity.

### 4.5 FRONT & BACK MATTER

4.5.1 Leave adequate space at the beginning and end of every publication.

A brief research paper may look its best with no more space at beginning and end than is provided by the standard page margins. The same is rarely true of a book, whose text should generally be, and should seem to be, a living and breathing entity, not aged and shrink-wrapped meat. A chapbook or saddle-stitched booklet can begin directly with the title page. Otherwise, a half-title is customary, preceding the title page. It is equally customary to leave a blank leaf, or at least a blank page, at the end of a book. These blanks provide a place for inscriptions and notes and allow the text to relax in its binding.

### 4.5.2 *Give adequate space to the prelims.*

A text preceded by an interminable chain of forewords, prefaces, introductions and prologues is unlikely to be read. But a dedication that is stuffed, like a typographic afterthought, onto an already overfilled copyright page is no dedication at all. And a list of contents which is incomplete (or missing altogether), and which does not have the page to itself, is usually a sign of typographic desperation or of disregard for the reader.

Structural Forms and Devices

# 4.5.3 Balance the front and back matter.

Books are normally built up from gatherings or signatures – printed and folded sheets – with each signature forming a unit of 8, 12, 16, 24 or 32 pages. The 16-page signature is by far the most common. Typographers therefore work to make most of their books seem divinely ordained and conceived to be some multiple of 16 pages in length. Seasoned book typographers recite in their meditations not only the mantra of points and picas – 12, 24, 36, 48, 60, 72 ... – but also the mantra of octavo signatures: 16, 32, 48, 64, 80, 96, 112, 128, 144, 160, 176, 192, 208, 224, 240, 256, 272, 288, 304, 320, 336, 352, 368, 384, 400.... These are the lengths of the books that we read.

In a work of continuous prose, the illusion of divine love for the number sixteen is obtained by straightforward copyfitting. If the length of the text is accurately measured, the page can be designed to yield a book of appropriate length. More complicated books are often surrounded by paraphernalia - not only the standard half-title, title page, copyright page, dedication page and some blanks, but also perhaps a detailed table of contents, a list of charts, illustrations and maps, a table of abbreviations, a page or two of acknowledgements, and a preface, counterbalanced by appendices, endnotes, bibliography, index and a colophon. Copyfitting the main text for a volume of this kind may be highly complex, and room may be taken up or conserved in the large aura of front and back matter. But for complex books and simple books alike, it is up to the typographer to balance the front matter, back matter and text. A wad of blank leaves at the end of a book is a sign of carelessness, not of kindliness toward readers who like to take notes.

ABCDEFGHIKL
MNOPQ RSTV
XYZabcdefghil
mnopqrsftuvxyz
1234567890,..!?;:-,~
Æææfffiflæffiftflæ
&ãáàâçēéèêëeííììiľ

Iuris præcepta sunt hæc, Honesté viuere, alterum non lædere, suum cuiq; tribucre. Huius study duæ sunt positiones, Publicum & priuatum. Publicum ius est, quod ad statum rei Romanæ spectat. Priua tum, quod ad singulorum vtilitatem pertinet. Dicendum est igitur de iure priuato, quòd tripertitum est: collectum est enim ex naturalibus præceptis, aut getium aut ciuilibus. Ius naturale est quòd

A 42 pt roman titling font (cut c. 1530, revised c. 1550) and a 16 pt italic text font (c. 1539). Both were cut by Claude Garamond, Paris. The italic is shown actual size and the roman reduced by about one fifth. Matrices for the roman font survive at the Plantin-Moretus Museum, Antwerp.

#### 5.1 ANALPHABETIC STYLE

It falls to the typographer to deal with an increasing herd of flicks, squiggles, dashes, dots and ideographs that travel with the alphabet yet never quite belong. The most essential of these marks – period, comma, parentheses, and the like – are signs of logical pause and intonation, much like the rests and slurs in a musical score. Some, like the dollar and per cent signs, are stylized abbreviations. Others, like the asterisk and the dagger, are silent typographical cross-references. And a few that are normally unspoken have tried to sneak their way into the oral tradition. Speakers who say *quote unquote* or *who slash what* or *That's it*, *period!* are, of course, proving their debt to these enduring paraliterary signs.

Approached through the scribal and typographic tradition, the palette of analphabetic symbols is much more supple and expressive than it appears through the narrow grill of the typewriter keyboard. A typographer will not necessarily use more analphabetic symbols per page than a typist. In fact, many good typographers use fewer. But even the most laconic typographer learns to speak this sign language with an eloquence that conventional editing software, like the typewriter, seems to preclude.

### 5.1.1 To invoke the inscriptional tradition, use the midpoint.

The earliest alphabetic inscriptions have no analphabetic furniture at all, not even spaces between the words. As writing spread through Greece and Italy, spaces appeared between the words, and a further sign was added: the centered dot, for marking phrases or abbreviations. That dot, the *midpoint* or small bullet, remains one of the simplest, most effective forms of typographic punctuation – useful today in lists and letterheads and signage just as it was on engraved marble twenty centuries ago.

### Suite 6 · 325 Central Park South

Roman calligraphers lettered their inscriptions with a flat brush held in the right hand. The flat brush – thick in one direc-

5

### 愛さ

In Asian and European scripts alike, modulated strokes are usually serifed and unmodulated strokes are usually not. Transitive brush serifs are evident in the mincho typeface above, designed by Takaichi Hori. The same kanji and kana are shown below in an unserifed face designed by Yasubumi Miyake. Mincho katsuji or 'Ming Dynasty script' is, roughly, the Japanese counterpart of serifed roman - but its serif structure is more cursive, like that of italic.

### 愛さ

tion, thin in the other, like a broadnib pen – produces a *modulated stroke*. That is to say, the weight of the stroke varies predictably with direction. The letter O is an example. Because the brush is held in the scribe's right hand, the strokes are thickest in the northwest/southeast direction, at the natural inclination of the forearm and the hand. Using the same brush, Roman calligraphers also developed the subtle choreography of twists and turns at the stroke-ends that produces the imperial Roman serif. Roman capital letters have retained these forms for two thousand years.

### $O \cdot I \cdot M$

When the centered dot or midpoint is made in the same way with the same tool, it becomes a small, curved wedge: a clockwise twist of the brush, with a short tail. Falling to the baseline, this tailed dot became our comma. The same inscriptional and calligraphic traditions have left us other useful marks, such as the double dot or colon (:), the virgule (/), the hyphen (-), and the long dash (- or —).

5.1.2 Use analphabetic symbols and diacritics that are in tune with the basic font.

A normal font of type now includes about two dozen mutant forms of the few ancient signs of punctuation (period, comma, colon, quotation marks, brackets, parentheses, dashes, and so on). It also includes about a dozen diacritics (acute and grave accents, the circumflex, tilde, ogonek, umlaut, and others), some legal and commercial logograms (@ # \$ £ % ‰ etc) and a few arithmetical symbols. In the Iso Latin character sets (font tables defined by the International Organization for Standardization and now used as a standard by most digital foundries in Europe and North America), analphabetic symbols outnumber the basic Latin alphabet three to one.

On some fonts, these analphabetic characters are beautifully designed; on others they are not designed at all. Often they are simply borrowed from another font, which may have been drawn in a different weight and style.

Several analphabetic characters are notorious for poor design and should always be inspected when assessing a new font. These problem characters include *square brackets* [], which are often too dark; *parentheses* (), which are often too symmetrical and skinny; the asterisk \*, the *pilcrow* ¶ and the *section sign* §, which are often stiff and bland; and the *octothorp* or numeral sign #, which is frequently too large for anything more interesting than chain-store propaganda. Fonts equipped with good versions of these characters must often lend them to those without. But not just any good version will do.

Analphabetic Symbols

Neoclassical analphabetics, after John Baskerville, above, and the neo-humanist analphabetics of Hermann Zapf's Palatino, below. Analphabetics differ from one face to another, and from one historical period to another, just as much as the letterforms do - and they differ in essentially the same ways.

Baskerville, which is an eighteenth-century Neoclassical type-face, requires a Neoclassical asterisk: one with an even number of lobes, each in symmetrical teardrop form. But a twentieth-century neohumanist face like Palatino requires an asterisk with more calligraphic character – sharper, slightly asymmetrical lobes, more likely five than six in number, showing the trace of the broadnib pen. Well-made fonts are distinguished by similar differences in the question and exclamation marks, quotation marks and commas. Not even simple periods are freely interchangeable. Some are elliptical, diamond-shaped or square instead of round. Their weight and fitting varies as well. The *visible invisibility* of the marks of punctuation, which is essential to their function, depends on these details. So, therefore, does the visible invisibility of the typeface as a whole. In the republic of typography, the lowliest, most incidental mark is also a citizen.

### 5.1.3 In heads and titles, use the best available ampersand.

Earlier typographers made liberal use of ampersands, especially when setting italic and relished their variety of form. The 16th-century French printer Christophe Plantin sometimes uses four quite different ampersands in the course of a single paragraph, even when setting something as unwhimsical as the eight-volume polylingual Bible on which he risked his fortune and to which he devoted more than six years of his life. The ampersand is a symbol evolved from the Latin *et*, meaning *and*. It is one of the oldest alphabetic abbreviations, and it has assumed over the centuries a wonderful variety of forms. Contemporary offerings are for the most part uninspired, stolid pretzels: unmusical imitations of the treble clef. Often the italic font is equipped with an ampersand less repressed than its roman counterpart. Since the ampersand is more often used in display work than in ordinary text, the more creative versions are often the more useful. There is rarely any reason not to borrow the italic ampersand for use with roman text.

# Shakespeare & Co. Brown & Son Smith & Daughter

Trump Mediäval italic (top) was designed by Georg Trump, Pontifex roman (second two lines) by Friedrich Poppl. In both, the italic ampersand is more stylish than the roman.

### 5.1.4 Consider even the lowly hyphen.

It is worth taking a close look at hyphens, which were once more subtle and various than they tend to be today. The hyphen was originally a simple pen stroke, often the thinnest stroke the broadnib pen could make, at an angle of 20° to 45° above horizontal. To distinguish the hyphen from the comma (which could also be written as a simple, canted stroke), the hyphen was often doubled, like an equal sign heading uphill.

Many Renaissance typographers preferred the canted hyphen with italic and the level hyphen with roman. Others mixed the two at random – one of several techniques once used to give a touch of scribal variety to the typeset page. But after the death of the master printer Robert Estienne in 1559 and of Claude Garamond in 1561, the level hyphen was the norm.

Most hyphens currently offered are short, blunt, thick, and perfectly level, like refugees from a font of Helvetica. This has sometimes been the choice of the designer, sometimes not. The double hyphen designed by Hermann Zapf in 1953 for his type-face Aldus, as an example, was omitted when the face was com-

mercially issued in 1954. Foundry Centaur, designed by Bruce Rogers, had a hyphen inclined at 48°, but Monotype replaced it with a level bar when the face was adapted for machine composition in 1929. And the original Linotype issue of W.A. Dwiggins's Electra had a subtly tapered hyphen inclined at 7° from the horizontal; later copies of the face have substituted a bland, anonymous form.

If you are tempted to redesign an existing font, using a digital font editor, the hyphen is a good character to start on. It is a comparatively simple character, and you may be able to restore instead of subvert the designer's original intentions.

A few alternatives to the blunt and level hyphen are also still in circulation, and these are worth stealing on occasion for use with another face. The hyphen in Monotype Poliphilus is canted (as in the original design) at 42°. The hyphen in Monotype Blado (the companion italic to Poliphilus) is canted at 35° and tapered as well. The hyphens in most of Frederic Goudy's text faces are canted at angles ranging from 15° to 50°. Some digital versions preserve this feature; others are more homogenized. Canted and tapered hyphens are also to be found in many of the faces of Oldřich Menhart. (In the original version of Menhart's Figural, for example, the roman hyphen is tapered one way and the italic hyphen the other.) Frederic Warde's Arrighi, José Mendoza's Photina italic, and Warren Chappell's Trajanus all have hyphens that are level but asymmetrically serifed, which gives them a slight angular movement. The hyphen in Bram de Does's Trinité, a model of subtlety, is essentially level and unserifed but has a slight calligraphic lift at one end.

fine-tuned / eagle-eye

Frederic Warde's Arrighi, left, and Warren Chappell's Trajanus, right

Hyphens also once varied considerably in width, but most now are standardized to a quarter of an em. Sometimes a shorter hyphen is better. Some of Gerard Unger's and Martin Majoor's economical Dutch hyphens (in faces such as Swift, Flora and Scala) measure no more than a fifth of an em.

Line-end hyphens are often best hung in the right margin, like the line-end hyphens on this and the facing page. This was easy to do for the scribes, who made it a common practice, but

Analphabetic Symbols

g/h

g-h

Poliphilus & Blado, above; Kennerley below.


g-h

g-h

it is tedious to emulate in metal. Digital typography makes it potentially easy once again – though not all typesetting software is equally eager to oblige.

#### 5.2 DASHES, SLASHES & DOTS

Dashes, Slashes and Dots 5.2.1 Use spaced en dashes – rather than close-set em dashes or spaced hyphens – to set off phrases.



In typescript, a double hyphen (--) is often used for a long dash. Double hyphens in a typeset document are a sure sign that the type was set by a typist, not a typographer. A typographer will use an em dash, three-quarter em, or en dash, depending on context or personal style. The em dash is the nineteenth-century standard, still prescribed in many editorial style books, but the em dash is too long for use with the best text faces. Like the oversized space between sentences, it belongs to the padded and corseted aesthetic of Victorian typography.

Used as a phrase marker – thus – the en dash is set with a normal word space either side.

5.2.2 Use close-set en dashes or three-to-em dashes between digits to indicate a range.

Thus: 3–6 November; 4:30–5:00 PM; 25–30 mm. Set close in this way (and with careful attention to kerning and spacing), the dash stands for the word to. The hyphen is too short to serve this function, and in some faces the en dash (which is traditionally prescribed) appears too long. A *three-to-em* (M/3) dash is often the best choice. There is no need to edit the font in order to make such a creature. Typesetting software will happily condense the en or em dash by any desired amount.

When compound terms are linked with a dash in the midst of running prose, subtle clues of size and spacing can be crucial, and confusion can easily arise. A sentence such as *The office will be closed 25 December – 3 January* is a linguistic and typographic trap. When it stands all alone in a schedule or list, the phrase 25 *December – 3 January* will be clear, but in running prose it is better both editorially and typographically to omit the dash and insert an honest preposition: 25 *December to 3 January*.

Analphabetic Symbols

5.2.3 *Use the em dash to introduce speakers in narrative dialogue.* 

The em dash, followed by a thin space (M/5) or word space, is the normal European method of marking dialogue, and it is much less fussy than quotation marks:

- So this is a French novel? she said.
- No, he said, it's Manitoban.

5.2.4 In lists and bibliographies, use a three-em rule when required as a sign of repetition.

Set without spaces, a line of true em dashes forms a continuous midline rule. A three-em rule (three consecutive em dashes) is the old standard bibliographical sign for the repetition of a name. For example:

Boas, Franz. Primitive Art. Oslo: Aschehoug, 1927. Reissued Cambridge, Mass.:
Harvard University Press, 1928; New York: Dover, 1955.

——. Tsimshian Mythology. BAE Ann. Rep. 31. Washington, DC: Bureau of American Ethnology, 1916.

In recent years, many professional scholars have abandoned this style of bibliography, but the three-em rule still has many nonacademic uses.

5.2.5 Use the virgule with words and dates, the solidus with splitlevel fractions.

The slash, like the dash, is more various in real life than it is on the typewriter keyboard. A normal font of type includes a vertical bar and two slashes of differing inclinations. The steeper slash is the virgule (/), an alternative form of the comma. It is useful in Unicode (see p 181) defines a special character [U+2015] as the quotation dash. Fonts containing such a character are rare. The em dash is the typographic norm.

dates (6/6/99 = 6.VI.99 = 6 June 99) and in text where a comma or parenthesis might otherwise have been used.

Wednesday / August 3 / 1977
Tibetan Guest House / Thamel / Kathmandu
Victoria University, Toronto / Ontario
he/she hit him/her

Dashes, Slashes and Dots

The other slash mark on the font is a solidus or fraction bar, used to construct fractions such as 3/32. The solidus generally slopes at close to 45° and kerns on both sides. The virgule, not the solidus, is used to construct *level* fractions, such as  $2\pi/3$ . (Notice, for instance, the difference in slope and kerning between the two slash marks in the type specification  $8/9\frac{1}{2}$ .)

5.2.6 Use a dimension sign  $(\times)$  instead of the letter x when dimensions are given.

 $4 \times 4$ 

A picture is 26  $\times$  42 cm; studs are 2  $\times$  4 and shelving is 2  $\times$  10 inches; North American letter paper is  $8\frac{1}{2} \times 11$ .

5.2.7 Use ellipses that fit the font.

i ... j

k....

1...,1

1, ... 1

m...?

n...!

Most digital fonts now include, among other things, a prefabricated *ellipsis* (a row of three baseline dots). Many typographers nevertheless prefer to make their own. Some prefer to set the three dots flush ... with a normal word space before and after. Others prefer ... to add *thin* spaces between the dots. Thick spaces (M/3) are prescribed by the *Chicago Manual of Style*, but these are another Victorian eccentricity. In most contexts, the Chicago ellipsis is much too wide.

Flush-set ellipses work well with some fonts and faces but not with all. At small text sizes – in 8 pt footnotes, for example – it is generally better to add space (as much as M/5) between the dots. Extra space may also look best in the midst of light, open letterforms, such as Baskerville, and less space in the company of a dark font, such as Trajanus, or when setting in bold face. (The ellipsis generally used in this book is part of the font and sets as a single character.)

In English (but usually not in French), when the ellipsis occurs at the end of a sentence, a fourth dot, the period, is added and the space at the beginning of the ellipsis disappears.... When the

ellipsis combines with a comma, exclamation mark or question mark, the same typographic principle applies. Otherwise, a word space is required fore and aft.

5.2.8 Treat the punctuation as notation, not expression, most of the time.

Analphabetic Symbols

Now and again the typographer finds on his desk a manuscript in which the exclamation marks and question marks stand six or nine together. Certain words may be written in bold capitals and others may be underlined five times. If the page has been written by hand, the dashes may get longer, and the screamers (exclamations) may get taller as they go. With sufficient equipment and time, the typographer can actually come close to reproducing what he sees; he can even increase its dramatic intensity in any of several ways. Theatrical typography is a genre that flourished throughout most of the twentieth century, yet whose limits are still largely unexplored.

Most writing and typography nevertheless remain contentedly abstract, like a theater script or a musical score. The script of *Macbeth* does not need to be bloodstained and spattered with tears; it needs to be legible. And the score of Beethoven's *Hammerklavier Sonata* does not need bolder notes to mark fortissimos nor fractured notes to mark the broken chords. The score is abstract code and not raw gesture. The typeset script or musical score is also a performance in its way – but only of the text. The score is silent so the pianist can play. The script can whisper while the actors roar.

William Faulkner, like most American novelists of his generation, typed his final drafts. Noel Polk, a literary scholar and a specialist on Faulkner, has prepared new editions of these novels in recent years. He found that Faulkner usually typed three hyphens for a long dash and four or five dots for an ellipsis, but that once in a while he hammered away at the key, typing hyphens or dots a dozen or more in a row. Polk decided not to try to replicate Faulkner's keyboard jigs exactly, but he did not want to edit them entirely away. He evolved the rule of converting two, three or four hyphens to an em dash, and five or more hyphens to a two-em dash. Anything up to six dots, he replaced with a standard ellipsis, and he called for seven dots wherever Faulkner had typed seven dots or more.

These are typographic decisions that other editors or ty-

See Joseph Blotner & Noel Polk, "Note on the Texts," in William Faulkner, Novels 1930-1945 (New York: Library of America, 1985), p 1021, and Novels 1936-1940 (1990), p 1108. Photoreproductions of Faulkner's holographs and typescripts have also been published in 25 volumes as The Faulkner Manuscripts (New York: Garland, 1986-87).

pographers might have made in other ways. But the principle underlying them is sound. That principle is: punctuation is cold notation; it is not frustrated speech; it is typographic code.

Faulkner, we can presume, did not resort to bouts of extravagant punctuation because he was unable to express himself in words. He may, however, have been looking for some of the keys that the typewriter just doesn't have. The typographer's task is to know the vocabulary and grammar of typography, and to put them to meaningful use on Faulkner's behalf.

Dashes, Slashes and Dots

#### 5.3 PARENTHESES

5.3.1 *Use the best available brackets and parentheses, and set them with adequate space.* 

Typographic parentheses are traditionally pure line, like the virgule (/), the en dash (–) and the em dash (—). They are curved rules – usually portions of perfect circles, with no variation in weight – and in many older fonts they were loosely fitted, or set with plenty of space between them and the text they enclose. Parentheses in the form of swelled rules – thick in the middle and pointed at the ends – first appeared in the early Baroque, faded from view again in the Neoclassic age, and became the fashion, along with lining figures, in the nineteenth century. Many of the best twentieth-century text faces (Bruce Rogers's Centaur and the Monotype Corporation's Bembo, for example) were historical revivals that reasserted the older form.

(abc) (abc)

Monotype Centaur and Monotype Baskerville, above. Georg Trump's Trump Mediäval Antiqua and Karl-Erik Forsberg's Berling, below.

(abc) (abc)

The parentheses of some recent faces, such as Georg Trump's Trump Mediäval Antiqua and Hermann Zapf's Comenius, are modulated, asymmetrical strokes, based on the natural forms of the broadnib pen. In other recent designs (Zapf's Melior and Zapf International, and Karl-Erik Forsberg's Berling, for example), the parentheses are symmetrically thick in the middle and thin at the ends, like the nineteenth-century standard, but they are stretched into the form of a partial superellipse, which gives them greater tension and poise.

Parentheses in the form of nineteenth-century swelled rules are found by default on many digital fonts and have frequently been added, by mistake or by design, to alphabets with which they don't belong – historical revivals of the printing types of Garamond and Baskerville for example.

If you are forced to work with a font whose parentheses fall below standard, borrow a better pair from elsewhere. And whatever parentheses you use, check that they are not too tightly fitted (as in recent fonts they very often are).

5.3.2 Use upright (i.e., "roman") rather than sloped parentheses, brackets and braces, even if the context is italic.

Parentheses and brackets are not letters, and it makes little sense to speak of them as roman or italic. There are vertical parentheses and sloped ones, and the parentheses on italic fonts are almost always sloped, but vertical parentheses are generally to be preferred. That means they must come from the roman font, and may need extra spacing when used with italic letterforms.

(efg) (efg)

The sloped square brackets usually found on italic fonts are, if anything, even less useful than sloped parentheses. If, perish the thought, there were a book or film entitled *The View from My [sic] Bed*, sloped brackets might be useful as a way of indicating that the brackets and their contents are actually part of the title. Otherwise, vertical brackets should be used, no matter whether the text is roman or italic: "The View from My [sic] Bed" and "the view from my [sic] bed."

In older German typeface classifications, Antiqua means roman and mediäval actually means Renaissance because Italian Renaissance architects and scribes revived and updated romanesque and Carolingian forms from the medieval period. Trump Mediaval Antigua, or Trump Medieval roman, despite its name, stems from late Renaissance forms.

This rule has been broken more often than followed since the end of the 16th century. It was followed more often than broken by the best of the early typographers who set books in italic: Aldus Manutius, Gershom Soncino, Johann Froben, Simon de Colines. Robert Estienne, Ludovico degli Arrighi and Henri Estienne 11.

5.4.1 Minimize the use of quotation marks, especially with Renaissance faces.

Quotation Marks and Other Intrusions Typographers got by quite well for centuries without quotation marks. In the earliest printed books, quotation was marked merely by naming the speaker – as it still is in most editions of the Vulgate and King James Bibles. In the High Renaissance, quotation was generally marked by a change of font: from roman to italic or the other way around. Quotation marks were first cut in the middle of the sixteenth century, and by the seventeenth, some printers liked to use them profusely. In books from the Baroque and Romantic periods, quotation marks are sometimes repeated at the beginning of every line of a long quotation. When these distractions were finally omitted, the space they had occupied was frequently retained. This is the origin of the indented block quotation. Renaissance block quotations were set in a contrasting face at full size and full measure.

"and"
"und"
«et»
»und«

Three forms of quotation mark are still in common use. Inverted and raised commas – "quote" and 'quote' – are generally favored in Britain and North America. But baseline and inverted commas – "quote" – are more widely used in Germany, and many typographers prefer them to take the shape of sloped primes (,, –") instead of tailed commas (,, –"). Guillemets, otherwise known as duck-foot quotation marks, chevrons, or angle quotes – "quote" and 'quote" – are the normal form in France and Italy, and are widely used in the rest of Europe. French and Italian typographers set their guillemets with the points out, "thus", while German-speaking typographers usually set them "the opposite way". In either case, thin spaces are customary between the guillemets and the text they enclose.

An informative history of punctuation is M.B. Parkes, Pause and Effect (1993). Quotation marks are sufficiently ingrained in modern editorial sign language that it is difficult, in many kinds of texts, to do entirely without them. But many nonprofessional writers overuse quotation marks. Good editors and typographers will reduce their appearance to a minimum, retaining only those that contribute real information.

When quotation marks (including guillemets) are used, the question remains, how many should there be? The usual British practice is to use single quotes first, and doubles within singles: 'So does "analphabetic" mean what I think it means?' she said

suspiciously. When this convention is followed, most quotation marks will be singles and therefore less obtrusive.

Common American practice is the reverse: "So," she said, "does 'analphabetic' mean...?" This convention, using singles within doubles instead of doubles within singles, ensures that quotation flags will stand out. But some faces – Matthew Carter's Galliard, for example – have prominent quotation marks, while others have forms that are more discreet. Consider the face as well as the text when deciding which convention to follow in marking quotations.

Analphabetic Symbols

5.4.2 Position quotation marks consistently in relation to the rest of the punctuation.

Punctuation is normally placed inside a closing single or double guillemet if it belongs to the quotation, and outside otherwise. With other quotation marks, usage is less consistent. Most North American editors like their commas and periods inside the raised commas, "like this," but their colons and semicolons outside. Many British editors prefer to put all punctuation outside, with the milk and the cat. The kerning capabilities of digital typesetters, especially in the hands of advertising typographers, have evolved an intermediate third style, in which closing quotation marks are kerned over the top of commas and periods. Typographically, this is a good idea with some faces in large sizes, but a bad idea with many faces at text sizes, where a kerned quotation mark or apostrophe may look much like a question or exclamation mark.

"in."

"out".

### "kern, 'kerning,' kerned."

When quotation marks are not kerned, it makes no *typo-graphic* difference whether they follow commas and periods or precede them. The difference is one of editorial rather than visual discretion. But typographers, like editors, should be consistent, whichever route they choose.

5.4.3 Omit the apostrophe from numerical plurals.

Houses are built with  $2 \times 4s$ ; children and parents live through the terrible twos; Europeans killed as many Europeans in the 1930s as they did Native Americans and Africans in the 1800s.

### 5.4.4 Eliminate other unnecessary punctuation.

Omit the period after metric units and other self-evident abbreviations. Set 5.2 m and 520 cm but 36 in. or 36", and in bibliographical references, p 36f, or pp 396–424.

Quotation Marks and Other Intrusions North American editors and typesetters tend to put periods after all abbreviations or (more rarely) after none. The former practice produces a text full of birdshot and wormholes; the latter can cause confusion. As a form of compromise, the Oxford house style, which is widely followed in Britain, has much to commend it. This rule is: use a period only when the word stops prematurely. The period is omitted if the abbreviation begins with the first letter of the word and ends with the last. Thus: Mrs Bodoni, Mr John Adams Jr and Ms Lucy Chong-Adams, Dr McBain, St Thomas Aquinas, Msgr Kuruwezi and Fr O'Malley; but Prof. Czesław Miłosz and Capt. James Cook.

Periods are equally unnecessary in acronyms and other abbreviations written with small or large capitals. Thus: 3:00 AM and 450 BC; Washington, DC, and Mexico, DF; Vancouver, BC, and Darwin, NT.

In the interests of typographic hygiene, unnecessary hyphens should likewise be omitted. Thus: avant garde, bleeding heart, half-hearted, postmodern, prewar, silkscreen and typeface, in preference to the hyphenated alternatives. (It is good editorial practice, however, to hyphenate compound adjectives unless they can be fused into single words or will stand out as proper nouns. Thus, one finds twentieth-century typefaces in limited-edition books but publishes a limited edition at the end of the twentieth century and rides the New York Subway in New York. And one finds lowercase letters in the lower case.)

Apostrophes are needed for some plurals, but not for others, and inconsistency is better than a profusion of unnecessary marks. Thus: do's and don'ts; the ayes have it but the I's don't; the ewes are coming but the you's are staying home.

5.4.5 Add punctuation, or preserve it, where it is necessary to meaning.

The phrase *twenty one night stands* is ambiguous when written, but if the speaker knows what he means, it will be perfectly clear when spoken. Typography answers to vocal inflection in distinguishing *twenty one-night stands* from *twenty-one nightstands*.

In the careful language of science and poetry, hyphens can be more important still. Consider the following list of names: Douglas-fir, balsam fir, Oregon ash, mountain-ash, redcedar, yellowcedar, Atlas cedar, white pine, yellow pine, blue spruce. All these names are correct as they stand. They would be less so if an eager but ignorant editor, or a typographer obsessed with graphic hygiene, tried to standardize the hyphens. The terms are written differently because some are made from nouns that are only borrowed, others from nouns that are generic. The balsam fir is what it claims to be: a fir; the Douglas-fir is not; it is a separate genus waiting for a proper English name. The Oregon ash, likewise, is an ash, but the mountain-ash is not, and the Atlas cedar is a cedar, but redcedar and yellowcedar (or yellow-cedar) are not. The differences, though subtle, are perfectly audible in the speech of knowledgeable speakers (who say balsam fir and Douglas-fir and mountain-ash and Oregon ash). A good typographer will make the same distinctions subtly visible as well. In the present state of typographic art and editorial convention, this is done not by spattering the page with boldface syllables but by the judicious and subtle placement of hyphens.

Analphabetic Symbols

#### 5.5 DIACRITICS

5.5.1 Use the accents and alternate sorts that proper names and imported words and phrases require.

Simplicity is good, but so is plurality. Typography's principal function (not its only function) is communication, and the greatest threat to communication is not difference but sameness. Communication ceases when one being is no different from another: when there is nothing strange to wonder at and no new information to exchange. For that reason among others, typography and typographers must honor the variety and complexity of human language, thought and identity, instead of homogenizing or hiding it.

Typography was once a fluently multilingual and multicultural calling. The great typographers of the fifteenth and sixteenth centuries worked willingly with North Italian whiteletter, Italian or German blackletter, French script, Ashkenazi and Sephardic Hebrew, orthotic and cursive and chancery Greek. The best typographers of the twentieth century have followed their lead. But typographic ethnocentricity and racism also have thrived in

aaa  $x \approx \alpha x \dot{y}$ 

the last hundred years, and much of that narrow-mindedness is institutionalized in the workings of machines. Unregenerate, uneducated fonts and keyboards, defiantly incapable of setting anything beyond the most rudimentary Anglo-American alphabet, are getting scarcer but are still not difficult to find.

**Diacritics** 

Recent digital technology has made it possible for any typographer to create special characters on demand – a luxury most have been without since the seventeenth century. Prepackaged fonts of impeccable design, with character sets sufficient to set any word or name in any European and many Asian languages, and the software to compose and kern these characters, are also now available even to the smallest home and desktop operations. Yet there are large-circulation newspapers in North America still unwilling to spell correctly even the names of major cities, composers and statesmen, or the annual list of winners of the Nobel Prize, for fear of letters like ñ and é.

Neither typographers nor their tools should labor under the sad misapprehension that no one will enjoy or even mention crêpes flambées or aïoli, no one will have a name like Antonín Dvořák, Søren Kierkegaard, Stéphane Mallarmé or Chloë Jones, and no one will live in Óbidos or Århus, in Kroměříž or Øster Vrå, Průhonice, Nagykőrös, Dalasýsla, Kırkağaç or Köln.

5.5.2 Remap the font driver and keyboard to suit your own requirements.

The conventional computer keyboard includes a number of characters – @ # ^ + = { } | \ ~ < > - rarely required by most typesetters, while frequently needed characters, such as the en dash, em dash, acute accent, midpoint and ellipsis, are nowhere to be seen. Unless your keyboard fits your needs as is, remap it. It should give you ready access to whatever accented and analphabetic characters you regularly use.

Unless your composition software places ligatures automatically, you may find it easiest to insert them through a substitution routine after the text is fully set. Some typographers, however, (and I am one of them) prefer to rearrange their fonts or keyboards so that all the basic ligatures are accessible directly from the keyboard, as they are on a Monotype machine. Open and close quotes can also be inserted through substitution routines, but most typing and typesetting software will insert them automatically. (This means, of course, that in words or names such as

Dutch 's-Hertogenbosch or Navajo 'Áshijh 'Asdzáán, the software will always make the wrong choice, which the typographer must then correct by hand – or through yet another search-and-replace routine.)

Compositors who seldom use accented characters often prefer to set them through mnemonic codes, using a function key that momentarily redefines the keyboard. Software that operates in this way may produce  $\acute{o}$  from the combination o + /,  $\check{r}$  from r + v,  $\mathring{U}$  from U + o, and so on. But if you use accented characters with any frequency, you may find it worth your while to map them directly to the keyboard. One way to do this is to install the standard prefabricated keyboards for each language you may need. This, however, requires swapping from one to another as different languages or even different names come up in multilingual text, and it requires you to memorize a lot of different layouts. Another solution is to create a custom keyboard (or even several keyboards) that will meet your own particular requirements.

A typical customized keyboard for a Latin font is shown overleaf. The purpose of this particular layout is general multilingual text work. This could mean something as complex as polylingual manuals and packaging for technical products sold on the global market, or something as simple as addressing an envelope to Poland, or spelling the names correctly in the program for a symphony performance in Chicago or Detroit.

The keyboard shown accommodates more than twenty European languages, including Albanian, Basque, Breton, Catalan, Danish, Dutch, English, Faroese, Finnish, Flemish, French, Frisian, German, Hungarian, Icelandic, Italian, Norwegian, Polish, Portuguese, Romansch, Spanish, Swedish and Welsh. It will also accommodate many African and Native American languages and most of the Pacific languages written in Latin script (including Bahasa Indonesia, Bikol, Cebuano, Fijian, Hiligaynon, Ilocano, Malay, Tagalog and Tahitian).

Expanded to its maximum dimensions, a standard keyboard will give direct access to  $47 \times 6 = 282$  glyphs. This is enough to handle all current European versions of the Latin alphabet.

The individual characters are identified and discussed in appendices A & B, pages 288-320.

Analphabetic Symbols

Tagalog is the primary language of the Philippines. Bikol, Cebuano, Hiligaynon and Ilocano are other Philippine languages with several million speakers each.

	Cntrl SHIFT Plain Alt	i ! 1 â	Ŵ ŵ <b>2</b> ê	Ŷ ŷ 3 î	£ \$ 4 ô	ź % 5 û	Ź ° <b>6</b> Â	ż <b>&amp;</b> 7 Ê	Ż * 8 Î	í ( <b>9</b> Ô	Í ) o Û	ú Ú - -	× + =		
	Cntrl	Ø	É	È	Å	þ	Ý	Ù	Ì	Ò	_	Ś	ś		_
Sample	SHIFT	Q	W	E	R	T	Y	U	I	O	P	Ő	Ű		
Layout	Plain	q	W	e	r	t	y	u	i	0	P	[	]		
for an	Alt	Ø	é	è	å	þ	ý	ù	ì	Ò	9	ő	ű		
Expanded															_
Keyboard	Cntrl	À	<b>§</b>	Đ	Ä	Ë	Ϊ	Ö	Ü	Ł	Ÿ	Ć			
	SHIFT	A	S	D	F	G	H	J	K	L	:	"/"			
	Plain	a	S	d	f	g	h	j	k	1	;	<b>'/'</b>			
	Alt	à	ß	ð	ä	ë	ï	ö	ü	ł	ÿ	ć			
															_
	Cntrl	Ã	Õ	Ç	Ą	Ę	Ñ	Ó	<b>«</b>	<b>»</b>	કં		Ń	Æ	
	SHIFT	Z	X	C	$\mathbf{V}$	B	N	M	μ		?		Á	Œ	
	Plain	Z	X	c	v	b	n	m	,	•	/		á	œ	
	Alt	ã	Õ	ç	ą	ę	ñ	ó	a	•	0		ń	æ	

Ambiguous characters are as follows. **Row 1**: Shift-6 is the degree sign. Alt-hyphen is an en dash, and Alt-equal is an em dash. **Row 4**: Alt-comma is the ordinal A. Alt-period is a midpoint. The slash key is a virgule, not a fraction bar or solidus. Alt-slash is the ordinal O.

The two extra keys shown to the right in the bottom row are placed in different positions by different keyboard manufacturers. On an ordinary keyboard, one of these keys carries the backslash and pipe; the other carries the swung dash and floating grave. Here, the backslash key is reassigned to carry upper- and lowercase a-acute and n-acute. The swung dash key is reassigned to the four typographic diphthongs or ligatured vowels. The single and double quotation mark keys follow the "smart quotes" convention. All other keys are coded one to one; they give a single complete glyph for each stroke.

There are 188 characters in the keyboard layout shown. By employing the *Shift-Cntrl* and *Shift-Alt* combinations, another 94 characters can be added: enough to accommodate all variations on the Latin alphabet used in Eastern and Western Europe.

("Alt" and "Control" are keyboard codes of the PC persuasion. On the Macintosh keyboard, the counterparts are the "Option" and "Command" keys.)

#### 6.1 TECHNICAL CONSIDERATIONS

6.1.1 Consider the medium for which the typeface was originally designed.

6

Typographic purists like to see every typeface used with the technology for which it was designed. Taken literally, this means that virtually all faces designed before 1950 must be set in metal and printed letterpress, and the majority must be set by hand. Most typographers apply this principle in a more relaxed and complex way, and settle for preserving something rather than everything of a type's original character.

On the technical side, several things can be done to increase the chance that a letterpress typeface will survive translation to digital composition and offset printing.

6.1.2 When using digital adaptations of letterpress faces, choose fonts that are faithful to the spirit as well as the letter of the old designs.

Letterpress printing places the letterform *into* the paper, while offset printing lays it on the surface. Many subtle differences result from these two approaches to printing. The letterpress adds a little bulk and definition to the letter, especially in the thin strokes, and increases the prominence of the ends of thin serifs. Metal typefaces are designed to take advantage of these features of letterpress printing.

On the offset press – and in the photographic procedures by which camera-ready art and offset printing plates are prepared – thin strokes tend to get thinner and the ends of delicate serifs are eaten away. In a face like Bembo, for instance, offset printing tends to make features like the feet of i and l, and the heads and feet of H and I, slightly convex, while letterpress printing tends to make them slightly concave.

Faces designed for photographic manipulation and offset printing are therefore weighted and finished differently from letterpress designs. And adapting a letterpress face for digital composition is a far from simple task. Ili

Digital fonts poorly translated from metal originals are sometimes too dark or light or blunt throughout, or uneven in stroke weight, or faithless in their proportions. They sometimes lack text figures or other essential components of the original design. But digital translations can also be *too faithful* to the original. They sometimes neglect the subtle adjustments that the shift from three-dimensional letterpress to two-dimensional offset printing requires.

Technical Consider-

6.1.3 Choose faces that will survive, and if possible prosper, under the final printing conditions.

a a a a Bembo and Centaur, Spectrum and Palatino, are subtle and beautiful alphabets, but if you are setting 8 pt text with a laser printer on plain paper at 300 dpi, the refined forms of these faces will be rubbed into the coarse digital mud of the imaging process. If the final output will be 14 pt text set directly to plate at 2800 dpi, then printed by good offset lithography on the best coated paper, every nuance may be crystal clear, but the result will still lack the character and texture of the letterpress medium for which these faces were designed.

lr

Some of the most innocent looking faces are actually the most difficult to render by digital means. Optima, for example – an unserifed and apparently uncomplicated face – is (in its authentic form) entirely constructed of subtle tapers and curves that can be adequately rendered only at the highest resolutions.

a a a a Faces with blunt and substantial serifs, open counters, gentle modeling and minimal pretensions to aristocratic grace stand the best chance of surviving the indignities of low resolution. Amasis, Caecilia, Lucida Sans, Stone and Utopia, for example, while they prosper at high resolutions, are faces that will also survive under cruder conditions lethal to Centaur, Spectrum, Linotype Didot or almost any version of Bodoni.

6.1.4 Choose faces that suit the paper you intend to print on, or paper that suits the faces you wish to use.

Most Renaissance and Baroque types were made to be pressed into robust, lively papers by fairly robust means. They wilt when placed on the glossy, hard-surfaced sheets that came into vogue toward the end of the eighteenth century. Most Neoclassical and Romantic types, on the other hand, were designed to require smooth papers. Rough, three-dimensional papers break their fragile lines. Geometric Modernist types such as Futura, and overhauled Realist types such as Helvetica, can be printed on rough and smooth papers alike, because they are fundamentally *monochrome*. (That is to say, the stroke is nearly uniform in width.) But the aura of machine precision that emanates from a type like Futura is reinforced by a smooth paper and contradicted (*or* counterbalanced) by a paper that feels homespun.

The types associated with these historical categories are epitomized on pp 12–15 and explored in more detail in chapter 7.

#### 6.2 PRACTICAL TYPOGRAPHY

### 6.2.1 Choose faces that suit the task as well as the subject.

You are designing, let us say, a book about bicycle racing. You have found in the specimen books a typeface called Bicycle, which has spokes in the O, an A in the shape of a racing seat, a T that resembles a set of racing handlebars, and tiny cleated shoes perched on the long, one-sided serifs of ascenders and descenders, like pumping feet on the pedals. Surely this is the perfect face for your book?

Actually, typefaces and racing bikes are very much alike. Both are ideas as well as machines, and neither should be burdened with excess drag or baggage. Pictures of pumping feet will not make the type go faster, any more than smoke trails, pictures of rocket ships or imitation lightning bolts tied to the frame will improve the speed of the bike.

The best type for a book about bicycle racing will be, first of all, an inherently good type. Second, it will be a good type for books, which means a good type for comfortable long-distance reading. Third, it will be a type sympathetic to the theme. It will probably be lean, strong and swift; perhaps it will also be Italian. But it is unlikely to be carrying excess ornament or freight, and unlikely to be indulging in a masquerade.

### 6.2.2 Choose faces that can furnish whatever special effects you require.

If your text includes an abundance of numerals, you may want a face whose numerals are especially well designed. Palatino, Pontifex, Trump Mediäval and Zapf International, for example, all recommend themselves. If you prefer three-quarter-height lining numerals, your options include Bell, Trajanus and Weiss.

Practical Typography If you need small caps, faces that lack them (such as Frutiger and Méridien) are out of the running. If you need a range of weights, Spectrum is disqualified but Frutiger may work. If you need matching phonetics, your options include Stone Serif and Sans, Lucida Sans, and Times Roman. For the sake of a matching Cyrillic, you might choose Charter, Minion, Lazurski, Officina, Quadraat, Warnock, or, among the unserifed faces, Syntax, Myriad or Futura. For the sake of a matching Greek, you might choose Georgia or Palatino, or for the sake of a matching Cherokee, Plantagenet. To obtain a perfectly mated sanserif, you might choose Haarlemmer, Legacy, Lucida, Le Monde, Officina, Quadraat, Scala, Seria or Stone. These matters are explored in more detail in chapter 11, which addresses individual typefaces.

Special effects can also be obtained through more unorthodox combinations, which are the subject of §6.5.

### 6.2.3 Use what there is to the best advantage.

If there is nothing for dinner but beans, one may hunt for an onion, some pepper, salt, cilantro and sour cream to enliven the dish, but it is generally no help to pretend that the beans are really prawns or chanterelles.

When the only font available is Cheltenham or Times Roman, the typographer must make the most of its virtues, limited though they may be. An italic, small caps and text figures will help immensely if they can be added, but there is nothing to be gained by pretending that Times Roman is Bembo or Cheltenham is Aldus in disguise.

As a rule, a face of modest merits should be handled with great discretion, formality and care. It should be set in modest sizes (better yet, in one size only) with the caps well spaced, the lines well leaded, and the lower case well fitted and modestly kerned. The line length should be optimal and the page impeccably proportioned. In short, the typography should be richly and superbly *ordinary*, so that attention is drawn to the quality of the composition, not to the individual letterforms. Only a face that warrants close scrutiny should be set in a form that invites it.

Using what there is to best advantage almost always means using less than what is available. Baskerville, Helvetica, Palatino and Times Roman, for example – which are four of the most widely available typefaces – are four faces with nothing to offer

# Baskerville roman and its italic

# Helvetica roman and its oblique

Choosing and Combining Type

# Palatino roman and its italic

## Times New Roman and its italic

Baskerville is an English Neoclassical face designed in Birmingham in the 1750s by John Baskerville. It has a rationalist axis, thoroughgoing symmetry and delicate finish.

Helvetica is a twentieth-century Swiss revision of a late nineteenth-century German Realist face. The first weights were drawn in 1956 by Max Miedinger, based on the Berthold Foundry's old Odd-job Sanserif, or Akzidenz Grotesk, as it is called in German. The heavy, unmodulated line and tiny aperture evoke an image of uncultivated strength, force and persistence. The very light weights issued in recent years have done much to reduce Helvetica's coarseness but little to increase its readability.

Palatino is a lyrical modernist face with a neohumanist architecture, which is to say that it is *written*, not drawn, and that it is based on Renaissance forms. It was created in 1948 by Hermann Zapf.

Times Roman – properly Times New Roman – is an historical pastiche drawn by Victor Lardent for Stanley Morison in London in 1931. It has a humanist axis but Mannerist proportions, Baroque weight, and a sharp, Neoclassical finish.

one another except public disagreement. None makes a good companion face for any of the others, because each of them is rooted in a different concept of what constitutes a letterform. If the available palette is limited to these faces, the first thing to do is choose *one* for the task at hand and ignore the other three.

### Historical Considerations

#### 6.3 HISTORICAL CONSIDERATIONS

Typography, like other arts, preys on its own past. It can do so with the callousness of a grave robber, or with the piety of unquestioning ancestor worship. It can also do so in thoughtful, enlightened and deeply creative ways.

Roman type has been with us for more than five centuries. Its root components – the roman upper and lower case, basic analphabetic symbols, and the arabic numerals – have been with us for much longer yet. There are typographers who resolutely avoid using any typeface designed in an earlier era, but even they must learn something of how the older letterforms functioned, because the ancient forms are living in the new. Typographers who willingly use the old faces, and who wish to use them intelligently, need to know all they can learn about the heritage they enjoy.

6.3.1 Choose a face whose historical echoes and associations are in harmony with the text.

## abc abc

Any contemporary library will furnish examples of typographic anachronism. There are books on contemporary Italy and on seventeenth-century France set in typefaces such as Baskerville and Caslon, cut in eighteenth-century England. There are books about the Renaissance set in faces that belong to the Baroque, and books about the Baroque set in faces from the Renaissance. To a good typographer it is not enough merely to avoid these kinds of laughable contradictions. The typographer seeks to *shed light* on the text, to generate insight and energy, by setting every text in a face and form in which it actually belongs.

It is not that good typographers object to mixing centuries and cultures. Many take delight in doing so – especially when they have no other choice. A text from ancient Athens, for example, cannot be set in an ancient Athenian version of roman type. A face designed in North America in the 1990s may well be used instead. Texts from seventeenth-century France or eighteenth-

century England also might be set perfectly well in faces of recent design. But a face that truly suits an historical text is likely to have some fairly clear historical content of its own. There is no typeface *equally suited* to texts from Greek antiquity, the French Baroque and the English Neoclassical period – though faces equally *unsuited* to each of them abound.

The historical affiliations of individual typefaces are discussed in chapters 7 and 11.

Choosing and Combining Type

6.3.2 Allow the face to speak in its natural idiom.

Books that leap historical boundaries and mix historical subjects can pose complex and exciting typographic problems. But often, if a text calls for a Renaissance type, it calls for Renaissance typography as well. This usually means Renaissance page proportions and margins, and an absence of bold face. It may also mean large Renaissance versals, Renaissance style in the handling of quotations, and the segregation of roman and italic. If the text calls for a Neoclassical type, it likewise often calls for Neoclassical page design. When you undertake to use an historical typeface, take the trouble to learn the typographic idiom for which it was intended. (Works of reference that may be useful in solving particular problems are listed in the bibliography, page 357.)

#### 6.4 CULTURAL & PERSONAL CONSIDERATIONS

6.4.1 Choose faces whose individual spirit and character is in keeping with the text.

Accidental associations are rarely a good basis for choosing a typeface. Books of poems by the twentieth-century Jewish American poet Marvin Bell, for example, have sometimes been set in Bell type – which is eighteenth-century, English and Presbyterian – solely because of the name. Such puns are a private amusement for typographers; they also sometimes work. But a typographic page so well designed that it attains a life of its own will be based on real affinities, not on an inside joke.

Letterforms have character, spirit and personality. Typographers learn to discern these features through years of working first-hand with the forms, and through studying and comparing the work of other designers, present and past. On close inspec-

abc abc tion, typefaces reveal many hints of their designers' times and temperaments, and even their nationalities and religious faiths. Faces chosen on these grounds are likely to give more interesting results than faces chosen through mere convenience of availability or coincidence of name.

aa aa aG If, for example, you are setting a text by a woman, you might prefer a face, or several faces, designed by a woman. Such faces were rare or nonexistent in earlier centuries, but there are now a number to choose from. They include Gudrun Zapf-von Hesse's admirable Alcuin, Carmina, Diotima and Nofret families; Elizabeth Friedländer's Elizabeth; Kris Holmes's Sierra and Lucida; Kris Holmes's and Janice Prescott Fishman's Shannon; Carol Twombly's handsome text face Chaparral and her titling faces Charlemagne, Lithos, Nueva and Trajan; Zuzana Ličko's Journal and Mrs Eaves, and Ilse Schüle's Rhapsodie. For some purposes, one might also go back to the work of Elizabeth Colwell, whose Colwell Handletter, issued by ATF in 1916, was the first American typeface designed by a woman.

But perhaps a text by a French author, or a text dealing with France, might best be set in a French typeface, without regard to the gender of author or designer. The choices include Garamond, Jannon, Mendoza, Méridien, Vendôme and many others, but even this abbreviated list covers considerable range. Garamond - of which there are many recent revivals - was designed in sixteenthcentury Paris. It owes much to Italian forms and belongs to the world of Renaissance Catholicism. Jannon is equally elegant but nonconformist. It belongs to the Reformation rather than the Renaissance, and its designer, Jean Jannon, was a French Protestant who suffered all his life from religious persecution. Vendôme, designed by François Ganeau, is a witty twentieth-century face much indebted to Jannon. Mendoza, designed in Paris in 1990, goes back to the tough humanist roots from which Garamond sprang. Méridien, from the 1950s, is more in touch with the secular spirit of twentieth-century Swiss industrial design, yet it includes a regal, even imperious, upper case and a very crisp and graceful italic. These five different faces invite additional differences in page design, paper and binding as well as different texts, just as different musical instruments invite different phrasings, different tempi, different musical modes or keys.

Even nations such as Greece and Thailand, which have alphabets of their own, share in a multinational tradition of type

# Garamond roman and its italic

Jannon roman and its italic

Choosing and Combining Type

# Mendoza roman and its italic

## Méridien roman and its italic

# Vendôme roman and its oblique

Stempel Garamond is the Stempel Foundry's replica of a text roman and italic designed by Claude Garamond (c. 1490–1561). (Compare the reproductions of some of Garamond's actual type on page 74.)

Monotype 'Garamond' 156 is a revival of a type designed by Jean Jannon (1580–1658), the greatest typecutter of the French Baroque. Jannon's type was once misidentified as Garamond's and is still routinely sold under his name.

Mendoza was designed about 1990 by José Mendoza y Almeida. Adrian Frutiger's Méridien and François Ganeau's Vendôme are products of the 1950s. Ganeau – who worked as a painter, sculptor and set designer more than as a typographer – based Vendôme on Jannon's letters, but moved them playfully in the direction of French Neoclassicism.

design. Nevertheless, some typefaces seem more redolent of national character than others. Frederic Goudy, for example, is widely regarded as the most ebulliently American of all American type designers. The sensitive typographer would not choose one of Goudy's faces to set, let us say, the text of the Canadian or Mexican constitution.

Cultural and Personal Considerations This subject is a lifelong study, and for serious typographers it is a lifelong source of discovery and delight. Here it is pursued at greater length in chapter 11. Appendix D (page 333) is a cross-indexed list of type designers.

#### 6.5 THE MULTICULTURAL PAGE

Consistency is one of the forms of beauty. Contrast is another. A fine page, even a fine book, can be set from beginning to end in one type in one size. It can also teem with variety, like an equatorial forest or a modern city.

### 6.5.1 Start with a single typographic family.

Most pages, and most entire documents, can be set perfectly well with only one family of type. But perhaps the page confronting you requires a chapter title, two or three levels of subheads, an epigraph, a text in two languages, block quotations within the text, a couple of mathematical equations, a bar graph, several explanatory sidenotes, and captions for photographs and a map. An extended type family, such as Legacy, Lucida, Quadraat, Seria or Stone, may provide sufficient resources even for this task. Another possibility is Gerard Unger's comprehensive series known as Demos, Praxis and Flora - which is a family with no surname to unite it. Each of these series includes both roman and italic in a range of weights, matching serifed and unserifed forms, and other variations. If you restrict yourself to faces within the family, you can have variety and homogeneity at the same time: many shapes and sizes but a single typographic culture. Such an approach is well suited to some texts, poorly suited to others.

**a A a** a A a

a A a

You can also, of course, mix faces at random, by drawing them out of a hat.

Between these two extremes is the wide arena of thoughtful mixing and matching, in which the typographic intelligence often does its most creative work and play.

### 6.5.2 Respect the integrity of roman, italic and small caps.

It has been the normal practice of type designers since the middle of the sixteenth century to offer text faces in the form of a matched triad, consisting of roman, italic and small caps. Because some of these marriages are more successful than others, it is wise to examine the roman and the italic both separately and together when choosing a text face.

There are several celebrated instances in which an italic designed by one artist has been happily and permanently married to another designer's roman. These matches always involve some redrawing (and the face that is most heavily redrawn is almost always the italic, which is the subsidiary and 'feminine' font in post-Renaissance typography). There are also instances in which a roman and its italic have been designed by the same artist many years apart. But casual liaisons, in which the roman of one family is paired momentarily with the italic of another, have little hope of success. Mixing small caps from one face with full caps from another is even less likely to succeed.

If you use type strictly in the Renaissance manner, treating the roman and italic as separate but equal, not mixing them on the line, you may find that greater latitude is possible. Jan van Krimpen's Lutetia italic mixes well with his later Romanée roman, for example, if the two are not too intimately combined. One is visibly more mature than the other, but they are close in color and structure, and they are patently the work of the same designer.

### 6.5.3 Consider bold faces on their own merits.

The original boldface printing types are the blackletters used by Gutenberg in the 1440s. For the next two centuries, blackletter fonts were widely used not only in Germany but in France, Spain, the Netherlands and England. (That is why blackletter fonts are occasionally sold in the USA as 'Olde English.')

Boldface romans, however, are a nineteenth-century invention. Bold italic is even more recent, and it is hard to find a successful version designed before 1950. Bold romans and italics have been added retroactively to many earlier faces, but they are often simply parodies of the original designs.

Before using a bold weight, especially a bold italic, ask yourself whether you really need it at all. If the answer is yes, you may want Choosing and Combining Type



to avoid type families such as Bembo, Garamond or Baskerville, to which bold weights have been retroactively added but do not in fact belong. You might, instead, choose a twentieth-century family such as Apollo, Nofret or Scala, in which a range of weights is part of the original design.

The Multicultural Page If your text face lacks a bold weight, you may also find an appropriate bold close by. Hermann Zapf's Aldus, for example, is a twentieth-century family on the Renaissance model, limited to roman, italic and small caps. But Aldus is a close cousin of the same designer's Palatino family, which does include a bold, and Palatino bold sits comfortably enough with Aldus text.

### a aardvark; b balloon; 3 thruppence

Aldus 16 pt roman and italic with Palatino 15 pt bold

Equally interesting results can often be obtained by reaching much farther afield. The normal function of boldface type is, after all, to contrast with the roman text. If the bold is used in small amounts, and bold and roman are not too intimately combined, a difference in structure as well as weight may be an asset. Under these conditions, a typographer is free to choose both roman and bold on their own merits, seeking basic compatibility rather than close genetic connection.

### c chinstrap; d daffodil; 6 saxophone

Sabon 16 pt roman and italic with Zapf International 15 pt demibold

A text might be set in Sabon, for example, with Zapf International as a titling face and Zapf International demi or heavy for subheads and flags. Structurally, these are very different faces, with very different pedigrees. But Sabon has the calm and steady flow required for setting text, while Zapf International's vitality makes it a good face for titling – and this vitality persists even in the boldest weights. The bold weights of fonts that are closer in structure Sabon often look splayed and deformed.

Fifteenth-century typographers – Nicolas Jenson for example – rarely mixed fonts except when mixing languages. They loved an even page. Bold roman is therefore an appendage they did happily without. If, nevertheless, you were using one of the fine text faces

based on Jenson's single roman font and wanted to embellish it with bold, you might consider using Jenson's kind of bold. The only dark faces he cut were blackletters.

### Elève elephant; fool filibuster; lví phytogenic

Bruce Rogers's Centaur (here 16 pt) with Karlgeorg Hoefer's San Marco (12 pt). Centaur is based on the roman that Nicolas Jenson cut at Venice in 1469. San Marco is based on the rotundas he cut there in the 1470s.

Choosing
and
Combining
Type

6.5.4 Choose titling and display faces that reinforce the structure of the text face.

Titling faces, display faces and scripts can be chosen on much the same principles as bold faces. Incestuous similarity is rarely a necessity, but empathy and compatibility usually are. A geometrically constructed, high-contrast face such as Bauer Bodoni, beautiful though it may be, has marginal promise as a titling face for a text set in Garamond or Bembo, whose contrast is low and whose structure is fundamentally calligraphic. (Bodoni mixes far more happily with Baskerville – of which it is not a contradiction but rather an exaggeration.)

6.5.5 Pair serifed and unserifed faces on the basis of their inner structure.

When the basic text is set in a serifed face, a related sanserif is frequently useful for other elements, such as tables, captions or notes. In complicated texts, such as dictionary entries, it may also be necessary to mix unserifed and serifed fonts on the same line. If you've chosen a family that includes a matched sanserif, your problems may be solved. But many successful marriages between serifed and unserifed faces from different families are waiting to be made.

### Frutiger Méridien Univers

Suppose your main text is set in Méridien – a serifed roman and italic designed by Adrian Frutiger. It would be reasonable to look first of all among Frutiger's other creations for a related sanserif. Frutiger is a prolific designer of types, both serifed and

The version of Frutiger used here is the recent revision known as Frutiger Next. unserifed, so there are several from which to choose. Univers is his most widely used sanserif. But another of his unserifed faces – the one to which he gave his own name – is structurally much closer to Méridien and works handsomely as a companion.

The Multicultural Page Hans Eduard Meier's Syntax is a sanserif much different in structure from either Frutiger or Univers. It is based on serifed Renaissance forms like those of Garamond. It works well with such faces as Stempel or Adobe Garamond, or with Sabon, another descendant of Garamond, designed by Meier's contemporary and countryman, Jan Tschichold.

If your choice falls on a more geometric sanserif, such as Futura, a Renaissance roman will hardly suffice as a serifed companion. Many romans based on the work of Bodoni, however, breathe much the same spirit as Futura. They aspire not to calligraphic motion but to geometric purity.

## Gabocse escobaG Gabocse escobaG Gabocse escobaG

Syntax and Minion, above; Futura and Berthold Bodoni, center; Helvetica and Haas Clarendon, below.

6.6 MIXING ALPHABETS

6.6.1 Choose non-Latin faces as carefully as Latin ones.

a ĸ a ĸ

ax

Mixing Latin letters with Hebrew or Arabic is, in principle, scarcely different from mixing roman with blackletter or serif with sans. Different though they look, and even though they read in different directions, all these alphabets spring from the same source, and all are written with similar tools. Many structural similarities underlie the obvious differences. A book involving more than one alphabet therefore poses some of the same questions posed by a bilingual or polylingual book set entirely in Latin letters. The typographer must decide in each case – after studying the text – whether to emphasize or minimize the differences. In general, the more closely different alphabets are mixed, the more

important it becomes that they should be close in color and in size, no matter how superficially different in form.

The Latin, Greek and Cyrillic alphabets are as closely related in structure as roman, italic and small caps. (And in most Cyrillic faces, the lower case is close in color and shape to Latin small caps.) Random marriages of Latin and Greek, or Latin and Cyrillic, look just as ungainly and haphazard as random combinations of roman, italic and small caps – but excellent sets of related faces have developed, and a few homogeneous polyglot families have been designed.

Choosing and Combining Type

Plato and Aristotle both quote the line of Parmenides that says πρώτιστον μὲν Ἔρωτα θεῶν μητίσατο πάντων: "The first of all the gods to arise in the mind of their mother was PHYSICAL LOVE."

Греки боготворили природу и завещали миру свою религию, то есть философию и искусство, says a character named Shatov in Dostoevsky's novel Demons: "The Greeks deified nature and bequeathed to the world their religion, which is philosophy and art."

Robert Slimbach's Minion roman, italic and small caps, with upright and cursive forms of Minion Cyrillic and Minion Greek.

The text on this page is set in ITC Mendoza 10/13 with 12 pt GFS Neo Hellenic. On the facing page, the roman and italic are Figural 10/13; the Greek is 10.5 pt GFS Porson. The caps in both Greek fonts have been resized. (The original edition of Cornford's book, printed in 1912, was set in the curious combination

> of Century Expanded and

Porson Greek.)

ΥΣΙΣ AS THE SOUL / THE SOUL AS ΓΝΩΣΙΣ. The second proposition of Thales declares that the All is alive, or has Soul in it (τὸ πᾶν ἔμψυχον). This statement accounts for the mobility of φύσις. Its motion, and its power of generating things other than itself, are due to its life (ψυχή), an inward, spontaneous principle of activity. (Cf. Plato, Laws 892c: φύσιν βούλονται λέγειν γένεσιν τὴν περὶ τὰ πρῶτα· εἰ δὲ φανήσεται ψυχὴ πρῶτον, οὐ πῦρ οὐδὲ ἀἡρ, ψυχὴ Δ' ἐν πρώτοις γεγενημένη, σχεδὸν ὀρθότατα λέγοιτ' ἄν εἶναι διαφερόντως φύσει.)...

It is a general rule that the Greek philosophers describe φύσις as standing in the same relation to the universe as soul does to body. Anaximenes, the third Milesian, says: οἶον ἡ ψυχὴ ἡ ἡμετέρα ἀἡρ οὖσα συγκρατεῖ ἡμᾶς, καὶ ὅλον τὸν κόσμον πνεῦμα καὶ ἀἡρ περιέχει. "As our soul is air and holds us together, so a breath or air embraces the whole cosmos." ...

The second function of Soul – knowing – was not at first distinguished from motion. Aristotle says, φαμὲν γὰρ τὴν ψυχὴν λυπεῖσθαι χαίρειν, θαρρεῖν φοβεῖσθαι, ἔτι δὲ ὀργίζεσθαί τε καὶ αἰσθάνεσθαι καὶ διανοεῖσθαι· ταῦτα δὲ πάντα κινήσεις εἶναι δοκοῦσιν. ὅθεν οἰηθείη τις ἄν αὐτὴν κινεῖσθαι. "The soul is said to feel pain and joy, confidence and fear, and again to be angry, to perceive, and to think; and all these states are held to be movements, which might lead one to suppose that soul itself is moved." Senseperception (αἴσθησις), not distinguished from thought, was taken as the type of all cognition, and this is a form of action at a distance.<sup>3</sup>

<sup>1</sup> Frag. 2. Compare Pythagoras' "boundless breath" outside the heavens, which is inhaled by the world (Arist., *Phys.* 213*b*22), and Heraclitus' "divine reason," which surrounds (περιέχει) us and which we draw in by means of respiration (Sext. Emp., *Adv. Math.* vii.127).

<sup>2</sup> De anima 408b1.

<sup>3</sup> De anima 410a25: Those who make soul consist of all the elements, and who hold that like perceives and knows like, "assume that perceiving is a sort of being acted upon or moved and that the same is true of thinking and knowing" (τὸ Δ΄ αἰσθάνεσθαι πάσχειν τι καὶ κινεῖσθαι τιθέασιν ὁμοίως δὲ καὶ τὸ νοεῖν τε καὶ γιγνώσκειν).

All such action, moreover, was held to require a continuous vehicle or medium, uniting the soul which knows to the object which is known. Further, the soul and its object must not only be thus linked in physical contact, but they must be *alike* or *akin*....

It follows from this principle that, if the Soul is to know the world, the world must ultimately consist of the same substance as Soul.  $\Phi \acute{v}\sigma \iota s$  and Soul must be homogeneous. Aristotle formulates the doctrine with great precision:

ὅσοι δ' ἐπὶ τὸ γινώσκειν καὶ τὸ αἰσθάνεσθαι τῶν ὅντων, οὖτοι δὲ λέγουσι τὴν ψυχὴν τὰς ἀρχάς, οἱ μὲν πλείους ποι-οῦντες, ταύτας, οἱ δὲ μίαν, ταύτην, ὥσπερ Ἐμπεδοκλῆς μὲν ἐκ τῶν στοιχείων πάντων, εἶναι δὲ καὶ ἕκαστον ψυχὴν τούτων, λέγων οὕτως

γαίη μὲν γὰρ γαῖαν ὀπώπαμεν, ὕδατι δ' ὕδωρ, αἰθέρι δ' αἰθέρα δῖαν, ἀτὰρ πυρὶ πῦρ αΐδηλον, στοργῆ δὲ στοργήν, νεῖκος δέ τε νείκεϊ λυγρῷ.

τὸν αὐτὸν δὲ τρόπον καὶ Πλάτων ἐν τῷ Τιμαίω τὴν ψυχὴν ἐκ τῶν στοιχείων ποιεῖ· γιγνώσκεσθαι γὰρ τῷ ὁμοίῳ τὸ ὅμοιον, τὰ δὲ πράγματα ἐκ τῶν ἀρχῶν εἶναι.

"Those who laid stress on its knowledge and perception of all that exists, identified the soul with the ultimate principles, whether they recognized a plurality of these or only one. Thus, Empedocles compounded soul out of all the elements, while at the same time regarding each one of them as a soul. His words are,

«With earth we see earth, with water water, «with air bright air, ravaging fire by fire, «love by love, and strife by gruesome strife.

«In the same manner, Plato in the *Timaeus* constructs the soul out of the elements. Like, he there maintains, is known by like, and the things we know are composed of the ultimate principles....»<sup>4</sup>

facing page are adapted from F.M. CORNFORD'S From Religion to Philosophy: A Study in the Origins of Western Speculation (London, 1912). Some of the Greek quotations have been extended, and some have been moved from the footnotes into the main text. This makes Cornford's prose seem more pedantic and less lucid than it really is, but it poses a harder test for the type and at the same time permits a more compact typographic demonstration.

The texts on this and the

<sup>4</sup> De anima 404b8-18.

These lines are from \$5 of Anna Akhmatova's В сороковом году. Но я предупреждаю вас, But I'm warning you, Что я живу в последний раз. this is my last existence.

Ни ласточкой, ни кленом,
Not as a swallow, not as a maple,
Ни тростником и ни звездой ...
not as a cat-tail and not as a star ...

The words of Anna Akhmatova in the letters of Vadim Lazurski. The type is Lazurski Cyrillic with its companion roman.

Greek letters, like Greek words, are used for many purposes in non-Greek-speaking countries. Physicists and fraternity members, astronomers and novelists have raided the old alphabet for symbols. Because of their frequent use in mathematics and technical writing, a grab-bag of Greek letters lurks somewhere in nearly every digital typesetting system.  $\alpha, \beta, \gamma, \theta, \pi, \Omega$  (alpha, beta, gamma, theta, pi, cap omega) and their brethren are usually housed, with other mathematical symbols, in a ghetto called the pi font. But setting Greek *text* with such a font is not a thankful task. Pi fonts lack the breathing marks and accents used in the classical language, and even the two simple diacritics (acute and diaeresis) that survive in modern Greek; and some pi fonts include only ten Greek caps –  $\Gamma$   $\Delta$   $\Theta$   $\Lambda$   $\Xi$   $\Pi$   $\Sigma$   $\Phi$   $\Psi$   $\Omega$  – because the others –  $\Lambda$  B E H Z I K M N O P T Y X – have familiar roman forms, though not in every case the same phonetic value.

A text that includes even a single Greek quotation calls for a Greek text font rather than a pi font. A text font will include not only the full alphabet but matching punctuation and all the monotonic (modern) or polytonic (classical) diacritics. It will include two forms of lowercase sigma ( $\varsigma$ , used at the ends of words, and  $\sigma$ , used everywhere else). If it is a polytonic font, it will include

in addition three sets of long vowels with iota subscripts ( $\check{\alpha}$ ,  $\check{\eta}$ ,  $\dot{\psi}$ , etc). With luck, the font will include a sensible kerning table as well. This is a lot to ask from an industry in which there is, officially, no culture other than commerce and no purpose except monetary gain. It is a lot to ask, but not by itself enough. In Greek as in any other alphabet, the face must suit the text. It must also suit the context, which is likely to be roman and italic.

There may be 60,000 fonts of type for the Latin alphabet now on the market in digital form. These comprise some 7,000 families. Perhaps two per cent of them are truly useful for text work – but a hundred families of type is still a very generous number, and the available text faces cover a wide stylistic range. With a little scrounging, one can turn up several dozen digital fonts of Greek – but again, only a small percentage of these have any real potential for text work. It is therefore often best to choose a Greek font *first*, and then a roman and italic to go with it, even when only a few Greek words or a single Greek quotation is present in the text you are going to set.

Two Greek text fonts with eminent credentials – Victor Scholderer's New Hellenic, designed in 1927, and Richard Porson's Porson, designed in 1806 – are shown, in their digital incarnations, on pages 108–109. Porson's Greek was first commissioned by Cambridge University Press, but it became in the twentieth century the favorite Greek at Oxford, while Scholderer's New Hellenic became the favorite Cambridge Greek. New Hellenic in particular has an eminent Renaissance pedigree further discussed in §11.7.

6.6.2 Match the continuity of the typography to the continuity of thought.

A text composed in a single dialect may be full of leaps and holes, while a text that hops and skips through several languages and alphabets may in fact be tracing a path that is perfectly smooth. The continuity, or lack of continuity, that underlies the text should as a rule be revealed, not concealed, in the cloth the typographer weaves.

An author who quotes Greek or Hebrew or Russian or Arabic fluently and gracefully in speech should be permitted to do likewise on the page. Practically speaking, this means that when the alphabets are mixed, they should be very closely balanced both in *color* and in *contrast*.

Choosing and Combining Type



# abyohi ἄβγοθι abyohi abyohi ἄβγοθι abyohi ἄβγοθι abyohi

Mixing Alphabets

Victor Scholderer's New Hellenic paired with José Mendoza's Mendoza (above), with Peter Matthias Noordzij's Caecilia (center) and with Adobe Jenson (below). Mendoza is a face with very low contrast (the thicks and thins are nearly the same). New Hellenic and Caecilia have an unmodulated stroke – in other words, no contrast at all. New Hellenic and Adobe Jenson have stylistic compatibility of a different kind. Both stem from the work of Nicolas Jenson, who in 1469 cut the father of this roman and in 1471 the grandfather of this Greek.

Flow and slope are other factors to consider, especially when balancing Latin and Greek. Many Greek text faces (the Porson and Didot Greeks for example) are structurally comparable to italics. That is, they are cursive. Some of them are upright nonetheless (like the Didot), and some (like the Porson) slope. When roman, italic and Greek are combined on the page, the Greek may be upright like the roman, or it may harmonize with the italic in flow and slope. It may also stand aloof, with a gait and inclination of its own.

#### 6.6.3 Balance the type optically more than mathematically.

Two other factors of importance when types sit side by side are their torso (x-height) and extension. When a long-limbed Greek is paired with a short-limbed Latin, the difference will stand out. Large disparities in x-height are far more obvious still. In metal, this is a harsh typographic constraint. In the digital medium, it is easy to match the torso of any Greek face to that of any Latin face exactly, through microscopic adjustments in size. But an optical, not mathematical, match is the goal. Classical Greek, beneath its cloud of diacritics, needs more room to breathe than roman type. And when setting Greek in footnotes, the minimum practical size is the size at which the accents are still legible.

# abyohi ἄβγοθι abyohi abyohi ἄβγοθι abyohi ἄβγοθι abyohi

Choosing and Combining Type

Above: The Greek of Richard Porson paired with W. A. Dwiggins's Electra. Center: Didot Greek paired with Adobe Caslon. Below: The Bodoni Greek of Takis Katsoulides paired with the Esprit roman and italic of Jovica Veljović. Electra italic and Porson Greek both have a slope of 10°, while the Caslon italic slopes at 20°. Porson, with its rationalist axis, also has a structural kinship to Electra. The Didot Greek, though Neoclassical in form, is closer in color to Caslon. Katsoulides's more playful Bodoni Greek is closer both in structure and in spirit to Esprit.

The type on page 109 looked fine when it was first roughed out in bald Greek letters identical in x-height to the roman. When the bald sorts were replaced with accented letters, the Greek was still mathematically correct but optically too large. Balance was restored by shrinking the Greek from 11 to 10.5 pt. The x-height of the type is (as usual in a Neoclassical text face) only about two fifths of the body size. The difference in x-height between 10.5 and 11 pt type is accordingly two fifths of half a point. That is roughly 70  $\mu$ m, which is less than 0.003 inch. Not much, but enough to unbalance or balance the page.

#### 6.7 NEW ORTHOGRAPHIES

No writing system is fixed. Even our ways of writing classical Latin and Greek continue to change, along with our ways of writing and spelling such rapidly mutating languages as English. But many languages old to speech are new to writing, and many have not yet decided their literate form.

In North America, for example, Navajo, Hopi, Tlingit, Cree, Ojibwa, Inuktitut and Cherokee, among others, have evolved quite stable writing systems, in which a substantial printed literature has accrued. But many Native American languages are still being written in different ways by every scholar and student who hap-





pens by. Some, like Tsimshian, Fox and Kwakwala, already possess a considerable written literature, but in cumbersome scripts that even scholars have ceased to use.

Typographers must generally confront these problems piecemeal. Alphabets are often created by fiat, but it is usually in tiny increments that real typographic style evolves.

New Orthographies

6.7.1 Add no unnecessary characters.

đğ Ђљ ě ĉ Colonial expansion has carried the Arabic alphabet across the north of Africa and much of southern Asia, Cyrillic script across the north of Asia, and the Latin alphabet around the world. For better or for worse, most of those learning to read and write in newly literate languages are exposed to writing in a colonial language first. For readers and typographers alike, the basic Latin, Cyrillic or Arabic alphabet is therefore often the easiest place to start, and the fewer additional symbols required the better. The dream of a common language, imposed upon many minority cultures, has proven for most to be a nightmare. But in a world where there are hundreds of ancestral and classical languages and literatures instead of one or two, prayers for renewed diversification often entail the dream of a common script.

Wa'giên sq!ê'ngua lā'na hîn sā'wan, "K!wa la t!āla'n ł gia'Ļītc!în."

Wagyaan sqqinggwa llaana hin saawan, "Kkwa lla ttaalang hl gyadliittsin."

A sentence in the Haida language, in the earliest standard orthography (first used in 1900) and a more recent, simplified version. In the former, glottalized consonants are marked by exclamations and long vowels by macrons. In the latter, both are notated by doubling. (Translation: Then the one in the bow said, 'Let us take it aboard.')

6.7.2 Add only characters that are visually distinct.

The texture of the typographic page depends not only on how the type is designed, set and printed, but also on the frequency of different letters. Latin looks smoother than English (and much smoother than German) because it uses fewer ascending and descending letters, no accented characters, and (in the hands of most editors) very few caps. Polynesian languages – Maori and Hawaiian, for example – which are long on vowels and short on consonants, compose into a texture even creamier than Latin, and require an even smaller alphabet.

Most languages need more, not fewer, consonants than the basic Latin alphabet provides. There may be (as in Haida and Tlingit) four forms of k, or (as in the Khoisan languages of southwest Africa) 36 different clicks – and if each is lexically significant, each needs a distinctive typographic form.

Consonants are not quite so easy to ramify, just because so many have extenders. Typographically deficient forms therefore often crop up. Lakhota, for example – the language of the Sioux – requires two forms of h. The missionary Stephen Riggs, who published the first Lakhota dictionary and grammar in 1852, chose to mark the second form with an overdot: h. This character is easily mistaken for h. More recent Lakhota orthographies (including the Txakini system, developed by Violet Catches, a native speaker) replace Riggs's dotted h with h. This is easier to type. More importantly, it is harder to misread.

In the Tlingit language, spoken and written in southern Alaska, northern British Columbia and the Yukon, underscores are used to mark uvular consonants, which is fine for  $\underline{k}$  and  $\underline{x}$ , but maybe not so fine for  $\underline{g}$ . A form like  $\dot{g}$  or  $\check{g}$  or  $\check{g}$ , though less consistent, is more compact and, once again, harder to misread.

The desire for consistency was not the only factor that led earlier linguists to write g instead of ğ. The Tlingit alphabet was developed, like many early twentieth-century writing systems, using only the keyboard of a North American typewriter. Recent Tlingit publications are typeset with computers using modified fonts of Palatino or Stone, but the iron metaphor of the typewriter has not yet loosed its hold.

Elsewhere in the world, the mechanical typewriter and letterpress are still economically viable tools – and this need not prevent new alphabet design. The Pan Nigerian face shown overleaf was cut and cast commercially for hand composition in 1983. Mechanical typewriters using a monospaced version of the font entered production in 1985. Digital versions now also exist.

In the Navajo alphabet (saad bee 'ál'íní), long vowels are written double and nasal vowels are written with an ogonek. High tone is marked with an acute. Long high vowels carry two acutes, one on each vowel. Long falling vowels carry an acute on the first vowel only, long rising vowels carry an acute on the second vowel only. Glottalized (ejective) consonants are followed by apostrophes.

#### àbbcddeəéfghiîíjkkl ABBCDDE∃ÉFGHIIJKKL MNÒPRSŞTÛŪVWYZ mnòoprsștûūvwyz

New Orthographies

Pan-Nigerian alphabet designed in 1983 by Hermann Zapf, in collaboration with Victor Manfredi. This normalizes the missionary orthographies that had been used for Hausa, Igbo, Yoruba, Edo, Fulfulde and several other Nigerian languages.

6.7.3 Avoid capricious redefinition of familiar characters.

Mayan languages have been written in roman script since the 1550s, but more than one orthography remains in use. Perhaps the oldest, based on the manuscript tradition of the *Popol Vuh*, uses the numerals 3 and 4 and the digraphs 4h and 4, [including the comma] to write glottalized consonants. The Quiché words for sun and moon, for example, can be written *k'ih* and *ic'*, or *kkih* and *icc*, or *3ih* and *i4*, and the word for blood can be written *quit'z* or *quittz* or *qui4*,. In the final case – but not in any of the others – the comma is part of the word and not a mark of punctuation.

Though it is not as picturesque as Mayan hieroglyphs, this alphanumeric script appeals to some scholars and amateurs, perhaps because of its very strangeness. Typographically, it begs for clarification, either through the creation of unambiguous new symbols or through reversion to plain old roman letters (which is now a common practice).

6.7.4 Don't mix faces haphazardly when specialized sorts are required.

?að/aqóm is
Upper Chehalis,
meaning
you will emerge;
untənæʃənl
fənetiks
(international
phonetics)
is English.

If a text involves setting occasional words such as ?a¾'aqə́m or untə-næʃənl fəneruks, it is best to plan for them from the beginning. Two standard phonetic alphabets are in use: the international (IPA) and the American. But the extra characters involved have been cut for only a few faces. (Lucida Sans, Stone and Times Roman are examples. Stone phonetic – which is used here – exists in both serifed and unserifed forms.) The typographer therefore has two choices: to set the entire text in a face for which matching

phonetic characters are available, so that phonetic transcriptions can enter the text transparently and at will; or to set the main text in a suitably contrasting face, and switch to the phonetic font (along with its matching text font, if required) each time a phonetic transcription occurs.

If contrasting faces are used for phonetic transcriptions and main text, each entire phonetic word or passage, not just the individual phonetic characters, should be set in the chosen phonetic face. Patchwork typography, in which the letters of a single word come from different faces and fonts, is a sign of typographic failure. Forms such as ' $\theta$ at $\theta$ ęłi' and 'e $\theta$ ón heldéłi' (formerly employed in writing the Native Canadian language Chipewyan) or ' $\Theta$ raētona' and 'Usa $\delta$ an' (still used in writing the ancient language Avestan) are typographically problematic because they mix two alphabets within a single word. Such mixtures are almost sure to fail unless all the fonts involved have been designed as a single family. (Here they succeed, because a unified Latin and Greek are used.)

Choosing and Combining Type

#### 6.8 BUILDING A TYPE LIBRARY

#### 6.8.1 Choose your library of faces slowly and well.

Some of the best typographers who ever lived had no more than one roman font at a time, one blackletter and one Greek. Others had as many as five or six romans, two or three italics, three blackletters, three or four Greeks. Today, the typographer can buy fonts by the thousand on compact discs, and use the telephone to download thousands more: more fonts than any human could use, yet never a complete selection.

With type as with philosophy, music and food, it is better to have a little of the best than to be swamped with the derivative, the careless, the routine.

The stock fonts supplied with software packages and desktop printers are sometimes generous in number, but they are the wrong fonts for many tasks and people, and most of them are missing essential parts (small caps, text figures, ligatures, diacritics and important analphabetics).

Begin by buying one good face or family, or a few related faces, with all the components intact. And instead of skipping from face to face, attempting to try everything, stay with your first choices long enough to learn their virtues and limitations before you move on.

Carol Twombly's Lithos (1988) and Adrian Frutiger's
Herculanum (1990) and Rusticana (1991) are typefaces based on
early Mediterranean inscriptions. In this example, Lithos
is printed solid, Herculanum with a medium
screen, Rusticana with a light screen.

Printing from movable type was first invented not in Germany in the 1450s, as Europeans often claim, but in China in the 1040s. In preference to Gutenberg, we should honor a scholarly engineer by the name of Bí Shēng (季 昇). The earliest surviving works printed in Asia from movable type seem to date from the thirteenth century, but there is a clear account of the typesetting process, and Bí Shēng's role in its development, by the eleventh-century essayist Shěn Kuò.

The new technology reached Korea before the middle of the thirteenth century and Europe by the middle of the fifteenth. There it intersected the already long and fertile history of the roman letter. And there typesetting flourished as it had failed to do in China, because of the far smaller number of glyphs European scripts required. Even at the end of the nineteenth century, most printing in China was done by the same method used in the eighth century to make the first printed books: entire pages of text were carved by hand into wooden printing plates. Corrections were made by drilling out the error, installing a wooden plug, and cutting the new characters. Text, in other words, was treated just like woodcut illustrations. To this day, a page of type is known in Chinese as huóbǎn (活板), "a living plank."

#### 7.1 THE EARLY SCRIBAL FORMS

The earliest surviving European letterforms are Greek capitals scratched into stone. The strokes are bony and thin, almost ethereal – the opposite of the heavy substance they are carved in. The letters are made primarily from straight lines, and when curved forms appear, they have a very large *aperture*. This means that forms like S and C and M, which can be relatively open or relatively closed, are about as open as they can get. These early Greek letters were drawn freehand, not constructed with compasses and rule, and they have no serifs – neither the informal entry and exit strokes left by a relaxed and fluent writer, nor the symmetrical finishing strokes typically added to letters by a formal scribe.

In time, the strokes of these letters grew thicker, the aperture lessened, and serifs appeared. The new forms, used for inscriptions throughout the Greek empire, served as models for formal

7

Shěn Kuò's account is contained in his Mèngxī Bitán (夢溪筆談), "Dream Creek Essays." For more information in English, see Denis Twitchett, Printing and Publishing in Medieval China (1983) and Thomas F. Carter. The Invention of Printing in China and Its Spread Westward, 2nd ed. (1955).

lettering in imperial Rome. And those Roman inscriptional letters – written with a flat brush, held at an angle like a broadnib pen, then carved into the stone with mallet and chisel – have served in their turn as models for calligraphers and type designers for the past two thousand years. They have a modest aperture, a *modulated* stroke (a stroke whose thickness varies with direction), and they have lively but full and formal serifs.

The Early Scribal Forms

### ABCSPQR

Trajan, designed by Carol Twombly in 1988, is based on the inscription at the base of Trajan's Column, Rome, carved in AD 113.

Between the Roman inscriptions and Gutenberg's time, there were many further changes in European letterforms. Narrow rustic capitals, wide uncials and other forms evolved. Writing spread to the farthest corners of Europe, and many regional scripts and alphabets arose. Monastic scribes – who were designers, copyists and archivists as well – kept many of the older letterforms alive. They used them for titles, subheads and initials, choosing newer and more compact scripts for running text. Out of this rich multiplicity of letters, a basic dichotomy evolved: *majuscules* and *minuscules*: large formal letters and smaller, more casual ones: the upper and lower case, as we call them now.

## CAROLUS MAGNUS Caroline or Carolingian means of the time of the Emperor Charlemagne: «Big Charles».

Carol Twombly's Charlemagne (above), Gudrun Zapf-von Hesse's Alcuin (center) and Gottfried Pott's Carolina (below) are typefaces based on Carolingian majuscules and minuscules from ninth- and tenth-century European manuscripts.

Many of the old scribal conventions survive in typesetting today. Titles are still set in large, formal letters; large initials mark the beginnings of chapters or sections; small capitals mark an opening phrase. The well-made page is now what it was then: a window into history, language and the mind: a map of what is being said and a portrait of the voice that is silently speaking.

In the later Middle Ages and the early Renaissance, a well-trained European scribe might know eight or ten distinct styles of script. Each was defined as precisely as a typeface, stored like a font in the human memory, and each had certain uses. Sacred scriptures, legal documents, romance literature, business and personal letters all required different scripts, and particular forms evoked specific languages and regions.

Historical Interlude

When the technology of movable type arrived, Europe was rich with Gothic, Byzantine, Romanesque and humanistic hands, and with a wealth of older letters. They are all still with us in some way, but the humanistic hand, based on the Carolingian minuscule, has become the central form: the roman lower case, evolving into a thousand variations, sports and hybrids, like the willow or the rose.

#### 7.2 THE TYPOGRAPHIC LATIN LETTER

Several systems are in use for classifying typefaces. Some of them use fabricated terms such as 'garalde' and 'didone.' Others rely on familiar but vague labels such as 'old style,' 'modern' and 'transitional.' All these systems work to a certain extent, but all leave much to be desired. They are neither good science nor good history.

Rigorously scientific descriptions and classifications of typefaces are certainly possible, and important research has been under way in this field for several years. Like the scientific study of plants and animals, the infant science of typology involves precise measurement, close analysis, and the careful use of technically descriptive terms.

But letterforms are not only objects of science. They also belong to the realm of art, and they participate in its history. They have changed over time just as music, painting and architecture have changed, and the same historical terms – Renaissance, Baroque, Neoclassical, Romantic, and so on – are useful in each of these fields.

This approach to the classification of letterforms has another important advantage. Typography never occurs in isolation. Good typography demands not only a knowledge of type itself, but an understanding of the relationship between letterforms and the

The art history of Latin letter-forms is treated in greater detail in an incomplete series of essays in *Serif* magazine, issues 1–5 (1994–97).

other things that humans make and do. Typographic history is just that: the study of the relationships between type designs and the rest of human activity – politics, philosophy, the arts, and the history of ideas. It is a lifelong pursuit, but one that is informative and rewarding from the beginning.

The Typographic Latin Letter

#### 7.2.1 The Renaissance Roman Letter

Renaissance roman letters developed among the scholars and scribes of northern Italy in the fourteenth and fifteenth centuries. Their translation from script to type began in Italy in 1465 and continued for more than a century. Like Renaissance painting and music, Renaissance letterforms are full of sensuous

abcefgnopj abcefgnopj abcefgnopj abcefgnopj

Four twentieth-century reconstructions of Renaissance roman typefaces. Centaur (top) was designed by the American typographer Bruce Rogers, Boston, c. 1914, after Nicolas Jenson, Venice, 1469. Bembo (second) was cut by Monotype, London, in 1929, based on the design of Francesco Griffo, Venice, 1499. Adobe Garamond (third) was designed by Robert Slimbach, San Francisco, 1988, after Claude Garamond, Paris, c. 1540. DTL Van den Keere (bottom) is Frank Blokland's reconstruction of a font cut for Christophe Plantin by Hendrik van den Keere, Antwerp, in 1575.

and unhurried light and space. They have served as typographic benchmarks for five hundred years.

The earliest surviving roman punches or matrices may well be Garamond's, cut in Paris in the 1530s. For earlier type, we have no evidence beyond the printed books themselves. The basic structure and form of these early typefaces is clear beyond dispute, but in their subtlest details, all the existing replicas of fifteenth-century Italian type are hypothetical reconstructions.

Historical Interlude

Like Roman inscriptional capitals, Renaissance roman lowercase letters have a modulated stroke (the width varies with direction) and a *humanist* axis. This means that the letters have the form produced by a broadnib pen held in the right hand in a comfortable and relaxed writing position. The thick strokes run Nw/se, the axis of the writer's hand and forearm. The serifs are crisp, the stroke is light, and the contrast between thick strokes and thin strokes is generally modest.

In summary, the characteristics of the early Renaissance roman letter are these:

- stems vertical
- bowls nearly circular
- modulated stroke
- consistent humanist axis
- modest contrast
- modest x-height
- crisp, oblique head serifs (on letters such as b and r)
- abrupt, flat or slightly splayed bilateral foot serifs (on letters such as r, l and p)
- abrupt, pen-formed terminals on a, c, f and r
- rising crossbar in e, perpendicular to the stroke axis
- the roman font is solitary (there is no italic or bold)

In later Renaissance forms (from 1500 on), the letterforms grow softer, smoother and more self-contained in subtle ways:

- head serifs become more wedge-shaped
- foot serifs become adnate (flowing smoothly into the stem) instead of abrupt
- terminals of c, f and r become less abrupt and more lachrymal (teardrop-shaped)
- crossbar of e becomes horizontal

#### 7.2.2 The Renaissance Italic Letter

Rome is located in the midst of Italy. Why is roman type a category separate from italic? It seems a question to which typographers might possess the answer. But the question and the answer both have as much to do with politics and religion as with calligraphy and typography.

The Typographic Latin Letter

Roman type consists of two quite different basic parts. The upper case, which does indeed come from Rome, is based on Roman imperial inscriptions. The lower case was developed in northern Europe, chiefly in France and Germany, in the late Middle Ages, and given its final polish in Venice in the early Renaissance. Nevertheless, it too is Roman in the larger sense. While the roman upper case is a legacy of the Roman Empire, the lower case is a legacy of the Holy Roman Empire, the pagan empire's Christianized successor. It acquired its fundamental form at the hands of Christian scribes, many of them employed during the late eighth century as administrators and teachers by the Holy Roman Emperor Charlemagne.

Italic letterforms, on the other hand, are an Italian Renaissance creation. Some early italics come from Rome, others from elsewhere in Italy, and when they were first converted to type, italics were still full of local flavor and freshness. But the earliest italic fonts, cut between 1500 and 1540, consist of lower case only. They were used with upright roman caps but not in conjunction with the roman lower case.

# abcefgnopxyz abcefgnopxyz

Two revivals of Renaissance italic type. Monotype Arrighi (above) is derived from one of a series of italics designed by Frederic Warde, London and Paris, 1925–29, after Ludovico degli Arrighi, Rome, 1524. Monotype Bembo italic (below) was cut in London in 1929, based on the work of both Arrighi and Giovanantonio Tagliente, Venice, 1524.

The characteristics of the Renaissance italic letter can be summarized as follows:

- stems vertical or of fairly even slope, not exceeding 10°
- bowls generally elliptical
- light, modulated stroke
- consistent humanist axis
- low contrast
- modest x-height
- cursive forms with crisp, oblique entry and exit serifs
- · descenders serifed bilaterally or not at all
- terminals abrupt or lachrymal
- italic lower case paired with small, upright roman capitals, and with occasional swash capitals; italic otherwise fully independent of roman

Early Renaissance italics are known as *Aldine* italics, in honor of the scholar and publisher Aldus Manutius, who commissioned the first italic type from Francesco Griffo in 1499. Strange to say, in 2004, not a single authentic reconstruction of an Aldine italic appears to be on the market, in either metal or digital form. Monotype Bembo roman and Monotype Poliphilus are both based on Griffo's work, but their companion italics are not; they come from a different age. The digital italic nearest to an Aldine in design is Giovanni Mardersteig's Dante italic, but even this has sloped instead of upright capitals.

Historical Interlude

See page 210 for reproductions of two Aldine italics.

ae

# equbdaffglopsbz abefopabefop

Two recent typefaces in the Mannerist tradition. Poetica (above) is a chancery italic based on sixteenth-century models. It was designed by Robert Slimbach and issued by Adobe in 1992. Galliard (below), designed by Matthew Carter, was issued by Linotype in 1978. It is based on letterforms cut in the sixteenth century by Robert Granjon.

#### 7.2.3 The Mannerist Letter

The Typographic Latin Letter Mannerist art is Renaissance art to which subtle exaggerations – of length, angularity or tension, for example – have been added. Mannerist typographers, working chiefly in Italy and France early in the sixteenth century, began the practice of using roman and italic in the same book, and even on the same page – though rarely on the same line. It was also during the Mannerist period that sloped roman capitals were first added to the italic lower case.

There are many fine sixteenth-century examples of Mannerist typefaces, including roman titling fonts with long, delicate extenders, chancery italics with even longer and often ornamented extenders, and text faces with short extenders but increased tension in the forms. Digital interpretations of a number of these faces have recently been made. Two significant examples – one ornate and one restrained – are shown overleaf.

# abefopabefopabefopabefopabefopabefopabefop

Four revivals of Baroque typefaces. Monotype 'Garamond' (top) is based on fonts cut in France by Jean Jannon, about 1621. DTL Elzevir (second) is based on fonts cut by Christoffel van Dijck at Amsterdam in the 1660s. Linotype Janson Text (third) is based on fonts cut by Miklós Kis, Amsterdam, about 1685. Adobe Caslon (bottom), by Carol Twombly, is based on faces cut by William Caslon, London, in the 1730s.

#### 7.2.4 The Baroque Letter

Baroque typography, like Baroque painting and music, is rich with activity and takes delight in the restless and dramatic play of contradictory forms. One of the most obvious features of any Baroque typeface is the large *variation in axis* from one letter to the next. Baroque italics are *ambidextrous*: both right- and lefthanded. And it was during the Baroque that typographers first made a habit of mixing roman and italic *on the same line*.

Historical Interlude

In general, Baroque letterforms appear more modeled and less written than Renaissance forms. They give less evidence of the direct trace of the pen. Yet they take many different forms, and they thrived in Europe throughout the seventeenth century, endured through much of the eighteenth, and enjoyed an enthusiastic revival during the nineteenth.

Baroque letterforms generally differ from Renaissance letters in the following ways:

- stroke axis of the roman and italic lower case varies widely within a single alphabet
- slope of italic averages 15° to 20° and often varies considerably within a single alphabet
- contrast increased
- x-height increased
- aperture generally reduced
- further softening of terminals from abrupt to lachrymal
- roman head serifs become sharp wedges
- head serifs of italic ascenders become level and sharp

#### 7.2.5 The Rococo Letter

The historical periods listed here – Renaissance, Baroque and so on – belong to all the arts, and they are naturally not limited, in typography, to roman and italic letters. Blackletter and script types passed through the same phases as well. But the Rococo period, with its love of florid ornament, belongs almost entirely to blackletters and scripts.

Roman and italic type was certainly used by Rococo typographers, who often surrounded their texts with typographic ornaments, engraved medallions, and so on. They produced a good deal of Rococo *typography*, but not much Rococo roman and italic *type*. Several romans and italics that might indeed be classified

# abcefgnopy CEFOTZ abcefgnopy

The Typographic Latin Letter

DTL Fleischmann. Note the ornate forms of *g*, *y* and several of the capitals, and the exaggerated contrast in italic *o*. This exaggerated contrast is typical of the Romantic types cut by Firmin Didot and Giambattista Bodoni after Fleischman's death in 1768. But Romantic types have an obsessively vertical axis. The primary axis of Fleischman's type is oblique. Structurally, these letters belong to the Baroque. But their tendency to ornamentation and exaggeration sets them apart from earlier Baroque types. That is a reason for calling them Rococo.

Though he was born and trained in Germany, Fleischman moved to the Netherlands before his 30th birthday and remained there the rest of his life. Fleischmann is the German spelling of his name; the Dutch form Fleischman is the one he chose to use in all his published specimens. The digital versions of Fleischman's type, published in the Netherlands, were created by the German type designer Erhard Kaiser, who christened them Fleischmann.

as Rococo were, however, cut in Amsterdam in 1738–39 by the German-born punchcutter Johann Michael Fleischman. Digital versions of these fonts have recently been released by the Dutch Type Library in 's-Hertogenbosch.

#### 7.2.6 The Neoclassical Letter

Generally speaking, Neoclassical art is more static and restrained than either Renaissance or Baroque art, and far more interested in rigorous consistency. Neoclassical letterforms follow this pattern. In Neoclassical letters, an echo of the broadnib pen can still be seen, but it is rotated away from the natural writing angle to a strictly vertical or *rationalist* axis. The letters are moderate in contrast and aperture, but their axis is dictated by an idea, not by the truth of human anatomy. They are products of the Rationalist era: frequently beautiful, calm forms, but forms oblivious to the more complex beauty of organic fact. If Baroque letterforms are ambidextrous, Neoclassical letters are, in their quiet way, *neitherhanded*.

# abefopabefop abefopabefop abefopabefop

Historical Interlude

Three twentieth-century revivals of Neoclassical letterforms. *Above*: Monotype Fournier, which is based on types cut by Pierre Simon Fournier, Paris, about 1740. *Center*: Monotype Baskerville, which is based on the designs of John Baskerville, Birmingham, about 1754. *Below*: Monotype Bell, based on the types cut in London in 1788 by Richard Austin for the typefounder and publisher John Bell.

The first Neoclassical typeface, known as the *romain du roi* or King's Roman, was designed in France in the 1690s, not by a typographer but by a government committee consisting of two priests, an accountant and an engineer. Other Neoclassical faces were designed and cut in France, England, Italy and Spain during the eighteenth and nineteenth centuries, and some of them have remained in continuous use throughout all subsequent changes of style and fashion.

The American printer and statesman Benjamin Franklin deeply admired the Neoclassical type of his English contemporary John Baskerville, and it is partly due to Franklin's support that Baskerville's type became more important in the United States and France than it ever was in Baskerville's native land. But the connection between Baskerville and America rests on more than Benjamin Franklin's personal taste. Baskerville's letters correspond very closely to the federal style in American architecture. They are as purely and unperturbably Neoclassical as the Capitol Building, the White House, and many another federal and state edifice. (The Houses of Parliament in London and in Ottawa, which are Neogothic instead of Neoclassical, call for typography of a different kind.)

In brief, Neoclassical letterforms differ from Baroque letters as follows:

- predominantly vertical axis in both roman and italic
- slope of italic generally uniform, averaging 14° to 16°
- serifs generally adnate, but thinner, flatter, more level

The Typographic Latin

Letter

7.2.7 The Romantic Letter

Neoclassicism and Romanticism are not sequential movements in European history. They marched through the eighteenth century and much of the nineteenth side by side: vigorously opposed in some respects and closely united in others. Both Neoclassical and Romantic letterforms adhere to a rationalist axis, and both look more drawn than written, but it is possible to make some precise distinctions between the two. The most obvious difference is one of contrast. In Romantic letters we will normally find the following:

- abrupt modulation of the stroke
- · vertical axis intensified through exaggerated contrast
- hardening of terminals from lachrymal to round
- serifs thinner and more abrupt
- aperture reduced

This remarkable shift in type design – like *all* structural shifts in type design – is the record of an underlying change in handwriting. Romantic letters are forms from which the broadnib pen has vanished. In its place is the pointed and flexible quill. The broadnib pen produces a smoothly modulated stroke whose thickness varies with direction, but the pointed quill performs quite differently. The stroke of a flexible quill shifts suddenly from thin to thick to thin again, in response to changes in pressure. Used with restraint, it produces a Neoclassical flourish. Used with greater force, it produces a more dramatic and Romantic one. Dramatic contrast, which is essential to much Romantic music and painting, is essential to Romantic type design as well.

Romantic letters can be extraordinarily beautiful, but they lack the flowing and steady rhythm of Renaissance forms. It is that rhythm which invites the reader to enter the text and read. The statuesque forms of Romantic letters invite the reader to stand outside and *look* at the letters instead.

# abefop*abefop*abefop*abefop*abefop*abefop*abefop*abefop*

Historical Interlude

Four revivals of Romantic letterforms. Monotype Bulmer (top) is based on a series of fonts William Martin cut in London in the early 1790s. Linotype Didot (second), drawn by Adrian Frutiger, is based on fonts Firmin Didot cut in Paris between 1799 and 1811. Bauer Bodoni (third) is based on fonts cut by Giambattista Bodoni at Parma between 1803 and 1812. Berthold Walbaum (bottom) is based on types cut by Justus Erich Walbaum, Weimar, about 1805.

#### 7.2.8 The Realist Letter

The nineteenth and twentieth centuries have entertained a bewildering variety of artistic movements and schools – Realism, Naturalism, Impressionism, Expressionism, Art Nouveau, Art Deco, Constructivism, Cubism, Abstract Expressionism, Pop Art, Op Art, and many more. Virtually all of these movements have raised waves in the typographic world as well, though not all are important enough to merit a place in this brief survey. One of these movements – one which has not by any means yet expired – is typographic Realism.

The Realist painters of the nineteenth century – Gustave Courbet, François Millet and many others – turned their backs on the subjects and poses approved by the academy. They set out instead to paint ordinary people doing their ordinary tasks. Realist type designers – Alexander Phemister, Robert Besley

# abcefgnop abcefgnop

The Typographic Latin Letter

Akzidenz Grotesk (above) is a Realist typeface issued by the Berthold Foundry, Berlin, in 1898. It is the immediate ancestor of Morris Benton's Franklin Gothic (1903) and of Helvetica, issued by the Haas Foundry in 1952. Haas Clarendon (below), designed in 1951 by Hermann Eidenbenz, is a revival of an earlier Realist face, the first Clarendon, cut by Benjamin Fox for Robert Besley. London, 1845.

and others, who have not achieved the posthumous fame of the painters – worked in a similar spirit. They made blunt and simple letters, based on the script of people denied the opportunity to learn to read and write with fluency and poise. Realist letters very often have the same basic shape as Neoclassical and Romantic letters, but most of them have heavy, slab serifs or no serifs at all. The stroke is often uniform in weight, and the aperture (often a gauge of grace or good fortune in typefaces) is tiny. Small caps, text figures and other signs of sophistication and elegance are almost always missing.

#### 7.2.9 Geometric Modernism: The Distillation of Function

Early modernism took many intriguing typographic forms. One of the most obvious is geometric. The sparest, most rigorous architecture of the early twentieth century has its counterpart in the equally geometric typefaces designed at the same time, often by the same people. These typefaces, like their Realist predecessors, make no distinction between main stroke and serif. Their serifs are equal in weight with the main strokes or are missing altogether. But most Geometric Modernist faces seek purity more than populism. Some show the study of archaic inscriptions, and some include text figures and other subtleties, but their shapes owe more to pure mathematical forms – the circle and the line – than to scribal letters.

# abcefgnop abcefgnop

Historical Interlude

Two Geometric Modernist typefaces. Futura (above) was designed in Germany in 1924–26 by Paul Renner. Memphis (below) was designed in 1929 by Rudolf Wolf, art director at the Stempel Foundry. The original design for Futura included text figures and many highly geometric, alternative characters which have never been issued in metal, though The Foundry (London) issued them in digital form in 1994.

# abefopabefop abefopabefop abefopabefop abefopabefop

Four neohumanist or Lyrical Modernist typefaces. Spectrum (top) was designed by Jan van Krimpen in the Netherlands during the 1940s and issued by both Enschedé and Monotype in 1952. Palatino (second) was designed by Hermann Zapf, Frankfurt, 1948. Dante (third) was designed by Giovanni Mardersteig, Verona, 1952. Pontifex (bottom) was designed by Friedrich Poppl, Wiesbaden, 1974. All but the last were originally cut by hand in steel, just like Renaissance faces.

#### 7.2.10 Lyrical Modernism: The Rediscovery of Humanist Form

The Typographic Latin Letter Another major phase of modernism in type design is closely allied with abstract expressionist painting. Painters in the twentieth century rediscovered the physical and sensory pleasures of painting as an act, and the pleasures of making organic instead of mechanical forms. Designers of type during those years were equally busy rediscovering the pleasures of *writing* letterforms rather than drawing them. In rediscovering calligraphy, they rediscovered the broadnib pen, the humanist axis and humanist scale of Renaissance letters. Typographic modernism is fundamentally the reassertion of Renaissance form. There is no hard line between modernist design and Renaissance revival.

#### 7.2.11 The Expressionist Letter

In yet another of its aspects, typographic modernism is rough and concrete more than lyrical and abstract. Rudolf Koch, Vojtěch Preissig and Oldřich Menhart are three designers who explored this path in the early part of the twentieth century. They are in some respect the typographic counterparts of expressionist painters such as Vincent van Gogh and Oskar Kokoschka. More recent painters and type designers, such as Zuzana Ličko, have proven that the genre is still richly productive.

Expressionist designers use many different tools. Koch and Preissig often cut their own letters in metal or wood. Menhart worked with a pen and rough paper. Ličko has exploited the

# abcefghijop abefop*abefop*

Two Expressionist types – one Modernist and one Postmodern. Preissig (above) was designed in New York in 1924 by the Czech artist Vojtěch Preissig. It was cut and cast in Prague in 1925. Zuzana Ličko's Journal (below) was designed in Berkeley in 1990 and issued in digital form by Emigre.

harsh economies of digital plotting routines, slicing from control point to control point not with a knife, file or chisel but with digitized straight lines.

#### 7.2.12 Elegiac Postmodernism

Modernism in type design has its roots in the study of history, the facts of human anatomy, and in the pleasures of calligraphy. Like the Renaissance itself, modernism is more than a phase or fad that simply runs its course and expires. It remains very much alive in the arts generally and in type design in particular, though it no longer seems the final word. In the last decades of the twentieth century, critics of architecture, literature and music – along with others who study human affairs – all perceived movements away from modernism. Lacking any proper name of their own, these movements have come to be called by the single term postmodernism. And postmodernism is as evident in the world of type design as it is in other fields.

Historical Interlude

Postmodern letterforms, like Postmodern buildings, frequently recycle and revise Neoclassical, Romantic and other premodern forms. At their best, they do so with an engaging lightness of touch and a fine sense of humor. Postmodern art is for the most part highly self-conscious, but devoutly unserious. Postmodern designers – who frequently are or have been Modernist designers as well – have proven that it is possible to infuse Neoclassical and Romantic form, and the rationalist axis, with genuine calligraphic energy.

# abefop*abefop* abefop*abefop*

Two Postmodern faces. Esprit (above) was designed by Jovica Veljović, Beograd, 1985. Nofret (below) was designed by Gudrun Zapf-von Hesse, Darmstadt, 1990. Both types sing, where many Postmodern faces merely screech. But the song is elegiac more than lyrical.

## abefop*abefop* abefop*abefop*

The Typographic Latin Letter

Two Geometric Postmodern faces: Triplex Sans (above) and Officina Serif (below). Triplex italic was designed by John Downer in 1985. Its companion romans – one with serifs, one without – were designed by Zuzana Ličko in 1989–90, and the full *ménage à trois* was issued in 1990 by Emigre. Officina (ITC, 1990) was designed by Erik Spiekermann. It has been issued in both serifed and unserifed versions.

#### 7.2.13 Geometric Postmodernism

Some Postmodern faces are highly geometric. Like their predecessors the Geometric Modernist faces, they are usually slab-serifed or unserifed, but often they exist in both varieties at once or are hybrids of the two. They are rarely, it seems, based on the pure and simple line and circle, but almost always on more mannered, often asymmetric forms. And like other Postmodern types, they are rich with nostalgia for something premodern. Many of these faces are indebted to older industrial letterforms, including typewriter faces and the ubiquitous factory folk-art of North American highway signs. They recycle and revise not Romantic and Neoclassical but Realist ideas. To this industrial unpretentiousness, however, they often add not only Postmodern humor but also the fruits of typographic sophistication: text figures, small caps, large aperture, and subtle modeling and balancing of forms.

Postmodern art, like Neoclassical art, is above all an art of the surface: an art of reflections rather than visions. It has thrived in the depthless world of high-speed offset printing and digital design, where modernism starves. But the world of the scribes, in which the craft of type design is rooted, was a depthless world too. It was the world of the Gothic painters, in which everything is present in one plane. In that respect at least, postmodernism and modernism alike confront the basic task with which typography began. That is the task of answering in two (or little more than two) dimensions to a world that has many.

#### 7.3.1 The Linotype Machine

The Linotype machine, invented in the 1880s by Ottmar Mergenthaler and much modified over the years, is a kind of cross between a casting machine, a typewriter, a vending machine and a backhoe. It consists of a series of slides, belts, wheels, lifts, vises, plungers and screws, controlled from a large mechanical keyboard. Its complex mechanism composes a line of matrices, justifies the line by sliding tapered wedges into the spaces between the words, then casts the entire line as a single metal slug for letterpress printing.

Typeface design for the Linotype was restricted by three basic factors. First, kerning is impossible without special compound matrices. (The basic italic f in a Linotype font therefore always has a stunted head and tail.) Second, the em is divided into only 18 units, which discourages subtlety of proportion. Third, the italic and roman matrices are usually paired. In most faces, each italic letter must therefore have the same width as its counterpart in roman.

A number of typefaces designed for the Linotype were artistically successful in spite of these constraints. Hermann Zapf's Aldus and Optima, Rudolph Růžička's Fairfield, Sem Hartz's Juliana, and W. A. Dwiggins's Electra, Caledonia and Falcon were all designed for the Linotype machine. Linotype Janson, adapted by Zapf in 1952 from the seventeenth-century originals of Miklós Kis, is another eminent success. Many Linotype faces have nevertheless been modified in the course of digitization, to make use of the kerning capabilities of digital machines and restore the independent proportioning of roman and italic.

#### 7.3.2 The Monotype Machine

In 1887, in competition with Mergenthaler, Tolbert Lanston created a machine that stamped individual letters in cold metal and assembled them into lines. This device was soon abandoned for another – built in 1900 by Lanston's colleague John Bancroft – that cast individual letters from molten metal rather than cold-stamping them. It was soon sold worldwide as the Monotype machine. It is two machines in fact, a terminal and an output device, and in this respect resembles most computer-driven

For a detailed account of the growth of mechanized typesetting, see Richard E. Huss, The Development of Printers' Mechanical Typesetting Methods 1822–1925 (1973).

typesetting machines. But the Monotype terminal carries a large mechanical keyboard, including seven full alphabets as well as analphabetics. The keyboard punches holes in a paper tape, like a narrow player-piano roll, by driving pins with compressed air. The output device is the caster, which reads the paper tape by blowing more compressed air through the punched holes, then casts and assembles the letters.

Mechanical Typesetting

The Monotype em, like the Linotype em, is divided into only 18 units, but italic and roman are independent in width, kerning is possible, and because the type remains in the form of separate letters, typeset lines can be further adjusted by hand. Characters larger than 24 pt are cast individually and left for hand assembly. In fact, the Monotype machine is a portable typefoundry as much as it is a composing machine – and it is increasingly used as such, even though its unit system imposes restrictions on letterform design, and it is incapable of casting in hard metal.

#### 7.3.3 Two-Dimensional Printing

From the middle of the fifteenth century to the middle of the twentieth, most roman letters were printed by a technique rooted in sculpture. In this process, each letter is carved at actual size on the end of a steel punch. The punch is then struck into a matrix of softer metal, the matrix is fitted into a mold, and three-dimensional metal type is cast from an alloy of lead, tin and antimony. The cast letters are locked in a frame and placed in a printing press, where they are inked. Their image is then imprinted *into* the paper, producing a tactile and visual image. The color and sheen of the ink join with the smooth texture of crushed paper, recessed into the whiter and rougher fibers surrounding the letters and lines. A book produced by this means is a folding inscription, a flexible sculpture in low relief. The black light of the text *shines out from within* a well-printed letterpress page.

Renaissance typographers reveled in the physical depth and texture they could achieve by this method of printing. Neoclassical and Romantic printers, like Baskerville, often took a different view. Baskerville printed his sheets by letterpress – since he had no other method – but then had them ironed like laundry to remove the sculptural tinge.

With the development of lithography, at the end of the eighteenth century, printing moved another step back toward the two-dimensional world of the medieval scribes. Since the

middle of the twentieth century, most commercial printing has been by two-dimensional means. The normal method is offset photolithography, in which a photographic or digital image is etched into a plate, inked, *offset* to a smooth intermediary blanket, then laid flat on the surface of the page.

In the early days of commercial offset printing, type was still set with Linotype or Monotype machines. Proofs were pulled in a letterpress, then cut, pasted and photographed. Type designers saw their work altered by this process. Most letters designed to be printed in three dimensions look weaker when printed in two. But other letters prospered: geometric letters, which evoked the world of the draftsman rather than the goldsmith, and flowing letters recalling the heritage of the scribe.

Historical Interlude

#### 7.3.4 Phototype Machines

Light flashes through the image of a letter carried on glass or photographic film; the size of the letter is altered with a lens; its target location is fixed by a mirror, and it is exposed like any other photographic image onto photosensitive paper or film. Machines that operate on this principle are the natural children of the camera and the offset press. They were designed and patented in the 1890s and in regular use for setting titles and headlines by 1925, though it was not until the 1960s that they came to dominate the trade.

Just as the sophistication and subtlety of handset type seemed at first to be swept aside when composing machines appeared, so the sophistication slowly achieved with Linotype and Monotype machines seemed to be swept aside by this new technological wave. The photosetters were fast, but they knew nothing of subtle changes in proportion from size to size. Their fonts lacked ligatures, text figures and small caps. American-made fonts lacked even the simplest accented characters. The choice of faces was poor. And with the sudden, widespread use of these complex but simplistic machines came the final collapse of the old craft system of apprenticeships and guilds.

Phototypesetting machines and their users had only begun to answer these complaints when digital equipment arrived to replace them. Some excellent faces were designed for phototype machines – from Adrian Frutiger's Apollo (1962) to Bram de Does's Trinité (1982) – but in retrospect, the era of phototype seems only a brief interregnum between hot metal and digital composition. The important innovation of the period was not, after all, the conversion of fonts from metal to film, but the introduction of microcomputers to edit, compose and correct the text and to drive the last generations of photosetting machines.

#### 7.3.5 Historical Recutting and Twentieth-Century Design

Mechanical Typesetting

New typefaces have been designed in vast numbers in the past hundred years, and many old ones have been resuscitated. From 1960 to 1980, most new types and revivals were designed for photosetting, and since 1980, almost all have been planned for digital composition. But most of the older faces now sold in digital form have already passed through another stylistic filter. They were recut in the early twentieth century, either as foundry type or as matrices for the Monotype or Linotype machines. Typography was radically reformed between 1920 and 1950, through the commercial reinvention of typographic history. It is worth looking back at this process to see something of what went on, because its legacy affects us still.

Two separate companies - one based in England, one in America - rose up around the Monotype machine and followed two quite separate development programs. The English company, advised during its heyday by a scholar named Stanley Morison, cut a series of facsimiles based on the work of Francesco Griffo, Giovanantonio Tagliente, Ludovico degli Arrighi and other early designers. It was Morison who conceived the idea of turning independent Renaissance faces into families by mating one designer's roman with another's formerly self-sufficient italic. The fruits of this enterprise included Poliphilus and Blado (one of Griffo's romans mated with an altered version of one of Arrighi's italics), Bembo (a later version of the same roman, paired with an altered version of one of Tagliente's italics), and the brilliantly successful shotgun marriage of Centaur roman (designed by Bruce Rogers) with the Arrighi italic (designed by Frederic Warde). This program was supplemented by commissioning new faces from artists such as Eric Gill, Alfred Fairbank, Jan van Krimpen and Berthold Wolpe.

a aa a

Lanston Monotype, as the American company was called, made some historical recuttings of its own and issued many new and historically based faces designed by its own advisor, Frederic Goudy. A third campaign to recreate typographic history in

marketable form was mounted by Linotype, under the direction of the English master printer George William Jones.

Several of the larger typefoundries – including ATF (American Type Founders) in the United States, Deberny & Peignot in France, Enschedé in the Netherlands, Stempel in Germany and Grafotechna in Czechoslovakia – continued ambitious programs of their own, lasting in some cases into the 1980s. Revivals of faces by Claude Garamond, Miklós Kis and other early designers came from these foundries during the twentieth century, along with important new faces by such designers as Hermann Zapf, Jan van Krimpen, Adrian Frutiger, Oldřich Menhart and Hans Eduard Meier. Zapf's Palatino, which became the most widely used (and most widely pirated) face of the twentieth century, was cut by hand in steel and cast as a foundry type in the ancient way, in 1949–50, while phototype machines and a few cumbersome early computers were humming no great distance away.

Historical Interlude

The earlier history of type design is the history of forms made by individual artists and artisans who began their careers as apprentices and ended them as independent masters and small businessmen. The scale of the industry enlarged in the seventeenth and eighteenth centuries, and questions of fashion increasingly superseded questions of artistry. By the end of the nineteenth century, commercial considerations had changed the methods as well as the taste of the trade. Punches and matrices were increasingly cut by machine from large pattern letters, and calligraphic models were all but unknown.

The twentieth-century rediscovery of the history and principles of typographic form was not associated with any particular technology. It occurred among scholars and artists who brought their discoveries to fruition wherever they found employment: in typefoundries, typesetting-machine companies, art schools and their own small, independent studios.

Despite commercial pressures, the best of the old metal foundries, like the best of the new digital ones, were more than merely market-driven factories. They were cultural institutions, on a par with fine publishing houses and the ateliers of printmakers, potters, weavers and instrument makers. What made them so was the stature of the type designers, living and dead, whose work they produced – for type designers are, at their best, the Stradivarii of literature: not merely makers of salable products, but artists who design and make the instruments that other artists use.

#### 7.3.6 Digital Typography

raphy, but the evolution of computerized bitmapping, hinting and scaling techniques has proceeded very quickly since the development of the microchip at the beginning of the 1970s. At the same time, the old technologies, freed from commercial duties, have by no means died. Foundry type, the Monotype, the Linotype and letterpress remain important artistic instruments, alongside brush and chisel, pencil, graver and pen.

Mechanical **Typesetting** 

> Typographic style is founded not on any one technology of typesetting or printing, but on the primitive yet subtle craft of writing. Letters derive their form from the motions of the human hand, restrained and amplified by a tool. That tool may be as complex as a digitizing tablet or a specially programmed keyboard, or as simple as a sharpened stick. Meaning resides, in either case, in the firmness and grace of the gesture itself, not in the tool with which it is made.

> It is much too soon to summarize the history of digital typog-

#### 7.4 THE PLURALITY OF TYPOGRAPHIC HISTORY

Every alphabet is a culture. Every culture has its own version of history and its own accumulation of tradition - and this chapter has dwelt on the recent history of one alphabet only. The Arabic, Armenian, Burmese, Cherokee, Cree, Cyrillic, Devanagari, Georgian, Greek, Gujarati, Hebrew, Japanese, Korean, Malayalam, Tamil and Telugu alphabets and syllabaries - to name only a few - have other histories of their own, in some cases every bit as intricate and long as - or longer than - the history of Latin letterforms. So, of course, has the logographic script of Chinese. These histories have touched at certain points; at other points, they diverge. Here at the beginning of the twenty-first century, an unusual degree of convergence can be seen. But the challenge and excitement of multilingual typography still lies largely in the fact that different typographic histories momentarily share the page. Typographers working with multiple alphabets are multiply blessed: with a chance to learn the cultural history as well as the typographic technicalities of every script concerned.

The histories of Greek and Cyrillic types are taken up more briefly in chapter 11, and the legacies of individual typefoundries are summarized briefly in appendix E, page 346.







8

A book is a flexible mirror of the mind and the body. Its overall size and proportions, the color and texture of the paper, the sound it makes as the pages turn, and the smell of the paper, adhesive and ink, all blend with the size and form and placement of the type to reveal a little about the world in which it was made. If the book appears to be only a paper machine, produced at their own convenience by other machines, only machines will want to read it.

#### 8.1 ORGANIC, MECHANICAL & MUSICAL PROPORTION

A page, like a building or a room, can be of any size and proportion, but some are distinctly more pleasing than others, and some have quite specific connotations. A brochure that unfolds and refolds in the hand is intrinsically different from a formal letter that lies motionless and flat, or a handwritten note that folds into quarters and comes in an envelope of a different shape and size. All of these are different again from a book, in which the pages flow sequentially in pairs.

Much typography is based, for the sake of convenience, on standard industrial paper sizes, from  $35 \times 45$  inch press sheets to  $3\frac{1}{2} \times 2$  inch conventional business cards. Some formats, such as the booklets that accompany compact discs, are condemned to especially rigid restrictions of size. But many typographic projects begin with the opportunity and necessity of selecting the dimensions of the page.

There is rarely a free choice. A page size of  $12 \times 19$  inches, for example, is likely to be both inconvenient and expensive because it is just in excess of  $11 \times 17$ , which is a standard industrial unit. And a brochure that is  $5 \times 9$  inches, no matter how handsome, might be unacceptable because it is too wide to fit into a standard business envelope ( $4 \times 9\frac{1}{2}$ ). But when the realm of practicality has been established, and it is known that the page must fall within certain limits, how is one to choose? By taking whatever is easiest, or biggest, or whatever is the most convenient standard size? By trusting to blind instinct?

Instinct, in matters such as these, is largely memory in disguise. It works quite well when it is trained, and poorly otherwise.

But in a craft like typography, no matter how perfectly honed one's instincts are, it is useful to be able to calculate answers exactly. History, natural science, geometry and mathematics are all relevant to typography in this regard – and can all be counted on for aid.

Organic, Mechanical and Musical Proportion

Two very useful works on natural form and structure are D'Arcy Thompson, On Growth and Form (rev. ed., 1942) and Peter S. Stevens, Patterns in Nature (1974). An equally important book on structures made by humans is Dorothy Washburn & Donald Crowe. Symmetries of Culture: Theory and Practice of Plane Pattern Analysis (1988)

Scribes and typographers, like architects, have been shaping visual spaces for thousands of years. Certain proportions keep recurring in their work because they please the eye and the mind, just as certain sizes keep recurring because they are comfortable to the hand. Many of these proportions are inherent in simple geometric figures – equilateral triangle, square, regular pentagon, hexagon and octagon. And these proportions not only seem to please human beings in many different centuries and countries, they are also prominent in nature far beyond the human realm. They occur in the structures of molecules, mineral crystals, soap bubbles, flowers, as well as books and temples, manuscripts and mosques.

The tables on pages 148–149 list a number of page proportions derivable from simple geometric figures. These proportions occur repeatedly in nature, and pages that embody them recur in manuscripts and books from Renaissance Europe, Táng and Sòng dynasty China, early Egypt, precolumbian Mexico and ancient Rome. It seems that the beauty of these proportions is more than a matter of regional taste or immediate fashion. They are therefore useful for two purposes. Working and playing with them is a way of developing good typographic instincts, and they serve as useful references in analyzing old designs and calculating new ones.

For comparison, several other proportions are included in the tables. There are several simple numerical ratios, several standard industrial sizes, and several proportions involving four irrational numbers important in the analysis of natural structures and processes. These numbers are  $\pi = 3.14159...$ , which is the circumference of a circle whose diameter is one;  $\sqrt{2} = 1.41421...$ , which is the diagonal of a unit square; e = 2.71828..., which is the base of the natural logarithms; and  $\varphi = 1.61803...$ , a number discussed in greater detail on page 155. Certain of these proportions reappear in the structure of the human body; others appear in musical scales. Indeed, one of the simplest of all systems of page proportions is based on the familiar intervals of the diatonic scale. Pages that embody these basic musical proportions have been in common use in Europe for more than a thousand years.

Sizing and spacing type, like composing and performing music or applying paint to canvas, is largely concerned with intervals and differences. As the texture builds, precise relationships and very small discrepancies are easily perceived. Establishing the overall dimensions of the page is more a matter of limits and sums. In this realm, it is usually sufficient, and often it is better, if structural harmony is not so much enforced as implied. That is one of the reasons typographers tend to fall in love with books. The pages flex and turn; their proportions ebb and flow against the underlying form. But the harmony of that underlying form is no less important, and no less easy to perceive, than the harmony of the letterforms themselves.


Shaping the Page

The page is a piece of paper. It is also a visible and tangible proportion, silently sounding the thoroughbass of the book. On it lies the textblock, which must answer to the page. The two together – page and textblock – produce an antiphonal geometry. That geometry alone can bond the reader to the book. Or conversely, it can put the reader to sleep, or put the reader's nerves on edge, or drive the reader away.

The textblock is known in Chinese as yèxīn (頁心), a useful phrase. Yè means page; xīn means heart and mind.

Arithmetic and mathematics also drive away some readers, and this is a chapter peppered with both. Readers may well ask whether all this is necessary, merely in order to choose where some letters should sit on a piece of paper and where the paper itself should be trimmed. The answer, naturally, is no. It is not in the least necessary to understand the mathematics in order to perform the actions that the math describes. People walk and ride bicycles without mathematical analyses of these complex operations. The chambered nautilus and the snail construct perfect logarithmic spirals without any need of logarithmic tables, sliderules or the theory of infinite series. The typographer likewise can construct beautiful pages without knowing the meaning of symbols like  $\pi$  or  $\phi$ , and indeed without ever learning to add and subtract, if he has a well-educated eye and knows which buttons to push on the calculator and keyboard.

The mathematics are not here to impose drudgery upon anyone. On the contrary, they are here entirely for pleasure. They are here for the pleasure of those who like to examine what they are doing, or what they might do or have already done, perhaps in the hope of doing it still better. Those who prefer to act directly at all times, and to leave the analysis to others, may be content in this chapter to study the pictures and skim the text.



Page proportions corresponding to the chromatic scale, from unison (at the bottom) to octave (at the top). The musical correlations are shown in detail on the facing page.

octave	1:2	1:2	c - c'	double square
major 7th minor 7th major 6th minor 6th	9:16 3:5	1 : 1.778 1 : 1.667	$ \left.\begin{array}{c} C - B \\ C - A \end{array}\right\} $	
<sub> </sub> fifth	2:3	1:1.5	C – G	
dim. 5th } aug. 4th }	$1:\sqrt{2}$	1:1.414 {	C - Gb C - F#	self-replicating page
fourth	3:4	1:1.333	C - F	
major 3rd minor 3rd major 2nd minor 2nd	5:6	1:1.2 1:1.125	C - D	
unison	1:1	1:1	C - C	square page

The value for the diminished 5th/ augmented 4th is calculated here according to the system of equal temperament. All other intervals are calculated according to the system of just intonation.

Page shapes derived from the chromatic scale. Two-page spreads that embody these proportions are shown on the facing page.

The perfect intervals (fifth and fourth) coincide exactly with the favorite page shapes of the European Middle Ages, which are still in use today: the page proportions 2:3 and 3:4. Renaissance typographers made extensive use of narrower pages, corresponding to the larger impure intervals (major and minor sixth, major and minor seventh).

Each page shape has a counterpart with which it alternates. If a sheet whose proportions are 5:8 is folded in half, it produces a sheet whose proportions are 4:5. If this is folded once again, it produces another sheet whose proportions are 5:8. In the same way, the proportion 1:2 alternates with the proportion 1:1. The proportion 1: $\sqrt{2}$ , corresponding to the diminished fifth and augmented fourth of equal temperament, is the only one that alternates with itself.

In musical terms, these alternating proportions form harmonic inversions. (The harmonic inversion of a fifth, for example, is a fourth, and the harmonic inversion of a minor sixth is a major third.) The total of each such pair of intervals is always one octave.


	_					
octave	Α	Double Square	1:2	4.5 × 9	5 × 10	5.5 × 11
	В	Tall Octagon	1:1.924	4.7 × 9	5.2 × 10	5.7 × 11
major 7th		8 : 15	1:1.875	4.8 × 9		
	C	Tall Hexagon	1:1.866			5.9 × 11
	D	Octagon	1:1.848	4.9 × 9	5.4 × 10	6 × 11
		5:9	1:1.8	5 × 9		
minor 7th		9:16	1:1.778		5.1 × 9	
	Ε	$HEXAGON = 1: \sqrt{3}$	1:1.732	$4.9 \times 8.5$	5.2 × 9	6.4 × 11
	F	Tall Pentagon	1:1.701	5 × 8.5	5.3 × 9	6.5 × 11
major 6th		3:5	1:1.667	5.1 × 8.5		
		Legal Sheet	1:1.647			$8.5 \times 14$
	G	GOLDEN SECTION	1:1.618	5.3 × 8.5	5.6 × 9	6.8 × 11
minor 6th		5:8	1:1.6	5 × 8		
	Н	PENTAGON	1:1.539	5.5 × 8.5	5.9 × 9	7.2 × 11
<b>&gt;</b> fifth		2:3	1:1.5		6×9	7.3 × 11
	Z	$ISO = 1: \sqrt{2}$	1:1.414	6.4 × 9	7.1 × 10	7.8 × 11
		5:7	1:1.4			
	J	Short Pentagon	1:1.376	$6.5 \times 9$	7.3 × 10	8 × 11
➤ fourth		3:4	1:1.333	6.8 × 9	7.5 × 10	9 × 12
	Κ	Tall Half Octagon	1:1.307	6.9 × 9	7.7 × 10	8.4 × 11
		Letter Sheet	1:1.294			8.5 × 11
major 3rd		4:5	1:1.25	7.2 × 9	8 × 10	8.8 × 11
	L	Half Octagon	1:1.207		8.3 × 10	9.1 × 11
minor 3rd		5:6	1:1.2	7.5 × 9		
	М	Truncated Pentagon	1:1.176		8.5 × 10	9.4 × 11
		6:7	1:1.167	7.7 × 9		
		<b>e</b> :π	1:1.156			
	Ν	Turned Hexagon	1:1.155	7.8 × 9	8.7 × 10	9.5 × 11
major 2nd		8:9	1:1.125	8 × 9	8.9 × 10	9.8 × 11
	0	Tall Cross Octagon	1:1.082	8.3 × 9	9.2 × 10	10.2 × 11
minor 2nd		15 : 16	1:1.067	8.4 × 9	9.4 × 10	10.3 × 11
	Р	Turned Pentagon	1:1.051	8.6 × 9	9.5 × 10	10.5 × 11
unison	Q	SQUARE	1:1	9×9	10 × 10	11 × 11
	R	Broad Pentagon	1:0.951	8.9 × 8.5	10 × 9.5	11 × 10.5
	S	Broad Cross Octagon	1:0.924	9.2 × 8.5	10 × 9.2	11 × 10.1
major 2nd		9:8	1:0.889	$9.6 \times 8.5$		11 × 9.8
	Т	Broad Hexagon	1:0.866	9.8 × 8.5	10 x 8.7	11 × 9.5
	U	Full Cross Octagon	1:0.829	10.3 × 8.5	10 × 8.3	11 × 9.1
major 3rd		5:4	1:0.8	10.6 × 8.5		11 × 8.8
		Landscape Letter	1:0.773	11 × 8.5	10 × 7.7	

Column F	Proportions
----------	-------------

Sample sizes in picas

2	Quadruple Square	1:4	10 × 40	11 × 44	12 × 48	double octave
	1 : √15	1:3.873	10 × 40	11 ^ 44	12 × 40	double octave
	4:15	1:3.75	10 ^ 39	12 × 45		major 14th
	5:18	1:3.6	10 × 36	12 × 43		1114501 14411
	-	-	-	12 ^ 45		minor 14th
	9:32 1: $\sqrt{12}$	1:3.556	11 × 39		35 V 50	minor 14m
L		1:3.464	11 × 38	10.14.41	15 × 52	
D	Octagon Wing	1:3.414		12 × 41		
	3:10	1:3.333		12 × 40	15 × 50	major 13th
	1:2φ	1:3.236			0	
	5:16	1:3.2	0		15 × 48	minor 13th
	1:√10	1:3.162	12 × 38			
	1:π	1:3.142		14 × 44	_	
	Double Pentagon	1:3.078	12 × 37			
d	Triple Square	1:3	12 × 36	14 × 42	16 × 48	twelfth
е	Wide Octagon Wing	1:2.993				
Z	•	1:2.828				
f	Pentagon Wing	1:2.753		16 × 44		
	1:e	1:2.718	14 × 38		18 × 49	
	3:8	1:2.667		15 × 40	$18 \times 48$	eleventh
	$1:\sqrt{7}$	1:2.646				
g	Extended Section	1:2.618				
h	Tall Octagon Column	1:2.613			18 × 47	
i	Mid Octagon					
	Column	1:2.514				
	2:5	1:2.5	16 × 40	18 × 45	20 × 50	major 10th
j	Short Octagon					
	Column	1:2.414				
	5:12	1:2.4			20 × 48	minor 10th
k	Hexagon Wing	1:2.309	16 × 37	20 × 46	·	
	Double Truncated			·		
	Pentagon	1:2.252				
	4:9	1:2.25		20 × 45		major 9th
	1:√5	1:2.236	17 × 38	15	21 × 47	, ,
	5:11	1:2.2	. ,	20 × 44	24 × 53	
	15:32	1:2.133		ं चन	24 × 52	minor 9th
Α	Double Square	1:2	18 × 36	21 × 42	24 × 48	octave
	-:-: d-:	. –	- , , -	- · · · ¬-	- T - T -	


[The intervals listed in the right hand column on this page are *compound intervals* of the chromatic scale. Octave + minor 2nd = minor 9th; octave + major 3rd = major 10th; octave + fifth = twelfth, etc.]



F, P, R and f are shown here as two-page spreads. H, J, M and m are shown as single pages.


Organic, Mechanical and Musical Proportion

Pages derived from the pentagon: **F** the Tall Pentagon page, 1:1.701; **H** Pentagon page, 1:1.539; **J** Short Pentagon page, 1:1.376; **M** the Truncated Pentagon page, 1:1.176; **P** Turned Pentagon page, 1:1.051; **R** the Broad Pentagon page, 1:0.951; **f** Pentagon Wing, 1:2.753; **m** the Double Truncated Pentagon, 1:2.252. The pentagon page differs by 2% from the North American standard small trade book size, which is half the size of a letter sheet: 5½ × 8½ inches. A more eminent page proportion, the *golden section*, is also present in the pentagon (see page 156). In nature, pentagonal symmetry is rare in inanimate forms. Packed soap bubbles seem to strive for it but never quite succeed, and there are no mineral crystals with true pentagonal structures. But pentagonal geometry is basic to many living things, from roses and forget-me-nots to sea urchins and starfish.



Pages derived from the hexagon: **C** the Tall Hexagon page, 1:1.866; **E** Hexagon page, 1: $\sqrt{3}$  = 1:1.732; **N** Turned Hexagon page, 1:1.155; **T** Broad Hexagon page, 1:0.866; **k** Hexagon Wing, 1:2.309. The hexagon consists of six equilateral triangles, and each of these page shapes can be derived directly from the triangle instead. The hexagon merely clarifies their existence as mirror images, like the pages of a book. Hexagonal structures are present in both the organic and the inorganic world – in lilies and wasps' nests, for example, and in snowflakes, silica crystals and sunbaked mudflats. The proportions of the broad hexagon page are within one tenth of one per cent of the natural ratio  $\pi/e$ , while the turned hexagon page (which is the broad hexagon rotated 90°) approximates the ratio  $e/\pi$ . (The hexagon page used in this book is analyzed on page 6.)


All formats on this page are shown as twopage spreads.



B, D, O, S and U are shown as twopage spreads.

Organic, Mechanical and Musical Proportion


Pages derived from the octagon: **B** the Tall Octagon page, 1:1.924; **D** Octagon page, 1:1.848; **K** Tall Half Octagon page, 1:1.307; **L** Half Octagon page, 1:1.207; **O** Tall Cross Octagon, 1:1.082; **S** Broad Cross Octagon page, 1:0.924; **U** the Full Cross Octagon page, 1:0.829; **b** Octagon Wing, 1:3.414; **e** Wide Octagon Wing, 1:2.993; **h**, **i**, **j** Tall, Middle and Short Octagon Columns, 1:2.613, 1:2.514 and 1:2.414. The tall half octagon page (**K**), used in Roman times, differs by a margin of 1% from the standard North American letter size. Are proportions derived from the hexagon and pentagon livelier and more pleasing than those derived from the octagon? Forms based on the hexagon and pentagon are, at any rate, far more frequent than octagonal forms in the structure of flowering plants and elsewhere in the living world.



Pages derived from the circle and square: A Double Square page, 1:2; **Z** the Broad Square page, which is the IsO standard,  $1:\sqrt{2}=1:1.414$ ; **Q** the Perfect Square; **z** Double IsO,  $1:2\sqrt{2}=1:2.828$ . The proportion  $1:\sqrt{2}$  is that of side to diagonal in a square. A rectangle of these proportions (and no others) can be halved or doubled indefinitely to produce new rectangles of the same proportion. The proportion was chosen for that reason as the basis for IsO (International Organization for Standardization) paper sizes. The A4 sheet, for example, is standard European letter size,  $210 \times 297 \text{ mm} = 8\frac{1}{2}\%$ . An  $8\frac{1}{2}\%$  × 12% book page also embodies this proportion.

The 150 or broad square page is latent not only in the square but in the octagon.

Except for Z<sub>3</sub>, all formats on this page are shown as two-page spreads.



rso sheet sizes:	AO =841 × 1189 mm	A3 = 297 × 420 mn
	A1 = $594 \times 841 \text{ mm}$	A4 = 210 × 297 mm
	$A2 = 420 \times 594 \text{ mm}$	$A5 = 148 \times 210 \text{ mm}$

When a sheet whose proportions are  $1:\sqrt{2}$  is folded in half, the result is a sheet half as large but with the same proportions. Standard paper sizes based on this principle have been in use in Germany since the early 1920s. The basis of the system is the AO sheet, which has an area of 1 m². Yet precisely because it is reciprocal with nothing but itself, the 150 page is, in isolation, the least musical of all the major page shapes. It needs a textblock of another shape for contrast.

Organic, Mechanical and Musical Proportion The golden section is a symmetrical relation built from asymmetrical parts. Two numbers, shapes or elements embody the golden section when the smaller is to the larger as the larger is to the sum. That is, a:b=b:(a+b). In the language of algebra, this ratio is  $1:\varphi=1:(1+\sqrt{5})/2$ , and in the language of trigonometry, it is  $1:(2\sin 54^\circ)$ . Its approximate value in decimal terms is 1:1.61803.

Shaping the Page

The second term of this ratio,  $\varphi$  (the Greek letter *phi*), is a number with several unusual properties. If you *add* one to  $\varphi$ , you get its square ( $\varphi \times \varphi$ ). If you *subtract* one from  $\varphi$ , you get its reciprocal (1/ $\varphi$ ). And if you multiply  $\varphi$  endlessly by itself, you get an infinite series embodying a single proportion. That proportion is 1:  $\varphi$ . If we rewrite these facts in the typographic form mathematicians like to use, they look like this:

$$\phi + 1 = \phi^{2}$$

$$\phi - 1 = 1/\phi$$


$$\phi^{-1} : 1 = 1 : \phi = \phi : \phi^{2} = \phi^{2} : \phi^{3} = \phi^{3} : \phi^{4} = \phi^{4} : \phi^{5} ...$$

If we look for a numerical approximation to this ratio,  $\iota: \phi$ , we will find it in something called the Fibonacci series, named for the thirteenth-century mathematician Leonardo Fibonacci. Though he died two centuries before Gutenberg, Fibonacci is important in the history of European typography as well as mathematics. He was born in Pisa but studied in North Africa. On his return, he introduced Arabic mathematics to North Italian scholars and also arabic numerals to the North Italian scribes.

As a mathematician, Fibonacci took an interest in many problems, including the problem of unchecked propagation. What happens, he asked, if everything breeds and nothing dies? The answer is a logarithmic spiral of increase. Expressed as a series of integers, such a spiral takes the following form:

Here each term after the first two is the sum of the two preceding. And the farther we proceed along this series, the closer

The Golden Section



The screened area represents a two-page spread in which each page embodies the golden section. The root of the spiral, which is the navel of the page, lies at the intersection of the diagonals. This is a Renaissance structure: precisely measured and formed, yet open-ended, unconfined. Like Thoreau's vision of the mind (page 66), it is hypethral. (Compare the equally elegant but closed, medieval structure on page 173 and the resolutely linear structure on

page 154.)

**G** Golden Section,  $1: \varphi = 1:1.618...$  In the pentagon, the sides and the chord c embody the golden section. The smaller is to the larger as the larger is to the whole, or s: c = c: (s + c). When two chords intersect, they divide each other in the same proportion: a: b = b: c, where c = a + b. Moreover, b = s. Thus,  $a: s = s: c = c: (s + c) = 1: \varphi$ .

An evolving sequence of figures that embody the golden section also defines the path of a logarithmic spiral. And if the lengths of the sides of the figures are rounded off to the nearest whole numbers, the result is a Fibonacci series of integers.

we come to an accurate approximation of the number  $\varphi$ . Thus 5:8 = 1:1.6; 8:13 = 1:1.625; 13:21 = 1:1.615; 21:34 = 1:1.619, and so on.

In the world of pure mathematics, this spiral of increase, the Fibonacci series, proceeds without end. In the world of mortal living things, of course, the spiral soon breaks off. It is repeatedly interrupted by death and other practical considerations – but it is visible nevertheless in the short term. Abbreviated versions of the Fibonacci series, and the proportion 1:  $\phi$ , can be seen in the structure of pineapples, pinecones, sunflowers, sea urchins, snails, the chambered nautilus, and in the proportions of the human body as well.

Shaping the Page

The golden section,  $1: \varphi$ ,

one per cent

of the minor sixth in the

differs by roughly

from the interval

chromatic scale.

The proportion

of the minor

sixth in music,

5.8, which is the arithmetic value

If we convert the ratio 1:  $\phi$  or 1:1.61803 to percentages, the smaller part is roughly 38.2% and the larger 61.8% of the whole. But we will find the *exact* proportions of the golden section in several simple geometric figures. These include the pentagon, where they are relatively obvious, and the square, where they are somewhat more deeply concealed. Sunflowers, snails and humans who use the golden section *choose* it; they do not invent it.

The golden section was much admired by classical Greek geometers and architects, and by Renaissance mathematicians, architects and scribes, who often used it in their work. It has also been much admired by artists and craftsmen, including typographers, in the modern age. Paperback books in the Penguin Classics series have been manufactured for more than half a century to the standard size of 111  $\times$  180 mm, which embodies the golden section. The Modulor system of the Swiss architect Le Corbusier is based on the golden section as well.

is often used in typography as a rough approximation to the golden section.

If type sizes are chosen according to the golden section, the result is again a Fibonacci series:

(a) 
$$5 \cdot 8 \cdot 13 \cdot 21 \cdot 34 \cdot 55 \cdot 89 \dots$$

These sizes alone are adequate for many typographic tasks. But to create a more versatile scale of sizes, a second or third interlocking series can be added. The possibilities include:

(b) 
$$6 \cdot 10 \cdot 16 \cdot 26 \cdot 42 \cdot 68 \cdot 110 \dots$$


(c) 
$$4 \cdot 7 \cdot 11 \cdot 18 \cdot 29 \cdot 47 \cdot 76 \dots$$

All three of these series -a, b and c - obey the Fibonacci rule (each term is the sum of the two terms preceding). Series b is also


related to series a by simple doubling. The combination of a and **b** is therefore a two-stranded Fibonacci series with incremental symmetry, forming a very versatile scale of type sizes:

(d) 
$$6 \cdot 8 \cdot 10 \cdot 13 \cdot 16 \cdot 21 \cdot 26 \cdot 34 \cdot 42 \cdot 55 \cdot 68 \dots$$

The Golden Section The double-stranded Fibonacci series used by Le Corbusier (with other units of measurement) in his architectural work is similarly useful in typography:



Finding the golden section in the square. Begin with the square abcd. Bisect the square (with the line ef) and draw diagonals (ec and ed) in each half. An isosceles triangle, cde, consisting of two right triangles, is formed. Extend the base of the square (draw the line gk) and project each of the diagonals (the hypotenuse of each of the right triangles) onto the extended base. Now ce = cg, and de = dk. Draw the new rectangle, efgh. This and its mirror image, ejkf, each have the proportions of the golden section. That is to say,  $eh: gh = gh: (gh + eh) = ej: jk = jk: (jk + ej) = 1: \varphi$ . (Contrast this with figure  $Z_2$  on page 153.)



The relationship between the square and the golden section is perpetual. Each time a square is subtracted from a golden section, a new golden section remains. If two overlapping squares are formed within a golden-section rectangle, two smaller rectangles of golden-section proportions are created, along with a narrow column whose proportions are 1:  $(\phi + 1) = 1$ : 2.618. This is **g**, the Extended Section, from the table on page 149. If a square is subtracted from this, the golden section is restored.



ample, is indented according to the golden section. The indent is to the remainder of the line as that remainder is to the full text measure. Here the measure is 21 picas, and the indent is 38.2% of that, which is to say 8 picas.

The amount of *sinkage* (the extra white space allowed at the top of the page) is 7 lines (here equal to 7 picas). Add the extra pica of white space created by the indent itself, and you have an imaginary 8-pica square of empty space in the upper left corner of the textblock.

The size of the elevated cap is related in turn to the size of the indent and the sinkage. Eight picas is 96 pt, and 61.8% of that is 59.3 pt. But the relationship between 59 or 60 pt type and an 8-pica indent would be difficult to perceive, because a 60 pt letter is not visibly 60 pt high. The initial used has an actual 60 pt cap height instead. Depending on the face, such a letter could be anywhere from 72 to 100 pt nominal size; here it is 84 pt Castellar.

#### 8.3 PROPORTIONS OF THE EMPTY PAGE

8.3.1 Choose inherently satisfying page proportions in preference to stock sizes or arbitrary shapes.

The proportions of a page are like an interval in music. In a given context, some are consonant, others dissonant. Some are familiar; some are also inescapable, because of their presence in the structures of the natural as well as the man-made world. Some proportions also seem particularly linked to living things. It is true that wastage is often increased when an  $8\frac{1}{2} \times 11$  inch page is trimmed to  $7\frac{3}{4} \times 11$  or  $6\frac{3}{4} \times 11$ , or when a  $6 \times 9$  book page is narrowed to  $5\frac{5}{8} \times 9$ . But an organic page looks and feels different from a mechanical page, and the shape of the page itself will provoke certain responses and expectations in the reader, independently of whatever text it contains.

8.3.2 Choose page proportions suited to the content, size and ambitions of the publication.

There is no one ideal proportion, but some are clearly more ponderous, others more brittle. In general, a book page, like a human being, should not peer down its nose, nor should it sag.

The narrower page shapes require a soft or open spine so that the opened book lies flat, and at smaller sizes, narrower pages are suitable only for text that can be set to a narrow measure. At larger sizes, the narrow page is more adaptable.

Shaping the Page

For ordinary books, consisting of simple text in a modest size, typographers and readers both gravitate to proportions ranging from the light, agile 5:9 [1:1.8] to the heavier and more stolid 4:5 [1:1.25]. Pages wider than 1: $\sqrt{2}$  are useful primarily in books that need the extra width for maps, tables, sidenotes or wide illustrations, and for books in which a multiple-column page is preferred.

When important illustrations are involved, these generally decide the shape of the page. Typically, one would choose a page somewhat deeper than the average illustration, both to leave extra blank space at the foot of the page, and to permit the insertion of captions. The  $e/\pi$  or turned hexagon page, 1:1.16, for example, which is slightly deeper than a perfect square, is useful for square artwork, such as photographs taken with a square-format camera. The  $\pi/e$  or broad hexagon page, 1:0.87, is useful for landscape photographs in the 4 × 5 format, and the full cross octagon page, 1:0.83, for landscape photos in the wider format of 35 mm. (Uncropped 35 mm transparencies embody the proportion 2:3.)

# 8.3.3 Choose page and column proportions whose historical associations suit your intended design.

Early Egyptian scribes (when not writing vertically) tended to write a long line and a wide column. This long Egyptian line reappears in other contexts over the centuries – on Roman imperial writing tablets, in medieval European charters and deeds, and in many poorly designed twentieth-century works of academic prose. It is a sign, generally speaking, that the emphasis is on the writing instead of the reading, and that writing is seen as an instrument of power, not an instrument of freedom. Whether oral or visual, longwindedness is very rarely a virtue.

Proportions of the Empty Page Early Hebrew scribes generally favored a narrower column, and early Greek scribes a column narrower still. But they, like the Egyptians, were making scrolls instead of bound books. It is difficult, therefore, to compare modern notions of the page directly with theirs. You can open a scroll as wide as you like, exposing one column, two columns, three. This flexible approach to the concept of the page survives to some extent in early codices (bound books). There are early books that are three times taller than wide, others that are close to square, and many shapes between.

In medieval Europe, most books, though certainly not all, settled down to proportions ranging from 1:1.5 to 1:1.25. Paper – once the mills were built in Europe – was commonly made in sheets whose proportions were 2:3 [1:1.5] or 3:4 [1:1.33]. These proportions, which correspond to the acoustically perfect musical intervals of fifth and fourth, also reproduce one another with each fold. If a sheet is  $40 \times 60$  cm [2:3] to start with, it folds to  $30 \times 40$  [3:4], which folds to  $20 \times 30$ , and so on. The  $25 \times 38$  inch [roughly 2:3] and  $20 \times 26$  inch [roughly 3:4] press sheets used in North America today are survivors of this medieval tradition.

The page proportion  $1:\sqrt{2}$ , which is now the European standard, was also known to the medieval scribes. And the tall half octagon page, 1:1.3 (the shape enshrined now in North American letter paper) has a similar pedigree. The British Museum has a Roman wax-tablet book of precisely this proportion, dated to about AD 300.

Renaissance typographers continued to produce books in the proportions 1:1.5. They also developed an enthusiasm for narrower proportions. The proportions 1:1.87 (tall hexagon), 1:1.7 (tall pentagon), 1:1.67 [3:5], and of course 1:1.62, the golden section, were used by typographers in Venice before the end of the fifteenth century. The narrower page was preferred especially for works in the arts and sciences. Wider pages, better able to carry a double column, were preferred for legal and ecclesiastical texts. (Even now, a Bible, a volume of court reports or a manual on mortgages or wills is likely to be on a wider page than a book of poems or a novel.)

Renaissance page proportions (generally in the range of 1:1.4 to 1:2) survived through the Baroque, but Neoclassical books are often wider, returning to the heavier Roman proportion of 1:1.3.

8.4.1 If the text is meant to invite continuous reading, set it in columns that are clearly taller than wide.

Horizontal motion predominates in alphabetic writing, and for beginners, it predominates in reading. But vertical motion predominates in reading for those who have really acquired the skill. The tall column of type is a symbol of fluency, a sign that the typographer does not expect the reader to have to puzzle out the words.

Shaping the Page

The very long and very narrow columns of newspapers and magazines, however, have come to suggest disposable prose and quick, unthoughtful reading. A little more width not only gives the text more presence; it implies that it might be worth savoring, quoting and reading again.

8.4.2 Shape the textblock so that it balances and contrasts with the shape of the overall page.

The proportions that are useful for the shapes of pages are equally useful in shaping the textblock. This is not to say that the proportions of the textblock and the page should be the same. They often were the same in medieval books. In the Renaissance, many typographers preferred a more polyphonic page, in which the proportions of page and textblock differ. But it is pointless for them to differ unless, like intervals in music, they differ to a clear and purposeful degree.

For all the beauty of pure geometry, a perfectly square block of type on a perfectly square page with even margins all around is a form unlikely to encourage reading. Reading, like walking, involves navigation – and the square block of type on a square block of paper is short of basic landmarks and clues. To give the reader a sense of direction, and the page a sense of liveliness and poise, it is necessary to break this inexorable sameness and find a new balance of another kind. Some space must be narrow so that other space may be wide, and some space emptied so that other space may be filled.


In the simple format shown overleaf, a page whose proportions are 1:1.62 (the golden section) carries a textblock whose proportions are 1:1.8 [5:9]. This difference constitutes a primary visual chord which generates both energy and harmony in the

page. It is supplemented by secondary harmonies created by the proportions of the margins and the placement of the textblock – not in the center of the page but high and toward the spine.

The textblock itself, in this example, is symmetrical, but it is placed asymmetrically on the page. The lefthand page is a mirror image of the right, but no mirror image runs the other way. The two-page spread is symmetrical horizontally – the direction in which the pages turn, either backward or forward, as the reader consults the book – but it is asymmetrical vertically – the direction in which the page stays put while the reader's eye repeatedly works its way in one direction: down.

The Textblock

This interlocking relationship of symmetry and asymmetry, and of balanced and contrasted shape and size, was not new when this example was designed (in Venice in 1501). The first European typographers inherited some two thousand years' worth of research into these principles from their predecessors, the scribes. Yet the principles are flexible enough that countless new typographic pages and page-spreads wait to be designed.



Page spread, probably by Francesco Griffo, Venice, 1501. The text is Virgil's *Aeneid*, set entirely in a crisp, simple italic lower case,  $12/12 \times 16$ , with roman small capitals, approximately 5 pt high. The original page size is  $10.7 \times 17.3$  cm.

### 8.5.1 Bring the margins into the design.

In typography, margins must do three things. They must lock the textblock to the page and lock the facing pages to each other through the force of their proportions. Second, they must frame the textblock in a manner that suits its design. Third, they must protect the textblock, leaving it easy for the reader to see and convenient to handle. (That is, they must leave room for the reader's thumbs.) The third of these is easy, and the second is not difficult. The first is like choosing type: it is an endless opportunity for typographic play and a serious test of skill.

Shaping the Page

Perhaps fifty per cent of the character and integrity of a printed page lies in its letterforms. Much of the other fifty per cent resides in its margins.

#### 8.5.2 Bring the design into the margins.

The boundaries of the textblock are rarely absolute. They are nibbled and punctured by paragraph indents, blank lines between sections, gutters between columns, and the sinkage of chapter openings. They are overrun by hanging numbers, outdented paragraphs or heads, marginal bullets, folios (page numbers) and often running heads, marginal notes and other typographic satellites. These features – whether recurrent, like folios, or unpredictable, like marginal notes and numbers – should be designed to give vitality to the page and further bind the page and the textblock.

## 8.5.3 Mark the reader's way.

Folios are useful in most documents longer than two pages. They can be anywhere on the page that is graphically pleasing and easy to find, but in practice this reduces to few possibilities: (1) at the head of the page, aligned with the outside edge of the textblock (a common place for folios accompanied by running heads); (2) at the foot of the page, aligned with or slightly indented from the outside edge of the text; (3) in the upper quarter of the outside margin, beyond the outside edge of the text; (4) at the foot of the page, horizontally centered beneath the textblock.

The fourth of these choices offers Neoclassical poise but is not the best for quick navigation. Folios near the upper or lower outside corner are the easiest to find by flipping pages in a small book. In large books and magazines, the bottom outside corner is generally more convenient for joint assaults by eye and thumb. Folios placed on the inner margin are rarely worth considering. They are invisible when needed and all too visible otherwise.

Margins and Satellites It is usual to set folios in the text size and to position them near the textblock. Unless they are very black, brightly colored or large, the folios usually drown when they get very far away from the text. Strengthened enough to survive on their own, they are likely to prove a distraction.

#### 8.5.4 Don't restate the obvious.

In Bibles and other large works, running heads have been standard equipment for two thousand years. Photocopying machines, which can easily separate a chapter or a page from the rest of a book or journal, have also given running heads (and running feet, or footers) new importance.

Except as insurance against photocopying pirates, running heads are nevertheless pointless in many books and documents with a strong authorial voice or a unified subject. They remain essential in most anthologies and works of reference, large or small.


Like folios, running heads pose an interesting typographic problem. They are useless if the reader has to hunt for them, so they must somehow be distinguished from the text, yet they have no independent value and must not become a distraction. It has been a common typographic practice since 1501 to set them in spaced small caps of the text size, or if the budget permits, to print them in the text face in a second color.

#### 8.6 PAGE GRIDS & MODULAR SCALES

## 8.6.1 Use a modular scale if you need one to subdivide the page.

Grids are often used in magazine design and in other situations where unpredictable graphic elements must be combined in a rapid and orderly way.

Modular scales serve much the same purpose as grids, but they are more flexible. A modular scale, like a musical scale, is a prearranged set of harmonious proportions. In essence, it is a measuring stick whose units are *indivisible* (or are treated as



Shaping the Page


Standard grid for three-column magazine

such) and are *not of uniform size*. The traditional sequence of type sizes shown on page 45, for example, is a modular scale. The single- and double-stranded Fibonacci series discussed on pp 157–158 are modular scales as well. These scales can, in fact, be put directly to use in page design by altering the units from points to picas. More examples of modular scales are shown on the following page.


It is perfectly feasible to create a new modular scale for any project requiring one, and the scale can be founded on any convenient single or multiple proportion – a given page size, for example, or the dimensions of a set of illustrations, or something implicit in the subject matter. A work on astronomy might use a modular scale based on star charts or Bode's law of interplanetary distances. A book on Greek art might be laid out using intervals from one or more of the Greek musical scales or, of course, the golden section. A work of modernist literature might be designed using something more deliberately arcane – perhaps a scale based on the proportions of the author's hand. Generally speaking, a scale based on two ratios (1:  $\varphi$  and 1: 2, for example) will give more flexible and interesting results than a scale founded on just one.

The Half Pica Modular scale illustrated overleaf is actually a miniaturized version of the architectural scale of Le Corbusier, which is based in turn on the proportions of the human body.

See Le Corbusier, The Modulor (2nd ed., 1954).



Four examples of modular pica sticks (shown at half actual size). **A** Whole Pica Modular scale. **B** Half Pica Modular scale. These are both two-stranded Fibonacci series, based on the ratios 1:  $\varphi$  and 1: 2. **C** Medieval Interval scale, based on the proportions 2: 3 and 1: 2. **D** Timaean Scale, a simplified version of the Pythagorean scale outlined in Plato's *Timaeus*.



Use of the modular scale. These pages and textblocks have been subdivided using the Half Pica Modular scale. The pages are  $52 \times 55$  picas ( $8\%" \times 9\%"$ ), with margins of 5, 5, 5 & 8 picas. The basic textblock is 42 picas square. Thousands of different subdivisions are possible. (For more complex examples on similar principles, see Le Corbusier, *The Modulor*.)

Examples

The formula for designing a perfect page is the same as the formula for writing one: start at the upper left hand corner and work your way across and down; then turn the page and try again. The examples on the following pages show only a few of the many kinds of typographic structures that might evolve along the way.

In fact, the weaving of the text and the tailoring of the page are thoroughly interdependent. We can discuss them one by one, and we can separate each in turn into a series of simple, unintimidating questions. But the answers to these questions must all, in the end, fold back into a single answer. The page, the pamphlet or the book must be seen as a whole if it is to look like one. If it appears to be only a series of individual solutions to separate typographic problems, who will believe that its message coheres?

In analyzing the examples on the following pages, these symbols are used:

Proportions: P = page proportion: h/w

T = textblock proportion: d/m

Page size: w =width of page (trim-size)

h = height of page (trim-size)

Textblock: m = measure (width of primary textblock)

d = depth (height) of primary textblock
 (excluding running heads, folios, etc)

 $\lambda$  = line height (type size plus added lead)

n = secondary measure (width of secondary column) c = column width, where there are even multiple

columns

Margins: s = spine margin (back margin)


t = top margin (head margin)

e = fore-edge (front margin)


f = foot margin

g = internal gutter (on a multiple-column page)


Page and textblock proportions (P and T in the examples) are given here as single values (1.414, for example). To find the same values in the table on page 148, look up the corresponding *ratio* (1:1.414, for example).



P = variable; T = 1.75. Margins: t = h/12; f = 3t/2; g = t/2 or t/3. Text columns from Isaiah Scroll A, from Qumran Cave 1, on the Dead Sea. The column depth is 29 lines and the measure is 28 picas, giving a line length of roughly 40 characters. Elsewhere in the scroll, column widths range from 21.5 to 39 picas. Paragraphs begin on a new line but – in keeping with the crisp, square Hebrew characters – are not indented. (Palestine, perhaps first century BC.) Original size:  $26 \times 725$  cm.





P = 1.5 [2:3]; T = 1.7 [tall pentagon]. Margins: s = t = w/9; e = 2s. The text is a fantasy novel, Francesco Colonna's *Hypnerotomachia Poliphili*, set in a roman font cut by Francesco Griffo. (Aldus Manutius, Venice, 1499.) Original size: 20.5 × 31 cm.



P = 1.62 [golden section]; T = 1.87 [tall hexagon]. Margins: s = w/9; t = s; e = 2s. Secondary column: g = w/75; n = s. The text is in Claude Garamond's 14 pt roman; the sidenotes are 12 pt italic. The gutter between main text and sidenotes is tiny: 6 or 7 pt against a main text measure of 33.5 picas. But the differences in size and face prevent any confusion. The text is a history of the Hundred Years' War. (Jean Froissart, *Histoire et chronique*, Jean de Tournes, Paris, 1559.) Original size: roughly  $21 \times 34$  cm.

This grid is analyzed on the facing page.






Shaping the Page

P = T = 1.5 [2:3]. Margins: s = w/9; t = h/9; e = 2s; f = 2t. The margins are thus in the proportion s: t: e: f = 2:3:4:6. A sound, elegant and basic medieval structure, which will work for any proportion of page and textblock, so long as the two remain in unison. Spine and head margins may be ninths, tenths, twelfths or any other desired proportion of the page size. Twelfths, of course, give a fuller and more efficient page, with less white space. But if the page proportion is 2:3 and the spine and head margins are ninths, as shown here, the consonance of textblock and page is considerably deepened, because d = w, which is to say, the depth of the textblock matches the width of the page. Thus m: w = d: h = w: h = m: d = s: t = e: f = 2:3. Point a, where the half and full diagonals intersect, is one third of the way down and across the textblock and the page. Jan Tschichold, 1955, after Villard de Honnecourt, France, c. 1280. See Tschichold's *The Form of the Book* (1991).

Scribes employing this format often designed their pages so that the line height was an even factor of the spine margin. If  $\lambda = s/3$ , the depth of the textblock will be 27 lines. If  $\lambda = s/4$ , the depth of the textblock will be 36 lines.


FACING PAGE: P = 1.5 [2:3]; T = 2 [double square]. Margins: s = e = w/5; t = s/2. The text is a book of poems, set throughout in a chancery italic with roman capitals. The designer and publisher of this book was a master calligrapher, certainly aware of the tradition that the inner margins should be smaller than the outer. He followed that tradition himself with books of prose, but in this book of poems he chose to center the textblock on the page. The text throughout is set in one size. Titles are set in the capitals of the text font, letterspaced about 30%. There are no running heads or other diversions. (Giangiorgio Trissino, *Canzone*, Ludovico degli Arrighi, Rome, c. 1523.) Original size: 12.5 × 18.75 cm.




P = 1.5 [2:3]; T = 1.54 [pentagon textblock]. Margins: s = w/20; t = s = h/30; e = w/15 = 4s/3; f = 2t. This is the format used for the index to the fifth edition of the *Times Atlas of the World* (London, 1975). The page is a standard medieval shape. The text is set in 5.5 pt Univers leaded 0.1 pt on a 12-pica measure, in five subdivided columns per page. Columns are separated by thin vertical rules. Keywords and folios, at the top of the page, are in 16 pt Univers semibold. (Because of their prominence, these running heads are included here in calculating the size and shape of the textblock.) The text is 204 lines deep, yielding an average of 1000 names per page for 217 pages. This index is a masterpiece of its kind: a potent typographic symbol, an efficient work of reference, and a comfortable text to browse. Original size:  $30 \times 45$  cm.



Examples







Shaping the Page

P = 1.414  $[\sqrt{2}]$ ; T = 1.62  $[\varphi]$ , the golden section]. Margins: s = t = w/9 and e = f = 2s. This is a simple format for placing a golden-section textblock on an 1s0 page, locking the two together with margins in the proportions 1 : 2. Two possible locations for folios are shown: in the upper outside margin and (as an alternative) underneath the lower outside corner of the textblock. There is also ample room for sidenotes in the fore-edge if required. If the spine and top margins on these pages are increased to w/8, while the textblock and page are held at their original proportion, the relationship of the margins becomes  $e = f = \varphi s$ , another golden section.

FACING PAGE: P = 1.1; T = 0.91; c = w/6. Margins: s = w/14; e = 2s; t = 3s; f = 3s/2; g = m/20. The proportions of the textblock are the reciprocal of the proportions of the page: 0.91 = 1/1.1, which is to say that the textblock is the same shape as the page, rotated  $90^\circ$ . But if the gutters are removed from the textblock and the four columns closed up solid, the textblock collapses to the same shape in the same orientation as the page. In other words, the textblock has been expanded from the same shape to the reciprocal shape of the page entirely by the addition of white space. The text is the Greek Bible, lettered in uncials, about 13 characters per line. There are no spaces between the words, but there is some punctuation, and the text has a slight rag, with line breaks carefully chosen. This subtle piece of craftsmanship was produced in Egypt in the fourth century. It is the Codex Sinaiticus, Add. Ms. 43725, at the British Library, London. Original size:  $34.5 \times 38$  cm.



P = 1.414 [ $\sqrt{2}$ ]; T = 2 [double square]. Margins: s = w/12; f = 2t = h/9; e = w/3. The wide fore-edge of this manuscript book had a purpose: it was deliberately left free for sidenotes to be added by the owner. The text is a sequence of short poems by the Roman poet Horace, written in Caroline minuscule. (Ms. Plut. 34.1, Laurentian Library, Florence; tenth century.)



P = 1.176 [truncated pentagon page]; T = 1.46. Margins: s = h/11; t = 5s/6; e = 5s/2; f = 3s/2. Columns: c = 3w/10; g = s/4. The text (set in Friedrich Poppl's Pontifex,  $11/13 \times 17$  RR) is a series of essays on twentieth-century art, published in Canada in 1983, with many full-page illustrations. Original size:  $24 \times 28$  cm.

### 8.8.1 Improvise, calculate, and improvise some more.

Numerical values – used by all typographers in their daily work – give an impression of exactness. Careful measurement and accurate calculation are indeed important in typography, but they are not its final purpose, and moments arise in every project when exactness bumps its head against approximation. On the mechanical side, paper expands and contracts, and printing presses, folding machines and trimming knives – not to speak of typesetting hardware and software – all have their margins of error. The typographer can rarely profit from these variations and cannot entirely prevent them. On the planning side, however, imprecision can often be put to better use.

Shaping the Page

Some typographers prefer to design by arithmetic from the outset, in a space composed of little invisible bricks called points and picas. Others prefer to work in the free two-dimensional space of a sketchpad, converting their layouts afterward to typographic measure. Most work involves a combination of these methods, with occasional collisions between the two. But the margins of inexactness that crop up in the rounding of units, in conflicts between optical and arithmetic spacing and centering, in combining proportions, and in translating from one form of measurement to another should be welcomed as opportunities, not as inconsistencies to be ignored, glossed over or begrudged. The equal temperament of the typesetting machine and the just intonation of the sketchpad should be used to test and refine one another until the final answer sings.

8.8.2 Adjust the type and the spaces within the textblock using typographic increments, but rely on free proportions to adjust the empty space.

Proportions are more flexible than picas, and it is usually convenient and appealing to work in even units. A margin of 5.32 picas, for example, begs to be altered to 5 or 5½ or 5½. But picas per se are less important than proportions, and the system of typographic sizes and units serves the interrelations of letterforms better than it serves the interrelations of empty space. As a general rule, it is better to make incremental jumps in the textblock first and to re-

adjust the margins thereafter – paying more attention in the latter case to absolute proportion than to convenient units of measurement. When space is measured purely in points, the temptation to rearrange it into even picas is miraculously lessened.

8.8.3 Keep the page design supple enough to provide a livable home for the text.

Improvisations and Adjustments

Architects build perfectly proportioned kitchens, living rooms and bedrooms in which their clients will make, among other things, a mess. Typographers likewise build perfectly proportioned pages, then distort them on demand. The text takes precedence over the purity of the design, and the typographic texture of the text takes precedence over the absolute proportions of the individual page.

If, for instance, three lines remain at the end of a chapter, looking forlorn on a page of their own, the design must flex to accommodate them. The obvious choices are: (1) running two of the previous spreads a line long (that is, adding one line to the depth of two pairs of facing pages), which will leave the final page one line short; (2) running half a dozen of the previous spreads a line short, thereby bumping a dozen lines along to the final page; or (3) reproportioning some non-textual element – perhaps an illustration or the sinkage, if any, at the head of the chapter.

Spacious chapter heads stand out in a book, as they are meant to. Reproportioning the sinkage is therefore a poor option unless all chapter heads can be reproportioned to match. And running six spreads short is, on the face of it, clearly a greater evil than running two spreads long.

If there are only a few pages to the document, the whole thing can, and probably should, be redesigned to fit the text. But in a book of many pages, widow lines, orphaned subheads, and the runt ends of chapters or sections are certain to require reproportioning some spreads. A rigid design that demands an invariant page depth is therefore inappropriate for a work of any length. Altering the leading on short pages to preserve a standard depth (vertical justification, it is sometimes called) is not a solution. Neither is stuffing extra space between the paragraphs. These antics destroy the fabric of the text and thus strike at the heart of the book.

\_\_\_\_\_

The state of the art has more by far to do with the knowledge and skill of its practitioners than with the subtleties of their tools, but tools can constrain that skill or set it free. The limitations of the tools are therefore also of some interest. They are of special interest now, because they are subject to rapid change.

9

#### 9.1 THE HUNDRED-THOUSAND CHARACTER ALPHABET

It is often said that the Latin alphabet consists of 26 letters, the Greek of 24 and the Arabic of 28. If you confine yourself to one case only, a narrow historical window and the dialect in power, this assertion can hold true. If you include both caps and lower case, accented letters and a global set of consonants and vowels –  $\dot{a}$  à  $\ddot{a}$  ä  $\ddot{a}$  ä  $\ddot{a}$  ä  $\ddot{a}$  æ  $\dot{e}$  ç  $\dot{c}$  č  $\dot{c}$  ð đ  $\dot{e}$  ł ñ ň  $\ddot{n}$  ő  $\ddot{s}$  s  $\ddot{s}$  þ ű ů  $\ddot{u}$   $\dot{w}$  ý  $\dot{z}$   $\dot{z}$  and all the rest – the Latin alphabet is not 26 letters long after all; it is closer to 600 and able to increase at any time. The alphabet that classicists now use for classical Greek, with its long parade of vowels and diacritics –  $\dot{a}$  à  $\ddot{a}$  å  $\ddot{a}$  å  $\ddot{a}$  å  $\ddot{a}$   $\ddot{a}$ , and so on – is modest by comparison: fewer than 300 glyphs altogether.

To the 600-character globalized Latin alphabet, mathematicians, grammarians, chemists and even typographers are prone to make additions: arabic numerals, punctuation, technical symbols, letters borrowed from Hebrew, Greek and Cyrillic, and, where the letterforms require or invite them, a few typographic ligatures and alternates as well. There is no hope at this stage of counting the number of sorts or glyphs precisely, but the total is clearly over a thousand.

At the end of the eighteenth century, an English-speaking hand compositor's standard lower case had 54 compartments, holding roman or italic a to z, arabic numerals, basic ligatures, spaces and punctuation. The upper case had another 98, containing caps and analphabetics. That total, 98 + 54 = 152, is the English-speaking hand compositor's minimum basic allotment. When more sorts are required, as they very often are, supplementary cases are used. Two pair give 304 compartments; three pair give 456; four pair give 608. This has been the ordinary typographic ballpark for some time. How Gutenberg's cases were arranged we do not know, but we know how big they were. He used not 26

Printing enthusiasts sometimes speak of the lay of the case as if it were universal law - but the lay of the case is as localized as the lay of the land. Hand compositors often set not from paired but from single cases. These have been reduced to as few as 89 compartments but sometimes contain 400 or more.

Many computer keyboards have over 100 keys, but only 47 are tied to characters. (This odd number is made even by the spacebar.) Each character key has, at minimum, a plain and a shift position, reaching 94 characters in all: ordinarily the 94 basic ASCII characters. But the keys can be remapped and can easily be coded to reach four characters each instead of two. (An example of such a keyboard is shown on page 92.) When more than 47 × 4 = 188 characters are needed at one time, more than one keyboard map is in order as well. Function keys are normally used to jump from one map to another: Latin to Greek to Cyrillic to Hebrew for example. but 290 different sorts, in one face and one size, in an unaccented script, to set his 42-line Bible. The Monotype machine, built five centuries later, with 255 (later 272) positions in a standard matrix case, had fallen only a little ways behind.

Early computers and e-mail links were, by comparison, living in typographic poverty. The alphabet they used was the basic character set defined by the American Standard Code for Information Interchange, or ASCII. Each character was limited to seven bits of binary information, so the maximum number of characters was  $2^7 = 128$ . Thirty-three of those were normally subtracted for control codes, and one was the code for an empty space. This leaves 94: not even enough to hold the standard working character set of Spanish, French or German. The fact that such a character set was long considered adequate tells us something about the cultural narrowness of American civilization, or American technocracy, in the midst of the twentieth century.

The extended ASCII character set, which has been in general use since 1980, is made from eight-bit characters. This gives  $2^8 = 256$  slots altogether. As a rule, glyphs are assigned to some 230 of these. Editing and composition software often limits the working selection to 216 or less. The upper register of this set – altogether invisible on a normal computer keyboard – is usually filled out with characters selected from the Latin 1 Character Set established by 150 (the International Organization for Standardization, Geneva). These characters –  $\ddot{a}$   $\dot{c}$   $\dot{e}$   $\ddot{n}$  and so on – are identified and discussed in appendix B, page 301.

The allotment of 216 or 230 characters is meagre but adequate for basic communication in all the 'official' languages of Western Europe and North America. This ignores the needs of mathematicians, linguists and other specialists, and of millions of normal human beings who use the Latin alphabet for Czech, Hausa, Hungarian, Latvian, Navajo, Polish, Romanian, Turkish, Vietnamese, Welsh, Yoruba, and so on. The extended ASCII character set is the alphabet not of the real world nor of the UN General Assembly but of NATO: a technological memento of the them-and-us mentality that thrived in the Cold War.

Good, affordable software that would handle thousands of characters efficiently was for sale (and in fact was widely used) in the early 1980s. Standardization within the industry shrank this palette down, then enormously increased it. Some typographic tools have not caught up. Typographically sectarian and culturally stunted software is widespread.

Earlier typographers were free to cut another punch at any time and cast another character. The freedom to do likewise exists with the computer. But finding room for all these letters in a shared standard alphabet involves, in the digital world, a shift from eight-bit to sixteen-bit characters. When we make this change, the alphabet increases to  $2^{16} = 65,536$  characters. The first version of a standard set of characters this size – known as Unicode – was roughed out at the end of the 1980s and published in the early 1990s. By the year 2000, the rudiments of Unicode were embedded in the operating systems of home computers, and major digital founders had adopted it as the new encoding standard.

See The Unicode Standard,

The State

of the Art

It is, like any standard, less than perfect, but it forms a working protocol both for a global Latin alphabet and for the technological coexistence of Arabic, Bengali, Chinese, Cyrillic, Devanagari, Greek, Hebrew, Korean, Latin, Thai, Tibetan and hundreds of other scripts. It was soon clear, however, that 65,000 characters wasn't enough. To extend the set,  $2^{10} = 2,048$  of the original allotment were assigned to function in pairs. This permits an additional  $1024^2 = 1,048,576$  characters. In its latest published form (version 4.0.0, issued in 2003), Unicode defines 96,382 characters, sets 137,468 aside for private use, and still has roughly 878,000 free for future allocation.

See The Unicode Standard, Version 4.0.0 (2003), on line at www.unicode.org.

ä

Few of us may need (and few may want to memorize) 100,000 characters. Typographers working in Chinese have often mastered 20,000; those who work in Korean learn 3,000 or more; most literate humans learn a thousand characters or fewer. Yet authors, editors, typographers and ordinary citizens who just want to be able to spell Dvořák, Miłosz, Mą'ii or al-Fārābī, or to quote a line of Sophocles or Pushkin, or the Vedas or the Sutras or the Psalms, or to write  $\varphi \neq \pi$ , are beneficiaries of a system this inclusive. So is everyone who want to read their e-mail in an alphabet other than Latin or a language other than English.

There may also never be a font of 100,000 well-made characters designed by one designer. But good fonts with well over ten thousand characters, keyed to the Unicode system, are now readily available. Computer operating systems now support them. More importantly, fonts for particular symbol sets and alphabets can be linked and tuned to one another by adjusting weight, letterfit and scale. This kind of typographic diplomacy is a task of some importance – and when character sets are joined in this way, sharing typographic space whether or not they are all on one font, Unicode can serve as a coordinating mechanism.

Unicode is relatively new, but many of the resources it catalogues are ancient. Composition software, communication links and keyboards are just starting to catch up.

#### 9.2 THE SUBSTANCE OF THE FONT

Type metal is typically 60% to 80% lead, 15% to 20% antimony and 5% to 10% tin. Some founders also like to add a trace of copper.

Within the tiny confraternity of metal typefounders and letterpress printers there is a subtribe that can argue day and night about recipes for type metal. In such a company, the question of whether to add or subtract five per cent of tin or antimony, or one per cent of copper, can lead to a long and heated exchange. In the community of digital founders and programmers, there is a corresponding subtribe capable of arguing till death about the merits of one digital format versus another.

Between 1980 and 2000, several digital formats were introduced. Each format's sponsors claimed their product was superior to its predecessors, and sometimes they had grounds to make such claims. In every case, however, it has turned out that what genuinely matters is not the format used so much as the level of hands-on workmanship, good sense and attention to detail. In metal and digital founding alike, the standard is set by the human who does the work, not by the recipe or by the brand name of the tools.


Bitmapped fonts came into use in the 1970s. Fonts of this sort are defined by simple addition and subtraction: this pixel on, that pixel off, these pixels on, those pixels off. In 1982, with the introduction of PostScript, bitmapped printer fonts rapidly gave way to fonts defined as scalable outlines. A decade later came the TrueType format, which differs from PostScript in two essential respects. First, PostScript and TrueType take a quite different approach to hinting (that is, they have different ways of addressing the problems caused by inadequate resolution). Second, their descriptive mathematics are different. Both interpret letterforms in terms of Bézier splines (that is to say, they rely on algebraic techniques developed by Paul de Casteljau and Pierre Bézier in France in the 1960s and 1970s) – but PostScript splines are cubic, while TrueType's are quadratic.

In mechanics, a spline is a flexible strip that will bend under tension. Boatbuilders and furniture makers use them for laying out curves. In mathematics, a spline is a curve that behaves as if it had fiber: sturdy enough to hold itself up yet limber enough to straighten and bend, stretch and retract. Think of a curve as a tensile line, bent by means of a lever attached to each end. Such a curve can be mathematically defined in terms of four points. Two of these are the *endpoints* of the curve. The other two, at the far ends of the levers, are known as the curve's *control points*. If the two imaginary levers can be controlled independently, then cubic equations [as for example,  $f(t) = (1-t)^3 E_1 + 3t(1-t)^2 C_1 + 3t^2(1-t) C_2 + t^3 E_2$ ] will be required to describe the curve, and it is called a cubic spline.

The levers themselves *are not part of the curve*, and the control points are usually off the curve. In the simplest case, however, these imaginary levers have a length of zero. Then the control points and the endpoints coincide, and the curve is a straight line.

One way to simplify a cubic spline is to tie the levers together so that both control points coincide (or so that one control point has a fixed relation to the other). If that is done, the mathematical description can be simplified from cubic to quadratic [along the lines,  $f(t) = (1-t)^2 E_1 + 2t(1-t)C + t^2 E_2$ ].

There are some other complications. A cubic spline, for instance, can have additional anchors or points of inflection; a quadratic spline cannot. In brief, cubic splines can be simple or complex; quadratic splines can only be comparatively simple. So translating a cubic spline to quadratic form can mean converting one spline into several (and the translation even then may be imperfect). A TrueType letterform will therefore often have more splines than the equivalent form in PostScript, but these are usually defined by fewer points, and mathematically speaking, the points are usually simpler to describe.



The *e* on the left, encoded in PostScript, is described by way of 18 cubic splines defined by 60 points. The *e* on the right, encoded in TrueType, is described by way of 23 quadratic splines defined by 52 points. Endpoints are represented by squares, control points by circles.

The State of the Art



A simple cubic spline, above, and the same curve (more or less) reconceived as two quadratic splines, below.



All quadratic splines can be perfectly expressed as cubic splines, but *not vice versa*. In quadratic equations, the highest power is *two* (e.g., *x* squared: *x*<sup>2</sup>); in cubic equations, it is three (e.g., *x* cubed: *x*<sup>3</sup>).

The Substance of the Font Several font formats based on PostScript have developed over the years. The one that has prospered is the early version known as Type One. PostScript fonts are accordingly referred to as PS, T-1 or PS-1. (For most purposes, these are synonymous.) Tens of thousands of fonts are now available in this format. Many are available now in TrueType (TT) format too (often directly converted from PostScript). In both, the level of technical quality ranges – like the design – from pathetic to superb.

A promising amplification of PS-1, developed at the beginning of the 1990s, is known as Multiple Master (MM). Fonts in the MM format are continuously adjustable along any of several axes, determined by the designer. These axes can include, for example, width, weight, optimal size, extender length, terminal shape or serif formation. To date, however, relatively few such fonts have actually been made.

# aaaaaaaaa

In Adobe's terminology, the size axis is called optical, not optimal size. What is at issue, however, is physical scale, which is visceral as much as optical. Adobe Jenson MM is scalable both for weight and for optimal size. Here one letter of uniform weight is scaled from 6 to 72 pt optimal size. The forms are then resized to the same x-height so their shapes and effective weights can be compared. If each letter is set at the size intended, optical balance is achieved.

The initial TrueType format led to two important variations. These are Graphic Extension (Gx) fonts, first released in 1994, and TrueType Open (TTO), dating from 1995. These formats are significant for their ability to accommodate large character sets together with automatic contextual substitution of variants and ligatures. Both these capabilities are essential for many Asian scripts (Arabic, Devanagari, Tibetan and Malayalam for example). They are also vital to many historical forms (and possibly some future forms) of Greek and Latin script.

Makers of editorial and composition software did not respond to these advances as eagerly as hoped. Partly for this reason, an agreement was reached in the late 1990s between the originators of PostScript (Adobe Systems) and the inheritors of TrueType (Microsoft) on yet another font format known as OpenType (OT OTF). Outwardly, an OpenType font resembles a GX or TTO font. It can include a colossal character set with multiple encodings. (It can hold, for example, thousands of Chinese or

Korean characters, and a complete pan-European set of Latin, Greek and Cyrillic with regional variants.) Several styles of figures and several sets of small caps can reside on the same font with the u&lc. The font can also include a set (or many sets) of rules for automatic substitution of alternates and ligatures and automatic repositioning of glyphs in certain contexts. And the letterforms within an ot font can be described in *either* cubic or quadratic terms. The kernel of the font, in other words, can be either PS or TT.

The State of the Art

The composition software has to work with such a font to bring its features into play. When run with parochial software, an ot font's ot features disappear. It behaves like a normal T-1 or TT font with 216 or fewer accessible characters.

Several thousand OT fonts have now been issued – and again, the quality ranges from dismal to superb. Some OT fonts in fact take no advantage of the format's capabilities; they are functionally identical to plain vanilla PS OT TT fonts. Others are rich and subtle. Without opening the package and checking out the contents, there is no real way to tell.

Typography and typefounding will not save the world. But peaceful coexistence and exchange among all the world's writing systems could be a gesture in that direction. Even this modest goal is a good ways off and may never be reached. But it is now a perceptible goal, which is something in itself.

#### 9.3 THE MULTIDIMENSIONAL FONT

#### 9.3.1 Glyphs and Characters

Typographers are frequently surprised to learn that small caps, text figures, swashes and other things they need and use are nowhere to be found in the lengthening Unicode catalogue. But Unicode lists textual not typographic symbols. Its aim is to embrace all linguistically meaningful signs, not all their typographically desirable forms and permutations. Because of inconsistencies in its original design, and because it has absorbed inconsistent Iso standards, even the recently purified version of Unicode includes some lingering compound characters. In theory, however, authors, editors and denizens of Unicode think and transmit elemental signs (f + f + i), for instance, rather than f(i), and typographers transform these underlying abstract entities into their endlessly varying outward manifestations.

zyz zzz

For the origins of Sophia, see Stanley Morison, Politics and Script (1972): 98–103, and the review of Sophia and Mantinia in Print 48.2 (New York, 1994): 121–22.

This mode of thinking about text transmission and typography has proven very fruitful, especially in relation to non-Latin scripts. And it has prompted type designers and founders to distinguish with some care between a character set and a *glyph palette*. The plain and swash forms of *z* in Arrighi or Poetica, for example, are different glyphs (or different *sorts*, a hand compositor would say) that correspond to a single character. In fact this distinction between characters and glyphs has been familiar to scribes for millennia. It was also familiar to Gutenberg.

In the early days of letterpress, punchcutters frequently cut multiple versions of common letters and other characters (such as the hyphen), so that their subtle, often subliminal, variations would invigorate the page. A hand compositor reaching into the typecase for an e might then come up with any of several similar but not identical forms. Few readers may have consciously noticed the difference, yet each of these slyly variant letters contributed its mote of vitality to the page. After five hundred years on the library shelf, that vitality remains. It comes in part from the artistry of the cutters, and in part from the use of a system that lets the glyphs outnumber the characters.

Matthew Carter's Sophia, to take a more recent example, is a digital face consisting only of capitals, yet it includes multiple glyphs for many characters. There are four forms of T, three forms each of E, F and R, two forms of A, C, G, H, I, K and many other letters. Some of the variant forms are independent; others are components used in custom-building ligatures. Sophia's stake in the character set is small, because it has no lower case, but its glyph palette is relatively large (and Carter has been urged to make it larger).

Apart from special cases like Sophia and Zapfino, most fonts of Latin type are limited at present to only one glyph for most characters, and a few contextual glyphs like ff and ffi. At the level of the family there are several glyphs per character: a, a, A, a, a and sometimes many more. But in English the rules for choosing among these glyphs are editorial as much as typographic. In the Arabic alphabet, by contrast, multiple glyphs are essential in every font, and the choice of glyph is governed mostly by scriptorial or typographic rules. There are no capitals, small caps or italics in Arabic script, but ligatures are frequent, and even a font of simplified Arabic type contains about a hundred basic glyphs for the 28 Arabic letters, because most letters have four different forms: initial, medial, final and free-standing.

THE INTELLECT OF MAN

IS FORCED TO CHOOSE +

The State of the Art

PERFECTION OF THE LIFE

OR °F TH€ WORK



- AND IF IT TAKE THE

SECOND MUST REFUSE +

A HEAVENLY MANSION,

RAGING IN THE DARK+

WILLIAM BUTLER YEATS

Matthew Carter's Sophia (Carter & Cone, 1993) is a face with alternate glyphs for many characters. Many of these alternates form ligatures.

Lexical ligatures (æ, œ, ß, etc) are those whose usage is defined by lexicographers and grammarians. These are in Unicode. Typographic ligatures (ff, fi, ct, etc) are those whose usage is primarily a matter of typographic style. The distinction is by no means absolute.

How many ligatures is a lot? There are only 10 or 12 nowadays  $(x, x, E, E, \beta,$ fi, fl, ff, ffi, ffl; sometimes fi and ffj) in a normal Latin text font, but there are 36 in the font for Gutenberg's 42-line Bible (c. 1455), 45 in Robert Granjon's second civilité (c. 1570), 55 in Robert Slimbach's Poetica (1992), 70 in Francesco Griffo's first italic (1499), and about 350 in each font of Claude Garamond's Royal Greeks (c. 1541).

This explains the necessity for 'private use' characters in Unicode. Typographic ligatures, text figures, small caps, swashes and other alternate glyphs are placed in that domain. The composition software must then be taught to find them.

#### 9.3.2 Manual, Random and Programmed Variation

The text is a string of characters; the font is a palette of glyphs – along with all the information (width tables, kerning tables and so on) needed for stringing the glyphs to match the characters. If we think about typography in these terms, it is clear that every font could offer the typographer a different range of choices: a different palette of glyphs, in other words, mapped perhaps in many different ways, to the same set of standard characters.

Zuzana Ličko's type family Mrs Eaves (Emigre, 1996) is an example. There are five basic members of the family: roman, italic, bold roman, and two sizes of small caps. The roman, italic and bold are each equipped with a supplementary battery of 71 ligatures. Some of these are subtle, some distinctly cheeky. A supporting piece of software, engineered by Just van Rossum, lets the compositor decide which ligatures to use, then implants them automatically wherever the equivalent string of characters appears. This is how most systems for handling optional ligatures ought to work – and how, perhaps, one day, they will.

ae æ cky ee ffy ffr gg ggy gi
ip it ky oe œ sp ss ss Th tt tty ty
ae æ cky ct ee fb ff ffy ffr ft ggy gi gy ip
it ky oe œ @ sp ss st by tt tty ty tw

Some of the ligatures in Zuzana Ličko's typeface Mrs Eaves. There are 30 ligatures for the caps, 40 for the lower case, and one hybrid (Th). Each of these exists in three forms: roman, italic and bold. The face (though not its complement of ligatures) is based on John Baskerville's roman and italic. It is named for Sarah Ruston Eaves (Mrs Richard Eaves), who for sixteen years was Baskerville's resident housekeeper and lover, and for another eleven years (after the death of her first husband) was his lawful wedded wife.

If every font can have a slightly different set of glyphs, it is pointless to expect the composition software by itself to choose effectively among them. Three other possibilities suggest themselves: (1) the choice of glyphs can be left to the typographer, who picks them and inserts them each by hand; (2) where there are variant forms of single letters, the choice can be left to chance; (3) the rules for choosing glyphs can be tailored to the typeface and embedded in the font itself.

The State of the Art

The first of these options has been the normal practice with foundry type for centuries. Poetica, Sophia and Zapf Renaissance, in their ordinary PostScript incarnations, belong to the same tradition. By including extra glyphs for certain characters, these faces offer digital typographers the same degree of freedom (and require in return the same investment of skill and attention) that hand compositors have enjoyed since the days of Gutenberg, Ratdolt and Jenson.

The second option – letting the designer's chosen variants assert themselves at random – is an old and distinguished method too. Francesco Griffo, Claude Garamond and Simon de Colines are three of many early masters who cut multiple forms of letters. Some alternates (with forms like  $\neg '$  and  $n_{\rightarrow}$ ) were used selectively at the beginnings and ends of words, in contexts where their extra width was useful to the line. Others, which differed among themselves scarcely enough to reach the threshold of visibility, could serve – and did serve – to enliven the text at random.

Another kind of random variation involves the interaction of the craftsman's skill and the texture of materials. The letterforms of Griffo and Colines were cut with immense care. But the letters they cut were struck by hand in brass, then cast and dressed and set by hand, inked by hand with handmade ink and printed by hand in a handmade wooden press on handmade paper. Every step along the way introduced small variations planned by no one. In the world of the finely honed machine, those human-scale textures are erased. A sterile sameness supervenes.

The computer is, on the face of it, an ideal device for reviving the old luxury of *random variations at the threshold of perception* (quite a different thing from chaos). But conventional typesetting software and hardware focuses instead on the unsustainable ideal of absolute control – and has been hamstrung in the past by the idea of a single glyph per character. There have been several recent attempts to introduce a layer of random variation, but all have had to work against the grain of technological development.

David Pye discusses the importance of the threshold of visibility in his perceptive book The Nature and Art of Workmanship (1968).

In the Open-Type version of Hermann Zapf's Zapfino, the sequence p + p can automatically convert to  $p_1 + p_2$ , but there are several other options. Four of these are shown below An early example was Erik van Blokland and Just van Rossum's typeface Beowolf. In its first experimental version (1990), this face relied on the output device to create truly random perturbations from a single set of letterforms. Though it would not work on all systems, and the evolving hardware and software quickly passed it by, it remains an important landmark in the effort to teach computers what typography really entails.

#### eeeeeeee eeeeeeee eeeeeeee

Beowolf (FontShop, 1990) is at root a statuesque text roman drawn by Erik van Blokland. The letterforms are sent to the output device through a subroutine, devised by Just van Rossum, that provokes distortions of each letter within predetermined limits in unpredetermined ways. Three degrees of randomization are available. Within the specified limits, every letter is a surprise.

Those are two options: manual and random substitution. There is still the third: building glyph-selection rules into the font itself. This gives *predictable* variation. It is now the reigning method for achieving typographic variation, because this is the method adopted by the sponsors of GX, TTO and OT fonts.

For now, therefore, the goal of pleasing randomness – constrained but unplanned variation – goes begging in computerized typography. Is it worth pursuing? Communication requires control, just as life requires control, but it also requires a context beyond its control. Unpremeditated grace is as crucial to the liveliness of the page as it is to the liveliness of the garden.

#### 9.4 METHODS OF JUSTIFICATION

9.4.1 Use the best available justification engine.

Most of the type set in the past five hundred years is justified type, and most of it has been justified line by line, by the simple expedient of altering the space between the words. There are, however, better ways. Scribes justify text as they write, by introducing abbreviations and subtly altering the widths of letters. Gutenberg replicated the feat by cutting and casting a host of abbreviations and ligatures along with multiple versions of certain letters, differing modestly in width. In the early 1990s, Peter Karow and Hermann Zapf devised a means of doing much the same in the

danner dapper dapper dapper Nations are not truly great solely because the individuals composing them are numerous, free, and active; [nor corporations because of their market share and profits;] but they are great when these numbers, this freedom, and this activity [or this market share and profit] are employed in the service of an ideal higher than that of an ordinary [hu]man, taken by himself. – MATTHEW ARNOLD [& EVE SMITH]

FL/RR, with invariant wordspacing, letterspacing and glyph shape.

Nations are not truly great solely because the individuals composing them are numerous, free, and active; [nor corporations because of their market share and profits;] but they are great when these numbers, this freedom, and this activity [or this market share and profit] are employed in the service of an ideal higher than that of an ordinary [hu]man, taken by himself. – MATTHEW ARNOLD [& EVE SMITH]

Justified by wordspacing only.

Nations are not truly great solely because the individuals composing them are numerous, free, and active; [nor corporations because of their market share and profits;] but they are great when these numbers, this freedom, and this activity [or this market share and profit] are employed in the service of an ideal higher than that of an ordinary [hu]man, taken by himself. – MATTHEW ARNOLD [& EVE SMITH]

Justified by letterspacing only.

Nations are not truly great solely because the individuals composing them are numerous, free, and active; [nor corporations because of their market share and profits;] but they are great when these numbers, this freedom, and this activity [or this market share and profit] are employed in the service of an ideal higher than that of an ordinary [hu]man, taken by himself. – MATTHEW ARNOLD [& EVE SMITH]

Justified by glyph reshaping only.

Nations are not truly great solely because the individuals composing them are numerous, free, and active; [nor corporations because of their market share and profits;] but they are great when these numbers, this freedom, and this activity [or this market share and profit] are employed in the service of an ideal higher than that of an ordinary [hu]man, taken by himself. – MATTHEW ARNOLD [& EVE SMITH]

Justified by a combination of wordspacing, letterspacing and glyph reshaping.

digital medium – and without relying on scribal abbreviations. When the method they had devised was first offered for sale, it was rejected. Now it is being absorbed. The justification engine used in setting this book is in essence the one imagined by Zapf and engineered by Karow more than a decade ago: an electronic version of what Gutenberg envisioned in the 1440s, as he analyzed the work of master scribes.

Methods of Justification

Unlike a Monotype or Linotype machine, the computer is perfectly capable of calculating the pros and cons of linebreaks over a whole paragraph. It can break a line in one place, then go back and break it again, and again, and again, if subsequent lines give it reason to do so. Hand compositors have been known to do the same – but rejustification by hand is a tedious business. The computer, once it learns the trick, can do it in an flash.

Another thing computer software can do – because Karow taught it how – is justify text by making subtle alterations in the widths of letters.

Good justification is calculated paragraph by paragraph instead of line by line. And the best computer justification now relies on microscopic adjustments to the space between and within the letters as well as the space between the words. In this book, for example, the justification engine has been permitted to vary the intercharacter spacing by  $\pm 3\%$  and to adjust the width of individual glyphs by  $\pm 2\%$ . The bulk of the work is still done by adjusting the spaces between words, but there are more letters than spaces in these lines. Tiny adjustments to spaces within and between the letters therefore go a long way toward creating a page of even color and texture.

In English, where on average there are five times more letters than spaces on a page, the allowable elasticity in intra- and intercharacter spacing should usually be held to around one fifth of the elasticity permitted in the spaces between words.

#### 9.5 PIXELS, PROOFS & PRINTING

9.5.1 If the text will be read on the screen, design it for that medium.

Like a forest or a garden or a field, an honest page of letters can absorb – and will repay – as much attention as it is given. Much type now, however, is composed not for the page but for the screen of a computer. That screen can be alive with flowing color, but the

best computer monitors have dismal resolution (about 140 dpi: less than a quarter the current norm for laser printers and less than 6% of the norm for professional digital typesetting). When the text is crudely rendered, the eye goes looking for distraction, which the screen is all too able to provide.

The screen mimics the sky, not the earth. It bombards the eye with light instead of waiting to repay the gift of vision. It is not simultaneously restful and lively, like a field full of flowers, or the face of a thinking human being, or a well-made typographic page. And we read the screen the way we read the sky: in quick sweeps, guessing at the weather from the changing shapes of clouds, or like astronomers, in magnified small bits, examining details. We look to it for clues and revelations more than wisdom. This makes it an attractive place for the open storage of pulverized information – names, dates, library call numbers, for instance – but not so good a place for thoughtful text.

The State of the Art

The screen, in other words, is a reading environment even more fugitive than the newspaper. Intricate, long sentences full of unfamiliar words stand little chance. At text size, subtle and delicate letterforms stand little chance as well. Superscripts and subscripts, footnotes, endnotes, sidenotes disappear. In the harsh light and coarse resolution of the screen, such literate accessories are difficult to see; what is worse, they dispel the essential illusion of speed. So the links and jumps of hypertext replace them. All the subtexts then can be the same size, and readers are at liberty to skip from text to text like children switching channels on Tv. When reading takes this form, both sentences and letterforms retreat to blunt simplicity. Forms bred on newsprint and signage are most likely to survive. Good text faces for the screen are therefore as a rule faces with low contrast, a large torso, open counters, sturdy terminals, and slab serifs or no serifs at all.

If it has anything significant to say, a text that scrolls across the screen still needs the typographer's attention, just like any printed text. It may be that the reader, not the typographer, will actually choose the typeface. The typographer may still have some control over other factors of typographic rhythm – type size, measure, leading. Most importantly, the typographer shapes the virtual page, determining the form and frequency of heads, the orientation and placement of illustrations, the disposition of lists and paragraphs. The typographer gives outward and visible form to the text's intrinsic, invisible order. This determines, in large part, who will read the text and how.

#### 9.5.2 Check the type at every stage.

Pixels, Proofs and Printing Digital letterforms can be printed directly on paper with laser printers; they can be typeset onto photosensitive paper, negative film or positive film, from which lithographic printing plates, letterpress blocks or serigraphic stencils are then made; or they can be etched directly onto printing plates that run on an offset press. Each of these electrostatic and photographic transformations provides an opportunity for overexposing or underexposing the type.

Check for accurate color and sharpness in the letterforms at every stage, and check for consistency throughout. Inconsistent exposure is often encountered when the work is set a section at a time, or when corrected pages are rerun. But even when all the work is run at once on one machine, inconsistencies can occur. If, for instance, two shelf lots of film or photosensitive paper are inadvertently mixed, the same machine settings will give two different results.

Mechanical errors are also not unknown in the superficially sanitized, high-tech world of computerized type. Many a finely tooled page has been spoiled in the end by a loose roller or unlubricated ratchet. Check the output against a grid to make sure the leading is consistent, multiple columns align as they should, and the textblock is not trapezoidal unless it is meant to be.

#### 9.5.3 Follow the work to the printer.

All typographic decisions – the choice of the type, the choice of size and leading, the calculation of margins and the shaping of the page – involve assumptions about the printing. It is well to find out in advance whether these assumptions stand any chance of being fulfilled. Good printers have much else to teach their clients, and the best typographer can always find something to learn. But the path from the editor's desk to the pressroom floor remains a journey often fraught with danger and surprise. The reason is that it is frequently a journey between economic realms. On the one side, a singular thing, a manuscript, moves slowly through the hands of individual human beings – author, editor, typographer – who make judgements and decisions one by one, and who are free (for a time at least) to change their minds. On the other side, an immensely expensive commodity (blank paper) passes

at great speed and irreversibly through an immensely expensive (and therefore obsessively hungry) machine.

Digital methods have helped to bring editing, typography and type design back, in some respects, to the close relationship they enjoyed in the golden age of letterpress. But everything the writer, type designer, editor and typographer do is still contingent on the skills and methods of the printer – and while typography, for many, has returned to cottage scale, printing has enlarged to the dimensions of heavy industry. The freedom afforded by cheap and standardized typesetting hardware and software also comes at a price. That price is the danger of weary sameness and thinness in all the work the typographer does. The use of standard industrial papers, inks, presses and binding machinery can easily erase whatever remains of the typographer's personal touch. Yet printing is what typography is usually thought to be for.

The State of the Art

If only by default, it falls to the typographer more than to anyone else to bridge this gap between a world focused on the perfect final proof and the world of its industrial replication. No one else works as close to that frontier as the typographer, and no one has a greater need to understand what happens on both sides.

The margins of books cannot be calculated correctly until the binding method is chosen, and they cannot be right in the end unless the chosen method is followed. The type cannot be chosen without coming to some decision about the kind of paper it will be printed on, and cannot look right in the end if that decision is later betrayed. A change of one eighth inch in the folding pattern or trim size will ruin a precisely measured page.

Yet another way to undercut the type is to print it with the wrong ink. Color control is important whether or not color is used, for there are many hues of black, some veering toward red, some veering toward blue. Redder blacks are acceptable on ivory paper. If the paper is closer to gray or white, the black of the ink should move closer to blue. But it will be process black by default – and the density of the type will be at the mercy of the press foreman's final color adjustments – if the text and process-color illustrations are printed in one go.

Ink gloss is rarely a problem on uncoated paper. On coated stock, the sheen of the ink is frequently out of control. For the sake of legibility in artificial light, inks that are used for printing text on a coated sheet should have *less* reflectivity than the paper, rather than more.

#### 9.6.1 Consult the ancestors.

Maintaining the System

Typography is an ancient craft and an old profession as well as a constant technological frontier. It is also in some sense a trust. The lexicon of the tribe and the letters of the alphabet – which are the chromosomes and genes of literate culture – are in the typographer's care. Maintaining the system means more than merely buying the newest fonts from digital foundries and the latest updates for typesetting software.

The rate of change in typesetting methods has been steep – perhaps it has approximated the Fibonacci series – for more than a century. Yet, like poetry and painting, storytelling and weaving, typography itself has not improved. There is no greater proof that typography is more art than engineering. Like all the arts, it is basically immune to progress, though it is not immune to change. Typography at its best is sometimes as good, and at its worst is just as bad, as it ever was. The speed of certain processes has certainly increased; some old, hard tricks have come to seem easy, and some new ones have been learned. But the quality of typography and printing, their faithfulness to themselves, and the inherent grace and poise of the finished page, is not greater now than it was in 1465. In several respects, digital typography still lags far behind the methods and resources of Renaissance compositors and medieval scribes.

Maintaining the system means openness to the surprises and gifts of the future; it also means keeping the future in touch with the past. This is done by looking with equal eagerness at the old work and the new. Reproductions, of course, are fine as far as they go, but you will never know what a fifteenth-century manuscript or printed book is like until you touch one, smell one, hold one in your hands.

#### 9.6.2 Look after the low- as well as the high-technology end.

A digital typographer is now likely to use two rather flimsy but capable pieces of hardware: a computer, with keyboard and screen, and some kind of proofing device, usually a laser printer. The rest of the system – another computer which imposes the work for the press, and a high-resolution digital plate-maker or other output device – may be miles away.

In the typographer's computer there are likely to be a number of interdependent pieces of software. These will probably include a text editor, composition software, a library of digital fonts, a font manager, and a font editor. There may also be a photo editor and some electronic drawing tools. And the composition software will nowadays include a host of tools for manipulating type, erasing the ancient boundary between text and illustration. All these tools are new, but the craft is old.

The State of the Art

Outside the hardware, but no less essential to the system, more primitive tools are still required: a pica stick, a sketch pad, a drawing board and instruments, and a library of reference works and examples of fine typography for discussion and inspiration. It is the latter, low-technology end of most typesetting systems that is usually in the most urgent need of upgrading.

One good typeface is better and more useful than an infinity of poor ones. Here as always, good means several things. It means that the letterforms themselves are clearly envisioned, lucidly rendered and, beyond all that, convincing. It means they make mute, irrefutable sense to both body and mind. It means that the fabric in which these letterforms are held is well made too. If the type is metal, it means that the metal is well cast – hard, sharp, free of bubbles or sags – and evenly dressed. If the type is digital, it means that the glyphs are correctly aligned and consistently sized, with accurate widths and sensitive kerning instructions. A font of type can be (and may or may not be in fact) an electronic artefact of immense sophistication: not only a masterpiece of design but an intangible piece of craftsmanship enriched by many skilled and often uncredited eyes and minds.

Some observers are dismayed and some excited by the complexity of the equipment most typographers now use. Some are excited and others unnerved by the evident power of that equipment and the ease of its operation. Yet inside that complexity, typography persists as what it is: the making of meaningful, durable, abstract, visible signs. When the system crashes, the craft, its purposes, its values and all its possibilities remain.

10

Writing begins with the making of meaningful marks. That is to say, leaving the traces of meaningful gestures. Typography begins with arranging meaningful marks that are already made. In that respect, the practice of typography is like playing the piano – an instrument quite different from the human voice. On the piano, the notes are already fixed, although their order, duration and amplitude are not. The notes are fixed but they can be endlessly rearranged, into meaningful music or meaningless noise.

Pianos, however, need to be tuned. The same is true of fonts. To put this in more literary terms, fonts need to be *edited* just as carefully as texts do – and may need to be re-edited, like texts, when their circumstances change. The editing of fonts, like the editing of texts, begins before their birth and never ends.

You may prefer to entrust the editing of your fonts, like the tuning of your piano, to a professional. If you are the editor of a magazine or the manager of a publishing house, that is probably the best way to proceed. But devoted typographers, like lutenists and guitarists, often feel that they themselves must tune the instruments they play.

#### 10.1 LEGAL CONSIDERATIONS

#### 10.1.1 Check the license before tuning a digital font.

Digital fonts are usually licensed to the user, not sold outright, and the license terms vary. Some manufacturers claim to believe that improving a font produced by them is an infringement of their rights. No one believes that tuning a piano or pumping up the tires of a car infringes on the rights of the manufacturer – and this is true no matter whether the car or the piano has been rented, leased or purchased. Printing type was treated the same way from Bí Shēng's time until the 1980s. Generally speaking, metal type and phototype are treated that way still. In the digital realm, where the font is wholly intangible, those older notions of ownership are under pressure to change.

The Linotype Library's standard font license says that "You may modify the Font-Software to satisfy your design requirements." FontShop's standard license has a similar provision: "You

do have the right to modify and alter Font Software for your customary personal and business use, but not for resale or further distribution." Adobe's and Agfa Monotype's licenses contain no such provision. Monotype's says instead that "You may not alter Font Software for the purpose of adding any functionality.... You agree not to adapt, modify, alter, translate, convert, or otherwise change the Font Software...."

Grooming the Font

If your license forbids improving the font itself, the only legal way to tune it is through a software override. For example, you can use an external kerning editor to override the kerning table built into the font. This is the least elegant way to do it, but a multitude of errors in fitting and kerning can be masked, if need be, by this means.

#### 10.2 ETHICAL & AESTHETIC CONSIDERATIONS

#### 10.2.1 If it ain't broke....

Any part of the font can be tuned – lettershapes, character set, character encoding, fitting and sidebearings, kerning table, hinting, and, in an OpenType font, the rules governing character substitution. What doesn't need tuning or fixing shouldn't be touched. If you want to revise the font just for the sake of revising it, you might do better to design your own instead. And if you hack up someone else's font for practice, like a biology student cutting up a frog, you might cremate or bury the results.

#### 10.2.2 If the font is out of tune, fix it once and for all.

One way to refine the typography of a text is to work your way through it line by line, putting space in here, removing it there, and repositioning errant characters one by one. But if these refinements are made to the font itself, you will never need to make them again. They are done for good.

10.2.3 Respect the text first of all, the letterforms second, the type designer third, the foundry fourth.

The needs of the text should take precedence over the layout of the font, the integrity of the letterforms over the ego of the designer, the artistic sensibility of the designer over the foundry's desire for profit, and the founder's craft over a good deal else. 10.2.4 Keep on fixing.

Check every text you set to see where improvements can be made. Then return to the font and make them. Little by little, you and the instrument – the font, that is – will fuse, and the type you set will start to sing. Remember, though, this process never ends. There is no such thing as the perfect font.

Ethical and Aesthetic Considerations

10.3 HONING THE CHARACTER SET

10.3.1 If there are defective glyphs, mend them.

If the basic lettershapes of your font are poorly drawn, it is probably better to abandon it rather than edit it. But many fonts combine superb basic letterforms with alien or sloppy supplementary characters. Where this is the case, you can usually rest assured that the basic letterforms are the work of a real designer, whose craftsmanship merits respect, and that the supplementary characters were added by an inattentive foundry employee. The latter's errors should be remedied at once.

You may find for example that analphabetic characters such as @  $+ \pm \times = \cdot - - \odot$  are too big or too small, too light or too dark, too high or too low, or are otherwise out of tune with the basic alphabet. You may also find that diacritics in glyphs such as å  $\varsigma$  é  $\tilde{n}$  o  $\tilde{u}$  are poorly drawn, poorly postioned, or out of scale with the letterforms.

$$a + b = c \cdot a@b \cdot © 2007$$
  
 $a + b = c \cdot a@b \cdot © 2007$   
 $a + b = c \cdot a@b \cdot © 2007$   
 $a + b = c \cdot a@b \cdot © 2007$ 

José Mendoza y Almeida's Photina is an excellent piece of design, but in every weight and style of Monotype digital Photina, as issued by the foundry, arithmetical signs and other analphabetics are out of scale and out of position, and the copyright symbol and at sign are alien to the font. The raw versions are shown in grey, corrected versions in black.

# é ù ô ã → é ù ô ã

Frederic Goudy's Kennerley is a homely but quite pleasant type, useful for many purposes, but in Lanston's digital version, the letterforms are burdened with some preposterous diacritics. *Above left*: four accented sorts as issued by the foundry. *Above right*: corrected versions. All fonts are candidates for similar improvement. *Below left*: four accented sorts from Robert Slimbach's carefully honed Minion, as originally issued by Adobe in 1989. *Below right*: the same glyphs, revised by Slimbach ten years later, while preparing the OpenType version of the face.

Grooming the Font

# áèïû → áèïû

10.3.2 If text figures, ligatures or other glyphs you need on a regular basis don't reside on the base font, move them.

For readable text, you almost always need text figures, but most digital fonts are sold with titling figures instead. Most digital fonts also include the ligatures fi and fl but not ff, ffi, ffl, fj or ffj. You may find at least some of the missing glyphs on a supplementary font (an 'expert font'), but that is not enough. Put all the basic glyphs together on the base font.

If, like a good Renaissance typographer, you use only upright parentheses and brackets (see §5.3.2), copy the upright forms from the roman to the italic font. Only then can they be kerned and spaced correctly without fuss.

[f]

10.3.3 If glyphs you need are missing altogether, make them.

Standard 150 digital text fonts (PostScript or TrueType) have 256 slots and carry a basic set of Western European characters. Eastern European characters such as  $a \in d \in b$   $b \in b$ 

The components required to make these characters may be present on the font, and assembling the pieces is not hard, but you need a place to put whatever characters you make. If you need only a few and do not care about system compatibility, you can place them in wasted slots – e.g., the  $\land < > \setminus | \sim `$  positions,

which are accessible directly from the keyboard, or slots such as  $\phi \div^{1} \circ {}^{3} \stackrel{\text{\tiny TM}}{=} \text{\%}$ , which can be reached through insertion utilities or by typing character codes or by customizing the keyboard.

If you need to add many such characters, you will need to make a supplementary font or, better yet, an enlarged font (True-Type or OpenType). If these are for your own use only, the extra characters can be placed wherever you wish. If the fonts are to be shared, every new glyph should be labeled with its PostScript name and Unicode number.

Honing the Character Set

#### 10.3.4 Check and correct the sidebearings.

The spacing of letters is part of the essence of their design. A well-made font should need little adjustment, except for refining the kerning. Remember, however, that kerning tables exist for the sake of problematical sequences such as  $f^*$ , gy, "A, To, Va and 74. If you find that simple pairs such as oo or oe require kerning, this is a sign that the letters are poorly fitted. It is better to correct the sidebearings than to write a bloated kerning table.

The spacing of many analphabetics, however, has as much to do with editorial style as with typographic design. Unless your fonts are custom made, neither the type designer nor the founder can know what you need or prefer. I habitually increase the left sidebearing of semicolon, colon, question and exclamation marks, and the inner bearings of guillemets and parentheses, in search of a kind of Channel Island compromise: neither the tight fitting preferred by most anglophone editors nor the wide-open spacing customary in France. If I worked in French all the time, I might increase these sidebearings further.

abc: def; ghx? klm! «non» abc: def; ghx? klm! «hmm» abç: déf; ghx? klm! «oui»

Three options for the spacing of basic analphabetics in Monotype digital Centaur: foundry issue (top); French spacing (bottom); and something in between. Making such adjustments one by one by the insertion of fixed spaces can be tedious. It is easier by far, if you know what you want and you want it consistently, to incorporate your preferences into the font.

Digital type can be printed in three dimensions, using zinc or polymer plates, and metal type can be printed flat, from photos or scans of the letterpress proofs. Usually, however, metal type is printed in three dimensions and digital type is printed in two. Two-dimensional type can be printed more cleanly and sharply than three-dimensional type, but the gain in sharpness rarely equals what is lost in depth and texture. A digital page is therefore apt to look aenemic next to a page printed directly from handset metal.

Grooming the Font

This imbalance can be addressed by going deeper into two dimensions. Digital type is capable of refinements of spacing and kerning beyond those attainable in metal, and the primary means of achieving this refinement is the kerning table.

Always check the sidebearings of figures and letters *before* you edit the kerning table. Sidebearings can be checked quickly for errors by disabling kerning and setting characters, at ample size, in pairs: 11223344 ... qqwweerrttyy.... If the spacing within the pairs appears to vary, or if it appears consistently cramped or loose, the sidebearings probably need to be changed.

Class-based kerning (now a standard capability of font editing software) can be used to speed the process. In class-based kerning, similar letters, such as a  $\acute{a}$   $\ddot{a}$   $\ddot{a}$  and treated as one and kerned alike. This is an excellent way to begin when you are kerning a large font, but not a way to finish. The combinations Ta and Tä, Ti and Tï, il and fl, i) and i), are likely to require different treatment.

Kerning sequences such as Tp, Tt and f( may seem to you absurd, but they can and do occur in legitimate text. (Tpig is the name of a town in the mountains of Dagestan, near the southern tip of the Russian Federation; Ttanuu is an important historical site on the British Columbia coast; sequences such as y = f(x) occur routinely in mathematics.) If you know what texts you wish to set with a given font, and know that combinations such as

The font on this page is straight off the shelf: a magnificently complex piece of digital engineering capable of setting bad type in five different scripts and over a hundred different languages.

On the facing page is a wellgroomed version of the same font: the same big set of plain vanilla letterforms, tuned to set type well.

Some but not all of the lapses in the original kerning table are circled. "Ask Jeff" or 'Ask Jeff'. Take the chef d'œuvre! Two of [of] (of) 'of' "of' of? of! of\*. Two of [of] (of) 'of' "of" of? of! of\*. Ydes, Yffignac and Ygrande are in France: so are Ypres, Les Woëvres, the Fôret de Wœvres, the Voire and Vauvise. Yves is in heaven: D'Amboise is in jail. Lyford's in Texas & L'Anse-aux-Griffons in Québec; the Lyna in Poland. Yriarte, Yciar and Ysaÿe are at Yale. Kyoto and Ryotsu are both in Japan, Kwikpak on the Yukon delta, Kvæven in Norway, Kyulu in Kenya, not in Rwanda.... Walton's in West Virginia, but «Wren» is in Oregon. Tlálpan is near Xochimilco in México, The Zygos & Xylophagou are in Cyprus, Zwettl in Austria, Fænø in Denmark, the Vøringsfossen and Værøy in Norway. Tchula is in Mississippi, the Tittabawassee in Michigan. Twodot is here in Montana, Ywamun in Burma. Yggdrasil and Ymir, Yngvi and Vóden, Vídrið and Skeggjöld and Tyr are all in the Eddas. Torberget and Våg, of course, are in Norway, Ktipas and Tmolos in Greece, but Vázquez is in Argentina, Vreden in Germany, Von-Vincke-Straße in Münster, Vdovino in Russia, Ytterbium in the periodic table. Are Toussaint L'Ouverture, Wölfflin, Wolfe, Miłosz and Wū Wŭ) all in the library? 1510–1620, 11:00 pm, and the 1980s are over.

Part of a text file designed to test for missing or dislocated glyphs and for lapses in the kerning table. Raw font at left; groomed font at right.

There are many versions of Times New Roman. The version tested here is Times New Roman PS MT, version 2.76, the default text font in recent versions of the Microsoft Windows operating system. This is a

"Ask Jeff" or 'Ask Jeff'. Take the chef d'œuvre! Two of [of] (of) 'of' "of" of? of! of\*. Two of [of] (of) 'of' "of" of? of! of\*. Ydes, Yffignac and Ygrande are in France: so are Ypres, Les Woëvres, the Fôret de Wœvres, the Voire and Vauvise. Yves is in heaven; D'Amboise is in jail. Lyford's in Texas & L'Anse-aux-Griffons in Québec; the Łyna in Poland. Yriarte, Yciar and Ysaÿe are at Yale. Kyoto and Ryotsu are both in Japan, Kwikpak on the Yukon delta, Kvæven in Norway, Kyulu in Kenya, not in Rwanda.... Walton's in West Virginia, but «Wren» is in Oregon. Tlálpan is near Xochimilco in México. The Zygos & Xylophagou are in Cyprus, Zwettl in Austria, Fænø in Denmark, the Vøringsfossen and Værøy in Norway. Tchula is in Mississippi, the Tittabawassee in Michigan. Twodot is here in Montana, Ywamun in Burma. Yggdrasil and Ymir, Yngvi and Vóden, Vídrið and Skeggjöld and Tyr are all in the Eddas. Tørberget and Våg, of course, are in Norway, Ktipas and Tmolos in Greece, but Vázquez is in Argentina, Vreden in Germany, Von-Vincke-Straße in Münster, Vdovino in Russia, Ytterbium in the periodic table. Are Toussaint L'Ouverture, Wölfflin, Wolfe, Miłosz and Wū Wǔ all in the library? 1510–1620, 11:00 PM, and the 1980s are over.

Grooming the Font

TrueType-flavored OpenType font, including pan-European Latin, Greek, Vietnamese, Cyrillic, Hebrew and Arabic glyphs. It lacks the text figures, ligatures and small caps typical of full-featured OpenType fonts, and its o $\tau$  features are actually limited to the Arabic character set. The kerning is good as far as it goes, but it does not go nearly far enough.

Honing the Character Set these will never occur, you can certainly omit them from the table. But if you are preparing a font for general use, even in a single language, remember that it should accommodate the occasional foreign phrase and the names of real and fictional people, places and things. These can involve some unusual combinations. (A few additional examples: McTavish, FitzWilliam, O'Quinn, dogfish, jack o'-lantern, Hallowe'en.)

It is also wise to check the font by running a test file – a specially written text designed to hunt out missing or malformed characters and kerning pairs that are either too tight or too loose. On pages 204–205 is a short example of such a test file, showing the difference between an ungroomed font and a groomed one.

It is nothing unusual for a well-groomed 150 font (which might contain around two hundred working characters) to have a kerning table listing a thousand pairs. Kerning instructions for large OpenType fonts are usually stored in a different form, but if converted to tabular form, the kerning data for a pan-European Latin font may easily reach 30,000 pairs. For a well-groomed Latin-Greek-Cyrillic font, decompiling the kerning instructions can generate a table of 150,000 pairs. Remember, though, that the number isn't what counts. What matters is the intelligence and style of the kerning. Remember too that there is no such thing as a font whose kerning cannot be improved.

#### 10.3.6 Check the kerning of the word space.

The word space – that invisible blank box – is the most common character in almost every text. It is normally kerned against sloping and undercut glyphs: quotation marks, apostrophe, the letters A, T, V, W, Y, and often to the numerals 1, 3, 5. It is *not*, however, normally kerned more than a hair either to or away from a preceding lowercase *f* in either roman or italic.

A cautionary example. Most of the Monotype digital revivals I have tested over the years have serious flaws in the kerning tables. One problem in particular recurs in Monotype Baskerville, Centaur & Arrighi, Dante, Fournier, Gill Sans, Poliphilus & Blado, Van Dijck and other masterworks in the Monotype collection. These are well-tried faces of superb design – yet in defiance of tradition, the maker's kerning tables call for a large space (as much as M/4) to be added whenever the f is followed by a word space. The result is a large white blotch after every word ending in f unless a mark of punctuation intervenes.

# Is it east of the sun and west of the moon — or

# is it west of the moon and east of the sun?

Monotype digital Van Dijck, before and after editing the kerning table. As issued, the kerning table adds 127 units (thousandths of an em) in the roman, and 228 in the italic, between the letter f and the word space. The corrected table adds 6 units in the roman, none in the italic. Other, less drastic refinements have also been made to the kerning table used in the second two lines.

This error – documented in methodical tests of Monotype fonts in 1991 – was still present in fonts purchased from Agfa Monotype in the summer of 2004.

Professional typographers may argue about whether the added space should be zero, or ten, or even 25 thousandths of an em. But there is no professional dispute about whether it should be on the order of an eighth or a quarter of an em. An extra space that large is a prefabricated typographic error — one that would bring snorts of disbelief and instantaneous correction from Stanley Morison, Bruce Rogers, Jan van Krimpen, Eric Gill and others on whose expertise and genius the Monotype heritage is built. But it is an easy error to fix for anyone equipped with the requisite tool: a digital font editor.

#### 10.4 HINTING

#### 10.4.1 If the font looks poor at low resolutions, check the hinting.

Digital hints are important chiefly for the sake of how the type will look on screen. Broadly speaking, hints are of two kinds: generic hints that apply to the font as a whole and specific hints applicable only to individual characters. Many fonts are sold unhinted, and few fonts indeed are sold with hints that cannot be improved.

Manual hinting is tedious in the extreme, but any good font editor of recent vintage will include routines for automated hinting. These routines are usually enough to make a poorly hinted text font more legible on screen. (In the long run, the solution is high-resolution screens, making the hinting of fonts irrelevant except at tiny sizes.) Grooming the Font

The presumption of common law is that inherited designs, like inherited texts, belong in the public domain. New designs (or in the USA, the software in which they are enshrined) are protected for a certain term by copyright; the *names* of the designs are also normally protected by trademark legislation. The names are often better protected, in fact, because infringements on the rights conferred by a trademark are often much easier to prove than infringements of copyright. Nevertheless there are times when a typographer must tinker with the names manufacturers give to their digital fonts.

Text fonts are generally sold in families, which may include a smorgasbord of weights and variations. Most editing and typesetting software takes a narrower, more stereotypical view. It recognizes only the nuclear family of roman, italic, bold and bold italic. Keyboard shortcuts make it easy to switch from one to another of these, and the switch codes employed are generic. Instead of saying "Switch to such and such a font at such and such a size," they say, for instance, "Switch to this font's italic counterpart, whatever that may be." This convention makes the instructions transferable. You can change the face and size of a whole paragraph or file and the roman, italic and bold should all convert correctly. The slightest inconsistency in font names can prevent this trick from working - and not all manufacturers name their fonts according to the same conventions. For the fonts to be linked, their family names must be identical and the font names must abide by rules known to the operating system and software in use.

If, for example, you install Martin Majoor's Scala or Scala Sans (issued by FontShop) on a PC, you will find that the italic and the roman are unlinked. These are superbly designed fonts, handsomely kerned and fully equipped with the requisite text figures and small caps – almost everything a digital font should be – but the PC versions must be placed in a font editor and renamed in order to make them work as expected.

Type is idealized writing - yet there is no end of typefaces, as there is no end to visions of the ideal. The faces discussed in this chapter cover a wide historical range - Renaissance, Baroque, Neoclassical, Romantic, Modern and Postmodern. They also constitute a wide stylistic variety - formal, informal, fluid, crisp, delicate and robust. The emphasis, however, is on types I like to read and to reread. Each face shown seems to me of both historical and practical importance, and each seems to me one of the finest of its kind. Each also has its limitations. I've included some very well-known types, such as Baskerville and Palatino; some others, such as Romulus Sans, Heraklit, and Manuscript Cyrillic, that are undeservedly forgotten; and several that are new enough they have not yet had time to establish themselves. Some, like Photina and Vendôme, have long been known in Europe but are rarely seen in North America; others, such as Deepdene, have had just as unbalanced a reception the other way round.

Most readers of this book will have access to digital catalogues, maintained on font vendors' websites. Now that type is principally a digital commodity, printed type specimens are quickly disappearing. Yet they remain an invaluable resource. because the Web, like the subway, is not a destination. Printing is still what type is for. By giving printed samples here, and pointing out some landmarks as well as hidden features, I hope to make it easier to navigate at will among the disembodied spectres.

Almost all faces listed in this chapter now exist in digital form, though a few are still missing essential components – text figures, for example – in their digital incarnations. Many such shortcomings have been remedied in recent years because typographers have made their wishes known. Yet some digital foundries continue making faces in abbreviated, deformed or pirated form. The presence of a typeface in this list is by no means an endorsement of every or any marketed version. (I have noted some of the instances, but not all, in which a font I wanted to include seemed first to require drastic editing.)

Buyers of type should be aware that they are always buying a copy of someone's original design. Licensed copies are preferable to unlicensed copies for two important reasons. First, if the designer is still alive, the license implies that the fonts are being 11

Candido, leggiadretto, & caro guanto; Che copria netto auorio, & fresche rose; Chi vidi al mondo mai si dolci spoglie? Cosi haues s'io del bel velo altretanto O inconstantia de l'humane cose. Pur questo è surto; Evie, ch'io me ne spoglie.

#### Four Italic Benchmarks

stro, & domino Iesu Christo. Gratias ago deo meo semper pro uobis de gratia dei, quæ data est uobis per Christu Iesum, quod in omnibus ditati estis per ipsum, in omni sermone, & omni cor gnitione (quibus rebus testimonium Iesu Christi consirmatu suit in uobis) adeo, ut no destituamini in ullo dono, expectates reue

# Nuda latus Marti, ac fulg Thermodoontiaca munita

Le génie étonnant qui lui donna naissance. Toi qui sus concevoir tant de plans à la fois, A l'immortalité pourquoi perdre tes droits?

Many thousands of types, including thousands of copies of earlier foundry types, are currently for sale. This page shows four of the thousands of excellent types that are *not* for sale. None of these fonts now exists in original form – and to the best of my knowledge, no reasonably faithful metal, photographic or digital copies of these fonts have yet been made. From top to bottom, they are:

- 1 The Petrarca Italic: a 12 pt Aldine italic designed and cut by Francesco Griffo in 1503 for Gershom Soncino, who printed with it at Fano, on the Adriatic coast, east of Florence. (Note the two forms of *d* throughout.)
- 2 The Froben Italic: a 12 pt Aldine italic cut for Johann Froben by the unidentified Master of Basel (possibly Peter Schoeffer the Younger). Froben started using this type in 1519.
- 3 The Colines St Augustin Italic [enlarged]: a 13 pt italic designed and cut by Simon de Colines, Paris. Colines had cut several romans by the time he finished this type, in 1528, but it may have been his first italic.
- 4 Firmin Didot Italic N° 1: a 12 pt Neoclassical italic cut by the 19-year-old Firmin Didot in his father's shop in Paris, 1783.

For more about Colines, see Kay Amert, "Origins of the French Old Style: The Types of Simon de Colines" (1992), and Fred Schreiber, Simon de Colines (Provo, Utah, 1995).

sold with the designer's permission and that royalties from the sale are being paid. Second, the license gives some hope – though rarely, alas, a guarantee – that the fonts are not being sold in truncated or mutilated form.

#### 11.1 NOMENCLATURE & SYNONYMY

Only one guiding principle is stated in this chapter:

11.1.1 Call the type by its honest name if you can.

Prowling the Specimen Books

The oldest types usually come to us without distinctive names and with only meager clues to who designed them. Setting this record straight, establishing the chronology, and giving credit where credit is due is the basic work of typographic history. People who admire the old types like to talk about them too. For that purpose they need names. These are bestowed for pure convenience, but out of pure affection.

Newer types, and copies of the old ones, need names too. As objects of commerce, they are almost always named by those who sell them, with or without the designer's cooperation. Early in his career, Hermann Zapf designed a type that he called Medici. After some consultation between founder and designer, that name was scrapped. When the first fonts were advertised for sale, they were known as Palatino.

That, however, is not the end of the story. A decade after its release as both a foundry type and Linotype machine face, Palatino became the object of commercial envy among the manufacturers of fonts for phototype machines. Zapf's design – or rather, his two quite different designs, one for the Linotype, one for the foundry – were then copied right and left, and the copies were sold under names like Pontiac, Patina, Paladium and Malibu. A more recently plagiarized version is sold as Book Antiqua. Max Miedinger's Helvetica – though not so distinguished a face nor so original a design in the first instance – has also been an object of widespread commercial envy. It is copied to this day under names such as Vega, Swiss and Geneva. Zapf's Optima is plagiarized as Oracle; Friedrich Poppl's Pontifex is plagiarized as Power, and so on.

The problem is not new. Nicolas Jenson's roman and Greek types were copied by other printers in the 1470s. So were Griffo's types, and Caslon's and Baskerville's and Bodoni's in their days. So are they now; though now, with these artists safely dead and Palatino alludes to the 16thcentury Italian calligrapher Giovanni Battista Palatino, but the type is not based on any alphabet Palatino himself designed. The ultimate source of the name is the Mons Palatinus - the Palatine hill in Rome, site of a major temple of Apollo and of several imperial palaces.

The name

their work in the public domain, we are free both to make the copies honest and to give them honest names.

Part of the problem is that, in most jurisdictions, type designs themselves are not effectively protected as intellectual property. Courts have not learned to distinguish between typographic artistry and typographic plagiarism. Names, however, can easily be registered as trademarks. Competitors who plagiarize designs can then be forced to give their copies different names. In the literary world, the law works the other way around. It is the substance and the text, not the title, of a story, poem or book that is protected by copyright legislation.

Nomenclature and Synonymy

> 의 승

Other complications sometimes spring from this anomaly in the law. The first sizes and weights of Paul Renner's Futura were issued by the Bauer Foundry, Frankfurt, in 1927. The type was a commercial as well as artistic success, and other founders soon copied the design. Sol Hess at Lanston Monotype redrew the face and called it Twentieth Century; ATF sold its own imitation as Spartan. But the Futura that the Bauer Foundry had issued was a timid incarnation of Renner's original design. Renner drew many alternate characters; Bauer issued, for each letter, only the single most conventional of Renner's several forms. In 1993, when David Quay and Freda Sack at The Foundry, London, made a digital translation of Renner's original design, the conventions of the trade prevented them from calling it Futura. Their version - artistically the earliest known version of Futura, though commercially one of the latest to be produced – was sold instead under the trade name Architype Renner. Though it was not Renner's choice, this is a serviceable name to the serious typographer, because it plays no invidious tricks and it plainly acknowledges the originating designer.

# cordia uale

Type categories such as *roman* and *italic* are not fixed. This is the enlarged trace of a 16 pt serifed type cut in central Italy in 1466–67, probably by Konrad Sweynheym. It is the second type used by Sweynheym and his partner Arnold Pannartz, who printed books with it at Rome from 1467 to 1473. Like Gudrun Zapf-von Hesse's Alcuin type, designed five centuries later, it is really neither roman nor italic. It is rooted in the Carolingian scriptorial tradition, which precedes any such division.

The balance of this chapter is a litany of names, with the briefest of histories attached. Part of every font's history is that it was born in a certain medium. At the beginning of each entry, that medium is shown by a simple code:

H = originally a metal type for hand composition

M = originally for machine composition in metal

P = originally designed for photosetting

D = originally designed in digital form

Prowling the Specimen Books

11.2 SERIFED TEXT FACES

## abcëfghijop 123 AQ abcéfghijop

Albertina P This graceful, understated text family – embracing Latin, Greek and Cyrillic – was designed in 1965 by the Dutch calligrapher Chris Brand. The Latin portion of the family was issued by Monotype, not in metal but as one of the corporation's first proprietary faces for photocomposition. Technology then moved on, and Albertina was left behind. The Latin component was issued anew in digital form by DTL (the Dutch Type Library) in 1996, complete with its requisite text figures and both roman and italic small caps. The Cyrillic and Greek followed at last in 2004. The forms are quiet and alert, the width economical, and the axis is that of the humanist hand. The crisp italic, with its subtly elliptical dots, slopes at a modest 5°. There is a full range of weights. (See also pp 275, 280.)

# AQ 123 ábçdèfghijklmñöpqrstûvwxyz abcëfghijõp AQ 123 ABCËFGHIJÕP

Alcuin D A strong and graceful Carolingian face designed in 1991 by Gudrun Zapf-von Hesse and first issued by URW. As a genuine Carolingian, Alcuin is rooted in handwritten scripts that predate by 600 years the separation of roman and italic. It is neither of these itself, though it contains the seeds of both. As such, it does not have and does not need a sloped companion face. There is instead an extensive range of weights with text figures and small caps. This is everything required for setting excellent text. The face should not be used where editorial inflexibility demands the use of roman and italic. (See also pp 120, 212.)



Digital translations of Palatino (on the left) and Aldus (on the right). These are two related faces designed in 1948-53 by Hermann Zapf. To illustrate the difference in proportion, selected characters of both are shown here at 72 pt. The basic alphabets (Palatino above, Aldus below) are also shown at 18 pt.

# hh

(Note that neither of these cuts was ever intended to be seen at the 72 pt size. Display sizes of foundry Palatino are more delicate than this, and Aldus is a text face for which no display sizes were designed. But the enlargements facilitate comparison.)

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1 2 3 4 5 6 7 8 9 0 · A B C D É F G
1 2 3 4 5 6 7 8 9 0 · A B C D É F G
A B C D E F G H I J K L M N O
A B C D E F G H I J K L M N O
abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz

## abcëfghijõp 123 AQ abcéfghijôp

Aldus M Roman and italic, designed in 1953 by Hermann Zapf as a text-size Linotype companion for his new foundry face, Palatino. Aldus is narrower than Palatino and has a lower midline (smaller x-height). It is a crisply sculptured and compact text face, rooted in Renaissance scribal tradition. Small caps and text figures are essential to the spirit of the face, but it needs no ligatures. Digital Aldus preserves the Linotype equality of set-width in roman and italic. Palatino, Michelangelo and Sistina are the allied titling faces, and Palatino bold can be used when a bold companion is required. (See also pp 64, 104, 214.)

# a

## abcëfghijop 123 AQ abcéfghijop

Amethyst D Canadian printer and punchcutter Jim Rimmer designed the caps for this face in Vancouver in 1994 and initially called the face Maxwellian. He rechristened it Amethyst in 1999, when he drew the lower case. In 2002, after the first printing trials, Rimmer revised the book weight, darkening it by roughly 2%. It became a working typeface at that point. The fonts come rough from the foundry and must be edited in order to set text. It is worth the effort. Rimmer's affection for Frederic Goudy is visible in Amethyst and in some of his other faces – Albertan, for example. It is also visible in Kaatskill, a transgenerational collaboration for which Goudy drew the roman and Rimmer the italic.

# a

# abcëfghijõp 123 AQ abcéfghijõp

Apollo P Adrian Frutiger's Apollo was commissioned for the Monophoto machine in 1960 and produced in 1962. Frutiger used the opportunity to rethink his first text face, Méridien, drawn eight years earlier. Apollo lacks the sharpness of Méridien, but its smaller eye, blunter serifs and reduced modulation can make it a better choice for text, and it comes with the f-ligatures, text figures and small caps that Méridien lacks. (See also page 238.)

# n

## abcëfghijõp 123 AQ abcéfghijõp

Arrus **D** This is an elegant and graceful text face designed by calligrapher Richard Lipton for Bitstream in 1991. It is distinguished by the symmetrically notched roman foot serifs and asymmetri-



cally notched head serifs. There is a full range of weights, with text figures and small caps. The same designer's Cataneo, an equally graceful chancery italic (Bitstream, 1994), makes an excellent companion face for Arrus.

### abcëfghijõp 123 AQ abcéfghijõp

Baskerville H John Baskerville designed this roman and italic in the 1750s. The initial versions were cut by John Handy under Baskerville's watchful eye. The result is the epitome of Neoclassicism and eighteenth-century rationalism in type – a face far more popular in Republican France and the American colonies than in eighteenth-century England, where it was made.

Many of the digital faces sold under Baskerville's name are passably faithful to his designs, but small caps and text figures, often omitted, are essential to the spirit of the original, and to an even flow of text. The digital version shown here is Monotype Baskerville. At least two Cyrillic versions also exist: one produced by Monotype and one produced by ParaType under license from ITC. (See also pp 13, 56, 77, 84, 97, 129, 280.)

## abcëfghijõp 123 AQ abcéfghijõp

Bell H The original Bell type was cut in London in 1788 by Richard Austin for a publisher named John Bell. It was warmly greeted there and in the USA and was widely used at Boston and Philadelphia in the 1790s. It remains useful for period design work, as an alternative to Baskerville. Monotype cut a facsimile in 1931, and this version has been digitized. Bell has more variation in axis than Baskerville, but it too is an English Neoclassical face. The serifs are very sharp, but the overall spirit is nevertheless closer to brick than to granite, evoking Lincoln's Inn more than St Paul's, and Harvard Yard more than Pennsylvania Avenue. Bell numerals are three-quarter height, neither hanging nor fully ranging. (See also pp 47, 129.)

# abcëfghijõp 123 AQ abcéfghijôpy

Bembo н Bembo was produced by Monotype in 1929, based on a roman cut at Venice by Francesco Griffo in 1495. The fifteenthcentury original had no italic, and Monotype tested two possibilities as a companion face. One was Fairbank italic; the other was the softer Bembo italic shown here. This italic is in essence a revision of Blado (the italic cut for Poliphilus), with sidelong reference to a font designed in Venice in the 1520s by Giovanni Tagliente. Bembo roman and italic are quieter and farther from their sources than Centaur and Arrighi. They are nevertheless serene and versatile faces of genuine Renaissance structure, and they have in some measure survived the transition to digital composition and offset printing. Text figures and small caps are essential. The bold fonts are irrelevant to the spirit of the face. (See also pp 51, 122, 124, 242.)

Bembo is named for the Venetian writer Pietro Bembo (1470–1547) because the roman on which it is based was first used in Bembo's little book *De Aetna*, published by Aldus in 1496.

## abcëfghijõpy! AQ abcéfghijôpy

Berling H Designed by the Swedish typographer and calligrapher Karl-Erik Forsberg. This face was issued in 1951 by the foundry from which it takes its name, the Berlingska Stilgjuteriet in Lund, Sweden. It is a neohumanist design, with vigorous modulation of the stroke. Ascenders and descenders are even more frequent in Swedish than in English, and Berling's descenders are unusually short. The ascenders are of normal height but designed to require no ligatures. The face has a Scandinavian sharpness and clarity, with sharply beaked f, j, y and ! in the roman. The titling figures are well formed, but the text figures (omitted from every digital cut I have seen) are decidedly better. (See also page 84.)

f!

## abcëfghijõp 123 AQ *abcéfghijõp*

Bodoni H Giambattista Bodoni of Parma, one of the most prolific of all type designers, is also the nearest typographic counterpart to Byron and Liszt. That is to say, he is typography's arch-romantic. His hundreds of faces, designed between about 1765 and his death in 1813, embrace considerable variety, and more than 25,000 of his punches are in the Bodoni Museum in Parma. The revivals issued in his name reflect only a tiny part of this legacy, and many are simply parodies of his ideas. The typical features of Bodoni revivals are abrupt hairline serifs, ball terminals, vertical axis, small aperture, high contrast and exaggerated modulation. The ITC Bodonis, digitized in 1994–95 under the direction of Sumner Stone, are the closest of all the revivals to Bodoni's mature style. (There are three versions, based on 6, 12 and 72 pt originals.) Other favorites are the Bodoni cut by Louis Hoell for the Bauer Foundry, Frankfurt, in 1924, and the Berthold Foundry version,

O

produced in 1930. Both have been issued in digital form. Small caps and text figures are essential to all of these designs. The version shown is the Bauer. (See also pp 13, 131.)

#### abcëfghijop 123 AQ abcéfghijop

Bulmer H William Martin of Birmingham was the brother of Robert Martin, Baskerville's chief assistant. He may have learned to cut punches from Baskerville's punchcutter John Handy and may have got his first lessons in type design from Baskerville himself. He moved to London in 1786 and in the early 1790s started cutting types full of Baskervillean shapes yet considerably harsher than Baskerville's. The serifs were abrupt and the contrast much increased. This was the inception of English Romantic typography. Martin's types were sponsored and promoted by the printer William Bulmer, whose name overshadowed that of the designer. They were copied in 1928 by Morris Benton for ATF, and then by Monotype and Intertype. Several digital versions now exist. The most comprehensive of these is the one released by Monotype in 1994. (See also page 131.)

#### abcëfghijõp 123 AQ abcéfghijõp

Caecilia D This face, first issued by Linotype in 1991, was designed in the Netherlands by Peter Matthias Noordzij, whose wife is named Cécile. An earlier bearer of the name, Caecilia Metella, was the fourth wife of the Roman general Lucius Cornelius Sulla (c. 138-78 BC), whose army plundered Athens in 86 BC. On his return from that campaign, he led the winning side in the Roman civil war of 82 and was installed as Roman Dictator. In 81 BC, his wife Caecilia was stricken with an unidentified disease - caught, some Romans claimed, from Sulla himself. As Caecilia lay dying, her husband divorced her and had her carried out of the house to avoid contamination. A later Caecilia, also a native of Rome, is revered in the Christian tradition as the patron saint of music. The type that shares the name of these three women is a graceful, sturdy face, useful for text of many kinds. It is a neohumanist slabserif, perhaps the first of its kind, with a slab-serifed true italic to match. The italic is built to Renaissance parameters, sloping at a modest 5°. There is a range of weights, with small caps and text figures. Licensed versions are sold as PMN Caecilia. There is no face called Sulla. (See also page 112.)



#### abcëfghijop 123 AQ abcéfghijop

Californian H The ancestor of this face is Frederic Goudy's University of California Old Style, cut as a proprietary typeface in 1938. Lanston Monotype issued it publicly in 1956 under the name Californian. The digital version shown is FB Californian, made in 1990 by David Berlow for the Font Bureau, Boston. It is useful to compare this with ITC Berkeley, a more pasteurized interpretation of the same original, produced in 1983 by Tony Stan for photocomposition. While Berkeley retains many virtues of the original type, it has lost much of its character. It also lacks the text figures and small caps required by the design. These are present in Berlow's version. (See overleaf.)

The diacritics have been repositioned in these fonts of FB Californian.

#### abcëfghijõp 123 AQ abcéfghijôp

Carmina D Gudrun Zapf-von Hesse designed this face, released by Bitstream in 1987. While it builds upon her earlier text faces, Diotima and Nofret, Carmina is more versatile and lyrical (hence the name: carmina are songs or lyrical poems). There is a good range of weights. Like many early digital fonts, however, it was issued in a Procrustean character set making no provision for text figures. Such figures were a part of the original design but still have never been released.

a

#### abcëfghijõp 123 AQ abcéfghijõp

Cartier P Canadian typographer Carl Dair began working on this face in the Netherlands in 1957. At his death in 1967, the display version of the roman was effectively complete, but the italic was still an overwrought and over-narrow draft. No text weight or small caps had been drawn. The type was hurriedly issued for filmsetting nevertheless, in time for the Canadian centenary in 1967. Cartier roman then became, despite its weaknesses, the *de facto* Canadian national typeface, often used for stamps and other celebratory projects. It was in principle a roman with enough French Gothic flavor to assert a crucial difference between Ottawa and Washington. The letterforms are rooted in Dair's study of fifteenth-century Parisian and Florentine printing, especially the work of Ulrich Gering and Antonio Miscomini.

In the 1970s, British typographer Robert Norton confused things slightly by producing a tamed and sanitized version of

**FB** Californian (on the left) and ITC Berkeley (on the right) are both derived from Frederic Goudy's University of California Old Style. To facilitate comparison, these two cuts are shown here at slightly different sizes: 74 pt (FB Californian) and 77 pt (ITC Berkeley). In the lower half of the page, both fonts are shown at 18 pt (Californian above, Berkeley below).

# bb cc

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1 2 3 4 5 6 7 8 9 0 · A B C D É
1 2 3 4 5 6 7 8 9 0 · A B C D É
A B C D E F G H I J K L M N O
A B C D E F G H I J K L M N O
abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz

Cartier and giving it the name of an English colonial partisan: Raleigh. (Raleigh, however, is almost never seen as a book face because Norton gave it no italic.) In the 1990s another Canadian, Rod McDonald, undertook to rescue the design. He gave Dair's roman and italic the editing required to make them useful at text size, supplied the missing small caps, semibold and bold weight, and gave the type its first meticulous fitting. The result, called Cartier Book, began to circulate in 1998 and was issued by Agfa Monotype in 2000. Greek and Cyrillic companion faces are now underway. So is a suite of fleurons (maple leaf, spruce limbs, etc) for which Dair made some preliminary drawings.

# g

# abcëfghijõp 123 AQ abcéfghijõp abcëfghijõp 123 so so abcéfghijõp abcëfghijõp 123 so so abcéfghijõp abcëfghijõp 123 so so abcéfghijõp

shown at 20 pt
Great Primer
Founder's

Adobe Caslon,

Founder's Caslon, at 24 pt

Pica Founder's Caslon, at 21 pt

Brevier Founder's Caslon, at 21 pt

Caslon H William Caslon designed and cut a large number of romans, italics and non-Latin faces between 1720 and his death in 1766. His work is the typographic epitome of the English Baroque and is remarkably well preserved. He published thorough specimens, and a large collection of his punches is now in the St Bride Printing Library, London. There is not much doubt that Caslon was the first great English typecutter, and in the Englishspeaking world his type has long possessed the semilegendary, unexciting status of the pipe and slippers, good used car and favorite chair. Typographic opportunists have therefore freely helped themselves to Caslon's reassuring name, and many of the faces sold as Caslons now are merely parodies. Adobe Caslon, drawn by Carol Twombly in 1989, is a respectful, sensitive and well-made digital descendant of the originals, equipped not only with text figures and small caps, but with optional swash caps, ornaments and other antiquarian accessories. It is now made as an OpenType font with a pan-European Latin character set but without Greek and Cyrillic. (No one, alas, has yet made a digital version of Caslon's handsome polytonic Greeks.)

For those in search of more historical veracity, Justin Howes has produced digital versions directly from printed specimens

d



of several sizes of the original Caslon types. These preserve, in their perfectly static way, a taste of the dynamic, rugged texture of printing in Caslon's time. They are issued as Founder's Caslon, by H.W. Caslon & Co. (See also pp 12, 51, 66, 113, 126.)

#### abcëfghijõp 123 AQ abcéfghijõp

Centaur & Arrighi H Centaur roman was designed by Bruce Rogers in 1912–14, based on the roman type cut at Venice by Nicolas Jenson in 1469. In 1928, the face was mildly sanitized in the course of transposition to the Monotype machine. Frederic Warde drew the Arrighi italic in 1925, based on a chancery font designed by the calligrapher Ludovico degli Arrighi in the 1520s. In 1929, after several revisions, Rogers chose Warde's face as the companion italic for Centaur, provoking more revisions still. The fonts are used both separately and together.

Printed letterpress, Centaur and Arrighi are unrivalled in their power to re-evoke the typographic spirit of the Venetian Renaissance. In the two-dimensional world of digital composition and offset printing, this power is easily lost. The problem is aggravated by weaknesses in the digitization of Arrighi, destroying the balance achieved when the faces were married in metal.

Morris Benton's Cloister Old Style (ATF, 1913–25), George Jones's Venezia (Shanks, 1916; Linotype 1928), Ernst Detterer's Eusebius (Ludlow, 1924), Ronald Arnholm's Legacy (ITC, 1992) and Robert Slimbach's Adobe Jenson (Adobe, 1996) are other significant attempts to do some justice to the same original. (See also pp 12, 16, 67, 79, 84, 105, 122, 124, 186, 202.)

#### abcëfghijõp 123 AQ abcèfghijõp

Chaparral D The evergreen oaks of the California foothills are known in Spanish as chaparros. The lean and sunny landscape in where they thrive is known as chaparral. Carol Twombly completed this extraordinarily clean and seemingly imperturbable typeface in 1997 and retired soon thereafter as staff designer at Adobe. Most good text types owe their power in part to the rhythmic modulation of the line. Here there is some modulation, but very little, and the power comes from the path of the stroke: the subtle out-of-roundness of the bowls and microscopic taper of the stems. There is a range of weights, and the character set is pan-European Latin.



William Morris's Golden Type, cut in 1890, was the first modern attempt to recreate Jenson's roman. A more successful version was the Doves Roman, drawn by Emery Walker and cut by Edward Prince in 1900. But Walker's type has vanished just like Jenson's own. After using it for sixteen years, Thomas Cobden-Sanderson threw it surreptitiously into the Thames from Hammersmith Bridge.



#### AQ ábcdèfghijklmñöpqrstûvwxyz

Clarendon H Clarendon is the name of a whole genus of Victorian typefaces, spawned by a font that Benjamin Fox cut for Robert Besley at the Fann Street Foundry, London, in 1845. These faces reflect the hearty, stolid, bland, unstoppable aspects of the British Empire. They lack cultivation, but they also lack menace and guile. They squint and stand their ground, but they do not glare. In other words, they consist of thick strokes melding into thick slab serifs, fat ball terminals, vertical axis, large eye, low contrast and tiny aperture. The original had no italic, as the face had nothing of the fluent hand or sculpted nib left in its pedigree. (Stephenson Blake did however issue a sloped roman version of Besley's original Clarendon – known to them as Consort – in foundry metal in 1953.)

Hermann Eidenbenz drew a version of Clarendon for the Haas Foundry in Münchenstein, Switzerland, in 1951, and in 1962 the foundry finally added the light weight that transformed the series, paring it down from premodern ponderousness to post-modern insubstantiality. In this guise, as a kind of nostalgic steel frame from which all the Victorian murk has been removed, the face has many genuine uses. Monotype Clarendon lacks the presence of Haas Clarendon, which is the version shown.

A related face – a kind of muted Clarendon – is Morris Fuller Benton's Century Schoolbook, issued by ATF in 1924 and in machine form by Monotype in 1928. This too is now available in a light weight and in digital form. (See also pp 106, 132.)

#### abcëfghijõp 123 AQ abcéfghijôp

Comenius P The seventeenth-century Czech theologian Jan Ámos Komenský, or Comenius, is remembered for his efforts to establish universal public education throughout Europe and for his insistence that there is no incongruity between sacred and secular learning. The typeface aptly named for him is distinguished by its lucid blend of humanist and rationalist forms. It was designed by Hermann Zapf and first released by Berthold in 1980. The axis in the roman varies, and the bowls are asymmetrical. The result is a face alive with static energy. The italic is consistent in its axis and full of vibrant motion. There are two bold weights, both graceful and dramatic in their contrast. The requisite text figures were designed but have never been issued.







Diotima roman (on the left) and the normal weight of Nofret roman (on the right): two related faces designed some thirty years apart by Gudrun Zapfvon Hesse. Diotima was designed as a foundry face for letterpress printing. Nofret was designed initially for the medium of phototype. They are shown here for comparison at 70 pt and 18 pt, both in digital form.

abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz

1234567890

1234567890

ABCDEFGHIJKLMNOPQ

ABCDEFGHIJKLMNOPQ

abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz

#### abcëfghijõp 123 AQ abcéfghijôp

Dante H Roman and italic, designed by Giovanni Mardersteig and cut by hand in steel in 1954 by Charles Malin. Monotype adapted the face for machine setting in 1957 and in the early 1990s produced a digitized version. In its foundry form, Dante is one of the great achievements of twentieth-century typography: a finely tooled and stately neohumanist roman coupled with a very lively and lucid italic.

Mardersteig was the greatest modern scholar of Francesco Griffo's work, and his Dante – though not in fact a copy of any of Griffo's types – has more of Griffo's spirit than any other face now commercially available. Used with a reduced size of the upright roman capitals, Dante italic is also the nearest modern counterpart to a true Aldine italic. The Monotype digital version is, however, somewhat coarser than its metal antecedents. Small caps and text figures are, of course, quintessential to the design. (See also page 133.)

#### abcëfghijop 123 AQ abcéfghijop

Deepdene M This may be the gentlest and most lyrical of Frederic Goudy's many book faces. The aperture is larger than usual with Goudy, the x-height is modest, the axis is serenely neohumanist, and the drawing is graceful and even. Goudy drew the roman in 1927, naming it after his house in Marlborough, New York. (The house was named in turn for Deepdene Road on Long Island.) The italic – which slopes at only 3° – was completed the following year, when the face was issued by Lanston Monotype. Light as it is, the italic also has the strength to function as an independent text face. Small caps and text figures (included in the Lanston digital version) are requirements of the design. The swash characters available on supplementary fonts are less an asset than a temptation.

#### abcëfghijõp 123 AQ abcéfghijôp

Diotima н Designed by Gudrun Zapf-von Hesse and cut by the Stempel Foundry, Frankfurt, in 1953, Diotima is now issued by Linotype-Hell in digital form. The roman is wide and the italic markedly narrow. There are small caps but no bold weights. The face is named for the earliest woman philosopher on record:

g

8

The alignment and character fit of Lanston digital Deepdene have been edited to produce the font used here.

9

Diotima of Mantinea, whose metaphysic of love is recited in Plato's *Symposium* by her former student, Socrates. Diotima is part of an extended family of faces by the same designer that has accrued over more than thirty years. Its relatives include the Nofret series, Ariadne (a font of swash initials) and the handsome inline titling face, Smaragd. (See also page 224.)

#### abcëfghijõp 123 AQ abcéfghijõp

Documenta D Frank Blokland started work on this sturdy, open text face in 1986. It was issued by his firm, DTL, in 1993. Small caps and text figures are supplied for the full range of weights. An equally unpretentious and well-made sanserif companion face was released in 1997.

#### abcëfghijõp 123 AQ abcéfghijõp

Electra M Several early twentieth-century book faces are creative variations on Neoclassical and Romantic form. This makes them seem, in retrospect, significant precursors of postmodern design. Three were created in the USA for the Linotype machine and became immediate staples of American publishing. One is Rudolph Růžička's Fairfield, issued in 1940. The others are W. A. Dwiggins's Electra, issued in 1935, and his Caledonia, issued in 1938. In their original Linotype form, Electra was the liveliest of the three, though in digital form this may no longer be the case. Electra was first issued with a sloped roman in lieu of an italic, but in 1940 Dwiggins himself replaced this sloped roman with the simple, crisp italic now normally used. Small caps and text figures are inherent in the design. (See also page 113.)

#### abcëfghijõp 123 AQ *abcéfghijõp*

Esprit P Designed by Jovica Veljović in Beograd and issued through ITC, New York, in 1985. A sharply serifed roman and italic of variable axis, large x-height and small aperture. The strokes and bowls of the lower case are full of oblique lines and asymmetric curves which add further energy to the basically rowdy Neobaroque structure. A related but somewhat simpler face is the same designer's earlier Veljović. Small caps and text figures are implicit in the design—but the italic text figures, drawn long ago, have yet to be released. (See also pp 113, 135.)

g

#### AHQ 123 ábçdèfghijklmñöpqrstûvwxyz

Fairbank M In 1928, when English calligrapher Alfred Fairbank designed this face and offered it to Monotype, the corporation considered it as a possible companion for their new Bembo roman. It is narrow and has a slope of only 4°, yet it is full of tensile strength, and in the estimation of Monotype's typographical advisor, Stanley Morison, even after it was tamed by Monotype draftsmen, it overpowered the dignified and soft-spoken roman to which it was betrothed. A new and milder italic – the present Bembo italic – was cut to replace it. Fairbank's italic has since remained a typographic loner, routinely misdescribed (against its designer's explicit wish) as 'Bembo Condensed Italic.'

In fact, a typographic loner is what it needs to be. The humanist italics from which it descends – those of Griffo, the Master of Basel, and Arrighi – were employed on their own for setting extended texts, not as helpmeets to existing roman faces. Fairbank has the same rich potential.

When Robin Nicholas and Carl Cossgrove at Monotype finally digitized the face, in 2003, they returned to Fairbank's drawings, restoring the original upright capitals and the long extenders of the lower case. They also added several needless but legitimate swash characters and a wholly illegitimate set of lining figures that has no basis whatsoever in chancery tradition or in Fairbank's personal aesthetic. To make a working digital version of this highly useful type, Fairbank's own text figures must be moved from the swash font to the base font.

#### abcëfghijõp 123 AQ abcéfghijõp

Fairfield M A text face designed by Rudolph Růžička for the Linotype machine and issued in 1939. Fairfield has a rationalist axis, like the Electra of Růžička's friend and colleague W. A. Dwiggins, and it remained, like Electra, a standard text face in American publishing for roughly forty years. Alex Kazcun digitized Fairfield in 1991, replacing the narrow Linotype italic f and f with kerning characters and narrowing the set of the italic. He also increased the contrast of the face (thereby delicately tilting it from a preto a postmodern design), added additional weights to the range, and included Růžička's alternate italic, oddly rechristened the 'caption font.'





#### abcëfghijõp 123 AQ abcéfghijõp

Figural H The real Figural was designed in Czechoslovakia by Oldřich Menhart in 1940 and finally cut and cast by the Grafotechna Foundry, Prague, in 1949. A digital version was created by Michael Gills and issued by Letraset in 1992. Except to a few fortunate letterpress printers, this muffled digital version is the only form in which the type is currently available.

Menhart was the master of Expressionism in type design, and Figural is among his finest creations: a rugged but graceful roman and italic, deliberately preserving the expressive irregularity of pen-written forms. The same designer's Manuscript is similar in character but rougher, and his Monument is a congenial titling face for use with either Manuscript or Figural. Though digital Figural lacks the marvellous abrasiveness of the original, it is still a good text face for use at modest size. But like all of Menhart's work, Figural deserves a more authentic digital revival. (See also page 109.)

#### abcëfghijõp 123 AQ *abcéfghijõp* CFGIT·*CFGIJOQT*

Fleischmann H This is a digital family based on roman and italic fonts cut by Johann Michael Fleischman [sic] in Amsterdam in 1738–39. Fleischman was a prolific, and skilled punchcutter and founder whose work, like Bodoni's, covers considerable range. In the late 1730s, he and his competitor Jacques-François Rosart both cut text types that are truly Rococo. The architecture of these fonts is fundamentally Baroque, but exaggerated contrast is found in the roman and italic o and g, and in all the round uppercase letters. The serifs on the caps are ostentatious and abrupt. Erhard Kaiser's digital interpretation, issued by DTL in 1995, is a little tamer than the metal. It includes text figures, small caps and a range of ornamental ligatures. (See also page 128.)

#### abcëfghijop 123 AQ abcéfghijop

Fournier H The typefaces of Pierre-Simon Fournier come from the same historical period – and much the same rationalist spirit – as Baskerville's designs and the Bell type of Richard Austin. Yet these faces are by no means all alike. The types of Fournier are as French as Bell and Baskerville are English, and Fournier's type is Fournier's, speaking subtly of the man himself.

Fournier is also famous for his use of ornaments. Like Mozart, he moves between pure, and surprisingly powerful, Neoclassicism and airy Rococo. His letters have more variation of axis than Baskerville's, his romans are a little narrower, and his italics are sharper. Late in his life, he cut some of the first condensed roman faces. And like Mozart, he delights in sliding backward from the Neoclassical forms he pioneered to the older forms of the Baroque, which he admired and inherited.

In one important respect, however, Fournier turned his back on the Baroque. He cut his romans and italics as coequal, independent fonts which differ quite deliberately in x-height. In 1925, Monotype cut two separate series based on his work. These were issued in metal as Monotype Fournier and Monotype Barbou. Only the former has been digitized, but both series preserve Fournier's disparate proportioning of roman and italic. Modern editorial convention is still stuck in the Baroque and often demands that roman and italic be mixed on a single line. But Fournier should be used, I think, in Fournier's fashion, or else it should be recut. (See also page 129.)

#### abcëfghijop 123 AQ abcéfghijop

Galliard P Galliard was once the name of a type size – 9 pt – as well as a dance and its musical form. The family of type now known by this name was designed by Matthew Carter, issued initially by Mergenthaler in 1978, and later licensed by ITC. It is a crisp, formal but energetic roman and italic, based on the designs of the sixteenth-century French typecutter Robert Granjon. Enough of Granjon's work survives, both in steel and in print, to prove that he was one of the finest punchcutters who ever lived. Galliard is Carter's homage to the man as well as to his work. It is also the preeminent example of a Mannerist revival typeface.

Text figures and small caps are implicit in the design. For period typography, additional sets of Mannerist ligatures and swash capitals are available as well. The best of the several digital versions appears, not surprisingly, to be Carter's own, released in 1992 by Carter & Cone. The obvious titling face is Carter's Mantinia (page 284) – another act of homage to an artist of extraordinary intellect, precision and exemplary technical skill. (See also page 125.)

f

х*хо*о b*p*р





f

a

The large sorts above are from William Ross Mills's "1520 Garamond," a titling face closer than any other digital version to Garamond's actual designs. It is issued by Tiro Typeworks, Vancouver.

18 pt Stempel Garamond 18 pt Linotype Granjon

> 18 pt Adobe Garamond

Garamond (1) H Claude Garamond (or Garamont), who died in 1561, was one of several great typecutters at work in Paris during the early sixteenth century. His teacher, Antoine Augereau, and his gifted contemporaries are remembered now only by scholars, while Garamond suffers posthumous fame. Many of his punches and matrices survive in museum collections, and his style is not hard to learn to recognize. This has not prevented people from crediting him with type he could not possibly have designed and would not, perhaps, have admired.

Garamond's romans are stately High Renaissance forms with humanist axis, moderate contrast and long extenders. He cut several beautiful italics as well, with some of the first sloped capitals, but he took no apparent interest in the radical new idea of actually *pairing* italics with romans. Revivals of his roman faces are often mated instead with italics based on the work of a younger artist, Robert Granjon. Three Garamond and Garamond/Granjon revivals worthy of serious consideration are:

- 1 Stempel Garamond, issued by the Stempel Foundry in 1924 and later digitized by Linotype;
- 2 Granjon, drawn by George William Jones and issued by Linotype in 1928 – now also in the Linotype digital library – and
- 3 Adobe Garamond, drawn by Robert Slimbach, issued in digital form by Adobe in 1989, and re-released in 2000 in the form of pan-European Latin OpenType.

Jan Tschichold's Sabon, listed separately on page 231, is also closely based on Garamond's originals. Small caps and text figures exist and are essential to all of these designs.

# abcëfghijõp 123 AQ *abcéfghijõp* abcëfghijõp 123 AQ *abcéfghijõp* abcëfghijõp 123 AQ *abcéfghijõp*

Stempel Garamond is the only one of these in which the italic as well as the roman is based on a genuine Garamond. (The model used, Garamond's *gros romain* italic, is reproduced on page 74.) The rhythm and proportions of the Stempel face are, however, much changed from the original, and the *f*'s are deformed.

An entirely separate strain of designs, based on the work of Jean Jannon, is also sold under the name Garamond. These are discussed in the following entry. (See also pp 101, 122, 232.)

Garamond (2) H Jean Jannon, born in 1580, was the earliest of the great typographic artists of the European Baroque. He was also a French Protestant, printing illegally in a Catholic regime, and the type he cut and cast during the early seventeenth century was seized in 1641 by agents of the French crown. (Jannon may later have been reimbursed.) After two centuries in storage, it was revived and misidentified as the work of Claude Garamond. The surviving punches are still at the Imprimerie Nationale, Paris.

Jannon's type is elegant and disorderly: of widely varying axis and slope, sharply serifed and asymmetrical. The best revivals of these lovely, distinctly non-Garamondian letters are:

- 1 ATF 'Garamond,' drawn by M.F. Benton and issued in 1918-20;
- 2 Lanston's 'Garamont,' which was drawn by Frederic Goudy and issued in 1921;
- 3 Monotype 'Garamond,' issued in 1922; and
- 4 Simoncini 'Garamond,' drawn by Francesco Simoncini and issued in metal by the Simoncini Foundry, Bologna, in 1958.

Monotype has been particularly thorough in Jannon's case, issuing two different cuts of italic, both in metal and in digital form. Monotype 156, in which the slope of the caps varies rambunctiously, is closer to Jannon's originals. Monotype 176 was the corporate revision: an attempt to bring the unrepentant French typecutter, or at least his italic upper case, back into line. But irregularity lies at the heart of the Baroque, and at the heart of Jannon's letters, just as it may lie at the heart of his refusal to conform to the state religion of his day. I prefer Monotype 156 italic (called 'alternate' in digital form) for that reason.

## abcëfghijõp 123 AQ *abcéfghijõp* abcëfghijõp 123 AQ *abcéfghijõp*

Yet another version of Jannon's type is sold as 'Garamond 3.' This is the ATF 'Garamond' of 1918 as adapted in 1936 for the Linotype machine, now re-revised for digital composition. It is perfectly serviceable as a text face, but it lacks both the slightly disheveled grace of Monotype 'Garamond' and the more carefully combed and erect grace of the Simoncini version.

ITC 'Garamond,' designed in the 1970s by Tony Stan, also has nothing to do with Garamond's type. It is a radically distorted form of Jannon's: distant from the spirit of the Baroque and of the Renaissance alike. (See also pp 101, 126, 232.)

a

18 pt Monotype 'Garamond'

18 pt Simoncini 'Garamond'

As issued, Simoncini Garamond lacks text figures and small caps. They have been added to the version shown here.

Stempel Garamond roman (on the left) is indeed based on the work of Claude Garamond (though its f, in both roman and italic. is distorted in a misguided attempt to escape the need for ligatures). Monotype 'Garamond' (on the right) is based on the work of Jean Jannon. These two excellent types come from different centuries and spirits as well as different hands. Surely they also therefore merit different names. They are shown here side by side, the Stempel at 70 pt and the Monotype at 78 pt, and one above the other, both at 18 pt.

# Height rrkkx

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1 2 3 4 5 6 7 8 9 0 · A B C D É F G
1 2 3 4 5 6 7 8 9 0 · A B C D É F G
A B C D E F G H I J K L M T
A B C D E F G H I J K L M N T
abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz

#### abcëfghijop 123 AQ abcéfghijop

Haarlemmer M Jan van Krimpen drew this face for Monotype in 1938 to fulfill a private commission. It was issued at last in 1996, in digital form, by DTL. The roman is based on Romulus. The italic however was a new design in 1938. In the 1940s, Van Krimpen revised Haarlemmer into Spectrum. While digitizing the face, Frank Blokland created an unserifed companion, based largely on Van Krimpen's Romulus Sans. This was issued in 1998 as Haarlemmer Sans. (See also page 248.)

# a

#### abcëfghijõp 123 AQ abcéfghijõp

Hollander D Few things are more useful in the typographic world than plain, sturdy, unpretentious and good-natured fonts of type. Hollander is one of several families of such type designed by Gerard Unger in 1983, but not issued until 1986. The same designer's Swift (1985) and Oranda (1992) are similar. Hollander has greater bulk than Swift but also sharper serifs. It therefore suffers more from harsh commercial treatment (low resolution, low-grade presswork, low-grade paper).

a

Jannon See Garamond (2), page 231.

Janson See Kis, page 235.

#### abcëfghijõp 123 AQ abcéfghijõp

Jenson H Many types of many kinds claim to be inspired by the roman cut at Venice in 1469 by Nicolas Jenson. Some of these derivatives are masterpieces; others are anything but. Bruce Rogers's Centaur is deservedly the best known recreation of Jenson's roman, but Monotype's digital Centaur is a two-dimensional ghost of Rogers's three-dimensional homage to the original Jenson type. Adobe Jenson, drawn by Robert Slimbach and issued in 1995, retraces Rogers's steps and also Frederic Warde's. The italic is based on the same model as Warde's Arrighi italic – a separate design later revised to serve as Centaur's italic. When only the digital fonts are compared, it is clear – to me at least – that Adobe Jenson has better balance between roman and italic and is generally more tolerant of the fundamental flimsiness of two-dimensional printing, though it is otherwise when the two are printed letterpress

a

a

(using polymer plates for Adobe Jenson). Other families of type with which these should be compared are M.F. Benton's Cloister and Ronald Arnholm's Legacy. (Adobe Jenson and Cloister are closer than Adobe Jenson and Centaur in some interesting respects.) The family has been issued both in Multiple Master and OpenType form. The ot versions include small caps, text figures, swash italic, a few fleurons, and a pan-European Latin character set. (See also pp 16, 112, 186.)

#### abcëfghijõp 123 AQ abcéfghijõp

Joanna н Designed by the English artist Eric Gill and cut by the Caslon Foundry, London, in 1930. The Monotype version was produced in 1937. This is a face of spartan simplicity, with flat serifs and very little contrast but considerable variation in stroke axis. The italic has a slope of only 3° and is full of roman forms, but it is sufficiently narrower than the roman to minimize confusion. Text figures are essential to Gill's design. Gill Sans is an obvious and very satisfying companion face.

#### abcëfghijõp 123 AQ abcéfghijõp

Journal D A rough and eminently readable face designed by Zuzana Ličko, issued in 1990 by Emigre. Text figures and small caps are part of the design. There is a wide version known as Journal Ultra as well as a range of weights. (See also page 134.)

#### abcëfghijop 123 AQ abcèfghijop

Kennerley H This was Frederic Goudy's first successful typeface, designed in 1911. (Goudy was 46 at the time, but his career as a type designer was just beginning.) By his own account, the designer wanted a new type with some of the flavor of Caslon – and Kennerley has Caslon's homey unpretentiousness, though it has returned to Renaissance forms for its underlying architecture and many of its structural details. The italic was drawn seven years after the roman, but Goudy had found his style; the two mate well. The text figures and small caps required by the design are included in Lanston's digital version.

(The spelling 'Kennerly' appears in some type catalogues, but the face was commissioned by and named for the publisher Mitchell Kennerley, 1878–1950.) (See also page 201.)

#### abcëfghijopz 123 AQ abcéfghijlop

Kinesis D Designed by Mark Jamra and issued by Adobe in 1997. Kinesis breaks several conventions of type design quite handsomely. The descenders have prominent, canted bilateral serifs. The ascenders, however, have no serifs at all: only an asymmetrically flared termination of the stroke, which is lightly cupped in the roman and beveled in the italic. Dots of i and j are tapered; so are the cross strokes of f and t, and all the unilateral serifs (except in the roman lowercase z). All the bilateral serifs, however, are blunt and nearly uniform in stroke-width. The italic includes some sloped roman forms (i, l) along with the cursive, triangular bowls of Mannerist calligraphy. The OpenType version of the family, issued in 2002, includes text figures and small caps in a wide range of weights but no East European characters.

# 5 11

#### abcëfghijop 123 AQ abcéfghijnôp

Kis H The Hungarian Miklós Kis is a major figure in Dutch typography, as well as that of his own country. He spent most of the 1680s in Amsterdam, where he learned the craft and cut some wonderfully toothy and compact Baroque type. For many years Kis's work was incorrectly ascribed to the Dutch punchcutter Anton Janson and taken to be the epitome of Dutch Baroque design. Commerce has no conscience, and to this day, Kis's type is sold, even by people who know better, under Janson's name.

Some of Kis's original punches and matrices found their way to the Stempel Foundry in Frankfurt, and Stempel Foundry Janson is in consequence Kis's actual type, with German sorts (ä, ß, ü, etc) rather clumsily added by other hands. Linotype Janson was cut in 1954, based on the Kis originals, under the supervision of Hermann Zapf. Monotype Janson and Monotype Erhardt are also adapted – less successfully, I think – from Kis's designs. Linotype Janson Text (1985) seems to me the most successful digital version. It was prepared under the supervision of Adrian Frutiger, based on Kis's originals and on Zapf's excellent Linotype machine version. (See also page 126.)

#### abcëfghijõp 123 AQ *abcéfghijôp*

Legacy D Ronald Arnholm's Legacy (ITC, 1992) is, I think, the blandest of the many twentieth-century attempts to give new,

two-dimensional life to the old three-dimensional type of the master typographer Nicolas Jenson. Blandness, however, is not always a disadvantage in a printing type, and Legacy is of interest on other grounds. It marries a redrawing of Jenson's roman with a redrawing of one of Garamond's italics, rather than one of Arrighi's, and it is the only revival of Jenson's roman that exists in both serifed and unserifed forms.

The model underlying the roman is reproduced on page 16 and the model underlying the italic on page 74. Legacy has a substantially larger eye than either, and in this respect it violates both Jenson's and Garamond's sense of proportion. It is nevertheless a family with many merits and uses. (See also page 258.)

#### 

Lexicon D Designed by Bram de Does in 1992 and issued in digital form by Enschedé. Lexicon was commissioned, as the name suggests, for a new Dutch dictionary. It was therefore designed to be as compact as a Bible type but to function in a range of sizes and to allow many shades and degrees of emphasis. There are six weights (A-F), with both roman and italic small caps in every weight, and in each weight there are two forms of roman and italic lower case: N° 1 with short extenders; N° 2 with extenders of normal length. Lexicon 2A (the light weight with normal extenders) makes an excellent text face for a variety of uses, and Lexicon 1B (the second weight with short extenders) a good companion face for notes and other compact matter.

#### abcefghijop 123 AQ abcefghijop

Manuscript H This was designed in Czechoslovakia by Oldřich Menhart during World War II and issued by Grafotechna, Prague, in 1951. Manuscript is even rougher than the same designer's Figural, but its rough forms are painstakingly chosen and juxtaposed. The roman and italic are perfectly balanced with each other and within themselves. The numerals are large, but their alignment satisfyingly uneven. There is a matching Cyrillic. (The version shown is a trial digitization by Alex White.)

#### abcëfghijõp 123 AQ abcéfghijôp

Mendoza **D** Designed by José Mendoza y Almeida, Paris, and released by ITC in 1991. This is a forceful and resilient neohumanist text face with low contrast and a spartan finish, closer in some ways to the tough and lovely text romans and italics of sixteenth-century Paris than anything else now to be found in digital form. Mendoza prospers under careful handling but is robust enough to survive printing conditions lethal to other text faces. Small caps and text figures are implicit in the design, but the ligatures are best recut or forgotten. There is also an extensive range of weights. (See also pp 101, 108, 112.)

#### abcëfghijop 123 AQ abcéfghijop

Méridien H/P This was Adrian Frutiger's first text face, designed in 1954 for Deberny & Peignot, Paris. The roman was cut and cast for hand composition, but the italic, despite its impeccable balance and flow, was forced to wait. It was then released (with a new incarnation of the roman) only in the form of phototype. The roman caps, which have unusual authority and poise, make an excellent titling face in themselves. The same designer's Frutiger makes a useful sanserif companion. But in the absence of small caps and text figures, the related Apollo is often more useful for text. (See also pp 58, 101, 105, 238.)

#### abcëfghijõp 123 AQ abcéfghijõp

Minion D The first version of this family, designed near San Francisco by Robert Slimbach, was issued by Adobe in 1989. Multiple Master and OpenType versions have been issued more recently. Minion is a fully developed neohumanist text family which is, in the typographic sense, especially economical to set. That is to say that it gives, size for size, a few more characters per line than most text faces without appearing squished or compressed. Small caps and text figures are essential to the design, and these are available across the range, in several weights of both roman and italic. The OpenType form of the face, called Minion Pro, includes a set of typographic ornaments, swash italics, and upright and cursive Greek and Cyrillic. Slimbach's chancery italic, Poetica, is a useful companion face. (Minion Pro is the face in which this book is set. See also pp 106, 107, 201, 280.)

a

g

a

Digital versions of Adrian Frutiger's Méridien (on the left) and Apollo (on the right). The former - initially a foundry face, though matricies were only engraved for the roman - was finished in 1954. Apollo, designed for filmsetting, was completed in 1962. Selected letters are shown here at 72 pt (Méridien) and 80 pt (Apollo). The basic alphabets (Méridien above, Apollo below) are both shown at 18 pt.

# aa bb cc éé ff ff gg pp tt CC HH

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1 2 3 4 5 6 7 8 9 0 · A B C D É
1 2 3 4 5 6 7 8 9 0 · A B C D É
A B C D E F G H I J K L M N O
A B C D E F G H I J K L M N O
abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz

#### abcëfghijop 123 AQ abcéfghijop

Nofret P Nofret, which means 'beautiful one,' was a popular woman's name in early Egypt. In 1984 an exhibition prepared by the Cairo Museum opened in Munich under the title Nofret: Die Schöne: Die Frau in Alten Ägypten, and in that year, Gudrun Zapf-von Hesse's typeface Nofret was released by the Berthold Foundry. It is in many respects a rethinking of the same designer's Diotima, drawn three decades earlier. It is more compact than Diotima in the roman, but of similar width in the italic. There is a wide range of weights, and even the heaviest of these retains its poise. This is not in the typographic sense an egyptian; it is an answer to the question, What might happen to a typographic egyptian if it acquired feminine grace? Small caps and text figures are implicit in the design. (See also pp 135, 224.)

# e

#### abcëfghijõp 123 AQ *abcéfghijôp*

Officina D Designed by Eric Spiekermann and colleagues, and issued in 1990 through ITC. This is a narrow and plain yet robust text face, inspired by the typewriter and useful for setting much matter that might, in an earlier age, have stayed in typescript form. It is sturdy enough to withstand rough treatment (low-grade laser printing, for example) yet sufficiently well-built to prosper under better printing conditions. There is a sanserif counterpart. Cyrillic versions of both Officina Serif and Officina Sans were designed in 1994 by Tagir Safaev and issued in digital form by ParaGraph (now ParaType). (See also page 136.)



## abcëfghijõp 123 AQ abcéfghijôp abcëfghijõp 123 AQ abcéfghijôp

18 pt digital Palatino Linotype 18 pt Linotype

digital Aldus

Palatino H/M This roman and italic were designed in 1948 by Hermann Zapf. The foundry version was cut in steel by August Rosenberger at the Stempel Foundry, Frankfurt. Zapf then adapted it for the Linotype machine. In photo and digital form, it has become the most widely used of all neohumanist faces, among typographic professionals and amateurs alike. As the most universally admired of Zapf's designs, it is also the most heavily pirated.

In its authentic incarnations, Palatino is a superbly balanced,

239

powerful and graceful contribution to typography – but its close relative, Aldus, which was designed expressly for text setting, is often a better choice for that purpose, in company with Palatino as a display face. There is a bold weight, designed in 1950. A bold italic was added, evidently to combat existing forgeries, nearly thirty years later. The extended Palatino family includes two sets of display capitals (Michelangelo and Sistina), a text Greek (Heraklit) and Greek capitals (Phidias). Small caps and text figures are essential to the face.

Because it was first designed as a display face for handsetting in metal, then adapted for use in text sizes on the Linotype machine, there are two fundamentally different yet authentic versions of Palatino italic. There is a wide version, originally matching the roman letter-for-letter in set-width, as required by the Linotype machine, and a narrower, more elegant version intended for hand composition. The current digital versions are based on the foundry design. The OpenType digital fonts (known officially as 'Palatino Linotype' rather than Linotype Palatino) include a new Greek and Cyrillic along with a full pan-European character set and, in some incarnations, also *chū quốc-ngũ*, the Latin character set employed for Vietnamese. (See also pp 15, 59, 77, 97, 104, 133, 211, 214, 254, 278, 281.)

#### abcëfghijop 123 AQ abcéfghijop

Photina P A text face with predominantly rationalist axis, small aperture and narrow set-width but unmistakable calligraphic energy. It was designed by José Mendoza y Almeida and first issued by Monotype in 1972 for photocomposition. There is a range of weights, and the bold versions are gracefully designed. Photina's proportions are deliberately close to those of Univers, which makes an excellent sanserif companion. This is one of the first and one of the finest postmodern text faces. Small caps and text figures are implicit in the design. (See also page 200.)

#### abcëfghijõp 123 AQ *abcèfghijôp* ልው\$▶У«ሥብት&&&&&®©«©

Plantagenet D William Ross Mills designed the initial version of Plantagenet in the mid 1990s. It was issued by his firm, Tiro Typeworks, in 1996. In 2004, he produced a thorough revision,

released as Plantagenet Novus. The new version includes pan-European Latin and Greek character sets with additional sorts for Native American languages that are written in Latin letters, a matching set of Cherokee syllabics, and a range of ornaments and swashes. Why should a face with Neoclassical structure and a character set that links classical Greece and Native America bear the nickname of the Anglo-Norman family that gave England all her kings from Henry II in 1154 to Richard III in 1485? I do not know. But *Plantagenet* is an old French name for the broom plant (in modern French, *la plante genêt*). It is said that Geoffrey of Anjou, founder of the family and an avid hunter, wore a sprig of it in his hat and had it planted as cover for birds. Broom was brought, along with the Latin alphabet, from Europe to North America, where both have since run wild.

#### AQ 123 AQ ábcdèfghíjklmñöpqrstûvwxyz eaqbabefeghghíjklnób QUA stym

Poetica D A chancery italic designed by Robert Slimbach and issued by Adobe in 1992. The basic family consists of four variations on one italic, with varying amounts of swash. There are also five fonts of swash capitals, two of alternate lowercase letters, two fonts of lowercase initials, two of lowercase terminals, two sets of small caps (ornamented and plain), a font of fractions and standard ligatures, another of ornamental ligatures, one font of analphabetic ornaments, and one font entirely of ampersands. The basic face is a plain neohumanist italic, well suited for extended text. The supplementary fonts permit any desired degree of typographic play or ostentation. (See also page 125.)

#### abcëfghijop 123 AQ abcéfghijop

Poliphilus & Blado H Poliphilus, meaning 'Multiple Love,' is the name of the lead character in Francesco Colonna's fantasy novel Hypnerotomachia Poliphili, "The Dream-Fight of Poliphilus," which Aldus Manutius printed in 1499 in a newly revised roman type by Francesco Griffo. In 1923, Monotype tried to replicate this font for use on their machine. The result was Monotype Poliphilus. It was an early experiment in the resuscitation of Renaissance designs, and the Monotype draftsmen copied the actual letterpress impression, including much of the ink squash, instead of par-

Bembo (on the left) and Poliphilus (on the right): two attempts at reproducing a fifteenth-century Venetian type in twentiethcentury terms. Both of these types are based on the same original lower case, but on two different sets of original capitals. They are shown here at 74 pt and at 18 pt.

# aa bb cc éé ff gg ññ ôô tt AACC

(Poliphilus, of course, was never meant to be seen in public enlarged to this degree. It was created as a text face only. The largest size cut in metal matrix form is 16 pt.)

abcdefghijklmnopqrstuvwxyz

1 2 3 4 5 6 7 8 9 0 · A B C D É F G

1 2 3 4 5 6 7 8 9 0 · A B C D É F G

A B C D E F G H I J K L M N O

A B C D E F G H I J K L M N O

abcdefghijklmnopqrstuvwxyz

abcdefghijklmnopqrstuvwxyz

ing back the printed forms to restore what the punchcutter had carved. The result is a rough, somewhat rumpled yet charming face, like a Renaissance aristocrat, unshaven and in stockinged feet, caught between the bedroom and the bath. In the squeaky clean world of offset printing, this roughness has finally come into its own.

Six years after producing Poliphilus, Monotype repeated its experiment with a very different result. Monotype Bembo (1929) is based on an earlier state of the same original: the same lower case with an earlier set of capitals. The differences between lowercase Monotype Bembo and Poliphilus, great as they are, are entirely differences of interpretation, not of design.

Blado, the italic companion to Poliphilus, is not based upon any of Griffo's own superb italics (one of which is shown on page 210) but on a font designed in a very different intellectual milieu, by Ludovico degli Arrighi about 1526. (Arrighi died soon after finishing that type – probably his sixth italic – and it was acquired by the master printer Antonio Blado of Rome. No type called Arrighi existed when the 1923 revival was made. Monotype chose nevertheless to name their revival of the face for the printer who used it, not the calligrapher who designed it.)

#### abcëfghijõp 123 AQ abcéfghijõp

Pontifex P Designed by Friedrich Poppl in Wiesbaden and issued in 1976 by Berthold in Berlin. Pontifex is one of several eminent twentieth-century faces built on Mannerist lines. Other examples include Adrian Frutiger's Méridien, Georg Trump's Trump Mediäval, and Matthew Carter's Galliard. These are four quite different faces, designed by four quite different artists for three different typographic media, but they share several structural presumptions. All have a humanist axis in the roman but an unusually large x-height, a tendency toward sharpness, angularity and tension in the conformation of individual letters, and a considerable slope - 12° to 14° - in the italic. These are features inherited from French Mannerist typecutters such as Jacques de Sanlecque, Guillaume Le Bé and Robert Granjon. Galliard is in fact a revival of Granjon's letters, while Pontifex, Trump and Méridien are independent modern creations sympathetic in spirit to the earlier Mannerist work. Together, these faces demonstrate the considerable range and depth of what one could call the neomannerist aspect of the Modernist tradition. (See also pp 78, 133.)

a

1

a

y

#### abcëfghijõp 123 AQ abcéfghijôp

Quadraat D Fred Smeijers's Quadraat, issued by FontShop in 1993, is a study in contrasts: a tensile and large-eyed yet smoothly flowing roman married to an angular, broken but robust italic. The creative ingenuity involved here extends to the matching Cyrillic and the companion sanserif as well. The fonts as issued are expertly kerned and sold with the requisite parts – small caps and text figures – intact. Some fine types were made during the late twentieth century, and this is one. It is not pretty; its beauty is deeper and stranger than that. (See also pp 260, 281.)

#### abcëfghijop 123 AQ abcéfghijop

Requiem D Requiem is pretty where Quadraat is not, but its beauty runs deeper than prettiness too. In its way, this is the equal of the great neohumanist book types of the early twentieth century: Bembo, Centaur and Dante. It is however the fruit of a later age, more self-conscious and self-involved. Its models are also therefore later: scripts of the High Renaissance, which were likewise acutely self-aware. And Requiem, unlike Bembo, Centaur and Dante, was born in the digital medium, where two dimensions have to do the work of three. It was created by Jonathan Hoefler in New York City, who drew the caps in the early 1990s and completed the family in 1999. It grew out of a commission from a magazine suspiciously entitled Travel and Leisure, but like any good type, it savors of self-discipline no less than self-indulgence. The italic, like Robert Slimbach's Poetica, is indebted to the work of Ludovico degli Arrighi and includes a set of artful, playful ligatures to prove it. The roman caps, with which the project started, are grounded in Arrighi's work as well. The roman lower case owes more to another sixteenth-century calligrapher, Ferdinando Ruano. (See also pp 51, 285.)

22 pt Rialto (for titling)

21 pt [sic] Rialto Piccolo (for text)

# abcëfghijõp 123 AQ abcéfighijõp abcëfghijõp 123 AQ abcéfighijõp

Rialto D Requiem is pretty; Rialto is prettier still, but again, its beauty is deeper than that. Named for the best-loved bridge in Venice, it is the product of joint effort by Venetian calligrapher Giovanni de Faccio and Austrian typographer Lui Karner. The

result is a face of extraordinary calligraphic loveliness which is nevertheless strong enough (properly used) for the texts of substantial books. Proper use begins with remembering that there are two sets of fonts. Rialto itself is actually a titling face, happiest at 18 pt and above. Rialto Piccolo is the better choice at 16 pt and below – which is to say, the choice for all text sizes. Besides the roman and italic there are small caps and semibold, a full set of ligatures and good italic alternates. The italic slopes at 2°, and the roman and italic share a single set of caps. It was issued in 1999 by df Type in Texing, near Vienna. (See also page 285.)

#### et of I the

#### abcefghijop 123 AO abcefghijop

Romanée H Designed by Jan van Krimpen and cut in steel by Paul Helmuth Rädisch at the Enschedé Foundry in Haarlem, Netherlands. The roman owes much to the spirit of Garamond. Van Krimpen designed it in 1928 as a companion for an italic cut in the middle of the seventeenth century by another of Garamond's admirers, Christoffel van Dijck. But Van Krimpen remained dissatisfied with the relationship between the two faces, cut in the same land three hundred years apart. In 1948 he designed an italic of his own – his last type – to mate with Romanée roman. The new italic is distinguished by its prominent descenders, serifed on both sides, and it has much less slope than the italic of Van Dijck. Like the italics of the early sixteenth century – and unlike the italics of both Garamond and Van Dijck – it mates a cursive lower case with upright capitals.

"United they fall, apart they stand as fine designs," said Van Krimpen's younger colleague, Sem Hartz. And it is true that Romanée italic stands very well on its own. Perhaps these faces are best used in the Renaissance manner – not the manner of Van Dijck but the manner of Garamond, his predecessors and colleagues – with the italic set in separate passages rather than laced into the midst of roman text. Digital Romanée, though it has now existed for years, is still awaiting commercial release.

#### abcëfghijõp 123 AQ abcéfghijõp

Romulus H It has been said with some justice that Jan van Krimpen designed three roman types: Lutetia (1925), Romanée (1928), and a third to which at various times in the 1930s and 1940s he gave the names Romulus, Haarlemmer, Sheldon and



Spectrum. The italic sequence is different: Lutetia (1925), Cancelleresca Bastarda (1934), Haarlemmer (1938), Spectrum (c. 1942) and Romanée (1949). For Romulus, Van Krimpen initially designed no italic. Instead, on Stanley Morison's advice, he drew a second version of the roman that slopes at 11°. He soon atoned for this however by designing the most elaborate and technically challenging italic of his career, the Cancelleresca Bastarda, and incorporating it into the Romulus family.

Regarded solely as a roman and sloped roman, Romulus looks like a well-made but impoverished type. In reality, it is part of a large family issued in part between 1931 and 1936: the forerunner of other large families such as Legacy, Scala and Quadraat. As of 2004, DTL has digitized only the serifed roman and oblique. These will be of greater use when they are joined by rest of the family: Cancelleresca Bastarda, Romulus Sans, Romulus Greek, and Romulus Open Capitals. (See also pp 58, 248.)

#### abcëfghijop 123 AQ abcéfghijop

Sabon H/M Designed by Jan Tschichold. The foundry version was issued by Stempel in 1964, followed by Monotype and Linotype machine versions in 1967. The series consists of a roman, italic, small caps and semibold, based broadly on the work of Claude Garamond and his pupil Jacques Sabon, who was once employed, after Garamond's death, to repair and complete a set of his teacher's punches. The structure of the letterforms is faithful to French Renaissance models, but Tschichold's face has a larger eye than any but the tiniest sizes cut by Garamond. The type was intended as a general-purpose book face, and it serves this purpose extremely well, though it is bland in comparison with Garamond's originals. (See also pp 34, 52, 104.)

#### abcëfghijõp 123 AQ abcéfghijõpy

Scala D A crisp, neohumanist text face with sharp serifs and low contrast, designed by Martin Majoor in the 1980s for the Vredenburg concert hall in Utrecht. (This may explain why it is named after an opera house in Milan.) It was publicly issued by FontShop International, Berlin, in 1991. This face has many of the merits of Eric Gill's Joanna – not to mention several merits distinctively its own – without Joanna's eccentricities. Small caps and text figures are implicit in the design – and the basic licensed

fonts of FF Scala come pre-equipped with text figures and a full set of ligatures, as if they were really meant for setting type instead of merely typing. There is also an unserifed branch of the family. (See also pp 260, 262–63.)

#### abcëfghijõp 123 AQ abcéfghijõp

Seria D Like Scala, this is the work of Martin Majoor, issued by FontShop in 2000. The designer has written that after completing Scala he wanted to produce a more "literary" face. Whether Seria is really more literary than Scala, I cannot say. Its small eye and long extenders do make it a less utilitarian face, but I have used it myself – and its matching sanserif – with great satisfaction for both literary and nonliterary texts. The italic slopes at only one degree. Italic and roman alike have upright caps, but not the same upright caps. Those of the italic are slightly but recognizably cursive. (See also page 261.)

#### ábçdèfghijklmñöpqrstûvwxyz 123 AQAQAQAEDEEGGMMM

Silentium D Designed by Jovica Veljović and issued in OpenType form by Adobe in 2000. This is a Carolingian face, like Gudrun Zapf-von Hesse's Alcuin. There is necessarily no italic, but there are four sets of caps (one written, three drawn, including one inline and one reversed set, useful for versals), many scribal alternates and ligatures, and an impressive set of ornaments.

#### abcëfghijõp 1234689 AQ abcéfghijôp

Spectrum H/M This is a refinement of Haarlemmer, designed by Jan van Krimpen in the early 1940s, then delayed by the Second World War and issued by both Enschedé and Monotype in 1952. It was Van Krimpen's last general text face and is now the one most widely used. The roman and italic are reserved, elegant and well matched. The axis is humanist, the aperture large, and the serifs simultaneously sharp and flat (a feature neither unwelcome nor contradictory in typography). Small caps and the distinctive Spectrum text figures, with their very short extenders, are essential to the design. A semibold was added by Sem Hartz and cut by Monotype in 1972. (See also pp 133, 248.)

a

3

a

Digital versions of three types by Jan van Krimpen: Romulus (left), Haarlemmer (middle) and Spectrum (right). Selected characters of Romulus are shown here at 78 pt, Haarlemmer at 72 pt,Spectrum at 82 pt. The basic lowercase alphabets of all three are shown at 18 pt.

The italics and the numerals of these three faces are quite distinct, but in the roman, the differences are such as one might expect to find among different sizes of a single hand-cut type.

# ááá bb hhh ccc

abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz 1234567890 1234567890 / 1234567890 abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz

#### abcëfghijop 123 AQ abcéfghijop

Swift D This large-eyed face was designed by Gerard Unger and first issued in 1987 by Rudolf Hell in Kiel. It is avowedly a newspaper type, but it has many additional uses. Though the eye is large and the set is narrow, the letters are crisp and open, with chisel-tipped, wedge-shaped terminals and serifs. The axis is humanist and the aperture large. The italic is taut and fluent, with a slope of 6°. The torso of these letterforms is large enough that Swift can function well without text figures and small caps, but these have now been issued by Elsner & Flake. Unger's sanserif family Praxis and his erect sanserif italic Flora make useful companion faces for Swift.

### a

#### abcëfghijop 123 AQ abcéfghijop

Trajanus H/M Warren Chappell's Trajanus was issued in 1939 as a foundry face by Stempel and in machine form by Linotype. The angular, black forms echo the early humanist scripts of the Renaissance and some of the earliest roman printing types, used in Italy and Germany until they were superseded by the early Venetian whiteletter and then by the Aldine roman and italic. But Trajanus is a remarkably graceful face, and the roman is matched by an equally crisp and fluent italic. The figures, like those of Bell, are three-quarter height lining forms.

a

There is a companion bold face designed by Chappell and a Trajanus Cyrillic designed by Hermann Zapf. Chappell's own sanserif, Lydian, is another related design, slightly darker than Trajanus but of similar angularity. After long delay, Linotype issued a digital version in 1997. The Cyrillic, however, exists only as Linotype metal matrices.

Trinité P A text family designed in 1978–81 by Bram de Does for the Enschedé Foundry in Haarlem. The commission began with a challenge: to create in the elastic and ephemeral world of phototype something as resonant and reserved as the handcut metal types of Jan van Krimpen. The impressive result was issued in film form in 1982 by Bobst/Autologic in Lausanne but never effectively distributed. Trinité was issued again in digital form by the Enschedé Font Foundry in 1991.

There are three weights of wide roman, two weights of narrow roman, two weights of small caps and two weights of italic.

The sample of Trinité is overleaf.

#### Q ábbbçdddêfffggg O (hhhijijijkkklllmñòppp) A qqqrstüvwxyyyž IJ

Serifed Text Faces

A qqqrstuvwxyyyz 1) + 1234567890 =

Q ábbbbçddddêffffggg O {hhhhijijijkkkkllllmñòpppp} A qqqqrstüvwxyyyž IJ + 1234567890 =

Qábbbçdddêfffggg O (hhhijijijkkklllmñòppp) A qqqrstüvwxyyyž IJ + 1234567890 =

Trinité roman wide (above), italic (center) and roman narrow (below). All three ranges of each roman face are shown together, and all four ranges of the italic. In each range, only the extending letters vary.

All weights and widths of roman and italic come in three ranges: with short, normal and long extenders. The capitals remain the same in height; so does the torso of the lower case, but the extenders range to different depths and altitudes. Both weights of italic are also issued in chancery form (with curved extenders). The ordinary roman (Trinité 2, with the normal extenders, in either the wide or the narrow width) makes a fine text face for conventional use. The wide version is 9% wider than the narrow and keeps the same internal rhythm. (In wide and narrow versions alike, for example, the set-widths of the roman letters *i*, *n* and *m* are in exactly the proportion 1:2:3.) The roman letters slope at 1°, the italics at 3°.

Prowling the Specimen Books

There are no separate characters for ligatures in Trinité. They construct themselves from parts. The f+i and f+j, for instance, combine to form the ligatures fi and fj. (This is the reason for the dancing dots on i and j in different versions of the face. In Trinité 1 and 2, the dots meld with the arch of the f. In Trinité 3, the tallest version, the dots tuck under the arm of f instead.) In its present form, with pi fonts, expert sets and other variants, the full family consists of 81 separate digital fonts. Half a dozen of these would be ample for many normal texts. The technical complexities of the series ought not to obscure the simple beauty of the face, which is rooted in the heritage of Van Krimpen and of Italian Renaissance forms. Even the arithmetical signs in Trinité have a slight scribal asymmetry. This is sufficient to enliven the forms for text use yet not enough to render them dysfunctionally ornate. Small caps and text figures are essential components of the family.

p

#### abcëfghijõp 123 AQ abcéfghijõp

Trump Mediäval H/M This is a very robust text face, designed by Georg Trump. It was first issued in 1954 by the Weber Foundry, Stuttgart, as a foundry type, and in machine form by Linotype. It is a strong, angular roman and italic with humanist axis but Mannerist torque and proportions. The aperture is moderate; the serifs are substantial and abrupt. The numerals, both in text form and in titling form, are notably well designed. The digital version retains the Linotype nonkerning f. There is a range of weights but only a partial set of ligatures. A number of Trump's excellent script faces – Codex, Delphin, Jaguar, Palomba and Time Script, for example – and his slab-serifed titling face called City, are potentially useful companions. (See also pp 52, 84.)

a

#### abcëfghijop 123 AQ abcéfghijop

Van den Keere H This is a family of digital romans, modeled on a 21 pt font that Hendrik van den Keere of Ghent cut in 1575 for Christophe Plantin of Antwerp. There are several weights, all with the requisite small caps and other components. But in his long, illustrious career as a punchcutter, Van den Keere did not cut a single italic. The italic paired here with his roman is based on the work of his older friend and colleague François Guyot. The digital versions of these types were produced by Frank Blokland in 's-Hertogenbosch and issued by DTL in 1995–97. (See also page 122.)

#### abcëfghijop 123 AQ abcéfghijop

Van Dijck H The type family now called Van Dijck – first issued by Monotype in 1935 – is based on an italic cut in Amsterdam about 1660 by Christoffel van Dijck and a roman which is probably also his. (Original matrices for the italic still survive; the roman is known only from printed specimens.) These are calm and graceful Dutch Baroque faces, modest in x-height, narrow in the italic and relatively spacious in the roman. A comparison of Van Dijck's work with that of Miklós Kis illuminates the range of Dutch Baroque tradition, but there is plenty of range in Van Dijck's work on its own. His blackletter types are very ornate, while his romans and italics breathe a deep and deliberate serenity, not unlike the works of his great contemporaries, the painters Pieter de Hooch and Jan Vermeer. The digital version of Monotype Van Dijck has unfortunately lost much of the power and resiliency of the Monotype metal version. (See also pp 51, 207.)

#### abcëfghijõp 123 AQ abcéfghijõp

Veljović P Designed by Jovica Veljović and issued in 1984 by ITC. Veljović is a lively postmodern face, with much inherent movement wrapped around its rationalist axis, and much prickly energy emerging in the long, sharp, abrupt wedge serifs. There is a wide range of weights. Fonts with text figures are produced by Elsner & Flake. Small caps, though part of the original design, have evidently never been released. Veljović makes an excellent companion for the same designer's Gamma or Esprit and can be mated with his fine script face Ex Ponto. (See also page 15.)

8

### abcëfghijõp 123 AQ *abcéfghijõp* abcëfghijõp 123 AQ *abcéfghijõp*

16 pt Berthold Walbaum

20 pt Monotype Walbaum

Walbaum H Justus Erich Walbaum, who was a contemporary of Beethoven, ranks with Giambattista Bodoni and Firmin Didot as one of the great European Romantic designers of type. He was the latest of the three, but he may well have been the most original. Walbaum cut his fonts at Goslar and Weimar early in the nineteenth century. His matrices were bought by the Berthold Foundry a century later, and Berthold Walbaum, in its metal form, is Walbaum's actual type. Berthold digital Walbaum is a close and careful translation. Monotype Walbaum, different though it is, is also quite authentic. The Berthold version is based on Walbaum's larger fonts, and the Monotype version on his small text sizes.

The letterfit of Berthold digital Walbaum has been edited extensively to produce the fonts used here.

Each of the major Romantic designers had his own effect on design in the twentieth century. Firmin Didot's ghost is palpable in Adrian Frutiger's Frutiger, Bodoni's ghost in Paul Renner's Futura, and Walbaum's spirit is alive in some of the later work of Hermann Zapf. Yet each of these instances involves a real creative leap, not imitation. (See also page 131.)

#### abcëfghijõp 123 AQ *abcéfghijõp* & the, qua sp fghj xyz &

Zapf Renaissance D Designed by Hermann Zapf in 1984–85 and issued in 1986 by Scangraphic. This family returns, after forty years, to many of the principles that animated one of Zapf's first typefaces, Palatino. But Zapf Renaissance is designed for the high-technology, two-dimensional world of digital imaging instead of the slower, more multidimensional world of the artist printer's handpress. The result is a less printerly and sculptural, more scribal and painterly typeface – and one which at the same time is more tolerant of digital typography's capricious, even licentious, freedom with size. The family includes a roman, italic, small caps, semibold and swash italic with a rich assortment of pilcrows and fleurons.

Palatino Linotype Greek – actually much closer in time to Zapf Renaissance than it is to the original Palatino – makes a fine Greek companion to this roman. (See also page 254.)

a

Linotype
digital Palatino
(on the left)
and Zapf
Renaissance
(on the right).
Both are shown
here at 72 pt
and 18 pt.

These types have much in common, but Palatino was first designed as a foundry face, with weight and proportion changing from size to size and the expectation that it would be printed in three dimensions. Zapf Renaissance was designed as a freely scalable digital face, in which one pattern serves for every size, and with the expectation that it would be printed in two dimensions only.

# a bb

abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz 1 2 3 4 5 6 7 8 9 0 · A B C D É F G 1 2 3 4 5 6 7 8 9 0 · A B C D É F G A B C D E F G H I J K L M N O A B C D E F G H I J K L M N O abcdefghijklmnopqrstuvwxyz abcdefghijklmnopqrstuvwxyz

# ES JD JD NE+MFIS +PY+NF+ 8PN+AC PMM EH OIMTE ITM LDNYAK CA8AT IAM RDNBD +FE M $\downarrow$ MK Ab3 DR +IHME TUI +KEEA+ YM Mbk OD TERC EK8EA

14 pt unserifed Etruscan cut by William Caslon for Oxford University Press, about 1745. Unserifed scripts are as old as writing itself, but this is one of the earliest unserifed types.

Prowling the Specimen Books

### 11.3 UNSERIFED TEXT FACES

Unserifed letters have a history at least as long, and quite as distinguished, as serifed letters. Unserifed capitals appear in the earliest Greek inscriptions. They reappear at Rome in the third and second centuries BC, and in Florence in the early Renaissance. Perhaps it is no more than an accident of history that the unserifed letters of fifteenth-century Florentine architects and sculptors were not translated into metal type in the 1470s.

At Athens and again at Rome, the modulated stroke and bilateral serif were the scribal trademarks and symbols of empire. Unserifed letters, with no modulation or, at most, a subtle taper in the stroke, were emblems of the Republic. This link between unserifed letterforms and populist or democratic movements recurs time and again, in Renaissance Italy and in the eighteenth and nineteenth centuries in northern Europe.

Unserifed types were first cut in the eighteenth century, but they were cut at first for alphabets other than Latin. A sanserif Latin printing type was cut for Valentin Haüy, Paris, in 1786 – but Haüy's type was meant to be invisible. It was designed to be embossed, without ink, for the blind to read with their fingers. The first unserifed Latin type for the sighted – cut by William Caslon IV, London, about 1812 – was based on signwriters' letters and consisted of capitals only. Bicameral (upper- and lowercase) unserifed roman fonts were apparently first cut in Leipzig in the 1820s.

Most, though not all, of the unserifed types of the nineteenth century were dark, coarse and tightly closed. These characteristics are still obvious in faces like Helvetica and Franklin Gothic, despite the weight-reductions and other refinements worked on them over the years. These faces are cultural souvenirs of some of the bleakest days of the Industrial Revolution.

During the twentieth century, sanserifs have evolved toward

Many rotundas and Greek types cut in the 1460s and 1470s include sanserif forms, but none is consistently unserifed (A recent example on similar lines is Karlgeorg Hoefer's San Marco, shown on page 252.)

The importance of the Hauy italic was first pointed out by James Mosley. For more on the history of unserifed letters, see his essay "The Nymph and the Grot," *Typographica* n.s. 12 (1965), and Nicolete Gray, *A History of Lettering* (1986)

Unserifed Text Faces much greater subtlety, and in this evolution there seem to be three major factors. One is the study of archaic Greek inscriptions, with their light, limber stroke and large aperture. Another is the pursuit of pure geometry: typographic meditation first on the circle and the line, then on more complex geometric figures. The third is the study of Renaissance calligraphy and humanistic form – vitally important in the recent history of serifed and unserifed letters alike. But in retrospect it seems that both type designers and founders were for many years strangely reluctant to believe that one could simply write a humanist letter and *leave the serifs off*. When this is done, everything happens and nothing happens: if the stroke has width, the stroke-end too has shape and form; it takes the serif's place.

# abcëfghijop 123 AQ abcéfghijop

fi

Caspari D Designed by Gerard Daniëls and issued by the Dutch Type Library in 1993. This is a subtly crafted and simple text face with the essential humanist attributes, including large aperture, a genuine italic with a modest slope of 6°, text figures, small caps and impressive economy of form. It was one of the first unserifed faces issued in a form truly suitable for text work, with all working parts in place. Daniëls added a Cyrillic version in 2003. One thing still missing is a book weight. (See also pp 264–65.)

# AQ ábçdèfghijklmñöpqrstûvwxyz

fi

Flora P/D Designed by Gerard Unger, released by Rudolf Hell in 1985 and licensed through ITC in 1989. Flora is a true sanserif italic – and it was, I believe, the first unserifed italic to approximate chancery form. It can be used very happily alone but is designed to function also as a companion to Unger's Praxis (unserifed roman) and Demos (serifed roman and italic). Because its slope is only 2.5°, Flora functions best with Praxis when it is used for setting separate blocks of text.

See Gerard Unger, "Dutch Landscape with Letters," in issue 14 of the Dutch journal Gravisie (Utrecht, 1989): 29–52.

Unger has spoken persuasively about the importance of horizontals in his type designs. He associates the strong horizontal thrust of Hollander and Swift with the flat Dutch landscape in the midst of which he lives. But in most of his italics – Swift, Hollander and Flora included – it is verticals that seem to matter most. (See also page 264.)

# abcëfghijõp 123 AQ *abcéfghijôp* abcëfghijõp 123 AQ *abcéfghijôp*

18 pt Original Frutiger

18 pt Frutiger Next



Frutiger P/D Adrian Frutiger designed this face in 1975, initially for signage at the Paris-Roissy Airport. It was then issued by Mergenthaler for use on their photosetting machines and immediately prospered as a typeface. What it lacked in the way of humanist structure it made up for in its open, fresh geometry, wide aperture and balance. It also mated well with the same designer's Méridien and Apollo, though such a mixture was not apparently part of the original design plan, and the fonts did not match in weight or body size. In the conversion from signage to typeface, a sloped roman was added, rather than a genuine italic.

In 1999–2000, Frutiger redrew the face, adding a true italic, incorporating subtle curves into the stems of the roman characters, and altering the range to include a book weight. There are other small improvements – repositioning of the diacritics, for example – which make the newer version better for text work, though there are still, as in Méridien, no text figures or small caps. The revised version, issued by Linotype in 2001, is known as Frutiger Next. (See also pp 105, 264–65.)

# abcëfghijõp 123 AQ abcéfghijôp

Futura H This was the first and remains the best of the geometric sanserif faces, designed by Paul Renner in 1924–26 and issued by the Bauer Foundry, Frankfurt, in 1927. Futura is a subtly crafted face, but many copies have been made, under various names, in metal, film and digital form. By no means all these cuts are equally well made – and not all weights that have been added to the family are Renner's own designs.

Geometric though it is, Futura is one of the most rhythmical sanserifs ever made. Its proportions are graceful and humane – close to those of Centaur in the vertical dimension. This helps to make it suitable – like all the unserifed faces examined here – for setting extended text. (Which is not, of course, to say that it is suitable for texts of every kind.) The new digital version issued by Neufville in Barcelona includes text figures and small caps, which were part of Renner's original design but never issued in metal. (See also pp 14, 106, 133, 212, 264.)







# abcëfghijõp 123 AQ abcéfghijôp

fi

Gill Sans M Designed by Eric Gill and issued by Monotype in 1927. Gill Sans is a distinctly British but highly readable sanserif, composed of latently humanist and overtly geometric forms. The aperture varies (it is large in c, moderate in roman s, smaller in roman e). The italic, like Fournier's, cut two centuries before, was a revolutionary achievement in its time. Books have been set successfully in Gill Sans, though it requires a sure sense of color and measure. Text figures and small caps – very useful when the face is used for text work – were finally added by the Monotype design staff in 1997. (See also pp 264, 277.)

# abcëfghijop 123 AQ abcéfghijop

Haarlemmer Sans D Frank Blokland at the Dutch Type Library created this face as a digital companion to Jan van Krimpen's Haarlemmer while digitizing the latter in the mid 1990s. Haarlemmer itself, cut by Monotype, began as a private commission. So did Haarlemmer Sans, six decades later. The face has been publicly available since 1998. Small caps and text figures are implicit in the design. (See also page 233 – and compare Van Krimpen's Romulus Sans, page 260.)

# abcëfghijõp 123 AQ abcéfghijõp

Legacy Sans D Designed by Ronald Arnholm and issued via ITC in 1992. To the best of my knowledge, this is the only published attempt to make an unserifed version of Nicolas Jenson's roman. Arnholm drew the serifed version first, and in the process made some drastic changes to Jenson's proportions, yet resemblances remain. The italic is based not on Arrighi but on Garamond's gros romain. There is more modulation of the stroke in Legacy Sans than in most unserifed types. Text figures and small caps are part of the design. (See also pp 235, 264.)

# abcëfghijop 123 AQ abcéfghijop

Lucida Sans D This admirable sans, designed by Kris Holmes and Charles Bigelow in 1985, is part of the largest type family in the world. The Lucida tribe now includes not just serifed and unserifed roman and italic but also Greek, Hebrew, Vietnamese,



pan-Asian and pan-European Latin and Cyrillic, a full phonetic character set, a multitude of mathematical symbol sets, swash italic, blackletter, script, a slightly rumpled offshoot known as Lucida Casual, a higher-contrast series called Lucida Bright, a series designed for crude resolutions, called Lucida Fax, a set of fixed-pitch typewriter fonts, and another fixed-pitch font, called Lucida Console, designed for terminal emulation. Yet the basic text figures and small caps, which are essential for civilized text work, are still omitted by every digital foundry that has merchandised the face. (See also page 264.)

# e

# abcëfghijõp 123 AQ *abcéfghijôp* abcëfghijõp 123 AQ *abcéfghijôp* BCDEFGHIJKLMNOPRSW BCDEFGHIJKLMNOPRSW

18 pt Original Optima

18 pt Optima Nova

18 pt Original Optima

18 pt Optima Nova

Optima H/M/D Designed by Hermann Zapf in 1952–55 and issued in 1958, both as a foundry face by Stempel and in the form of metal matrices for the Linotype machine. The taper of the stroke in these original metal versions derives from unserifed Greek inscriptions and the unserifed roman inscriptions of Renaissance Florence, but in other respects the architecture of Optima is Neoclassical. The original Optima 'italic' is pure sloped roman. There is a range of weights and a matching text Greek, designed by Zapf and issued by Linotype in 1971 (but the Greek, to the best of my knowledge, has never been digitized.)

Optima Nova – digital a revision undertaken by Zapf and Akira Kobayashi – was completed in 2003. It involves many changes to the roman, including the sharpening of the terminals (especially visible in a, c, f, s, C, G) and a return to the original subtle taper of the mainstrokes. (This taper, present in the metal typeface, was abandoned in the first conversion to digital format because of the staircasing it caused at low resolutions.) Roman text figures were also a part of the original foundry design, cut in steel a trial size but not offered for sale. These are revived in Optima Nova, and italic text figures have been added. The diacritics have been repositioned, and the width of some roman letters (D and W for instance) has noticeably changed. The italic is a new design, drawn by Kobayashi under Zapf's supervision. Optima

a

a



Nova italic slopes at 15° (compared with 11° in the original) and includes cursive forms of a, e, f, g and l. (See also page 264.)

# abcëfghijõp 123 AQ abcéfghijôp

Quadraat Sans D Fred Smeijers, a typographer based in Arnhem, Netherlands, is one of the few people trained as a type designer first and self-taught as a punchcutter second. FontShop International released the serifed version of his Quadraat in 1993 and the unserifed version in 1997. These are postmodern fonts, but they are strongly rooted in Dutch Baroque tradition. Quirkiness is a hallmark of the Baroque, and these are among the quirkier text faces I have ever used. They are also among the most rigorously designed. Quadraat Sans, like its serifed partner, is not pretty, nor does it need to be. It is intelligent instead. Text figures and small caps are standard equipment. (See also pp 244, 264.)

# AQ abcdefghijklmnopqrstuvwxyz

Romulus Sans H Jan van Krimpen's major project in the 1930s was the large Romulus family: serifed and unserifed roman, chancery italic, sloped roman, open titling, and Greek. Many designers have now embarked on similar projects, but in 1930, no one had done so. The most interesting part of the project was Romulus Sans, meant to challenge the new and revolutionary sans of Eric Gill (released in 1927). Four weights of the unserifed roman had been cut in a single size (12 pt) when Van Krimpen's employer, the Enschedé Foundry, halted the project. Romulus Sans is the basis for Frank Blokland's Haarlemmer Sans (page 258).

# abcëfghijop 123 AQ abcéfghijopy

Scala Sans D A fine neohumanist sanserif designed by Martin Majoor and issued by FontShop International, Berlin, in 1994. This is as fully humanized as any sanserif I know. It has a crisp and very legible italic and small caps. Text figures and the full array of standard ligatures are present on the basic font. In the italic, even the geometric letters at the tail of the Latin alphabet (v, w, y) are cursive in their sharp and bony way. The relationship between the serifed and unserifed forms of Scala is studied in detail on pp 262–63. (Scala Sans is the unserifed face used throughout this book. See also pp 246, 264.)

# abcëfghijõp 123 AQ abcéfghijôp

Seria Sans D Like its serifed counterpart, Martin Majoor's Seria Sans explores the common ground between Italian Renaissance structure and the world of Dutch reserve. The extenders are long and graceful, and the stroke weight subtly varied in fact though optically uniform. Seria Sans goes a long way toward fulfilling the dream of a pure sanserif type that began with Edward Johnston, Eric Gill and Jan van Krimpen. The italic, like its serifed cousin, slopes at only one degree and so shares many of its capitals with the roman. The family was issued by FontShop, Berlin, in 2000. (See also page 246.)

a

# abcëfghijõp 123 AQ *abcéfghijôpy* abcëfghijõp 123 AQ *abcéfghijôpy*

17 pt Original Syntax

17 pt "Linotype Syntax"

Syntax H/D This was the last sanserif text face commercially cast in metal, and in my opinion the best. Hans Eduard Meier designed the original version in Switzerland in the late 1960s, and it was cut and cast at the Stempel Foundry, Frankfurt, in 1969. The roman is a true neohumanist sanserif. Renaissance shapes that we are used to seeing in company with serifs and a modulated stroke are simply rendered in unserifed and (almost) unmodulated form. The italic, however, is a hybrid: primarily sloped roman. Close scrutiny reveals that in Syntax the roman is sloped too. The italic slopes at 12° and the roman at something close to half a degree. Half a degree, however, is enough to add perceptible vitality and motion to the forms. The stroke width changes very subtly, and the stroke ends are trimmed at a variety of angles. There are several weights, but as usual in neohumanist faces, the weights above semibold are severely distorted.

a

For text use, the original Syntax was hampered by the absence of text figures and small caps. Meier redrew the entire family in the late 1990s, adding these components, making very small adjustments to the roman and greater alterations to the italic. The new italic letterforms are narrower than the old, and three of them -f, j, y – are more cursive than before. Meier also added serifed and semiserifed versions of the face. These revisions add substantially to the range and versatility of the type, but the core of Meier's achievement remains exactly where it was: in the naked structure of the roman. (See also page 264.)

For a Native American variant of Syntax, see Dell Hymes, "Victoria Howard's 'Gitskux and His Older Brother'," in Brian Swann, ed., Smoothing the Ground. Essays on Native American Oral Literature (Berkeley, 1983). Martin Majoor's Scala and Scala Sans, shown here at 74 pt and 18 pt.

The serifed and unserifed forms of Scala are closely related and highly compatible, but there are many subtle differences as well. Taking the serifs away from an alphabet changes the relative widths of the characters. which changes the rhythm of the face. In Scala roman, for example, the unserifed caps are uniformly narrower than the serifed caps. The unserifed lower case is slightly narrower too. but most of the difference comes in the straightlegged letters h through n.

# aa hh cc

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1234567890·ABCDÉFG
1234567890·ABCDÉFG
ABCDEFGHIJKLMN
ABCDEFGHIJKLMN
OPQRSTUVWXYZ

# aa bb cc éé ff gg ññ ôô tt AAHH

abcdefghijklmnopqrstuvwxyz
abcdefghijklmnopqrstuvwxyz
1234567890
1234567890
ABCDEFGHIJKLMN
ABCDEFGHIJKLMN
OPQRSTUVWXYZ
OPQRSTUVWXYZ

In Scala italic, many lowercase letters are actually wider in the sans than in the serifed form, though the alphabet is narrower overall. And Scala Serif has a clearly modulated stroke, while Scala Sans is optically (not actually) monochrome. Thinned and tapered strokes occur in the sans and serifed forms alike (in the brow of roman a, the bar of roman e, and in the roman and italic g, for example) but the unserifed stroke is never thinned as much as the stroke with serifs.

### abcdefghijklmnopgrstuvwxyz FUTURA: Cursive characters: none abcdefghijklmnopgrstuvwxyz ORIGINAL FRUTIGER: Cursive characters: none O Italicization abcdefghijklmnopqrstuvwxyz **Ouotient** of Thirteen ORIGINAL OPTIMA: Cursive characters: none O Unserifed abcdefghijklmnopqrstuvwxyz 'Italics' ORIGINAL SYNTAX: Cursive characters: bcdpa 5 abcdefghijklmnopgrstuvwxyz GILL SANS: Cursive characters: abcdfpq 7 abcdefqhijklmnopgrstuvwxyz OPTIMA NOVA: Cursive characters: abdefglpqu 10 abcdefqhijklmnopgrstuvwxyz CASPARI: Cursive characters: abcdeghmnpq 11 abcdefahijklmnoparstuvwxyz Flora and Lucida Sans are shown FLORA: Cursive characters: abcdefghmnpgru 14 here at 17 pt, all other samples abcdefahijklmnopgrstuvwxyz at 18 pt. LUCIDA SANS: Cursive characters: abcdefghmnpqru 14 abcdefghijklmnopgrstuvwxyz SCALA SANS: Cursive characters: abcdefhmnpqtuvwy 16 abcdefghijklmnopgrstuvwxyz Triplex italic - the most broken LEGACY SANS: Cursive characters: abcdefghkmnpqrtuy 17 alphabet here - appears to get abcdefghijklmnopqrstuvwxyz the highest score Conclusion. QUADRAAT SANS: Cursive characters: abcdefghjmnpquvwy 17 brokenness can coexist with abcdefghijklmnopgrstuvwxyz cursiveness, though the two TRIPLEX: Cursive characters: abcdefghiklmnopgrtuvwxyz

24

are not the same.

Others are very italic indeed. This is one of the salient differences among sanserif types. We can measure this aspect of a typeface, in a crude way, by counting how many letters in the basic lower case have visibly cursive characteristics. This tells us nothing whatsoever about how *good* or *bad* the typeface is. It tells us, instead, something about the *kind* of goodness it may or may not possess.

The same analysis can be performed on serifed Italics too. But it is normal, in a serifed Italic of humanist form, for every letter in the lower case to be noticeably cursive. There are no purely sanserif Italics for which this seems to be true. (John Downer's Triplex Italic lower case is close to 100% cursive in this sense, despite its highly geometric form – but it is not 100% unserifed.)

The features that mark an unserifed letter as cursive are often very subtle. In a letter such as b, h, m, p or r, for example, it is usually only the shape of the bowl, or the angle and the height at which the curved strokes enter or leave the stem, that reveals its cursive form.

Prowling the Specimen Books

# $bb pp rr \cdot bb pp rr$

In Frutiger (on the left, above), the oblique forms of b, p and r are no more cursive than the upright. In Legacy Sans (on the right, above), the oblique forms are visibly italic. They differ from the corresponding roman forms in structure as well as in slope.

The g can be cursive or noncursive, no matter whether it has the binocular form that is usual in serifed roman faces or the monocular form that is typical both of chancery italics such as Trinité and of Realist sanserifs such as Helvetica.

$$ggggg\cdot gggg$$

In Syntax (1), the oblique g keeps its essentially uncursive roman form. In Legacy Sans (2), the italic g differs more from the roman: it develops at least a little bit of swing as well as a slope. The g from DTL Elzevir italic (3) – a Baroque serifed face, based on the work of Christoffel van Dijck – provides a comparison. The g of Frutiger (4) is monocular but not cursive, even when it slopes. In Gerard Daniëls's Caspari (5), the italic g is monocular and cursive, like the g in Méridien italic (6).

Blackletters

The first types cut in Europe, including all those used by Johann Gutenberg, were blackletters. Scripts and printing types of this kind were once used throughout Europe – in England, France, Hungary, Poland, Portugal, the Netherlands and Spain, as well as Germany – and some species thrived even in Italy. They are the typographic counterpart of the Gothic style in architecture, and like Gothic architecture, they are a prominent part of the European heritage, though they flourished longer and more vigorously in Germany than anywhere else.

## de heeft hp ons gheuandet die vten hoghen opgegaen is Inlichte here den ghenë die indupsternisse sittë eñ in die scheme des doots. om te lep dë

A 14-point textura cut by Henric Pieterszoon Lettersnider, probably at Antwerp in 1492. (Matrices for this font – likely the oldest set of matrices in existence – are now in the Enschedé Museum in Haarlem.)

Blackletter scripts, like roman scripts, exist in endless variety. Blackletter types are somewhat simpler, and not all of them need concern us here. But it is worth noting the presence of four major families: textura, fraktur, bastarda and rotunda. (Another variety of blackletter often listed in type catalogues is Schwabacher. This is bastarda by its domestic German name.) None of these families is confined to a particular historical period. All four of them have survived, like roman and italic, through many historical variations. Their differences are many and complex, but they can usually be distinguished by reference to the lowercase o alone. Though it is written with only two penstrokes, the o in a textura looks essentially hexagonal. In a fraktur, it is normally flat on the left side, curved on the right. In a bastarda, it is normally pointed at top and bottom and belled on both sides. In a rotunda, it is essentially oval or round.









Typical lowercase forms in textura, fraktur, bastarda and rotunda

Blackletters can be used in many contexts for emphasis or contrast – even in a world devoted to roman and italic – and need not be confined to the mastheads of newspapers or the titles of religious tracts. Type designers have also not abandoned them. Some excellent blackletters have been drawn in the twentieth century – by German artists such as Rudolf Koch and by the American Frederic Goudy.

# AO ábçdèfghijklmñöpqrstûvwxyz fs

Clairvaux D The blackletter of the White Monks. The Cistercian abbey of Clairvaux, about half way from Paris to Basel, was founded by St Bernard in 1115 and thrived throughout the twelfth century. The typeface of the same name, designed by Herbert Maring and issued by Linotype in 1990, has much of the simplicity espoused by the old Cistercian order. It is also closer than any other bastarda to the forms of the Caroline minuscule, and thus more legible than most to modern eyes.

# AO ábçdèfghijklmñöpqrstûvwxyz ß

Duc de Berry D A light French bastarda, designed by Gottfried Pott, issued in digital form by Linotype in 1991. Jean de France, the Duke of Berry (1340–1416) would, I think, have found these letterforms familiar, but they are not based on the script in any of the lavish Books of Hours he once owned.

# AO ábedefghijklműöpgrítűvwxyz f

Fette Fraktur H This heavy, Romantic fraktur was designed by Johann Christian Bauer and issued by his foundry at Frankfurt about 1850. It provides strong evidence that the Victorian 'fat face' is inherently more congenial to blackletter than to roman.

# A 🖸 ábçdèfghíjklmñöpqrstûvwxyz f

Goudy Text M Designed by Frederic Goudy and issued by Monotype in 1928. This is a narrow, smooth, lightly ornamented textura, relatively legible in the upper as well as the lower case. There is a second set of capitals, known as Lombardic caps. In machine form and digital form alike, the type is poorly fitted, but it is worth the work of salvage.

# A O abcdefghíjklmnopqrøtuvwxyz

Goudy Thirty M This was one of Frederic Goudy's last typefaces, deliberately conceived as his memorial to himself. ('Thirty' is, of course, journalists' code for 'end of story.') It is a light and simple rotunda, designed in 1942, issued by Lanston Monotype in 1948 and now available from the Lanston Type Co. in digital form. There are two versions, differing in the forms of *a*, *s*, *w* and several of the capitals.

Blackletters

# a O abedefghijklimnopgrestuwwryz

Rhapsodie H This is an energetic, legible Schwabacher (German bastarda) designed by Ilse Schüle and issued by Ludwig & Mayer, Frankfurt, in 1951. There is an alternate set of ornamental capitals. I have not found a digital version of the face.

# A O ábcdefghíjklmñőpqrstûvwryz ß



San Marco D Designed by Karlgeorg Hoefer and issued in digital form by Linotype in 1991. This is the first digital blackletter inspired by the rotundas cut at Venice in the 1470s by Nicolas Jenson. San Marco too is a rotunda – the genus of blackletter most closely connected to Italy and structurally closest to roman forms. It is named for the round-vaulted cathedral of San Marco, at the ceremonial center of Jenson's city. (See also page 105.)

# A abcdefghijklmnopgrfstuvwxyz

Trump Deutsch H Designed by Georg Trump and issued in metal by the Berthold Foundry in 1936. This is a dark, wide, concave, unornamented and energetic textura. Both upper and lower case are open and easily legible forms. To the best of my knowledge, it has never yet been digitized.

# 21 O ábçdefghíjklmnőparstûvwxyz f



Wilhelm Klingspor Schrift H Rudolf Koch completed this narrow, ornamental textura in 1925, naming it in honor of the recently deceased co-owner of the Klingspor Bros. Foundry in Offenbach, where Koch was chief designer. Not all the alternate glyphs in the handsome metal versions have been digitized.

Uncial letters were widely used by European scribes from the fourth through the ninth century AD, both for Latin and for Greek, but they had vanished from common use in the time of Gutenberg. Uncials were not cut into type until the nineteenth century, and then only for scholarly or antiquarian purposes. In the twentieth century, however, many designers – Sjoerd de Roos, William Addison Dwiggins, Frederic Goudy, Oldřich Menhart, Karlgeorg Hoefer and Günter Gerhard Lange, among others – took an interest in uncial forms, and one artist and printer, Victor Hammer, devoted his typographic life to them.

It is often said that uncial (from Latin uncia) means 'inch.' The two words are indeed related, but a better translation of uncial is simply 'small measure' or 'small standard.'

Historically, uncials are unicameral – they have only one case, as all European alphabets did until the late Middle Ages – but not all recent uncials are likewise. Early uncials, like recent ones, are sometimes serifed, sometimes not, and may be modulated or monochrome. They are now used chiefly for display, but some are quiet enough for extended texts.

# AQ 123 ábçðèfghíjklmñôp qrstűvwxyz 123 ogjo 456

American Uncial H This is the fourth type Victor Hammer designed, the second for which he cut the punches, and the first he produced after fleeing to the USA from Austria in 1939. All Hammer's types are uncials. Only two – this one and its predecessor Pindar – are bicameral. American Uncial was cast privately in Chicago in 1945, then commercially by Klingspor and marketed in Europe as Neue Hammer Unziale. Most digital types sold as 'American Uncial' are actually copies of a different face: a unicameral uncial called Samson, which Hammer designed in Italy in the 1920s. Digital versions of the real American Uncial are sold, like their metal forebears, under the name Neue Hammer Unziale.



# ÁBÇDÈFGÞYKLMÑÔP GRSTÜVWXYZ 123 ÆŒÞÕ

Omnia D Lightly serifed, round, cursive uncials with a large aperture and humanist axis, designed by Karlgeorg Hoefer. This is a unicameral face, issued by Linotype in 1991.



Script Types In ordinary usage, script is what is not type; it is writing: the mode of visual language used in public by calligraphers and in private by other literate humans, including typographers themselves. When script hardens, breaks and starts to look like type, we often call it printing – yet printing is what printers do with type, even type that looks like script, which we are likely to call script type. An innocent observer might conclude that English is an undernourished language, whose speakers cannot generate a new word even when they need one.

At the root of this confusion is a portion of good sense. Type is writing edited or imitated, translated or paraphrased, honored or mocked – but writing itself is a fluid and linear version of more disconnected epigraphic signs. The difference between 'type' and 'script' reiterates the difference between *glyphic* and *graphic*, or carved and written, characters. That difference was established at least 1500 years before the printing press was born.

The craving to mate roman with italic appears to be an effort to have type and script, or glyphic and graphic, at once. This explains in part why it is difficult to classify a typeface like Poetica. Is it a script, or is it a solitary (romanless) italic?

Scripts have thrived as foundry type, phototype and digital type, and several fine designers – Imre Reiner, for example – have focused as exclusively on scripts as others have on romans. But scripts had an importance in the world of commercial letterpress that they lack in the world of two-dimensional printing. Handwritten originals are expensive to photoengrave for reproduction on the letterpress. Specially commissioned calligraphy is easy to include, by way of scanning or photography, in artwork destined for the offset press. The best script to supplement a typographic page is now therefore more likely to be custom made.

Dozens of excellent script types are available. They include Arthur Baker's Marigold and Visigoth, Roger Excoffon's Choc and Mistral, Karlgeorg Hoefer's Salto and Saltino, Günter Gerhard Lange's Derby and El Greco, Michael Neugebauer's Squire, Friedrich Peter's Magnificat and Vivaldi, Imre Reiner's Matura and Pepita, Robert Slimbach's Caflisch and Sanvito, and Georg Trump's Jaguar and Palomba. I have chosen to illustrate here only a handful of the scripts that particularly interest me. Two of these – Eaglefeather and Tekton – are architectural scripts and could have been included just as easily among the text types. I have

On the early history of printed scripts, see Stanley Morison's essay "On Script Types," The Fleuron 4 (1921): 1-42. put them here instead for what they reveal about the process of transition from writing to printing, script to type, and script type to roman and italic.

# abcëfghijõp 123 ABDQ abcéfghijõp

Eaglefeather D This is a family of type created in 1994 by David Siegel and Carol Toriumi-Lawrence, based on some of the architectural lettering of Frank Lloyd Wright (1867–1959). Eaglefeather is issued in two forms, called formal and informal, but only the roman lower case actually differs. The two share one italic, one set of roman caps, small caps, figures and analphabetics. Eaglefeather Informal (the version shown) is actually two italics. The 'roman' is a crisp, unserifed italic with no slope. The 'italic' is the same set of letters with a slope of 10°. The series also includes small caps.



# AQ 123 ábçdèfghijklmñöporstûvwxyz AA EEE 4 \$ čdį fpgh ik vz

Ex Ponto D This rough-edged, lyrical script was designed by Jovica Veljović and issued by Adobe in three weights in 1995. The design was completed in exile, and its name, Ex Ponto, alludes to the *Epistulae ex Ponto*, 'letters from the Black Sea,' written in exile before AD 13 by the Roman poet Ovid. The newer OpenType version of the face includes three sets of capitals and a wide assortment of variant letters and ligatures.



# AO abcdefghijklmnopgrstuunnyz

Legende H A wide, dark, disconnected script with a small eye but excellent legibility. It was designed by Ernst Schneidler and issued by the Bauer Foundry, Frankfurt, in 1937. This is one of the best modern exemplars of a class of Mannerist scripts inaugurated by Robert Granjon at Lyon in 1557. Typographers call them civilités.

# use of Granjon's script in an early French translation of one of Desiderius Erasmus's best-sellers, De civilitate morum puerilium libellus: 'A little book for children

about civilized

behavior.'

The name civilité

stems from the

# AQ 123 ábçdèfghijkmñöprstûwxyz

Ondine н This is a dark but open, lucid, disconnected pen script designed by Adrian Frutiger and originally issued by Deberny & Peignot, Paris, in 1953. It was one of Frutiger's earliest designs and

it remains his only script face. (An *ondine* is a sea-nymph, and Frutiger's Ondine is full of waves.)

## AQ ábçdèfghijklmñöpqrstûvwxyz

Present н A light, broad, disconnected brush script designed by Friedrich Sallwey and issued by the Stempel Foundry, Frankfurt, in 1974. In digital form, the family has been enlarged to include both regular and condensed versions in three weights.

# abcdëfghijõp 123 AQ abcéfghijõp

Tekton D Designed by David Siegel, based on the lettering of architect Frank Ching, and issued by Adobe in 1989. Multiple Master, Gx and OpenType versions followed. The latter include text figures and small caps. In modest sizes, Tekton is functionally a sanserif. At larger sizes, its serifs are visible as tiny beads. The 'italic' is an oblique. The original script can be seen in Ching's book Architectural Graphics (New York, 1975; 2nd ed. 1985), which is printed from handwritten pages. (The third edition of the book, published in 1996, is set in semicondensed digital Tekton.)

AQ 123 ábçdèfőghijklmñöpgirstúvwxyz AQ 123 ábçàdèfőghijklmñöpgirstúvwxyz AQ 654 ábçàdèfőgîhijklmñöpgirstúvwxyz AQ 456 ábçdèfoghijklmñöngirstúvwxyz

Zapfino D This calligraphic tour de force designed by Hermann Zapf was issued by Linotype in 1998 as a set of four alphabets with a separate font of supplementary ligatures. In 2004 an enlarged, OpenType version appeared under the name Zapfino Extra. That incarnation of the family includes small caps, additional alternates and swashes, and a darker version of one of the alphabets, known as Zapfino Forte. It is an exemplary marriage of artistic and technical ability. Effective use of such a type requires considerable patience and skill. It therefore makes a useful training ground for typographers and calligraphers alike. (See also page 190.)

# μηχόμεμόμ Τε λέαμλρομ διμοῦ καὶ **λύχ**μο

# Δράσαντι δ' αίχρα, δεινα τάπιτί μια σος τον Δεον, κου Δεος Ιωδο λόγ .

Three early Greek types. Above: The Complutensian Greek, a 16 pt orthotic font cut by Arnaldo Guillén de Brocar at Alcalá de Henares, near Madrid, in 1510. Center: The 10 pt cursive cut by Francesco Griffo, Venice, in 1502 [here shown at twice actual size]. Bottom: An 18 pt chancery Greek cut by Robert Granjon in the 1560s.

Prowling the Specimen Books

### 11.7 GREEKS

Greek type has a long and complex history peculiarly its own, yet closely entwined with the history of roman. The first full fonts of Greek were cut in Venice and Florence by Nicolas Jenson, Francesco Griffo and others who were simultaneously cutting the first roman and italic faces. Simon de Colines, Claude Garamond, Robert Granjon, Miklós Kis, Johann Fleischman and William Caslon cut good Greeks as well, and their type was widely used. Yet the first Greek book printed in Greece itself was the Mt Athos Psalter of 1759, and the first secular printing press in Greece was established only during the War of Independence, with help from Ambroise Firmin-Didot, in 1821.

Greek adaptations of popular roman faces – Baskerville, Caledonia, Helvetica, Times New Roman, Univers and others – have been issued by Linotype, Monotype and other firms, and are widely used in Greece. But there, as in much of Eastern Europe, the more lyrical forms of modernism have been slower to arrive. Even in the multinational world of classical studies, where Greek types that will harmonize with neohumanist romans are perennially needed, they are in very short supply.

Three important classes of Greek type have been with us since the fifteenth century. These are the *orthotic*, the *cursive*, and the *chancery script*. Orthotic Greek is analogous to roman in the Latin alphabet. It is, in other words, *not cursive*. The letters are relatively self-contained, usually upright, and may or may not have serifs. Cursive Greek type – which exists in both sloped and vertical forms – is analogous to italic. Chancery Greeks are merely elaborate forms of the cursive, but they attained in Greek a level

Orthotic is from the Greek word ὀρθός, meaning upright; cursive from the Latin currere, to run or to hurry; and chancery from the Latin cancelli, literally 'little crabs.' Cancelli came to be the Latin term for a lattice or grate, and then for the ornamental barrier that stood between officials and petitioners at court. It is in other words the bar to which lawyers are still called. Chancery scripts flourished where lawyers worked.



Polytonic Greeks are fonts with a full complement of Alexandrian diacritics. See page 295 for details. of typographic intricacy never yet approached by chancery italic type in the Latin alphabet.

The orthotic Greek types of the Renaissance resemble Renaissance romans yet differ from them too, in several interesting ways. The stroke is usually quite uniform in thickness, the stroke-ends are sharply rectangular, and the serifs, when present, are usually short, abrupt and unilateral. The geometric figures of triangle, circle and line are prominent in the underlying structure of these faces, though not to the exclusion of more complex curves. This is the oldest form of Greek type, first seen in the partial alphabets cut by Peter Schoeffer the Elder at Mainz and by Konrad Sweynheym at Subiaco, near Rome, in 1465. It is also the style of the first full-fledged and polytonic Greek type, cut by Nicolas Jenson at Venice in 1471.

The finest early example of orthotic Greek, in the opinion of many historians, is the Complutensian Greek of Arnaldo Guillén de Brocar, cut in Spain in 1510. A few years after that, orthotic Greeks completely disappeared. They were not revived until the end of the nineteenth century. The most widely used modern version is the New Hellenic type designed by Victor Scholderer in London in 1927.

The first cursive Greek font was cut by an unidentified craftsman at Vicenza, west of Venice, in 1475. The second, cut at Venice by Francesco Griffo, did not appear for another twenty years – and it was not a simple cursive like the anonymous font from Vicenza but an elaborate chancery script. Griffo cut a simple Greek cursive in 1502, but chancery Greeks remained the fashion throughout Europe for the next two hundred years.

A simple Greek cursive can be turned to a chancery script by the addition of ligatures, and a chancery script converted to simple cursive by leaving the ligatures out. But the battery of ligatures involved often runs to several hundred, and sometimes to more than a thousand.



Chancery Greeks were cut by many artists from Garamond to Caslon, but Neoclassical and Romantic designers – including Baskerville, Bodoni, Alexander Wilson and Ambroise Firmin-Didot – all returned to simpler cursive forms. Firmin-Didot's Greek is still in frequent use, in France and Greece alike, but in the English-speaking world the cursive Greek most often seen is the one designed in 1806 by Richard Porson.

Neohumanist Greeks, such as Jan van Krimpen's Antigone, Hermann Zapf's Heraklit and Palatino Greek, and Robert Slimbach's Minion Greek, have opened a new chapter in the history of the Greek alphabet, bringing the humanist structure of Renaissance roman and italic into the Greek lower case. Ironically, these types have evolved just as the custodians of European culture were abandoning the study of the classics.

Greek, like Latin, evolved into bicameral form in the late Middle Ages. The upper case in the two alphabets shares the same heritage, and more than half the uppercase forms remain identical. (The same is true of Greek and Latin uncials.) But the Greek lower case has evolved along a different path. There is a quiet and formal Greek hand, not dissimilar in spirit to the roman lower case, but the usual Greek minuscule is cursive. As a consequence, most Greek faces are like Renaissance italics: upright, formal capitals married to a flowing, often sloping, lower case. No real supporting face has developed in the Greek typographic tradition: no face that augments and contrasts with the primary alphabet as italic does with roman.

That of course is subject to change. Several twentieth-century designers have added bold and inclined variants to their Greeks, in imitation of Latin models, and a shift in usage may be underway. But several of the faces shown here are solitary designs. They are meant to be used alone or as supplementary faces themselves, for setting Greek intermixed with roman.

# άβγδεζηθικλμνξοπρσςτυφχψω άβγδεζηθικλμνξοπρσςτυφχψω

Albertina D Chris Brand designed this Greek in the 1960s, together with Albertina Latin and Cyrillic. Initially only the Latin face was produced. The Greek was issued only in 2004, by DTL. It exists in both upright and cursive form – but for now at least, only in a monotonic version. (See also pp 213, 280.)

# αβγδεζηθικλμνξοπροςτυφχψω


Antigone H Designed by Jan van Krimpen and issued by Enschedé in 1927. This is a delicately sculpted neohumanist Greek, intended for the setting of lyric poetry. It was cut specifically to match the same designer's Lutetia roman and italic, but it composes well with his other Latin faces, including Romanée and Spectrum. There is no digital version of Antigone.

Prowling the Specimen Books





# ἄβγδεζῆθικλμνξοπρσςτυφχψω



I do not know which founder cut the first commercial adaptation of Bodoni's Greeks, but it was in use in Germany in the 1850s. Several German founders copied the initial trade version, and it served as the standard Greek type in German books for over a hundred years. The font shown here is a new digital interpretation, made in 1993 for the Greek Font Society, Athens, by Takis Katsoulides. It is Romantic in architecture but has been spared the exaggerated contrast found in many recent romans and italics that are advertised as Bodonis. As issued by GFS, the family includes both sloped and upright forms, a bold, and Greek small caps. (See also page 113.)

# ἄβγδεζῆθικλμνξοπρσςτυφχψω Α Β Γ Δ Ε Ζ Η Θ Κ Λ Μ Ξ

Didot H More than one typographer has wondered why Didot Greeks look so little like the Didot romans. The reason is that the original versions were cut in different eras by father and son, and they embody the two punchcutters' different relationships to two distinct typographic traditions. The original Didot Greeks are the work of Ambroise Firmin-Didot, whose father, Firmin Didot, cut the best-known Didot romans and italics. The romans, cut in the thick of the French Revolution, have a strictly rationalist structure. They have left every vestige of Baroque variety behind.

Didot Greeks have a lefthandedness learned from the Mannerist and Baroque Greeks of Granjon, Jannon, Kis, Caslon and Fleischman. The capitals are openly schizophrenic, with adnate, Neoclassical serifs on the thin strokes and abrupt, Romantic serifs on the thick ones. The digital version shown here was made for the Greek Font Society, Athens, by Takis Katsoulides in 1993. (See also page 113.)





### ΑΒΓΔΕΙΒΦΟΙΚΛΜΥΞΟΟΓΡ€CΤVΦΧ↓Ω

Diogenes D An alphabet of pure archaic capitals, designed by Christopher Stinehour, Berkeley, in 1996. The face was commissioned by the printer Peter Rutledge Koch for use in an edition of the fragments of Parmenides. It is based on inscriptions of the fifth century BC from the old Greek city of Phokaia and its colony Elea, on the coast of Italy, where Parmenides was born. A slightly darker book weight (shown above) was added in 2003.



# ἄβγδεζῆθικλμνξοπρσςτυφχψω

Gill Sans M This face was designed in the 1950s by Monotype draftsmen, not by Eric Gill himself, as a companion for the Gill Sans roman. Since the roman had also been modified from Gill's original drawings, Gill Sans Greek is twice removed from the artist for whom it is named. It is nevertheless a clean and usable design. The lower case, like its Latin counterpart, includes a few residual serifs. There are several weights, both upright and oblique, but no book weight has been commercially issued.



# αβγδεζηθικλμνξοποσςτυφχψω

Heraklit H/M This face was designed by Hermann Zapf and issued both by Stempel and by Linotype in 1954. It is a neohumanist text Greek, intended to be used with the same designer's Palatino and Aldus. There is a companion Greek titling face called Phidias: the Greek counterpart to Zapf's Michelangelo. Palatino Linotype Greek (page 278) is Heraklit's digital successor.

# ἄβγδεζῆθικλμνξοπρσςτυφχψω

New Hellenic M Designed by Victor Scholderer and issued by Monotype in 1927. This is an orthotic Greek, reasserting the tradition of Nicolas Jenson, Antonio Miscomini and Arnaldo Guillén de Brocar, instead of the cursive and chancery Greek tradition of Francesco Griffo, Simon de Colines and Claude Garamond. It is open, erect, gracious and stable, with minimal modulation of the stroke and minimal serifs. There are well-made variant forms of several letters. A digital version of the face, shown here, was made in 1993 for the Greek Font Society by Takis Katsoulides. (This is sold as Neo rather than New Hellenic. See also pp 108, 112.)

The digital New Hellenic shown here has been modified as follows: side bearings of several analphabetics have been revised, a kerning table has been added, all the caps and five alternate glyphs  $(2, 3, \epsilon,$  $C, \omega$ ) have been resized.

# ἄβγδεζῆθικλμνξοποσςτυφχψω ἄβγδεζῆθικλμνξοπρσςτυφχψω

Palatino D As part of the transformation of Palatino into the pan-European 'Palatino Linotype,' Hermann Zapf created an upright and italic Greek in two weights, based on his earlier Heraklit. The full range of monotonic and polytonic characters is included. The digitization, however, was done at Microsoft, not at Linotype. While the letterforms are lovely, kerning is nonexistent, and the diacritics are so pale they vanish at text sizes. When the diacritics are strengthened (as in the first of the two specimen lines above), this Greek mates handsomely not just with Palatino but with many Latin faces. (See also pp 239, 281.)

# άβγδεζηθικλμνξοπρσςτυφχψω

Porson H Designed by the English classicist Richard Porson for Cambridge University and cut by Richard Austin beginning in 1806. The face was soon copied by several founders, and in 1912 an edited version was issued by Monotype. This has been the standard Greek face for the Oxford Classical Texts for over a century. It is a calm yet energetic face of Neoclassical design that composes well with many romans. During its long and fruitful career, the Porson lower case has been fitted with several different series of caps, none of which quite matches Porson's original design. The digital version of the face shown here and elsewhere in this book is the one produced in 1996 by George Matthiopoulos for the Greek Font Society, Athens – edited by reducing the size of the caps some 10%. (See also pp 109, 113.)

# άβγδεζῆθικλμνξοπροςτυφχ ψω αί γὰ γς εῖ & πε & τλ τ χω καὶ

Wilson D Greek fonts this well-made have always been rare, though Greeks which aimed at this result were once common. At present, this is the only digital Greek of its kind. It was made by Matthew Carter in 1995, based on the Greek fonts of the eighteenth-century master punchcutter, physician and astronomer Alexander Wilson of Glasgow. The face is rich with alternate forms and ligatures, a few of which are shown here.





The Cyrillic alphabet was adapted from Greek in the ninth century, and the first Cyrillic type was cut in Kraków by Ludolf Borchtorp in 1490. An improved Cyrillic was cut in Prague in 1517 by the Belarusian Frantsysk Skaryna, but the first Cyrillic cursive was not cut until 1583. The subsequent history of Cyrillic is largely parallel to that of Latin type, with the important exception that there is no humanist or Renaissance phase, and the intimate linkage between upright and italic which is now taken for granted in Western European typography did not develop in the context of Cyrillic. Only in the eighteenth century were upright and cursive forms paired. Slavic type, like Slavic literature, passed more or less directly from the medieval to the late Baroque. For this and for other, more overtly political reasons, the neohumanist movement in type design also came late to Cyrillic letters.

Prowling the Specimen Books

With minor variations, Cyrillic is now used by close to half a billion people, writing in Russian, Ukrainian, Belarusian, Bulgarian, Macedonian and other Slavic languages. In Serbia and Montenegro it is used for Serbo-Croatian, and in Moldova for Romanian. It is also now the common alphabet for a host of unrelated languages, from Abkhaz to Uzbek, spoken and written across what once was the Soviet Union.

Several excellent type designers have worked in Russia and the neighboring republics in the past century. The list includes Vadim Lazurski from Odessa, Galina Bannikova from Sarapul, Anatoli Shchukin from Moscow, Pavel Kuzanyan and Solomon Telingater from Tbilisi. Few of their designs have been available in the West; many, in fact, have yet to be produced in type at all.

Linotype, Monotype, ParaType and other foundries have issued Cyrillic versions of Baskerville, Bodoni, Caslon, Charter, Frutiger, Futura, Gill Sans, Helvetica, Jannon, Kabel, Officina, Plantin, Syntax, Times, Univers and other Latin faces. Nearly all these have their uses, including setting multilingual texts, where matching Latin and Cyrillic fonts may be required. But not all of these derivative Cyrillics can claim to be distinguished designs, and not all are suited to running text.

Cyrillic text fonts are increasingly constructed with the same variations as the better Latin text types: roman, italic and small caps, with text as well as titling figures, often in several weights. Roman type is known in Russian as прямой шрифт (pryamoi shrift, 'upright type'). Italic is called курсив (kursiv) or

Text figures are available for all Cyrillic faces shown on the following pages.

курсивный шрифт (*kursivnyi shrift*). Unserifed Cyrillics, like Latin sanserifs, are often made with an oblique (наклонный шрифт = *naklonnyi shrift*, 'sloped type') in place of an italic.

# абвгдежофщ АЖО абвгдежофщ

Albertina D Like Albertina Greek, this was designed by Chris Brand in the 1960s but not produced until 2004. It mates perfectly with its Greek and Latin companions. (See also pp 213, 275.)

# абвгдежофщ АЖО абвгдежофщ

Baskerville M Baskerville himself did not design a Cyrillic, but Cyrillic adaptations of his roman and italic have been made by several foundries. The best of these is Monotype's, designed in 1930 by the young Harry Carter, who would soon grow into a great type historian. For some Russian texts of the eighteenth century and later, a face of Western origin and French Enlightenment spirit is highly appropriate. Baskerville Cyrillic is one obvious choice for this purpose – especially for bilingual publications, if Baskerville happens to suit the translation. (See also page 216.)

# абвгдежофи АЖО абвгдежофи

Lazurski H This is a neohumanist Cyrillic designed by the Russian book designer Vadim Lazurski. It was produced in 1962 in two forms, under two names. In Russia it was issued for machine setting as Garnitura Lazurskogo. The foundry version, edited by Giovanni Mardersteig and cut under his direction by Ruggiero Olivieri, is known as Pushkin. In that form, it has only been used at Mardersteig's press, the Officina Bodoni in Verona. Vladimir Yefimov adapted it for photosetting in 1984, adding a bold weight. Both the Cyrillic and its Latin companion were issued in digital form by ParaGraph, Moscow, in 1991. The requisite text figures were added in 1997. (See also page 110.)

# абвгдежофщ АЖО абвгдежофщ

Minion D A neohumanist Cyrillic designed by Robert Slimbach as a companion to his Minion Latin. It was first issued by Adobe in 1992, and re-issued in pan-European OpenType format in 2000. (See also pp 107, 237.)





# абвгдежофщ АЖО абвгдежофщ

Palatino D Palatino Cyrillic, like Palatino Greek, was designed by Hermann Zapf in the 1990s as part of the transformation of Palatino into 'Palatino Linotype.' It is particularly useful for multilingual work. (See also pp 239, 278.)



# абвгдежофщ АЖО абвгдежофщ

Quadraat D Most Cyrillic adaptations of Latin faces have an air of superficiality about them. Fred Smeijers's Quadraat Cyrillic is a wonderful exception to that rule. (See also page 244.)



# абвгдежофщ АЖО абвгдежофщ

Warnock D Warnock, like Minion, is a pan-European family of type – Latin, Greek and Cyrillic – designed by Robert Slimbach and issued by Adobe in OpenType format in 2000. It is spikier than Minion, and more artificial (plainly drawn instead of written). It is also steeper (the italic slopes at 15° instead of 12°). The Cyrillic seems to me the most successful branch of the family.



### 11.9 INSCRIPTIONAL & CALLIGRAPHIC CAPITALS

Every text begins at least once. Most stop and start again repeatedly before they run their course. These beginnings – of sentences, paragraphs, chapters or sections – are the doors and windows of the text. European scribes began to mark the major ones with large, sometimes ornate capital letters – versals – even before the Latin alphabet developed a lower case.

In many early printed books, space is left for such initials to be painted in by hand. Printers also began to print them, in multiple colors, as early as 1459. Many fine alphabets of capitals have sprung from this tradition: fonts of type designed for setting titles or short texts, or to be used one letter at a time. Some of these alphabets – Carol Twombly's Lithos and Gudrun Zapf-von Hesse's Smaragd, for example – are *glyphic* or inscriptional; others are purely calligraphic.

Because they are meant for use with other fonts of text size, many fonts of inscriptional initials are inlines: the interior of the stroke has been carved away to lighten the face. Jan van Krimpen's Lutetia and Romulus Open Capitals, for example, were made by hollowing out the caps of these text faces. But Cristal, designed by Rémy Peignot, and Castellar, designed by John Peters, were created from the start as inline types and exist in no other form.

The capitals from any text font can, of course, be enlarged for use as versals, but the proportions often suffer as a result, and specially proportioned titling capitals exist for only a few text faces (Giovanni Mardersteig's Dante and John Hudson's Manticore are examples). From time to time, however, the capitals from a bicameral text or titling face develop a separate life of their own. This has occurred, for example, with Berthold Wolpe's Albertus, Carl Dair's Cartier, Herb Lubalin's Avant Garde, and with Georg Trump's Codex and Delphin. The faces listed below were all designed specifically as capitals for titling, not text.

Samples of many of these faces are shown on page 287.

AEGQW

Ariadne H Calligraphic initials designed by Gudrun Zapf-von Hesse and issued by the Stempel Foundry, Frankfurt, in 1954. These initials combine especially well at text size with the same designer's Diotima and at larger sizes with Palatino and Aldus.

# ABCDXYZ

Augustea H/M Sharply serifed, formal inscriptional capitals, designed by Aldo Novarese and Alessandro Butti, issued in metal by the Nebiolo Foundry, Torino, in 1951. There is an inline version, originally sold as Augustea Filettata, now digitized as Augustea Open. A lower case was also later added to the capitals. The result is known as Augustea Nova. (See also page 287.)

# ABCDEFGHIJKLM Nopqrstuvwxyz

Castellar M Inline capitals, asymmetrically inscribed, so that the hollowed strokes are light on the left, dark on the right. The face was designed by John Peters and issued by Monotype in 1957. (See also pp 64, 160, 287.)

# ABCDEFGHIJKLM Nopqrstuvwxyz

Charlemagne D These lighthearted Caroline capitals, based on the Carolingian titling scripts and versals of the ninth and tenth centuries, were designed by Carol Twombly and issued in digital form by Adobe in 1989. The newer OpenType version of the face includes a pan-European Latin character set. (See also pp 120, 287.)

Prowling the Specimen Books

# ABCDEFGHIJKLM AKMNRUVXYZ NOPQRSTUVWXYZ

Herculanum D Designed by Adrian Frutiger and issued in digital form by Linotype in 1990. There are many variant letters. Herculanum was a Roman city near present-day Naples, buried, like Pompeii, by the eruption of Vesuvius in AD 79. The face that bears its name is based on written and painted Roman letters of the first and second centuries AD. These unofficial and informal Roman inscriptions have been a source of inspiration to Frutiger for half a century. The capitals of his Ondine (page 271), designed in the early 1950s, derive from them as well. (See also page 118.)

# ABCDEFGHIJKLM NOPQRSTUVWXYZ ΓΔΘΛΞΠΣΥΥΦΨΩ ĄČĔĘĢİĽŐŞŰŮŹ

Lithos D Unserifed capitals with a large aperture and cheerful form, based on early Greek inscriptional letters, designed by Carol Twombly and issued by Adobe in several weights. There are many subtle modulations in the stroke. The new OpenType version of the face includes pan-European Latin and Greek. An important precursor of this face is Robert Foster's now neglected Pericles, issued by ATF in 1934. (See also page 118.)

# ABBAGGIIL&LLQŒRETTT! ABCDEFGHIJKLM NOPQRSTUVWXYZ YYLAMECŸTTUH&C

Inscriptional and Calligraphic Capitals

Mantinia D This is a complex face based on letterforms found in the work of the painter Andrea Mantegna (1431–1506). Andrea del Castagno, Fra Angelico and other fifteenth-century artists lavished as much care on their letterforms as on their human figures, but no Renaissance painter took the alphabet more seriously than Mantegna. The type that honors him was designed by Matthew Carter and issued by Carter & Cone in 1992.

# A B C D B C D E

Michelangelo and Sistina H Two sets of serifed capitals designed by Hermann Zapf as complements to Palatino and Aldus. The original versions of both – the light, athletic Michelangelo and the darker, more ecclesiastical Sistina – were cut by August Rosenberger and issued by the Stempel Foundry in 1950–51. There is a third member of the series, Phidias, a Greek counterpart to Michelangelo. (See also page 287.)

# ABCDPQR

Monument H Open inline capitals, designed by Oldřich Menhart and cast in 1950 by the Grafotechna Foundry, Prague. The imperial stillness typical of Roman inscriptional letters is transformed to a kind of stately folk dance under Menhart's hand.

# ABCDEFGHIJKLMN OPQRSTUVWXYZ

Neuland н Dark, rugged, unserifed roman capitals, designed and cut by Rudolf Koch and issued in metal by the Klingspor Foundry,

Offenbach, in 1923. Koch cut the original punches freehand, without pattern drawings. Each size in the foundry version therefore has many idiosyncracies of its own. These subtleties are lost in all the existing digital versions. (See also page 287.)



Prowling the Specimen Books

Requiem Titling D The Requiem family, designed by Jonathan Hoefler (1999), includes not only two display weights of roman and italic but also two weights of banner letters, augmented by floriated terminals, spacers and connectors. (See also page 244.)

# ABCDEFGHIJKLM ILYTLYTIYLTITLYIR NOPQRSTUVWXYZ

Rialto Titling D This set of elegant, light calligraphic capitals is part of the Rialto family, designed by Giovanni De Faccio and Lui Karner, issued in 1999. (See also page 244.)

# AB(DEFGHIJKLM NOPQRSTVVWXYZ

Inscriptional and Calligraphic Capitals Rusticana D This is one of a group of three faces designed by Adrian Frutiger based on the more populist, less imperial varieties of Roman inscriptions. The other members of the family are Herculanum and Pompeijana. Rusticana owes its form to Roman inscriptional lettering of the fourth and fifth centuries AD. (See also page 118.)

# ABCDEFGHIJKLM NOPQRSTUVWXYZ

Smaragd D A set of light but powerful inline capitals designed by Gudrun Zapf-von Hesse and issued by the Stempel Foundry in 1952. Smaragd means emerald: the substance on which the secrets of Hermes Trismegistos – the Greek incarnation of Thoth, the inventor of writing – were reputedly engraved.

# AABCDEFGHIJKLMM NOPQRSTUVWXXYZ

Sophia D Designed by Matthew Carter and issued by Carter & Cone in 1993. This complex face with its many variant glyphs is based primarily on the alphabet found on an inscribed cross, made in Constantinople in the mid sixth century. The cross was a gift to the Bishop of Rome from the Byzantine Emperor Justin II and his wife (later also his regent) the Empress Sophia. (See also pp 186–87.)

# ABCDEFGHIJKLM Nopqrstuvwxyz

Trajan D Serifed capitals, based on the inscription at the base of Trajan's Column, Rome, carved at the beginning of the second century AD. The face was drawn by Carol Twombly and issued in digital form by Adobe. In its OpenType version, it includes the full pan-European Latin character set. (See also page 120.)

M M

From left to right

Albertus Augustea Avant Garde

M

M

M

Cartier Castellar Charlemagne





M

Codex Cristal Delphin







Michelangelo Monument Neuland





M

Pericles Romulus Open Sistina

### APPENDIX A: THE WORKING ALPHABET

\_\_\_\_\_\_

A census taken today will be inaccurate tomorrow, but in its travels through the world, the Latin alphabet has evolved to a working set of over 600 characters (counting caps and lower case), reinforced by about 500 more of its closest allies, Greek and Cyrillic. A few of the characters listed below are tied to a single language. Most are used by dozens or hundreds of languages. Three examples at most are given for each.

### **Additional Latin Letters**

### Examples of usage

All italicized terms in this list are discussed in appendix B, page 301.

70		r
æÆ	aesc	Faroese; Icelandic
	hooktop в	Fulfulde; Hausa; Kpelle
ðĐ		Faroese; Icelandic
đĐ		Serbo-Croatian; Vietnamese
	hooktop D	Fulfulde; Hausa
фĐ	hooktail D	Ewe
<b>G</b> \E <b>6</b>	schwa	Azeri; Kanuri; Lushootseed
3 3	African epsilon	Dinka; Ewe; Twi
f F	hooktail F	Ewe
χY	African gamma	Ewe; Kpelle
	barred н	Maltese
1	dotless i	Azeri; Turkish
i I	barred i	Micmac; Mixtec; Sahaptin
ƙΚ	hooktop ĸ	Hausa
κК'	kra	Old Greenlandic
łŁ	barred L	Heiltsuk; Navajo; Polish
łŁ	double-barred L	Kutenai
χ	blam (barred lambda)	Lillooet; Nuxalk; Okanagan
ŋŊ	eng	Ewe; Northern Saami; Wolof
øØ	slashed 0	Danish; Faroese; Norwegian
σO	horned o	Vietnamese
οО	open o	Atsina; Ewe; Twi
œŒ	_	French; archaic English
ſ	long s	Irish; archaic pan-European
ß	eszett	German; recent English
þÞ	thorn	Anglo-Saxon; Icelandic
-	barred т	Northern Saami
	horned U	Vietnamese
	<del></del>	

ν V curly v Ewe wynn early English y Y hooktop y Fulfulde yogh Anglo-Saxon; early English 5 Skolt 3 3 ezh

### Inflected Latin Letters Examples of usage The Working

		a-acute	Czech; Icelandic; Spanish
à	À	a-grave	Dogrib; French; Italian
ä	À	a-double grave	Serbo-Croatian poetics
â	Â	a-circumflex	Cree; French; Welsh
ă	Ă	a-caron / a-wedge	romanized Mandarin
ä	Ä	a-umlaut	Estonian; Finnish; German
å	Å	a-ring / round a	Arikara; Cheyenne; Swedish
		a-macron / long a	Cornish; Latvian; Maori
		a-breve / short a	Latin; Romanian; Vietnamese
â	Â	a-arch	Serbo-Croatian poetics
		a-tilde	Portuguese; Vietnamese
å	Å	a-hoi	Vietnamese
ã	Ã	a-circumflex-acute	Vietnamese
â	Â	a-circumflex-grave	Vietnamese
ã	Ã	a-circumflex-tilde	Vietnamese
â	Â	a-circumflex-hoi	Vietnamese
â	Â	a-circumflex-underdot a-breve-acute	Vietnamese
			Vietnamese
		a-breve-grave	Vietnamese
		a-breve-tilde	Vietnamese
		a-breve-hoi	Vietnamese
ă	Ă	a-breve-underdot a-umlaut-acute	Vietnamese
á	Ä	a-umlaut-acute	Tutchone
à	Ä	a-umlaut-grave	Tutchone
ā	Ä	a-umlaut-macron	Tutchone
ạ	Ą	a-underdot / a-nang	Twi; Vietnamese
<u>a</u>	<u>A</u>	a-underscore	Kwakwala; Tsimshian
	Á		Kwakwala
ą	Ą	a-ogonek / tailed a	Polish; Lithuanian; Navajo
á	Ą	a-acute-ogonek	Navajo; Western Apache
ą	À	a-ogonek / tailed a a-acute-ogonek a-grave-ogonek	Dogrib; Gwichin; Sekani
ǽ	Æ	aesc-acute	Old Icelandic; linguistics

æ Æ aesc-macron / long aesc Anglo-Saxon; Old Norse

Alphabet

	b B	b-overdot / dotted b	Old Gaelic
Inflected Latin Letters	<ul><li>ĉ Ĉ</li><li>č Č</li><li>ċ Ċ</li><li>ċ Č</li><li>ċ Č</li></ul>	c-acute c-circumflex c-caron / c-wedge / cha c-overdot / dotted c glottal c glottal cha c-cedilla / soft c	Polish; Serbo-Croatian Esperanto Czech; Latvian; Lithuanian Maltese; Old Gaelic Kalispel; Kiowa; Nuxalk Comox; Kalispel; Lillooet Albanian; French; Turkish
	ď Ď d D d D	d-overdot / dotted d d-palatal hook / d-háček d-macron d-underdot d-undercomma	Old Gaelic Czech; Slovak Old Basque Twi; romanized Arabic Livonian
	· · · · · · · · · · · · · ·	e-acute e-grave e-double grave e-circumflex e-caron / e-wedge e-overdot / dotted e e-diaeresis / e-trema e-ring e-macron / long e e-breve / short e e-arch e-tilde e-hoi e-circumflex-acute e-circumflex-grave e-circumflex-tilde e-circumflex-macron e-circumflex-hoi e-circumflex-underdot e-underdot / e-nang e-ogonek / tailed e e-acute-ogonek e-grave-ogonek	Czech; French; Hungarian Catalan; French; Italian Serbo-Croatian poetics French; Portuguese; Welsh Czech; romanized Mandarin Lithuanian Albanian; French Arikara; Cheyenne Cornish; Maori Latin Serbo-Croatian poetics Vietnamese Vietnamese Vietnamese Vietnamese Vietnamese romanized Mandarin romanized Mandarin Vietnamese
	á	schwa-acute	Comox; Lushootseed; Sechelt

ää	African epsilon umlaut	Dinka	
ε̃ε̃		Kpelle; Twi	
ĠΈ	f- <i>overdot</i> / dotted f	Old Gaelic	
ģĠ	g-acute	romanized Macedonian	
ĝĜ	g-circumflex	Aleut; Esperanto	The
ğĞ	g-caron	Heiltsuk; Kwakwala; Skolt	Working
ġĠ	g-overdot / dotted g	Iñupiaq; Kiksht; Maltese	Alphabet
	g-breve	Azeri; Tatar; Turkish	
	glottal g	American linguistics	
g G	g-underscore g-(turned) undercomma	Tlingit	
ξĢ	g-(turned) undercomma	Latvian; Livonian	
	h-circumflex	Esperanto	
μĤ	h- <i>overdot</i>	Old Lakhota	
μΉ	h- <i>underdot</i>	romanized Arabic & Hebrew	
	i-acute	Icelandic; Gaelic; Spanish	
ìÌ	i-grave	Dogrib; Italian; Sekani	
	i-double grave	Serbo-Croatian poetics	
îÎ	i-circumflex	French; Romanian; Welsh	
ĭΙ	i-caron / i-wedge	romanized Mandarin	
	dotted I	Azeri; Tatar; Turkish	
	i-diaeresis	French	
	i- <i>ring</i>	Arikara; Cheyenne	
īĬ	i- <i>macron /</i> long i	Cornish; Latvian; Maori	
	i- <i>breve</i> / short i	Latin; Vietnamese	
	i-arch	Serbo-Croatian poetics	
ĩĨ	i-tilde	Guaraní; Kikuyu; Vietnamese	
i Í	i- <i>hoi</i>	Vietnamese	
į Į	i-underdot / i-nang	Igbo; Vietnamese	
įĮ	i- <i>ogonek /</i> tailed i	Chiricahua; Dogrib; Navajo	
į Į į Į	i-acute-ogonek	Chiricahua; Mescalero; Navajo	
įĮ	i-grave-ogonek	Dogrib; Gwichin; Sekani	
ĵĴ ĭĬ	j-circumflex	Esperanto	
j Ĭ	j-caron / j-wedge	American linguistics	
	k-acute	romanized Macedonian	
	glottal k	Comox; Kiowa; Osage	
ΚΚ	k-caron	Skolt	

	ķ Ķ k-undercomma <u>k K</u> k-underscore	Latvian; Livonian Sahaptin; Tlingit
Inflected Latin Letters	Í Ĺ l-acute ľĽ/Ľ l-palatal hook ľĽ glottal l	Slovak Slovak Heiltsuk; Nisgha; Tsimshian romanized Sanskrit Latvian Livonian; Romanian romanized Malayalam romanized Sanskrit
	ł Ł barred l-underdot አ K glottal blam	Iñupiaq Kalispel; Lillooet; Nuxalk
	m M glottal m m M m-overdot / dotted m m M m-underdot	Kwakwala; Nisgha; Tsimshian Gaelic; romanized Sanskrit romanized Sanskrit
	<ul> <li>ń Ń n-acute</li> <li>ň Ň n-grave</li> <li>ň Ň glottal n</li> <li>ň Ň n-overdot / dotted n</li> <li>ň Ň n-ring</li> <li>ň Ň n-caron / n-wedge</li> <li>ñ Ñ n-tilde</li> <li>ŋ Ņ n-cedilla / soft n</li> <li>ŋ Ņ n-undercomma</li> </ul>	Chiricahua; Navajo; Polish romanized Mandarin Kwakwala; Nisgha; Tsimshian romanized Sanskrit Arikara Czech; romanized Mandarin Basque; Catalan; Spanish Latvian
	n N n-underdot n N n-underscore	Twi; romanized Sanskrit romanized Malayalam
	ó Ó o-acute ő Ő o-double-acute	Gaelic; Navajo; Spanish Hungarian
	<ul> <li>ò Ò o-grave</li> <li>ò Ö o-double grave</li> <li>ô Ô o-circumflex</li> <li>ŏ Ŏ o-caron / o-wedge</li> </ul>	Catalan; Dogrib; Italian Serbo-Croatian poetics French; Portuguese; Welsh romanized Mandarin
	<ul> <li>Ö O-overdot / dotted o</li> <li>Ö Ö o-umlaut</li> <li>Ö Ö o-ring</li> <li>Ö O-macron / long o</li> </ul>	Livonian Hopi; German; Turkish Arikara; Cheyenne Cornish; Maori
	ŏ Ŏ o-breve / short o	Latin; romanized Korean

ôÔ	o-arch	Serbo-Croatian poetics	
	o-tilde	Estonian; Portuguese	
	o-hoi	Vietnamese	
-	o-overdot-macron	Livonian	
_	o-umlaut-macron	Livonian	
_	o-tilde-macron	Livonian	
	o-circumflex-acute	Vietnamese	The
	o-circumflex-grave	Vietnamese	Working
	o-circumflex-tilde	Vietnamese	Alphabet
	o-circumflex-hoi	Vietnamese	Пірниосі
	o-circumflex-underdot	Vietnamese	
	o-underdot / o-nang	Igbo; Vietnamese; Yoruba	
		e e e e e e e e e e e e e e e e e e e	
_	o-ogonek / tailed o	Navajo; Seneca; Old Icelandic	
	o-acute-ogonek	Navajo; Slavey; Old Icelandic	
δĄ	o-grave-ogonek	Dogrib; Gwichin; Sekani	
ó Ø	slashed o-acute	Old Icelandic; linguistics	
άĆ	horned o acute	Viotnamasa	
		Vietnamese	
	horned o grave horned o tilde	Vietnamese	
		Vietnamese	
	horned o hoi	Vietnamese	
φŲ	horned o underdot	Vietnamese	
ó Ó	open o acute	Dangme	
	open o umlaut	Dinka	
	open o <i>tilde</i>	Kpelle; Twi	
ç ç	open o ogonek	Kiowa; American linguistics	
4 Å	-l-++-l	Vienn Venlander Ocean	
βŔ	glottal p	Kiowa; Kwakwala; Osage	
рР	p- <i>overdot</i> / dotted p	Old Gaelic	
q Q	glottal q	Kwakwala; Nuxalk; Tsimshian	
ŕŔ	r-acute	Sorbian; Old Basque	
r Ř	r-ring	Arikara	
_	r- <i>caron</i> / r-wedge	Alutiiq; Czech; Sorbian	
	r- <i>underdot</i> / syllabic r	romanized Sanskrit	
	r-cedilla / soft r	Latvian	
, ,	r-undercomma	Livonian; Romanian	
	r-underscore	romanized Malayalam	
_	r-underdot-macron	romanized Sanskrit	
	*******		

	4		
	ś Ś	s-acute / sharp s	Polish; romanized Sanskrit
		glottal s	American linguistics
		s-caron / s-wedge	Czech; Omaha; Latvian
	ġ Ś	s- <i>overdot</i> / dotted s	Old Gaelic
	İ	dotted long s	Old Gaelic
	šŠ	glottal s-caron	Lakhota; Omaha
Inflected	ș Ş	s-underdot	Yoruba; romanized Arabic
Latin	<u>s</u> <u>S</u>	s-underscore	Tlingit
Letters	ş Ş	s-cedilla	Turkish
	ş Ş	s-undercomma	Romanian
	ťΤ̈́	t-overdot / dotted t	Old Gaelic
	ťŤ	t-palatal hook / t-háček	Czech; Slovak
	ťŤ	glottal t	Kiowa; Tsimshian
	ŧŢ	t-macron	Lakhota; Old Basque
	ţŢ	t-underdot	romanized Arabic & Hebrew
	ţŢ	t-undercomma	Livonian; Romanian
	úÚ	u-acute	Icelandic; Navajo; Spanish
	űŰ	u-double-acute	Hungarian
	ùÙ	u-grave	Dogrib; Italian; Sekani
		u-double grave	Serbo-Croatian poetics
		u-circumflex	French; Welsh
		u- <i>caron</i> / u-wedge	romanized Mandarin
		u- <i>umlaut</i>	Estonian; German; Turkish
	ůŮ	u- <i>ring</i> / u-kroužek	Arikara; Cheyenne; Czech
		u- <i>macron</i> / long u	Cornish; Lithuanian; Maori
		u- <i>breve</i> / short u	Latin; romanized Korean
	ûÛ	u-arch	Serbo-Croatian poetics
	ũŨ	u- <i>tilde</i>	Kikuyu; Vietnamese
	ủ Ủ	u- <i>hoi</i>	Vietnamese
	űΰ	u-umlaut-acute	romanized Mandarin
	ùΰ	u-umlaut-grave	romanized Mandarin
		u-umlaut-macron	romanized Mandarin
		u-umlaut-caron	romanized Mandarin
		u- <i>underdot</i> / u-nang	Igbo; Vietnamese
		u- <i>ogonek</i> / tailed u	Lithuanian; Mescalero; Polish
		u-acute-ogonek	Mescalero; Navajo
		u-grave-ogonek	Gwichin; Sekani; Tagish
	ứ Ú	horned u acute	Vietnamese
	_	horned u grave	Vietnamese
	<b></b> 0		. 10011441400

$\tilde{\textbf{w}} \ \tilde{\textbf{U}}$	horned u tilde	Vietnamese	
ửŮ	horned u hoi	Vietnamese	
ự Ự	horned u underdot	Vietnamese	
	w-acute	Welsh	
	w-grave	Welsh	
ŵ Ŵ	glottal w	Heiltsuk; Klamath; Tsimshian	The
ŵŴ	w-circumflex	Chichewa; Welsh	Working
ψŴ	w-diaeresis	Tsimshian	Alphabet
w W	w-ring	Arikara	
ψΨ	w-breve	Gã; Twi	
χ̂ X̂	x-circumflex	Aleut	
χ̈́X	glottal x	Chiwere; Tsimshian	
χ̈́Ẍ́	glottal x underdot	Tsimshian	
χX	x-caron / x-wedge	Heiltsuk; Kwakwala	
	x-underdot	Nuxalk; Okanagan	
<u>x</u> <u>X</u>	x-underscore	Sahaptin; Tlingit	
хX	x-cedilla	romanized Caucasian	
ýÝ	y-acute	Faroese; Icelandic; Welsh	
γΫ́	y-grave	Welsh	
γΫ́	glottal y	Heiltsuk; Klamath; Tsimshian	
ŷŶ	y-circumflex	Welsh	
ÿΫ́	y-diaeresis / y-umlaut	French; Dutch	
	y-macron	Cornish; Livonian	
ÿΫ́	glottal y-umlaut	Tsimshian	
$\tilde{y}$ $\tilde{Y}$	y-tilde	Guaraní; Twi; Vietnamese	
γ̈́Ϋ́	y-hoi	Vietnamese	
уŸ	y-underdot / y-nang	Vietnamese	
•			
źŹ	z-acute / sharp s	Polish; Sorbian	
	glottal z	Lillooet	
	z-caron / z-wedge / zhet	Czech; Latvian; Lithuanian	
	z-overdot / dotted s	Maltese; Polish	
χŻ	z-underdot	romanized Arabic	
žŽ	ezh-caron	Klamath; Skolt	

	Basic Greek	<b>Monotonic Greek</b>	ą̈́Ą	ą psili
				perispomene
	α A alpha / 1	ά alpha tonos	άĄ	α daseia
	βB beta/2	έ epsilon tonos	ą̈́Ą	ą daseia oxeia
	γ Γ gamma/3	ή eta tonos	ą̈́Ą	φ daseia
	$\delta \Delta$ delta / 4	í iota tonos		bareia
Basic and	ε E epsilon/5	ï Ï iota dialytika	άĄ	α daseia
Inflected	ζZ zeta/7	î iota dialytika		perispomene
Greek	η Η eta/8	tonos		
Letters	$\theta$ $\Theta$ theta / 9	ó omicron tonos	έ	epsilon oxeia
	ι Ι iota/10	ύ upsilon tonos	È	epsilon bareia
	к K kappa / 20	ΰ Ϋ upsilon		$\varepsilon$ psili
	λ Λ lambda / 30	dialytika	ἕ "E	arepsilon psili oxeia
	μ M mu/40	ΰ upsilon	ἒ "E	ε psili bareia
	v N nu/50	dialytika tonos	έΈ	$\varepsilon$ daseia
	ξ Ξ xi/60	ώ omega tonos	ἕ "E	$\varepsilon$ daseia oxeia
	o O omicron / 70		ε̈́ "E	ε daseia
	π П рі/80	Polytonic Greek		bareia
	ρ P rho / 100			
	$\sigma \Sigma sigma / 200$	ά alpha oxeia	ή	eta oxeia
	τ T tau/300	à alpha bareia	ή	eta bareia
	υ Υ upsilon/	ã alpha	ῆ	eta
	400	perispomene		perispomene
	φ Φ phi / 500	ά Ά α psili	η̈́H	$\eta$ psili
	χ X khi / 600	ἄ Ἄ α psili oxeia	•	$\eta$ psili oxeia
	ψΨ psi / 700	ä Ä α psili bareia		$\eta$ psili bareia
	ω Ω omega / 800	å Å α psili	ή̈́H	$\eta$ psili
		perispomene		perispomene
	Alternate Greek	ά Ά α daseia	•	$\eta$ daseia
		ä "A α daseia		$\eta$ daseia oxeia
	в alternate beta	oxeia	η̈́H	$\eta$ daseia
	9 alternate theta	ä ൹ α daseia		bareia
	и alternate kappa	bareia	ήΉ	$\eta$ daseia
	യ alternate pi	å Ά α daseia		perispomene
	ς terminal sigma	perispomene	ηŲ	eta iota
	c lunate sigma	ą Ą alpha iota	ή	η oxeia
	C lunate cap sigma	ά α oxeia	'n	$\eta$ bareia
	φ alternate phi	ὰ <i>ᾳ</i> bareia	ñ	η perispo-
	(etc)	ą̃ ą perispo-		mene
		mene		$\eta$ psili
		ἀ Å φ psili		η psili oxeia
		ἄ Ἄ φ psili oxeia	Η̈́" μ̈́	η psili bareia
		ä ἢ ą psili bareia		

Ų, Ų	n psili	ρ̈́	rho psili	ψ Ω omega iota	
	perispomene	ρ̈́	rho daseia	φ φ oxeia	
-	η daseia			ψ ψ bareia	
ἥ″Ḥ	η daseia	ύ	upsilon oxeia	$\tilde{\psi}$ $\psi$ perispo-	
	oxeia	ΰ	upsilon	mene	
ŋ̈¨Ḥ	η daseia		bareia	ψ̈΄ Ω φ psili	
	bareia	ũ	upsilon	ῷ Ἅ φ psili oxeia The	
ή̈́Ή	η daseia		perispomene	ῷ Ὠ φ psili bareia Workin	_
	perispomene		v psili	$\dot{\psi} \hat{\Omega} \psi$ psili Alphab	et
			<i>v</i> psili oxeia	perispomene	
ί	iota oxeia	ΰ"Υ	v psili bareia	ψ Ώ <i>ψ</i> daseia	
ì	iota bareia	ΰ'nΥ	v psili	ῷ Ἅ ψ daseia	
ĩ	iota		perispomene	oxeia	
	perispomene	ύΥ	$oldsymbol{v}$ daseia	ῷ Ἅ φ daseia	
i 'I	ι psili	ΰ "Υ	v daseia oxeia	bareia	
ĭ ĭI	ι psili oxeia	ΰ "Υ	v daseia	ῷ Ὠ φ daseia	
ĩ Ï	ι psili bareia		bareia	perispomene	
ľĬ	ι psili	ΰΎ	v daseia		
	perispomene		perispomene	Numeric Greek	
ίΊ	ι daseia	ΰŸ	upsilon		
ι "I	ι daseia oxeia		dialytika	F digamma / old 6	
ï ï	ι daseia	ΰ	$\ddot{v}$ oxeia	ς stigma / new 6	
	bareia	ΰ	$\ddot{v}$ bareia	o qoppa / 90	
ľľ	ι daseia	$\tilde{\mathfrak{v}}$	<i>v</i> perispo-	⇒ sampi / 900	
	perispomene		mene	ל alternate qoppa	
ïΪ	iota dialytika			α' right horn (for	
î	ï oxeia	ώ	omega oxeia	numerals 1–999)	
î	ï bareia	ὼ	omega bareia	,α left horn (for	
ĩ	ϊ perispo-	ũ	omega	1000 and up)	
	mene		perispomene	<u>-</u>	
		ω̈́Ω	ω psili	Linguists' Greek	
ó	omicron	ű̈̈́Ω	$\omega$ psili oxeia		
	oxeia	Ω¨ὥ	$\omega$ psili bareia	ā Ā long alpha	
ò	omicron	$\Omega$ $\dot{\omega}$	$\omega$ psili	ă Ă short alpha	
	bareia		perispomene	ī Ī long iota	
oʻ oʻ	o psili	ώΏ		ĭ Ĭ short iota	
ŏ 'n	o psili oxeia	ű 'n	$\omega$ daseia	υ Y long upsilon	
	o psili bareia		oxeia	ŭ Υ short upsilon	
	o daseia	ω Ώ	$\omega$ daseia	γ γ-overdot	
	o daseia oxeia		bareia	$\hat{\delta}$ $\delta$ -circumflex	
	o daseia	űΩ	$\omega$ daseia	$\hat{\theta}$ $\theta$ -circumflex	
	bareia		perispomene	λ glam	
			- •	(glottal λ)	
				•	

-	~ ·III·
Russian	Cyrillic

#### **Other Cyrillic**

Basic	and
Infle	cted
Cy	rillic
Le	tters

To people raised on the Latin alphabet, it can come as a surprise that the cursive form of Cyrillic T is m, the cursive form of  $\pi$  is  $\partial$  or a, and the cursive form of to is no. Typical lowercase cursive forms are therefore shown for all Cyrillic letters in this list.

The invariant letter I, often romanized as h or x, is an independent letter of the alphabet in some Caucasian languages but more often used in digraphs and trigraphs, e.g., Abaza YI and YI, YIB and YIB.

a A a= a6  $\delta$   $\delta/\delta = b$ В в = vΓ 2/ī = g∂/a дД = d= e/ieeЕ e жЖж  $= \check{z}$ 3 3 3 = zиИи =iйЙй = j/iкКκ = kπЛл =1мМм = mн Н н = n000= 0 $\Pi \Pi n/\bar{u} = p$ pΡ D = rc C c= sт Т  $m/\bar{u}=t$ уУγ = uфФф = f $\mathbf{x} \mathbf{X} \mathbf{x}$ = x/khцЦи = c/tsч Ч ч  $= \check{c}/ch$ III III w  $= \frac{s}{sh}$ шШш = shch ъЪъ = 'hard' ыЫы = vьЬь ='soft' Ээ  $= \dot{e}$ юЮю = yu/iu

 $\check{\mathbf{A}} \quad \check{\mathbf{A}} \quad \check{\mathbf{A}} \quad = \check{\mathbf{A}}$ Chuvash äÄä = ä Mari. &c x + x = xOssetian Àä = ä Serbo-Croatian Т Ukrainian ſ = gŕ Macedonian, &c ź  $= \acute{g}/gj$ F Bashkir: Kazakh, &c = **ğ/gh** г Б ħ = g/ghAbkhaz: Yakut, &c Б Ë Bashkir; Tajik, &c ë ë = yoĚ ĕ = ĕ Chuvash a G Bashkir; Tatar, &c  $= a/\ddot{a}$ Ää = ë Khanty Ђħ = d/dySerbo-Croatian S  $= \dot{z}/dz$ Macedonian S ħ  $\mathcal{F}_{h}$  $= \dot{c}/chv$ Serbo-Croatian È ë Serbo-Croatian = **e** È è = è Macedonian  $\epsilon \in \epsilon$ Ukrainian = ye/ěӂӁӂ = dž Moldovan  $\ddot{x} \ddot{x} \ddot{x} = d\dot{z}$ **Udmurt** ж $\mathcal{K}\mathcal{K}\mathcal{K}=\dot{z}/\check{j}$ Kalmyk; Tatar, &c 3 3 = dzUdmurt 3  $= \eth/\acute{z}$ Bashkir 3 3 Abkhaz 3 = i/dz3 йЙù = i Macedonian йЙи  $= \bar{i}$ Taiik йЙй = ï Udmurt йЙü = ï Serbo-Croatian İ Khakass i  $= \hat{i}$ T =iBelarusian, &c I I Abaza; Ingush, &c = h/x= i/yiUkrainian Macedonian, &c = j/yκΚκ Macedonian, &c = kjκΚκ = kKazakh; Tajik, &c k K k Abhkaz = q'Azeri кКк = gChukchi, &c κК ĸ = qҡҠҡ Bashkir = qљ Љ љ = ljMacedonian, &c

яЯя

= ya/ia

њ Њ <i>њ</i> = nj	Macedonian, &c
$H$ $H$ $H$ = $\eta$ /ng	Bashkir; Tuvan, &c
$H H = nj/\tilde{n}$	Khanty; Koryak, &c
$HFH\tilde{H} = ngh$	Altay; Yakut, &c
$\ddot{o} \ddot{O} \ddot{o} = \ddot{o}$	Altay; Shor, &c
ö Ö ö = ö	Serbo-Croatian
ø Ø ø = ò	Abhkaz
$\Pi_1 \prod_j n_j = p'$	Abkhaz
$\ddot{p} \ \ddot{P} \ \ddot{p} = \ddot{r}$	Serbo-Croatian
$\varsigma \ \varsigma \ \varsigma = \varsigma$	Bashkir; Chuvash
T T m = t/t	Abkhaz
$\mathbf{T}\mathbf{J}$ $\mathbf{\bar{u}}$ = ts'	Abkhaz
$\ddot{y} \ \ddot{y} \ \ddot{y} = \ddot{u}/w$	Belarusian; Uzbek
$\bar{y}  y  \bar{y} = \bar{u}$	Tajik
$\ddot{\mathbf{v}} \ddot{\mathbf{y}} \ddot{\mathbf{v}} = \ddot{\mathbf{u}}$	Altay; Khanty, &c
$\ddot{y} \ \ddot{y} \ \ddot{y} = \ddot{u}$	Chuvash, &c
$\ddot{y} \ddot{y} \ddot{y} = \ddot{u}$	Serbo-Croatian
$\mathbf{Y}  \mathbf{Y}  \mathbf{Y} = \ddot{\mathbf{u}}/\ddot{\mathbf{u}}$	Bashkir; Kazakh, &c
Y Y Y = u	Kazakh
$\Theta \Theta \Theta = \bar{O}/\bar{O}$	Tuvan; Yukaghir, &c
$\ddot{\Theta} \ddot{\Theta} \ddot{\theta} = \ddot{O}$	Khanty
$x X x = h/\hbar$	Tajik; Uzbek, &c
ų Ц ų = č	Abkhaz; Tajik
ч Ч <i>ч</i> = č/j	Shor
$\Psi \Psi = d\check{z}/c$	Azeri
Ÿ Ÿ ü = ċ	Udmurt
ы Ы <i>ы</i> = ÿ	Mari
$e \cdot e \cdot e = tc$	Abkhaz
ę <i>'</i> Ç <i>ę</i> ' = tç'	Abkhaz
h h h = h	Bashkir; Buryat, &c
$\psi \ \ \psi \ \ \psi = d\check{z}$	Macedonian, &c
w W w = w	Yukaghir

## **Old Cyrillic**

ë	Ë	ë	yo	ъ	ъ	rb	yat
$\epsilon$	$\epsilon$	$\epsilon$	yest	ю	$\mathbf{E}$	ĸ	ye
s	S	s	zelo	ξ	Ξ	ξ	ksi
I	I	ï	izhe	Ψ	Ψ	ψ	psi
ħ	Ћ	ħ	derv	Θ	Θ	0	fita
ω	Ω	ω	ot	v	V	v	izhitsa

# International Phonetics

#### VOWELS

a	g	a	D	æ	Λ
e	ə	9	3	3	в
i	i	I	8		
o	Θ	Ø	œ	Œ	Э
u	ŧ	σ	ш	y	Y

#### CONSONANTS

b	b	В	β		
c	Ç	Ç			
d	ď	þ	ð		
f	φ	•			
g	g	G	G	Y	
h	ħ	h	Н		
j	j	J	f		
k					
1	l	λ	L	4	ß
m	m				
n	ŋ	ŋ	η	N	
p					
q					
r	ſ	τ	I	Į	1
	R	R			
S	Ş	ſ			
t	t	θ			
V	υ				
w	M	Ч	щ		
X	Χ	Ŋ			
Z	<b>Z</b>	<b>Z</b>	3		
?	?	ſ	£		
!	0	ı	<b>‡</b>	II	
[fŋ	ß	Þ	w	٦]	

#### INFLECTIONS

1	$\downarrow$	1	7	
7	1	4	1	J
1	V	1	1	7
:	٠	ı	_	

The Working Alphabet

This is only the skeleton of the IPA, which also admits the use of over fifty diacritics. For the names and functions of the symbols, see the Handbook of the International Phonetic Association (1999).

#### Single Stroke

# midpoint period underdot bullet

comma

overdot

apostrophe inverted comma; turned comma

undercomma

acute grave All the italicized terms prime are individually discussed macron in appendix в. The remaining - hyphen terms are treated in three groups: lowline (1) arithmetical signs; (2) cur-- en dash rency signs; and

Visual

Index of

Analphabetic

(3) musical signs.

Characters

3	glottal stop
~	tilde
~	swung dash
()	parentheses
{}	braces
•	ring
0	degree

### **Pictograms**

*	asterisk
†	dagger
‡	double dagger
(z. 1	fist
(No	hedera

#### **Modified Letters**

Double Stroke	@	at
	©	co <b>p</b> yright
diaeresis/umlaut	¢	cent
colon	€	euro
semicolon	& &	ampersand
quotation	f	guilder
quotation	£	sterling
exclamation	P	phonomark
question	•	pilcrow
double prime	9	registered
double acute	<b>§</b>	section
double grave	\$	dollar
dumb quote	TM	trademark
equal	¥	yen
pipe	Ø	null
double bar	%	per cent
addition	‰	per mille
dimension		_
guillemets		
square brackets		
natural		

There is, of course, no limit to the number of typographic characters. Still less is there a limit to the number of variant glyphs by which these characters are realized. This appendix lists characters included on standard ISO (PS-1, TrueType or OpenType) and pan-European (TTO or OpenType) Latin text fonts. It also lists a few additional characters of long-standing typographic importance. Unicode numbers are given in square brackets at the end of each entry. Some characters (especially diacritics) have more than one address in Unicode. As a rule, only one of these addresses is given here. Two addresses are given for characters (such as *aesc*) that occur in both the upper and lower case.

acute An accent used on vowels – á é í ó ú ý  $ilde{x}$  – in Czech, French, Gaelic, Hungarian, Icelandic, Italian, Navajo, Spanish and other languages, and on consonants –  $ilde{c}$  ń ŕ ś  $ilde{z}$  – in Basque, Croatian, Polish and romanized Sanskrit. In romanized Chinese it is used with vowels and a nasal – á é í ń ó ú  $ilde{u}$  – to mark the rising tone. It is also used with Cyrillic consonants – ŕ and  $ilde{k}$  – in Macedonian, and with all the vowels in Greek. Upper- and lowercase versions of the basic six acute vowels appear on standard 1so Latin text fonts. Pan-European fonts usually include both upper- and lowercase forms of the basic five acute consonants and the old Icelandic vowel  $ilde{x}$ . The acute schwa ( $ilde{s}$ ) and open 0 ( $ilde{s}$ ) and the Athapaskan high nasal vowels –  $ilde{q}$   $ildе{s}$   $ildе{u}$   $ildе{s}$   $ildе{u}$   $ildе{u}$  – are present only on specialized fonts. [U+0301]

a

aesc This ligature is a letter of the alphabet in Danish, Norwegian, Anglo-Saxon and Old Norse, corresponding in part to the Swedish ä. It is also sometimes used (unnecessarily) in Latin. In English, words of Greek origin were formerly spelled with æ corresponding to Greek αι (alpha iota). Thus aesthetics in older texts is æsthetics. Deliberate archaism and pedantically correct quotation still, therefore, require the ligature even in English. Aesc (æsc in the older spelling) is pronounced ash. [U+00C6, +00E6]

ææ

Æ

ampersand A scribal abbreviation for *and*, dating back to Roman times. It takes many forms – & & & & - all derived from the Latin word *et*. [U+0026]

め

⟨a⟩

angle brackets These useful characters are missing from most text fonts, but they are readily found on pi fonts and on some fonts of blackletter and Greek. They serve many functions in mathematical and scientific writing. In the editing of classical texts, angle brackets are used to mark editorial additions while braces mark the editor's deletions. See also square brackets. [U+2329, +232A]


a

apostrophe Also called raised comma or single close-quote. A mark of elision in English, French, Italian and many other languages. It grew from that use in English to become also a sign of the possessive. (*It's* = *it is*, but *John's* = *Johnes* = belonging to John.) A superimposed apostrophe (not to be confused with the *acute*) is the standard symbol in linguistics for a glottalized consonant: m p q w, etc. As a matter of convenience, these symbols are often converted to consonants followed by normal apostrophes: m' p' q', etc. Apostrophized consonants of this sort are frequent in typography. The apostrophized d and t (d and t, whose capital forms are Ď and Ť) are letters of the alphabet in Czech; so are ľ and Ľ in Slovak, while ch', k', k', l', s', t', tl', ts', x', x' and their corresponding capitals (written with apostrophes, not carons) are letters of the alphabet in Tlingit. Used alone, the apostrophe often serves as a sign for the glottal stop. In Unicode, these functions are carefully distinguished. See also dumb quotes, glottal stop, palatal hook and quotation marks. [U+02BC, +0313, +0315, +2019]

â

arch A diacritic used with vowels and one syllabic consonant –  $\hat{a}$   $\hat{e}$   $\hat{i}$   $\hat{o}$   $\hat{u}$   $\hat{i}$  (and the corresponding Cyrillic letters,  $\hat{a}$   $\hat{e}$   $\hat{u}$   $\hat{o}$   $\hat{y}$   $\hat{p}$ ) – to mark the long falling tone in Serbo-Croatian. Though not employed in ordinary writing, these forms are used in teaching, in linguistics, and in some editions of metrical poetry. Few text fonts include either the arch or the composite glyphs in which it is used. Not to be confused with the circumflex, which is pointed. Also known as a *dome* or *inverted breve*. It has also been called a *cap*, which leads to confusion. [U+0311]

± = < + > × ÷ arithmetical signs Only eight basic signs,  $+ - \pm \times \div < = >$ , are included in most text fonts. When other mathematical symbols, such as  $\neq \approx \nabla \equiv \sqrt{\leq} >$ , are required, it is generally best to take all signs, including the basic ones, from the same technical font so that all forms match in color and size. [U+002B, +2212, +00B1, +00D7, 00F7, 003C, 003D, 003E, &c.]



barred T A letter of the Northern Saami alphabet, representing a sound like th in English thing [IPA θ]. It is normally included on pan-European Latin text fonts. [U+0166, +0167]
 braces Braces are rarely required in text work, but they can function perfectly well as an extra and outer (or inner) set of parentheses: {([-])}. In mathematics they are used to mark

phrases and sets. In editing classical papyri, braces are often used to mark editorial deletions. [U+007B, +007D]

brackets See angle brackets and square brackets.

**breve** An accent used on vowels and consonants –  $\Bar{a}$   $\Bar{e}$   $\Bar{i}$   $\Bar{g}$   $\Bar{o}$   $\Bar{u}$  – in Malay, Romanian, Turkish, Vietnamese, and in some forms of romanized Korean. In English, it is used in informal phonetic transcriptions to mark lax (or so-called 'short') vowels. In writings on metrics and prosody, it is the sign of a quantitatively short vowel or syllable. It is also used on the Russian i ( $\Bar{u}$ , whose cursive form is  $\Bar{u}$ ) and on a second vowel,  $\Bar{v}$ , in Belarusian and Uzbek. The breve is always rounded, and should not be confused with the angular caron. (*Breve* is two syllables, with the stress on the first, as in *brave*, *eh?*) Also called *short*. [U+0306]

• bullet A large version of the midpoint, used chiefly as a typographic flag. Bullets are commonly hung, like numbers, in the margin to mark items in a list, or centered on the measure to separate larger blocks of text. See also *midpoint*. [U+2022]

caron An inverted circumflex. It is used on consonants and vowels – č ě ň ř š ž – in Croatian, Czech, Lithuanian, Northern Saami, Slovak, Slovene, Sorbian and other scripts. In romanized Thai, the caron indicates a rising tone. In romanized Chinese, it marks the retroflexive third tone (falling/rising tone) of standard Mandarin: å ě ě ĭ ň ŏ ǔ ů. It is also used in new scripts for sevferal Native American languages. For no good reason, most 150 fonts include a prefabricated upper- and lowercase š and ž, while other combinations must be built with the floating accent. Pan-European fonts contain a larger but still incomplete set of caroned letters, usually č ě ň ř š ž and Č Ď Ě Ň Ř Š Ť Ž. Also called a wedge or a háček (hah-check), which is its Czech name. In Czech, however, this character is actually a variant of the palatal hook, which can take the form of caron or apostrophe. [U+O3OC]

**cedilla** A diacritic used with consonants, such as the  $\varsigma$  in Catalan, French, Nahuatl and Portuguese, and  $\varsigma$  and  $\varsigma$  in Turkish. In Latvian and Romanian, the *undercomma* is preferred. Not to be confused with the *ogonek* or nasal hook, which curves the other way and is used with vowels. The name means *little z*. Turkish  $\varsigma$  and  $\varsigma$  are missing from standard 150 text fonts. [U+0327]

circumflex A diacritic used on vowels –  $\hat{a}$   $\hat{e}$   $\hat{i}$   $\hat{o}$   $\hat{w}$   $\hat{y}$  – in Cree, French, Portuguese, Romanian, Vietnamese, Welsh and many other languages. In transliterated texts (e.g., from Arabic, Greek, Hebrew and Sanskrit), it is sometimes used as a substitute for the macron, to mark long vowels. In romanized Thai, a circumflex signifies a falling tone. Most Latin text fonts include all the circumflected vowels except Welsh  $\hat{w}$  and  $\hat{y}$ . [U+O3O2]

â

colon A grammatical marker inherited from the medieval European scribes. It is also used in mathematics to indicate ratios and in linguistics as a mark of prolongation. The name is from Greek. In classical rhetoric and prosody, a *colon* (plural, *cola*) is a long clause, and a *comma* is a short one. [U+003A]

a:

comma A grammatical marker, descended from early scribal practice. In German, and often in East European languages, the comma is used as an open quote. Throughout Europe, it is also used as a decimal point, where most North Americans expect a period. In North American usage, the comma separates thousands, while a space is preferred in Europe. Thus 10,000,000 = 10 000 000, but a number such as 10,001 is typographically ambiguous. It could mean either ten and one one-thousandth or ten thousand and one. See also *quotation marks*. [U+002C]

a,

**copyright** On poorly designed fonts, the copyright symbol sometimes appears as a superscript, but its rightful place in typography is on the baseline: ©. [U+OOA9]

 $^{\circ}$ 

curl See hoi.

currency symbols Most 180 character sets of recent vintage include six genuine currency signs  $-\$ \notin f \notin -$  and one imaginary sign,  $\boxtimes$ . That so-called 'general currency sign,' the *louse*, has no typographic function. It merely holds a place on the font to which a real symbol for local currency (rupee, cruzeiro, peseta, etc) can be assigned. The cent sign (\$), now an American typographical heirloom, is equally irrelevant for most work. It remains in the character set chiefly out of nostalgia.

The dollar sign, a slashed S, is descended from an old symbol for the shilling. The same sign has come to be used for currencies with many other names: sol, peso, escudo, yuan, etc. The sign of the pound sterling, a crossed cursive L, actually stands

\$ £ €

f ¢ Rφ

Rs ¥ ¢

Ø

for the Latin *libra* (also the source of the abbreviation *lb*, used for the pound avoirdupois). This £ sign is now used not only for British currency but for the pound, lira or livre of many African and Middle Eastern states. The sign for Dutch guilders is f, for *florin*, which is the old name for the currency. This f is often cut shorter and wider than the normal italic lowercase f. The sign for the shekel (Hebrew *sheqel*), the Israeli currency unit, is  $\square$ . See also *louse*. [U+0024, +00A2, +00A3, +00A5, +0192, +20AC, &c.]

dagger A reference mark, used chiefly with footnotes. In European typography, it is also a sign of mortality, used to mark the year of death or the names of deceased persons, and in lexicography to mark obsolete forms. In editing classical texts, daggers are used to flag passages judged to be corrupt. Also called *obelisk*, *obelus* or *long cross*. [U+2020]

dashes Latin text fonts include, at minimum, an em dash, en dash and hyphen. A figure dash and three-quarter em dash are sometimes included as well, and a three-to-em dash more rarely. [U+2013, +2014, &c.]

**degree** Used in mathematics and in normal text to give temperatures, inclinations, latitudes, longitudes and compass bearings. Not to be confused with the *superior* o or *ordinal* o used in abbreviations such as  $N^o$ , nor with the *ring*, a diacritic. [U+00B0]

diaeresis / umlaut A diacritic used with vowels – ä ë ï ö ü w ÿ – in many languages, including Albanian, Dinka, Estonian, Finnish, German, Swedish, Turkish, Welsh, and less frequently also in English, Greek, Spanish, Portuguese and French. Linguists distinguish between the *umlaut*, which marks a *change* in pronunciation of a single vowel (as in the German *Schön*) and the *diaeresis*, which marks the *separation* of adjacent vowels (as in naïve and Noël). The typographic symbol is the same, but in reference to English and the Romance languages, the correct term is usually diaeresis, while umlaut is correct in reference to most other languages in which the symbol is used. Except for the Welsh w and African ë and ö, the umlauted or diaeretic vowels are present on most Latin text fonts. Also called *tréma*, its French name.

In Hungarian there are two forms of umlaut: the double dot, which is used for short vowels, and the *double acute* or *long umlaut*, used for long vowels (ű is the long form of ü).

The letter  $\ddot{y}$  is a vowel sometimes used in archaic French and still required in the modern form of a few personal names and place names. It is also an alternate form of the ij ligature in Flemish. [U+0308]

diesis An alternate name for the double dagger.

**dimension sign** An unserifed x, usually square, also known as a multiplication sign. See *arithmetical signs*. [U+00D7]

X

dotless i and dotted I These are both letters of the alphabet in Turkish, where the lowercase form of I is 1 and the uppercase form of i is İ. The dotless form signifies a back vowel (IPA III), the dotted one a front vowel (IPA i, as in English liter. [U+0130, +0131]



dome See arch.

double acute A diacritic used on two Hungarian vowels: ő and ű. Also called *long umlaut*. The name 'Hungarian umlaut' (used in PostScript jargon) is unhelpful, since the short umlauted vowels ö and ü also appear in Hungarian. Not to be confused with the double prime nor with the close quote. [U+O3OB]



double bar This is a standard symbol in bibliographical work and an old standard reference mark in European typography. It is missing from most text fonts but is easily made by kerning two single bars together. [U+2016]



**double dagger** A reference mark for footnoting. Also called *diesis* or *double obelisk*. [U+2021]



double grave A Serbo-Croatian diacritic used, like the arch, with five vowels and one syllabic consonant:  $\ddot{a} \ddot{e} \ddot{i} \ddot{o} \ddot{u} \ddot{r}$  (and in Cyrillic,  $\ddot{a} \ddot{e} \ddot{n} \ddot{o} \ddot{y} \ddot{p}$ ). This is a prosodic sign, to indicate the short falling tone. Though not employed in ordinary writing, the double grave is used in teaching, in linguistics, and in editions of metrical poetry. It is rarely found on text fonts. [U+030F]



**double prime** An abbreviation for inches (1'' = 2.54 cm) and for seconds of arc ( $360'' = 1^{\circ}$ ). Not to be confused with quotation marks, the double acute, nor with dumb quotes. Prime and double prime are rarely found on text fonts. See also *prime*. [U+2033]



a n b

**dumb** caret Also known, in vain, as the *ascii circumflex*. This is a stray, like the backslash and dumb quotes, ossified into the standard ASCII keyboard. The true circumflex (^) is a different and genuine character. So is the *logical and* (^, the sign of logical conjunction). Since it has no typographic function, the dumb caret also has no typographic form. In other words, this is not really a character at all. It is a wasted slot on the keyboard, waiting for something else to take up residence. [U+OO5E]

"a'i'a"

dumb quotes These are refugees from the typewriter keyboard. Typesetting software interprets quotation-mark keystrokes in context, converting the dumb quotes to smart quotes (never infallibly). Yet the dumb quotes are still there, taking space on the font. They have no typographic function. See also *double prime*, quotation marks and prime. [U+0022, +0027]

đĐ

dyet A basic letter of the alphabet in Serbo-Croatian (where it has the sound of IPA  $\widehat{d_3}$ ) and Vietnamese (where it is now IPA d and used to be d). The uppercase form of the letter is, as a rule, graphically the same as the uppercase *eth*, but it is notionally different. It therefore has a different Unicode address. [U+0110, +0111]

• • • ellipsis The sign of elision and of rhetorical pause: three dots.
[U+2026]

ŋŊ

eng A letter of the alphabet in Northern Saami and in many African languages. Lowercase eng is also used in linguistics and lexicography to represent the ng sound in the word wing. (Note the different sounds represented by the same letters in the words wing, Wingate, singlet and singe: n, n-g, ng, nd3.) The eng is found on pan-European and pan-African fonts. [U+014A, +014B]

ßß

eszett The ss ligature, long s + short s (f + s). It was once essential for setting English and is still essential for German. Not to be confused with the Greek beta,  $\beta$ . Also known as sharp s. Note that not all instances of ss in German turn to  $\beta$ . [U+00DF]

ðĐ

eth A letter of the alphabet in Anglo-Saxon, Faroese, Icelandic, and in IPA. The uppercase eth is the same as the uppercase *dyet*, but the lowercase forms are not interchangeable, and the letters represent quite different sounds. (The name *eth*, also spelled *edh*, is pronounced like the *eth* in *whether*.) [U+00D0, +00F0]

ethel A ligature formerly used in English and still essential for setting French. English words and names derived from Greek were formerly spelled with the ethel (or æthel) corresponding to the Greek οι (omicron iota). Thus the old form of ecumenical is æcumenical (from οἶκος, Greek for 'house') and the Greek name Οἰδίπους (Oidípous), Latinized as Oedipus, was formerly written Œdipus. The ligature is required, therefore, for deliberate archaism and for academically correct quotation from older English sources, as well as for spelling French terms such as hors d'œuvre. In IPA, @, @ and β are three different letters. [U+0152, +0153]

œŒ

ew See barred L.

exclamation In Spanish, the inverted exclamation mark is used at the beginning of the phrase and the upright mark at the end. In mathematics, the upright exclamation mark is the symbol for factorials ( $4! = 4 \times 3 \times 2 \times 1$ ). It is also often used to represent the palatal clicks of the Khoisan languages of Africa. Thus, for example, the name !Kung. British printers often call the exclamation mark a *screamer*. [U+OO21, +OOA1]

ia.

ezh This is an altered form of z, generally representing a sound like that of z in English azure or j in French justice, which is the sound of Czech ž or Polish ż. Ezh is a letter of the alphabet in Skolt, a language of the Saami family, spoken in northern Russia and Finland. The lowercase form is also part of the IPA and therefore present on any font of phonetic characters. Not to be confused with yogh. [U+01B7, +0292]

3

figures A text font normally includes at least one set of figures, which usually ought to be (and usually are not) text figures (OSF). Supporting fonts and OpenType fonts often include three further sets: titling (i.e., lining) figures, superiors and inferiors. The superiors are used for exponents, superscripts and the numerators of fractions, the inferiors for the denominators of fractions. For chemical formulae ( $H_2O$  etc) and mathematical subscripts, lowered inferior figures are needed. [U+0030-0039; +00B2, +00B3, +00B9, +2070, +2074-2079; +2080-2089]

1 2 3

45

fist The typographer's fist is neither a blunt instrument nor a closed purse. It is a silent, pointing hand. All too often, however, it is overdressed, with ruffles at the cuff. A Baroque invention, the

To Bo

fist is missing from the standard 150 character set and must be found on a supplementary font. [U+261A-261F]

1/2 2/3

fractions Three fractions – ¼ ½ ¾ – appear on most ISO text fonts, and six more – ½ ⅓ ¾ ½ ¾ – on some pan-European fonts. [U+00BC—00BE; +2153—215E]



glottal stop The glottal stop is a sound in search of a character: a basic sound in many languages now written in Latin letters, but one for which the Latin, Greek and Cyrillic alphabets have no traditional symbol. Linguists use the character ? or ? – a gelded question mark – to represent this sound, but the symbol most commonly used in setting texts is the apostrophe. In romanized Arabic the inverted comma or open quote (') is often used to represent the letter 'ain ( $\varepsilon$ ), whose phonetic symbol is  $\Gamma$  or  $\Gamma$ , and the apostrophe (') is used to represent hamza ( $\Gamma$ ,  $\Gamma$ ,  $\Gamma$ , etc.), the Arabic glottal stop. Thus, the Koran in romanized Arabic is al-Qur'ān; Arab is 'arab; the family is al-'ā'ila. Also known by its Spanish name, saltillo, "little leap." See also apostrophe, inverted comma and quotation marks. [U+0294, +02BC, +02C0]



grave An accent used with vowels – à è ì ò ù ỳ – in French, Italian, Portuguese, Catalan, Vietnamese and many other languages. In romanized Chinese it is used with vowels – à è ì ò ù  $\ddot{u}$  – to mark the falling tone. In Gaelic the grave is normally used instead of the macron to mark elongated vowels. The basic five grave vowels are present on most Latin text fonts. [U+0300]



guillemets Single and double guillemets are widely used as quotation marks with the Latin, Cyrillic and Greek alphabets in Europe, Asia and Africa. Attempts to introduce them into North America have met with only slight success. In French and Italian, the guillemets almost always point out, «thus» and ‹thus›, but in German they more frequently point in, »so« and ›so«. Single guillemets should not be confused with angle brackets nor with the arithmetical operators meaning greater-than and less-than.

Guillemet means Little Willy, in honor of the sixteenth-century French typecutter Guillaume [William] Le Bé, who may have invented them. Also called *chevrons*, *duck feet* and *angle quotes*. [U+00AB, +00BB, +2039, +203A]

háček See caron and palatal hook.

hedera An ivy leaf: a type of fleuron. (*Hedera* is the Latin name for ivy.) This is one of the oldest of all typographic ornaments, present in early Greek inscriptions. [U+2619, +2766, +2767]



**hoi** This is one of the five tonemarks used with vowels in the Vietnamese alphabet. It resembles a small dotless question mark and signifies the dipping-rising tone. The spelling in Vietnamese is, naturally,  $h \delta i - and$  the name in Vietnamese does mean "question." In English it is also called a *curl*. [U+0309]



**horned o** A letter of the Vietnamese alphabet, representing a close mid-back unrounded vowel (an unrounded o, the IPA v). [U+01AO, +01A1]



horned U A letter of the Vietnamese alphabet, representing a close back unrounded vowel (IPA W). [U+01AF, +01BO]



hyphen The shortest of the dashes. [U+002D]

inverted breve See arch.

inverted comma Also called a single open-quote, and used for that purpose in English, Spanish and many other languages. In transliterated Arabic and Hebrew, it also represents the letter 'ain ( $\varepsilon$ ) or ayin ( $\nu$ ), a pharyngeal continuant (IPA  $\Gamma$ ), while its opposite, the apostrophe, represents the glottal stop. Thus: King Ibn Sa'ūd; the Beqa'a Valley. Only the well-curved form of the glyph (' instead of ') is useful in transliteration. See also glottal stop, quotation marks, reversed apostrophe. [U+2018]



kropka See overdot.

kroužek See ring.

letters At least three varieties of letters appear in an ordinary font of Latin type. There is normally a full alphabet in both upper and lower case and a partial alphabet of superior letters. The latter are used in numerical abbreviations such as  $1^{st}$ ,  $2^{nd}$ ,  $3^{rd}$ , the French  $1^{e}$  (premier, première) and the Spanish  $2^{a}$ ,  $2^{o}$  (segunda, segundo). They are also used in a few verbal abbreviations, such as  $4^{o}$  = quarto;  $8^{o}$  = octavo;  $M^{r}$  = mister;  $N^{o}$  = number, but in English most such forms are now archaic. The basic Iso alphabet includes

a B

essential for setting text in Romance languages. (They are called ordinals because they are used for ordinal numbers: first, second, third....) A fuller set – conventionally limited to a b d e i l m n o r s t – is often to be found on an 'expert' or OpenType font.

only two superior letters, the ordinal a and ordinal o, which are

 $x^a$  A

OpenType fonts routinely include small caps in addition to u&lc and superior letters. Full pan-European fonts also include a complete set of Cyrillic and Greek characters. Some fonts include swashes and quaints such as the *long s* (f) and its ligatures.

Qu T

Note that the identity of the letters varies from language to language. The digraph *ch*, for example, is regarded as a single letter in Czech, Lithuanian and Spanish; *ll* is treated as a single letter in Spanish and Basque; *dd*, *ff*, *ng*, *ll*, *ph*, *rh*, *th* are all treated as single letters in Welsh; and in Serbo-Croatian the digraphs *dz*, *lj*, *nj* are regarded as single letters (corresponding to Cyrillic µ, љ and њ). [U+0041—005A; +0061—007A; +00C0—00D6; +00D8—00F6; +00F8—00FF, &c.]

fi*ffi* ß

**ligatures** Basic 150 fonts are limited to two typographic ligatures, *fi* and *fl*. Rigid definitions of the glyph set, leaving no provision for additional ligatures (such as *ff*, *ffi*, *ffl*, *ff*) are a hazard to typography. Ligatures required by the design of the individual typeface should always reside on the basic font.

ct sp

The *lexical* ligatures  $\alpha$ ,  $\alpha$ ,  $\alpha$  and  $\beta$  are bonafide Unicode characters, separately listed in this appendix. *Typographic* ligatures such as  $\beta$  and  $\beta$  are glyphs, not characters; they are now consigned to the 'private use' section of Unicode.

logical not See negation.

 $\int$ 

long s This taller form of s looks like f without its crossbar. (Note however that the roman form usually does have a spur on the left.) Long s was commonly used in English (used in English, used in English, used in English) through the end of the eighteenth century. It was then the normal form of s in initial and medial positions. Short s was used at the ends of words and (usually) as the second s in a pair. Long s + short s forms the ligature  $\beta$ , still used in German. Long s itself is still routinely used in blackletter though archaic in roman and italic. It often entails a substantial further set of ligatures – e.g.,  $\beta$  h h fi fk fl ff fi ffl. [U+017F]

long umlaut See double acute.

louse From *Filzlaus*, "pubic louse," a German name for the currency symbol placeholder (¤). Also known in English as a *sputnik*. Since the symbol is parasitic (it takes up space on the font but offers nothing in return), *louse* may be the better name. Having no true function, it has no authentic form. [U+00A4]

Ø

**lowline** This is a standard ISO character, positioned as a baseline rule. Not to be confused with the *underscore*. [U+005F]

a\_a

**macron** A diacritic used to mark long vowels –  $\bar{a}$   $\bar{e}$   $\bar{i}$   $\bar{o}$   $\bar{u}$  – in many languages: Fijian, Hausa, Latvian and Lithuanian, among others. It marks long vowels in romanized Arabic, Greek, Hebrew, Japanese, Sanskrit and other languages, and level tones in romanized Chinese. Some writers of Lakhota (Sioux) also use it to write de-aspirated consonants ( $\bar{c}$   $\bar{k}$   $\bar{p}$   $\bar{t}$ ). [U+0304]

a

midpoint An ancient European mark of punctuation, widely used in typography to flag items in a vertical list and to separate items in a horizontal line. A closely spaced midpoint is also often used to separate syllables or letters, especially in Catalan when one *l* adjoins another. (In Catalan as in Spanish, *ll* is treated as a single letter. When one *l* is adjacent to but separate from another, they are written *l·l*. Examples: the Catalan words *cel·les* [cells], *col·lecció* [collection] and *paral·lel*.) The same sign is used in mathematics for scalar multiplication and in symbolic logic for logical conjunction. Also called *interpoint*. [U+OOB7]

1.1

(Upper- and lowercase L + midpoint [L & l·] are needlessly treated by 150, and therefore by Unicode, as single characters: U+013F & +0140.)

mu The Greek lowercase m represents the prefix  $micro- = 10^{-6}$ . Thus milligrams is written mg and micrograms  $\mu g$ . (A millionth of a meter or micron, formerly written  $\mu$ , is now ordinarily written  $\mu m$ .) [U+03BC]

μ

musical signs Three elementary musical symbols – | # 4, the flat, sharp and natural – are needed for setting normal texts that make reference to standard European musical pitches and keys (Beethoven's Sonata Op. 110 in Al, Ennemond Gaultier's Suite for Lute in F#m, the drop from C# to C4, etc). These characters are, however, missing from most text fonts. (The octothorp is not an adequate substitute for the sharp.) [U+266D—266F]

b # 4

nang See underdot.

nasal hook See ogonek.

negation The negation sign used in the propositional calculus (symbolic logic) was formerly the swung dash ( $\sim$ ). Since the swung dash is also used as a sign of similarity, this created confusion. The usual form of the negation sign now is the angled dash ( $\neg$ ). This is part of the standard Iso Latin character set and is included on most digital text fonts, even though it is useless without the other logical operators, such as  $\cup \cap \land \lor \equiv$ , which are almost never found on text fonts. Also called *logical not*. [U+OOAC]

null Also known as a slashed or crossed zero. This glyph is used to distinguish zero from the letters O and o. But the null in its usual form is easily confused with slashed o ( $\emptyset$ ,  $\emptyset$ ), a letter of the alphabet in Danish and Norwegian, and even with the Greek letter phi ( $\varphi$ ,  $\varphi$ ). The crossed form of the null,  $\varphi$ , is also confusible with theta ( $\theta$ ). A null glyph is present on some text fonts and on many phonetic and technical fonts. (As an alternate form of zero, this glyph has no address of its own in Unicode.)

numeral sign See octothorp.

obelisk Also obelus (plural, obeli). Synonym for dagger.

**octothorp** Otherwise known as the numeral sign. It has also been used as a symbol for the pound avoirdupois, but this usage is now archaic. In cartography, it is a traditional symbol for *village*: eight fields around a central square. That is the source of its name. *Octothorp* means eight fields. [U+0023]

ogonek A diacritic used with vowels –  $q \neq i \neq q \neq -$  in Lithuanian, Navajo, Polish and other languages. Also called a *nasal hook*. Not to be confused with the cedilla, which is used with consonants and curves the other way. *Ogonek* is a Polish diminutive, meaning 'little tail.' It is also the Polish name for the stem of an apple. Vowels with ogonek are known as *tailed vowels*. A *reversed ogonek* is used in the Bashkir consonant 3. [U+0328]

ordinal a, ordinal o See letters.

C

overdot A diacritic used with consonants  $-\dot{c}$   $\dot{g}$   $\dot{m}$   $\dot{n}$   $\dot{z}$  – in Maltese, Polish, old Gaelic and romanized Sanskrit, and with vowels –  $\dot{e}$  and  $\dot{I}$  – in Lithuanian and Turkish. In phonetics, it is widely employed as a sign of palatalization. Often known by its Polish name, *kropka*. See also *dotless i and dotted I*. [U+O3O7]

Ċ

palatal hook A diacritic used in the Czech and Slovak alphabets to mark the so-called soft or palatal consonants. It usually looks like an apostrophe or single close quote but is differently fitted (cut closer on the left). In some fonts it also differs slightly from the apostrophe in shape and size. It combines with ascending lowercase consonants (d, l, t) and one capital (L). The uppercase forms of d and t are Ď and Ť (and Ľ is an alternate form of L). The caron form is used for both the caps and lower case of non-ascending letters (Č, č, Ř, ř). In Czech, both these forms of the diacritic are known as háček, "hook." Also sometimes called the apostrophe accent. See also undercomma. [U+030C]

ď

Ď

paragraph See pilcrow.

parentheses These are used as phrase markers in grammar and in mathematics, and sometimes to isolate figures or letters in a numerical or alphabetical list. [U+0028, +0029]

(a)

per cent Parts per hundred. Not to be confused with the symbol c/o, 'in care of,' which is also sometimes cut as a single character. [U+OO25]

%

per mille Parts per thousand (61% = 6.1%). Though it is very rarely needed in text typography, this sign has been given a place in the standard 150 Latin character set. [U+2030]

**‰** 

period The normal sign for the end of a sentence in all the languages of Europe. But it is also a letter of the alphabet in Tlingit, pronounced as a glottal stop, and in phonetics it is the sign of a syllable boundary. Also called *full point* or *full stop*. [U+O02E]

a.

**phonomark** The copyright symbol used for sound recordings. Also sometimes known, oddly, as the *publish* symbol. [U+2117]

P

pilcrow An old scribal mark used at the beginning of a paragraph or main text section. It is still used by typographers for that very

purpose, and occasionally as a reference mark. Well-designed faces offer pilcrows with some character -  $\P$   $\P$   $\P$   $\P$   $\P$   $\P$  - in preference to the overused, bland standard, ¶. [U+00B6]

pipe Despite its importance to computer programmers and its presence on the standard ASCII keyboard, the pipe has no function in typography. This is another key, and another slot in the font, that begs to be reassigned to something typographically useful. Also called a broken bar or parted rule. [U+00A6]

prime An abbreviation for feet (1' = 12") and for minutes of arc  $(60' = 1^{\circ})$ . Single and double primes should not be confused with apostrophes, dumb quotes or genuine quotation marks, though in some faces (frakturs especially) these glyphs may all have a similar shape and a pleasant slope. See also apostrophe, double prime, dumb quotes and quotation marks. [U+2032]

question In Spanish, the inverted question mark is used at the beginning of the phrase, in addition to the upright question mark at the end. [U+OO3F, +OOBF]

> quotation marks A standard 150 font includes four forms of guillemet and six forms of Anglo-Germanic quotation mark: '', "". One of these is also the apostrophe. Another is graphically identical to the comma but separately encloded. In English and Spanish, common usage is 'thus' and "thus"; in German, it is ,thus' and "thus". This parallels the difference in usage of guillemets. In the Romance languages, guillemets point outward; in German they normally point in: in French, "comme ça" et «comme ça»; in German, "auf diese Weise" und » diese Weise «. See also double prime, dumb quotes and prime. [U+2018-201F]

radical sign The sign of the square root, normally used in conjunction with the *vinculum*:  $\sqrt{10} = 3.16227766...[U+221A]$ 

registered trademark This is properly a superscript, though the (R) otherwise similar copyright symbol is not. [U+00AE]

reversed apostrophe(s) Mutant forms of the single and double ((( open quote. They appear in several American advertising and text faces cut in the first years of the twentieth century and in some made at the end of that century as well. [U+201B, +201F]

ring Also called *kroužek*. A diacritic used in Arikara, Cheyenne, Czech, Danish, Norwegian, Swedish and other languages. The Scandanavian *round A* (å, Å = IPA 5) is present on ISO text fonts, but û and  $\mathring{\mathbf{U}}$  (u with kroužek), just as common in Czech, must be found on an East European or pan-European font, or built from component parts. In Arikara and Cheyenne, the ring marks devoiced letters. Uppercase or small cap round A or A-ring is the symbol for ångström units ( $10^4$  Å =  $1 \mu m$ ). [U+030A]

å

ů

schwa A rotated e, representing a short, bland vowel (in the jargon of phonetics, a mid central unrounded vowel). It occurs in many African and Native American alphabets. Two uppercase forms are current in Africa:  $\exists$  and  $\partial$ . Note that the first of these is horizontally *mirrored* instead of rotated. [U+018E, +01DD, +0259.]

6

section A scribal form of double s, now used chiefly with reference to legal codes and statutes, when citing particular sections for reference. (The plural abbreviation, meaning sections, is written by doubling the symbol: §§.) [U+OOA7]

 $\S$ 

semicolon A grammatical marker, hybrid between colon and comma, derived from European scribal practice. In Greek, however, the same symbol is used as a question mark. [U+003B]

a;

slashed o This is a basic letter of the alphabet in Norwegian and Danish, generally corresponding to the Swedish ö. The lowercase form is also part of the IPA. Henrik Ibsen's last play, for example, was Når vi døde vågner, and one of his first was Fru Inger til Østråt. The letter is sometimes needed in English too, for setting names such as Jørgen Moe and Søren Kierkegaard. [U+00D8, +00F8]

ø Ø

solidus The fraction bar. Used with superior and inferior numbers to construct ad hoc fractions. The solidus was a Roman imperial coin introduced by Constantine in AD 309. There were 72 solidi to the libra, the Roman pound, and 25 denarii to the solidus. The British based their own imperial coinage and its symbols – £/s/d, for pounds, shillings and pence – on the Roman model, and solidus became in due course not only a byword for shilling but also the name of the slash mark with which shillings and pence were written. (Given the design and fitting of the characters on most modern type fonts, the solidus is now best used for fractions alone. An italic virgule is usually the best character for setting

5/9

references to British imperial money.) See also *virgule*, which is a separate character. [U+2044]

sputnik See louse.

square brackets These essentials of text typography are used for interpolations into quoted matter and as a secondary and inner set of parentheses. In the editing of classical texts, square brackets normally mark editorial *restorations* while angle brackets mark

normally mark editorial *restorations* while angle brackets mark editorial and conjectural insertions, and braces mark deletions. Double square brackets (rarely to be found except on technical fonts) are used by textual scholars to mark deletions made not by the editor but by the original author or scribe. In editing manu-

scripts and papyri, square brackets also mark hiatuses caused by physical damage. [U+005B, +005D]

\*\*swung dash A rare character in text but important in logic and mathematics as the sign of similarity (a ~ b) and in lexicography as a sign of repetition. The same sign has been used in symbolic logic to indicate negation, but to avoid confusion, the angular negation sign or logical not (¬) is preferred. In the eyes of 180 and Unicode, the swung dash found on computer keyboards is an ascii tilde – a character of use to computer programmers but meaningless to typographers. Most fonts actually carry a swung dash, not a tilde, in this position. To Unicode, the true swung dash has a different address, though not a different graphic form. The true tilde is different in every respect and functions only as a diacritic. [U+007E; +2053, +223C]

b h thorn A basic letter of the alphabet in Anglo-Saxon and Middle English, as well as in Icelandic: bótt bu langförull legðir.... Its sound is that of IPA θ: voiceless th, as in English thorn. Not to be confused with wynn. [U+00DE, +00FE]

tilde A diacritic used on vowels –  $\tilde{a}$   $\tilde{e}$   $\tilde{e}$   $\tilde{i}$   $\tilde{o}$   $\tilde{o}$   $\tilde{u}$   $\tilde{y}$  – in many languages (Estonian, Kikuyu, Portuguese, Twi, Vietnamese...) and on at least one consonant ( $\tilde{n}$ ) in many more.  $\tilde{A}$ ,  $\tilde{a}$ ,  $\tilde{N}$ ,  $\tilde{n}$ ,  $\tilde{O}$ ,  $\tilde{o}$  are found on standard 150 text fonts. Pan-European fonts include the old Greenlandic vowels  $\tilde{I}$ ,  $\tilde{i}$ ,  $\tilde{U}$ ,  $\tilde{u}$  as well. [U+O3O3]

trademark This is a superscript, found on most text fonts but useless except for commercial work. [U+2122]

a

a

turned undercomma This diacritic is a variant of the undercomma, used in the lowercase form of the Latvian soft g ( $\dot{g}$ ). The uppercase form of this letter is  $\dot{G}$ . (The g is the only palatalized Latvian letter that happens to have a descender.) See also *undercomma*. [U+0326, used in U+0123]

S

umlaut See diaeresis.

undercomma This is a variant form of the cedilla, popularized in the early twentieth century through the use of typewriters which lacked a real cedilla subscript. Through long habituation, it is now preferred to the cedilla by many writers and some typographers working in Latvian and Romanian. In these languages it is used to mark the soft (palatal) consonants:  $| \uparrow , \uparrow , \uparrow \rangle$  and their uppercase counterparts. It has become, in other words, a variant form of the *palatal hook*.

ņ

Because of its descender, Latvian lowercase palatal g (g) is marked with a raised and inverted form of this diacritic, the turned undercomma. [U+0326]

a

underscore A diacritic required for many African and Native American languages, and useful for some purposes in English. It is also used as an alternative to the underdot in setting romanized Arabic and Hebrew. To clear descenders, a repositioned version of the character is required. See also *lowline*. [U+0332]

a

unequal A useful symbol missing from most 150 text fonts. It is essential in setting mathematics and, on occasion, important in general text. [U+2260]

 $0 \neq 1$ 

vertical rule See bar.



**vinculum** An overbar or overline, used in mathematics ( $\sqrt{10}$ ) and in the sciences ( $\overline{AB}$ ) to signify the unity of a group. The name is Latin for *bond* or *chain*. [U+203E]



**virgule** An oblique stroke, used by medieval scribes and many later writers as a form of comma. It is also used to build *level* fractions (e.g.,  $\pi/3$ ), to represent a linebreak when verse is set as prose, and in dates, addresses and elsewhere as a sign of separation. In writing the Khoisan languages of western Africa, it is sometimes used to represent dental or lateral clicks. Also called *slash* or *front slash* (to distinguish it from the *backslash*). It is poorly positioned on many fonts and consequently needs some subtle editing. Compare *solidus*. [U+002F]

wedge Another name for the caron.

þ

wynn This is an archaic English predecessor of the modern letter w. It appears only in specialized fonts designed for medievalists, and it is all too easy to confuse with *thorn*, but out of faithfulness to the manuscript tradition, it is occasionally used in printing Middle English texts. [U+01BF, +01F7]

yen See currency symbols.

5

yogh This is an archaic Western European form of y, sometimes still used in Old and Middle English texts. The twelfth-century English poet Layamon, for example, wrote at a time when the English alphabet included aesc, eth, thorn and yogh, and the letter yogh appeared where we now put a y in Layamon's name: Lazamon. The pronunciation varies with context between the sound of y in English *layer* and that of g in German sagen. Yogh is very rarely found on text fonts. The numeral g is not an adequate substitute. g

NOTE: A number of reference works (including the first three editions of *The Unicode Standard*, both editions of Pullum & Ladusaw's *Phonetic Symbol Guide*, and the first two editions of *The Elements of Typographic Style*) fail to distinguish *yogh* from *ezh*. The two characters *can* be graphically identical and therefore can be realized by one in the same glyph, but they are different in origin and sound – and also different now in Unicode.

#### APPENDIX C: GLOSSARY OF TERMS

Names of individual characters and diacritics (circumflex, dyet, midpoint, virgule, etc) are not in this glossary. Look for them in appendix B. For summary definitions of historical categories (Renaissance, Baroque, etc), see chapter 7.

10/12 × 18 Ten on twelve by eighteen, which is to say, ten-point (10 pt) type set with 12 pt leading (2 pt extra lead, in addition to the body size of 10 pt, for a total of 12 pt from baseline to baseline) on a measure of 18 picas.

Abrupt and Adnate Serifs are either abrupt – meaning they break from the stem suddenly at an angle – or they are adnate, meaning that they flow smoothly into or out of the stem. In the older typographic literature, adnate serifs are generally described as bracketed.

Aldine Relating to the publishing house operated in Venice by Aldus Manutius between 1494 and 1515. Most of Aldus's type – which included roman, italic and Greek – was cut by Francesco Griffo of Bologna. Type that resembles Griffo's, like typography that resembles Aldus's, is called Aldine. Monotype Poliphilus and Bembo roman are Aldine revivals, though their companion italics are not. No Aldine italics or Aldine Greeks are in circulation at the present time.

Analphabetic A typographic symbol used with the alphabet but lacking a place in the alphabetical order. Diacritics such as the acute, umlaut, circumflex and caron are analphabetics. So are the asterisk, dagger, pilcrow, comma and parentheses.

Aperture The openings of letters such as C, c, S, s, a and e. Humanist faces such as Bembo and Centaur have large apertures, while Romantic faces such as Bodoni and Realist faces such as Helvetica have small apertures. Very large apertures occur in archaic Greek inscriptions and in typefaces such as Lithos, which are derived from them.

Axis In typography, the axis of a letter generally means the axis of the stroke, which in turn reveals the axis of the pen or other tool used to make the letter. If a letter has thick strokes and thin ones, find the thick strokes and extend them into lines. These lines reveal the axis (or axes; there may be several) of the letter. Not to be confused with slope.











cf

kp kp Ball Terminal A circular form at the end of the arm, leg or brow in letters such as a, c, f, j, r and y. Ball terminals are found in many romans and italics of the Romantic period, some Realist faces, and in many recent faces built on Romantic lines. Examples: Bodoni, Scotch Roman and Haas Clarendon. See also beak terminal and teardrop terminal.

Baseline Whether written by hand or set into type, the Latin lowercase alphabet implies an invisible staff consisting of at least four lines: topline, midline, baseline and beardline. The topline is the line reached by ascenders in letters like b, d, h, k, l. The midline marks the top of letters like a, c, e, m, x, and the top of the torso of letters like b, d, h. The baseline is the line on which all these letters rest. The beardline is the line reached by descenders in letters like p and q. The cap line, marking the top of uppercase letters like H, does not necessarily coincide with the topline of the lower case.

Round letters like e and o normally dent the baseline. Pointed letters like v and w normally pierce it, while the foot serifs of letters like h and m usually rest precisely upon it.

Bastarda A class of blackletter types. See page 266.

Beak Terminal A sharp spur, found particularly on the f, and also often on a, c, j, r and y, in many twentieth-century romans and, to a lesser degree, italics. Examples: Apollo, Berling, Calisto, Méridien, Perpetua, Pontifex, Veljović.

Bicameral A bicameral alphabet is two alphabets joined. The modern Latin alphabet, which you are reading, is an example. It has an upper and a lower case, as closely linked and yet as easy to distinguish as the Senate and the House of Representatives. Unicameral alphabets (the Arabic, Hebrew and Devanagari alphabets, for example) have only one case. Tricameral alphabets have three – and a normal font of roman type is tricameral, if it includes an upper case, a lower case and small caps.

Bilateral Extending to both sides. Bilateral serifs, which are always reflexive, are typical of roman faces, while unilateral serifs are typical of romans, Carolingians and italics.

Bitmap A digital image in unintelligent form. A letterform can be described morphologically, as a series of reference points and trajectories that mimic its perimeter, or embryologically, as the series of penstrokes that produce the form. Such descriptions are partially independent of size and position. The same image can also be described quite accurately but

cf

Aa

superficially as the addresses of all the dots (or *bits*) in its digital representation. This sort of description, a bitmap, ties the image to one orientation and size.

Blackletter Blackletter is to typography what Gothic is to architecture: a general name for a wide variety of forms that stem predominantly from the north of Europe. Like Gothic buildings, blackletter types can be massive or light. They are often tall and pointed, but sometimes round instead. Compare whiteletter. The categories of blackletter include bastarda, fraktur, quadrata, rotunda and textura. See page 266.



Bleed As a verb, to bleed means to reach to the edge of the printed page. As a noun, it means printed matter with no margin. If an image is printed so that it reaches beyond the trim line, it will bleed when the page is trimmed. Photographs, rules, solids and background screens or patterns are often allowed to bleed. Type can rarely do so.

Blind In letterpress work, printing blind means printing without ink, producing a colorless impression.

Blind Folio A page which is counted in the numbering sequence but carries no visible number.

Block Quotation A quotation set off from the main text, forming a paragraph of its own, often indented or set in a different face or smaller size than the main text. A *run-in quotation*, on the other hand, is run in with the main text and usually enclosed in quotation marks.

Body (1) In reference to foundry type: the actual block of type-metal from which the sculpted mirror-image of the printed letter protrudes. (2) In reference to phototype or digital type: the rectangular face of the metal block that the letter would be mounted on *if it were* three-dimensional metal instead of a two-dimensional image or bitmap. Retained as a fiction for use in sizing and spacing the type.

Body Size In graphic terms, the height of the face of the type, which in letterpress terms is the depth of the body of the type. Originally, this was the height of the face of the metal block on which each individual letter was cast. In digital type, it is the height of its imaginary equivalent, the rectangle defining the space owned by a given letter, and not the dimension of the letter itself. Body sizes are usually given in points – but European type sizes are often given in Didot points, which are 7% larger than the points used in Britain and North America.



Th

F

*Bowl* The generally round or elliptical forms which are the basic bodyshape of letters such as C, G, O in the upper case, and b, c, e, o, p in the lower case. Also called *eye*.

Cap Height The distance from baseline to cap line of an alphabet, which is the approximate height of the uppercase letters. It is often less, but sometimes greater, than the height of the ascending lowercase letters. See also baseline and x-height.

Chancery A class of cursive letterforms, generally featuring extra ligatures and lengthened and curved extenders. Many, but not all, chancery letterforms are also *swash* forms.

Cicero A unit of measure equal to 12 Didot points. This is the continental European counterpart to the British and American *pica*, but the cicero is slightly larger than the pica. It is equivalent to 4.52 mm or 0.178 inch. See *point*.

Color The darkness of the type as set in mass, which is not the same as the *weight* of the face itself. The spacing of words and letters, the leading of lines, and the incidence of capitals, not to mention the properties of the ink and of the paper it is printed on, all affect the color of the type.

Contrast In the analysis of letterforms, this usually refers to the degree of contrast between the thick strokes and thin strokes of a given letter. In Romantic faces such as Bulmer and Bodoni, the contrast is high. In unmodulated faces such as Gill Sans and Futura, contrast is low or nonexistent.

Counter The white space enclosed by a letterform, whether wholly enclosed, as in d or o, or partially, as in c or m.

Crosshead A heading or subhead centered over the text. Compare *sidehead*.

Cursive Flowing. Often used as a synonym for italic.

Dingbat A typographic glyph or symbol subject to scorn because it has no apparent relation to the alphabet. Many dingbats are pictograms – tiny pictures of churches, airplanes, skiers, telephones, and the like, used in the tourist industry. Others are more abstract symbols – check marks, crosses, cartographic symbols, the emblems of the suits of playing cards, and so on. Compare *fleuron* and *hedera*.

Dot Leader A row of evenly spaced periods or midpoints, occasionally used to link flush-left text with flush-right numerals in a table of contents or similar context. (There are none in this book.)

DPI Dots per inch. The usual measure of output *resolution* in digital typography and in laser printing.

00



Drop Cap A large initial capital or *versal* mortised into the text. (See page 64 for examples.) Compare *elevated cap*.

Drop Folio A folio (page number) dropped to the foot of the page when the folios on other pages are carried near the top. Drop folios are often used on chapter openings.

Dropline Paragraph A paragraph marked by dropping directly down one line space from the end of the previous paragraph, without going back to the left margin. (See page 40 for an example.)

Elevated Cap A large initial capital or versal rising up from the beginning of the text instead of nested down into it.

Em In linear measure, a distance equal to the type size, and in square measure, the square of the type size. Thus an em is 12 pt (or a 12 pt square) in 12 pt type, and 11 pt (or an 11 pt square) in 11 pt type. Also called mutton.

En Half an em. To avoid misunderstanding when instructions are given orally, typographers often speak of ems as *muttons* and ens as *nuts*.

Extenders Descenders and ascenders; i.e., any parts of the letterform that extend below the baseline, as in p and q, or above the midline, as in b, d and f.

Eye Synonym for bowl in the lower case. Large eye means large x-height, while open eye means large aperture.

FL Flush left, which means set with an even left margin. By implication, the right margin is ragged. To be more precise, one could write FL/RR, meaning flush left, ragged right.

FL&R Flush left and right, which is to say justified.

Fleuron A horticultural dingbat. That is to say, a typographic ornament ordinarily in the shape of a flower or leaf. Some fleurons are designed to be set in bulk and in combinations, to produce what amounts to typographic wallpaper.

Flush and Hung Set with the first line FL and subsequent lines indented, like the entries in this glossary.

Folio In bibliography, a page or leaf; but in typography, a folio is normally a typeset page *number*, not the page itself.

Font A set of sorts or glyphs. In the world of metal type, this means a given alphabet, with all its accessory characters, in a given size. In relation to phototype, it usually means the assortment of standard patterns forming the glyph palette, without regard to size, or the actual filmstrip or wheel on which these patterns are stored. In the world of digital type, the font is the glyph palette itself or the digital information

Glossary of Typographic Terms









encoding it. (The older British spelling, *fount*, has not only the same meaning but also the same pronunciation.)

Fore-edge The outside edge or margin of a book page; i.e., the edge or margin opposite the spine.

FR Flush right. With an even right margin. By implication, the left margin is ragged. The sidehead on this page is an example.

Fraktur A class of blackletter types. See page 266.

Glyph An incarnation of a character. See sort.

Typographic Gutter The blank column between two columns of type or the margins at the spine between two facing textblocks.

Hanging Figures Text figures.

Hair Space Normally M/24 or the width of a slip of paper.

Hard Space A word space that will not translate into a line-break. Also called *no-break space*.

Hint The letterforms that make up a digital font are usually defined mathematically in terms of outlines or templates, which can be freely scaled, rotated and moved about. When pages are composed, these outlines are given specific locations and sizes. They must then be rasterized: converted into solid forms made up of dots at the resolution of the output device. If the size is very small or the resolution low, the raster or grid will be coarse, and the dots will fill the mathematical template very imperfectly. Hints are the rules of compromise applied in this process of rasterization. At large sizes and high resolutions, they are irrelevant. At smaller sizes and lower resolutions, where distortion is inevitable, they are crucial. Hinted fonts include hints as integral parts of the font definition. See also bitmap.

Humanist Humanist letterforms originated among the humanists of the Italian Renaissance and persist to the present day. They are of two primary kinds: roman and italic, both of which derive from Roman capitals and Carolingian minuscules. Humanist letterforms show the clear trace of a broadnib pen held by a right-handed scribe. They have a modulated stroke and a humanist axis.

Humanist Axis An oblique stroke axis reflecting the natural inclination of the writing hand. See pp 12–15.

Inline A letter in which the inner portions of the main strokes have been carved away, leaving the edges more or less intact. Inline faces lighten the color while preserving the shapes and proportions of the original face. Outline letters, on the other hand, are produced by drawing a line around the outsides of



Glossary

the letters and removing the entire original form. Outline letters, in consequence, are fatter than the originals and have less definition. Castellar, Smaragd and Romulus Open Kapitalen are examples of inline faces.

IPA International Phonetic Association and its alphabet. The organization was founded in 1886. The alphabet is a set of phonetic letters, diacritics and tonemarks, widely used but – like any scientific system – subject to constant refinement and modification. (See page 299.)



180 International Organization for Standardization, headquartered in Geneva. An agency for international cooperation on industrial and scientific standards. Its membership consists of the national standards organizations of more than one hundred countries.

Italic A class of letterforms more cursive than roman but less cursive than script, developed from the Carolingian hand in fifteenth-century Italy. In most italics, the separate letters are implicitly connected by their *transitive* serifs.

Justify To adjust the length of the line so that it is flush left and right on the measure. Type in the Latin alphabet is commonly set either justified or FL/RR (flush left, ragged right).

Kern (1) Part of a letter that extends into the space of another. In many alphabets, the roman f has a kern to the right, the roman j a kern to the left, and the italic f one of each. (2) As a verb, to kern means to alter the fit of certain letter combinations – To or VA, for example – so that the limb of one projects over or under the body or limb of the other.



Lachrymal Terminal See teardrop terminal.

Lead [rhyming with red] Originally a strip of soft metal (type-metal or brass) used for vertical spacing between lines of type. Now meaning the vertical distance from the baseline of one line to the baseline of the next. Also called *leading*.

Lettrine Literally, 'a large letter.' Synonym for versal.

Ligature Two or more letters tied into a single character. The sequence ffi, for example, forms a ligature in most Latin text faces.



Lining Figures Figures of even height. Usually synonymous with *titling figures*, but some lining figures are smaller and lighter than the uppercase letters.

Logogram A specific typographic form tied to a certain word. Example: the nonstandard capitalizations in the names e.e. cummings, ΠαραΓραφ, TrueType and WordPerfect.

Lowercase Figures Synonym for text figures or old-style figures. M/3 A third of an em: e.g., 4 pt in 12 pt type; 8 pt in 24 pt type. Measure The standard length of the line; i.e., column width or width of the overall textblock, usually measured in picas.

Mid Space A space measuring M/4, a fourth of an em.

Modulation In relation to typography, modulation means a variation – usually cyclical and predictable – in the width of the stroke. In monochrome (unmodulated) letterforms such as Frutiger, the stroke is always fundamentally the same width. In a face such as Bembo or Centaur, the stroke is based on the trace of a broadnib pen, which makes thin cross strokes and thicker pull strokes. When letters are written with such an instrument, regular modulation automatically occurs.

Monotonic Modern Greek retains only one of the old tonic accent marks, the ὀξεῖα (oxeia) or acute. (Greek has often, in fact, been written and sometimes set this way, but the practice did not become official until 1982.) Fonts designed for setting Greek this way are known as monotonic. Their acute (renamed the tonos) is usually vertical. Compare polytonic.

Mutton An em. Also called mutton quad.

Negative Leading Leading – that is to say, line space – smaller than the body size. Type set 16/14, for example, is set with negative leading.

Neohumanist Recent letterforms that revive and reassert humanist principles are called neohumanist.

Nut An en.

Old-Style Figures (OSF) A common synonym for text figures.

Orthotic A class of Greek scripts and types that flourished in Western Europe between 1200 and 1520, revived in the early twentieth century. Orthotic Greeks are noncursive and usually bicameral. In other words, they are analogous to the roman form of Latin script. Both caps and lower case are usually upright. Serifs, when present, are usually short, abrupt and unilateral. The geometric figures of circle, line and triangle are usually prominent in their underlying structure. Victor Scholderer's New Hellenic is an example.

Pi Font A font of assorted mathematical or other symbols, designed to be used as an adjunct to one or more text fonts.

Pica A unit of measure equal to 12 points. Two different picas are in common use. (1) In traditional printers' measure, the pica is 4.22 mm or 0.166 inch: close to, but not exactly, one sixth of an inch. This is the customary British and American

e

e

άι

άι

unit for measuring the length of the line and the depth of the textblock. (2) The PostScript pica is precisely one sixth of an inch: 0.166666...". The difference between these units is roughly 0.03%. (Note: the continental European counterpart to the pica is the *cicero*, which is 7% larger.)

*Piece Fraction* A fraction (such as 5%4) that is not included in the font and must therefore be made on demand from separate components.

Point (1) In traditional British and American measure, a point is a twelfth of a pica, which makes it 0.3515 mm, or 0.01383 inch. In round numbers, there are 72 points per inch, or 28.5 points per centimeter. (2) In continental Europe a larger point, the Didot point, is used. The Didot point (one twelfth of a cicero) is 0.38 mm or 0.01483 inch. In round numbers, there are 26.5 Didot points per centimeter, or 67.5 per inch. (3) Nearly all digital typesetting devices, like the PostScript and TrueType languages they employ, make the point precisely ½ inch and the pica precisely one sixth of an inch.

Polytonic Classical Greek has been set since the fifteenth century with an array of tonic accents and other diacritics inherited from the Alexandrian scribes. These diacritics – oxeia (acute), bareia (grave), perispomene (circumflex), psili (smooth breathing), daseia (rough breathing), diaeresis and iota subscript – are used singly and in many combinations. Modern Greek retains only the acute (reinterpreted to a vertical mark called the tonos) and an occasional diaeresis. Greek fonts equipped with the full set of accents are accordingly known as polytonic Greeks, and modern Greek fonts as monotonic.

Quad An em. Also called mutton quad.

Quaint An antiquated sort or glyph, used to recreate the typographic flavor of a bygone age. The A, A and A ligatures, and the long s and its ligatures, are examples.

Ranging Figures Synonymous with lining figures.

Raster Digital grid. See hint.

Rationalist Axis Vertical axis, typical of Neoclassical and Romantic letterforms. See pp 12–13. Compare humanist axis.

Reflexive A type of serif that concludes the stroke of the pen by drawing back upon itself. Reflexive serifs are typical of roman faces, including the face in which these words are set. They always involve a sudden, small stoppage and reversal of the pen's direction, and more often than not they are bilateral. See also transitive.

Glossary of Typographic Terms







Glossary of Typographic Terms Resolution In digital typography, resolution is the fineness of the grain of the typeset image. It is usually measured in dots per inch (dpi). Laser printers, for example, generally have a resolution between 300 and 1200 dpi, and platemakers or typesetting machines a resolution significantly greater than 1200 dpi. The resolution of the conventional television screen is only about 50 dpi, and the resolution of most computer screens is also very low: between 72 and 133 dpi. But other factors besides resolution affect the apparent roughness or fineness of the typeset image. These factors include the inherent design of the characters, the skill with which they are digitized, the *hinting* technology used to compensate for coarse *rasterization*, and the nature of the surface on which they are reproduced.

Rotunda A class of blackletter types. See page 266.

RR Ragged right, which is to say unjustified.

Sanserif From the earlier English forms sans serif and sans surryphs, without serifs: synonymous with unserifed.

Serif A stroke added to the beginning or end of one of the main strokes of a letter. In the roman alphabet, serifs are usually reflexive finishing strokes, forming unilateral or bilateral stops. (They are unilateral if they project only to one side of the main stroke, like the serifs at the head of T and the foot of L, and bilateral if they project to both sides, like the serifs at the foot of T and the head of L.) Transitive serifs – smooth entry or exit strokes – are usual in italic.

There are many descriptive terms for serifs, especially as they have developed in roman faces. They may be not only unilateral or bilateral, but also long or short, thick or thin, pointed or blunt, abrupt or adnate, horizontal or vertical or oblique, tapered, triangular, and so on. In texturas and some frakturs, they are usually *scutulate* (diamond-shaped), and in some architectural scripts, such as Eaglefeather and Tekton, the serifs are virtually round.

Sidehead A heading or subhead set flush left (more rarely, flush right) or slightly indented. Compare crosshead.

Slab Serif An abrupt or adnate serif of the same thickness as the main stroke. Slab serifs are a hallmark of the so-called egyptian and clarendon types: two groups of Realist faces produced in substantial numbers since the early nineteenth century. Memphis, Rockwell and Serifa are examples. A more recent example is PMN Caecilia.

m

111

TL

ii

n

Slope The angle of inclination of the stems and extenders of letters. Most (but not all!) italics slope to the right at something between 2° and 20°. Not to be confused with axis.

Solid Set without additional *lead*, or with the line space equivalent to the type size. Type set 11/11 or 12/12, for example, is set solid.

Sort A single piece of metal type; thus a letter or other character in one particular style and size. In the world of digital type, where letters have no physical existence until printed, the word sort has been largely displaced by the word glyph. A glyph is a version – a conceptual, not material, incarnation – of the abstract symbol called a character. Thus, z and z are alternate glyphs (in the same face) for the same character.

Stem A main stroke that is more or less straight, not part of a bowl. The letter o has no stem; the letter l consists of stem and serifs alone.

Swash A letterform reveling in luxury. Some swash letters carry extra flourishes; others simply occupy an extra helping of space. Swash letters are usually cursive and swash typefaces therefore usually italic. True italic capitals (as distinct from sloped roman capitals) are usually swash. (The Caps in this Sentence are Examples.) Hermann Zapf's Zapf Renaissance italic and Robert Slimbach's Poetica are faces in which the swash can be extended to the lower case.

Teardrop Terminal A swelling, like a teardrop, at the end of the arm in letters such as a, c, f, g, j, r and y. This feature is typical of typefaces from the Late Renaissance, Baroque and Neoclassical periods, and is present in many recent faces built on Baroque or Neoclassical lines. Examples: Jannon, Van Dijck, Kis, Caslon, Fournier, Baskerville, Bell, Walbaum, Zapf International, Galliard. Also called *lachrymal terminal*. See also ball terminal and beak terminal.

Textblock The part of the page normally occupied by text.

Text Figures Figures – 123456 – designed to match the lowercase letters in size and color. Most text figures are ascending and descending forms. Also called *oldstyle figures*. Compare *lining figures*, ranging figures and titling figures.

Textura A class of blackletter types. See page 266.

Thick Space A space usually measuring M/3, a third of an em.

Thin Space In letterpress work, a space measuring M/5, a fifth of an em. In computer typesetting, sometimes understood as M/6 or M/8. Compare hair space, mid space and thick space.

dd g q

 $\mathcal{M}$ 

6

cf

М	М	м
3	4	5

Three-to-em One-third em. Also written M/3. See also thick.

Titling Figures Figures – 123456 – designed to match the up-

percase letters in size and color. Compare text figures.

 $\overline{m}$ 

Transitive A type of serif which flows directly into or out of the main stroke without stopping to reverse direction, typical of many italics. Transitive serifs are usually unilateral: they extend only to one side of the stem. See also *reflexive*.

Type Size See body size.

U&lc Upper and lower case: the normal form for setting text in the Latin, Greek and Cyrillic alphabets, all of which are now bicameral.

*Unicameral* Having only one case – like the Arabic, Hebrew, Thai and Tibetan scripts, and many roman titling faces. Compare *bicameral*.

*Unicode* A scheme, begun in 1988, for standardized encoding of all the characters in all the world's scripts. See page 181.

Versal A large initial capital, either elevated or dropped. Also called *lettrine*.

Weight The darkness (blackness) of a typeface, independent of its size. See also *color*.

ao

Whiteletter The generally light roman letterforms favored by humanist scribes and typographers in Italy in the fifteenth and sixteenth centuries, as distinct from the generally darker blackletter script and type used for ecclesiastical and legal texts. Whiteletter is the typographic counterpart to Romanesque in architecture, as blackletter is the counterpart to Gothic.

White Line A line space.

Word Space The space between words. When type is set FL/RR, the word space may be of fixed size. When the type is *justified*, the word space is usually elastic.

jxl

x-height The distance between the baseline and the midline of an alphabet, which is normally the approximate height of the unextended lowercase letters – a, c, e, m, n, o, r, s, u, v, w, x, z – and of the torso of b, d, h, k, p, q, y. The relation of x-height to cap height is an important characteristic of any bicameral Latin typeface, and the relation of x-height to extender length is a crucial property of any Latin or Greek lower case. See also baseline, cap height and eye.

A biographical index of designers important to typographic history, and of all those doing important work in the present day, would be a book in itself. The following list is little more than a cross-reference to important designers whose work is mentioned elsewhere in this book.

- LUDOVICO DEGLI ARRIGHI (c. 1480–1527) Italian calligrapher and designer of at least six chancery italic fonts. Frederic Warde's Vicenza and Arrighi (the italic companion to Centaur) are based on one of his faces. Monotype Blado (the italic companion to Poliphilus) is a rough approximation of another.
- ANTOINE AUGEREAU (c. 1490–1534) Parisian punchcutter and printer. Author of several text romans and at least one Greek. Along with his contemporary Simon de Colines, Augereau defined the style of French typography later identified with the name of his most famous apprentice, Claude Garamond. This activity came to an end when he was hanged and his corpse was publicly burnt, on Christmas Eve of 1534, for printing a psalm without permission.
- RICHARD AUSTIN (c. 1765–1830) English punchcutter producing Neoclassical and Romantic faces. He cut the original Bell type, the first Scotch Roman, and the original version of Porson Greek. W. A. Dwiggins's Caledonia is based primarily on Austin's work.
- JOHN BASKERVILLE (1706–1775) English calligrapher, printer and businessman. Designer of a series of Neoclassical romans, italics and one Greek. Most of the faces sold in his name are based on his work and some resemble it closely. His punches are now at the University Library, Cambridge, and the St Bride Printing Library, London. A set of original matrices, formerly in Paris, is now in the Frutiger Foundry, Münchenstein, Switzerland.
- LUCIAN BERNHARD (1885–1972) German immigrant to the USA. Painter, poet, industrial designer and typographer. Author of a large number of roman faces, distinguished by their long extenders. These were cut and cast primarily by ATE and Bauer.

- CHARLES BIGELOW (1945 ) American typographer and scholar. Codesigner, with Kris Holmes, of the Lucida family.
- ARCHIBALD BINNEY (1762–1838) Scottish immigrant to the USA. He was trained as a punchcutter in Edinburgh. With James Ronaldson, another Scottish immigrant, he established the Binney & Ronaldson Foundry in Philadelphia, where he cut Baroque, Neoclassical and Romantic type.

- FRANK BLOKLAND (1959 ) Dutch type designer and founder of the Dutch Type Library in 's-Hertogenbosch. His faces include Berenice and Documenta. His historical revivals include DTL Van den Keere and its companion, Guyot italic.
- GIAMBATTISTA BODONI (1740–1813) Italian punchcutter, printer and prolific designer of type, working at Rome and Parma. Bodoni is best known for his dark and razor-sharp Romantic romans, italics and sometimes wildly ornamental Greeks, but he also designed and cut a large number of Neoclassical fonts. Bauer Bodoni, Berthold Bodoni, and some of the other faces now sold in his name are based on his work. His punches are in the Museo Bodoniano, Parma.
- LUDOLF BORCHTORP (c. 1470–c. 1510) Polish mathematician and engraver. Author of the first fonts of Cyrillic type, which he evidently cut in Kraków about 1490, for the printer Szwajpolt Fiol.
- CHRIS BRAND (1921–1999) Dutch calligrapher, the designer of the Albertina family. Some of his finest work including the Hebrew face Zippora, the Elsschot family and the Denise italic has yet to be released.
- DAN CARR (1951– ) American punchcutter, poet, typographer and printer. Proprietor, with Julia Ferrari, of the Golgonooza Letter Foundry, Ashuelot, New Hampshire. Carr is one of the few active punchcutters now living. Designer and cutter of Regulus foundry roman and Parmenides foundry Greek; designer of the digital family Chêneau.
- MATTHEW CARTER (1937– ) English-born American type designer, punchcutter and scholar, based in Cambridge, Massachusetts. His text faces include Auriga, Charter, Galliard and Manutius; his titling faces include Mantinia and Sophia. His historical revivals include Wilson Greek.
- WILLIAM CASLON (1692–1766) English engraver, punchcutter and typefounder; author of many Baroque romans, italics, Greeks and other non-Latin faces. ATF Caslon, Monotype Caslon, and Carol Twombly's Adobe Caslon are closely based

- on his work. A collection of his punches is now in the St Bride Printing Library, London.
- warren Chappell (1904–1991) American book artist, trained in Germany, where he studied with Rudolf Koch. His type-faces include Trajanus, Lydian and the still unmanufactured Eichenauer.
- simon de colines (c. 1480–1547) French master printer, typographer and punchcutter. Author of a dozen or more roman fonts, several italics, several blackletters and a fine cursive Greek. Colines as much as any single person appears to be responsible for creating the typographic style of the French golden age. Garamond and Augereau were part of the same circle. None of Colines's faces has evidently yet been translated to digital form.

- CARL DAIR (1912–1967) Canadian book designer and typographer, working chiefly in Toronto. Designer of the Cartier family, which was left incomplete at Dair's death and later improved and completed by Rod McDonald.
- GERARD DANIËLS (1966– ) Dutch type designer and typographer, trained under Gerrit Noordzij in The Hague. Designer of Caspari.
- ISMAR DAVID (1910–1996) German-born American book designer, architect, graphic artist and type designer. His faces include David Hebrew, released by Intertype in 1954, and a number of photolettering faces still awaiting digital revival.
- GIOVANNI DEFACCIO (1966– ) Italian calligrapher. With Lui Karner, he is codesigner of the Rialto family, produced by their digital foundry *df* Type.
- FRANÇOIS-AMBROISE DIDOT (1730–1804) Parisian printer and publisher. Designer of several Neoclassical romans and italics, cut under his supervision by Pierre-Louis Vafflard. Father of Firmin Didot and founder of the Didot dynasty in printing and typography.
- FIRMIN DIDOT (1764–1836) Parisian printer and punchcutter; son of F.-A. Didot and student of Pierre-Louis Vafflard; father of Ambroise Firmin-Didot. Author of several Neoclassical faces as well as the Romantic fonts for which he is posthumously known. Monotype Didot and Linotype's digital Didot (drawn by Adrian Frutiger) are based on his work.
- BRAM DE DOES (1934- ) Dutch typographer, formerly chief designer at Joh. Enschedé en Zonen, Haarlem. Designer of the Trinité and Lexicon families.

WILLIAM ADDISON DWIGGINS (1880–1956) American designer and typographer. Dwiggins designed typefaces exclusively for the Linotype machine. In the 1930s and 1940s, he also created the typographic house style at Alfred Knopf, New York. His serifed faces include Caledonia, Eldorado, Electra and Falcon. His only completed sanserif is Metro. His one uncial face is Winchester. Many of his type drawings are now in the Boston Public Library.

- ALFRED FAIRBANK (1895–1982) English calligrapher and designer of Fairbank italic.
- AMBROISE FIRMIN-DIDOT (1790–1876) French scholar, typecutter and printer. He was the son of Firmin Didot (whose full name he took as his own surname) and grandson of François-Ambroise Didot. Author of the first Didot Greek fonts.
- JOHANN MICHAEL FLEISCHMAN (1701–1768) German-born punchcutter and founder working in the Netherlands. A prolific and skilled cutter of romans, italics and ornamental blackletters. Also the author of several Arabic and Greek fonts. His early romans and italics are Baroque, but in the 1730s he cut a series of text fonts idiosyncratic and self-conscious enough to be called Rococo. Most of his surviving material is now at the Enschedé Museum in Haarlem.
- KARL-ERIK FORSBERG (1914–1995) Swedish calligrapher and typographer, designer of the Berling text roman. His titling faces include Carolus, Ericus and Lunda.
- PIERRE SIMON FOURNIER (1712–1768) French printer and punchcutter. Author of many French Neoclassical fonts and typographic ornaments. Nearly all of his original material has been damaged or lost. Monotype Fournier and Barbou are based on his work, and W. A. Dwiggins's Electra owes much to the study of it.
- HENRI FRIEDLAENDER (1904–1996) Israeli book and type designer, born in France of a Dutch father and English mother, and trained primarily in Germany. In 1950, after twenty years on the drawing table, a trial casting of his Hadassah Hebrew family was made by the Amsterdam Foundry. After further revision, working versions were issued beginning in 1958.
- ADRIAN FRUTIGER (1928– ) Swiss immigrant to France. A prolific and versatile designer of type and signage. He was involved in the early transition from metal type to phototype. His serifed faces include Apollo, Breughel, Glypha, Iridium and Méridien. His sanserifs include Avenir, Frutiger, and

Univers. His titling and script types include Herculanum, Ondine, Pompeijana and Rusticana.

CLAUDE GARAMOND (c. 1490–1561) French punchcutter, working chiefly in Paris. Author of many roman fonts, at least two italics, and a full set of chancery Greeks. His surviving punches and matrices are now at the Plantin-Moretus Museum in Antwerp and at the Imprimerie Nationale, Paris. Stempel Garamond roman and italic, Linotype Granjon roman, Günter Gerhard Lange's Berthold Garamond roman, Robert Slimbach's Adobe Garamond roman, and Ronald Arnholm's Legacy italic are all based on his designs. Monotype Garamond is not. (See also pp 230–32.)

The spelling Garamont is now customary in France. The English spelling Garamond is derived from the Latin Garamondius, often used by Garamont himself.

- ERIC GILL (1882–1940) English engraver and stonecutter, working in England and Wales. His serifed faces include Joanna, Perpetua and Pilgrim. His one unserifed face is Gill Sans. Perpetua Greek is also his, but Gill Sans Greek is by other hands. Gill's type drawings are now in the St Bride Library, London. Some of the matrices and punches for his types are now at the University Library, Cambridge; others are in the Clark Library, Los Angeles but none of these punches were cut by Gill himself.
- FREDERIC GOUDY (1865–1947) American type designer and founder. His serifed faces include University of California Old Style (later adapted for machine composition as Californian), Deepdene, Italian Old Style, Kaatskill, Kennerley, Village N° 1 and Village N° 2. His blackletters include Franciscan, Goudy Text and Goudy Thirty. His titling faces include Forum, Goudy Old Style and Hadriano. Goudy Sans is his only unserifed face. His only uncial is Friar. Most of Goudy's original material was destroyed by fire in 1939. What survives is at the Rochester Institute of Technology.
- ROBERT GRANJON (c. 1513–1590) French typecutter working at Paris, Lyon, Antwerp, Frankfurt and Rome. Author of many Renaissance and Mannerist romans, italics, scripts, several Greeks, a Cyrillic, some Hebrews, and the first successful fonts of Arabic type. Some of his punches and matrices survive at the Plantin-Moretus Museum, Antwerp and the Nordiska Museet, Stockholm. Matthew Carter's Galliard is based primarily on Granjon's Ascendonica roman and italic.
- FRANCESCO GRIFFO (c. 1450–1518) Bolognese punchcutter, working in Venice, Bologna and elsewhere in Italy. Author of at least seven romans, three italics, four Greeks and a He-

Giovanni Mardersteig's postscript to Pietro Bembo. De Aetna (Verona: Officina Bodoni, 1969) gives a good introduction to Griffo's roman types and their derivatives. More important still is the series of essays collected in Mardersteig's Scritti (1988).

Complutensian means 'from Complutum,' which is the old Roman name for Alcalá. brew. None of Griffo's actual punches or matrices are known to survive, and the house of Aldus Manutius in Venice, where he did most of his work, has vanished. (The site is now occupied by a bank.) Griffo's letterforms have nonetheless been patiently reconstructed from the printed books in which his type appears. Giovanni Mardersteig's Griffo type is an exacting replica of one of Griffo's fonts. Monotype Bembo roman is based more loosely on the same font. Monotype Poliphilus is a rough reproduction of the same lower case with different caps. Mardersteig's Dante roman and italic are also based on a close study of Griffo's work. The italics, overall, have received far less attention than the romans.

ARNALDO GUILLÉN DE BROCAR (c. 1460–1524) Spanish master printer and typographer working at Alcalá de Henares, which is now a suburb of Madrid. Author of several romans and at least two Greek fonts. The most notable of these is the Complutensian Greek type, cut about 1510.

FRANÇOIS GUYOT (c. 1510–1570) Punchcutter and typefounder, born at Paris. He moved to Antwerp in the 1530s and spent most of the rest of his life there, cutting type for the printer Christophe Plantin and others.

- VICTOR HAMMER (1882–1967) Austrian-born printer working chiefly in Italy and the USA. All of Hammer's types are uncials. These include American Uncial, Andromache, Hammer Uncial, Pindar and Samson. His type drawings and punches are now at the University of Kentucky, Lexington.
- JONATHAN HOEFLER (1970– ) American type designer and digital founder. He established the Hoefler Type Foundry, New York, in 1989. Designer of Hoefler Text, Hoefler Titling, Gestalt, the Requiem family, and other faces.
- KRIS HOLMES (1950 ) American calligrapher. Designer of Isadora and Sierra; codesigner with Janice Fishman of Shannon, and with Charles Bigelow of the Lucida family.
- JOHN HUDSON (1968– ) English/Canadian type designer and expert in multilingual digital encoding. Designer of Aeneas and Manticore. Cofounder, with Ross Mills, of Tiro Typeworks in Vancouver.
- MARK JAMRA (1956 ) American typographer and graphic artist, trained in Switzerland. Designer of several artful postmodern faces, including Jamille, Latienne and Kinesis.
- JEAN JANNON (1580–1658) French punchcutter and printer. His romans and italics, cut at Paris and Sedan, appear to be the

first Baroque types ever made. Much of his material survives at the Imprimerie Nationale, Paris, where his type is known as the *caractères de l'université*. Monotype 'Garamond,' Linotype 'Garamond' 3, ATF 'Garamond,' Lanston 'Garamont' and Simoncini 'Garamond' are based on his work. (See pp 230–32.)

- NICOLAS JENSON (c. 1420–1480) French punchcutter and printer, working in Venice. Author of at least one roman, one Greek and five rotundas. Jenson's punches and matrices have long vanished, but his type has often been copied from his printed books. Bruce Rogers's Centaur, Ronald Arnholm's Legacy roman and Robert Slimbach's Adobe Jenson roman are based on his. Karlgeorg Hoefer's San Marco is based in large part on Jenson's rotundas.
- GEORGE WILLIAM JONES (1860–1942) English printer and type designer. Author of Linotype Estienne, Linotype Granjon, and the Venezia roman, which was later mated with an italic by Frederic Goudy. All Jones's faces are historical reconstructions. Linotype Granjon was the first commercial adaptation of a Garamond roman, mated with a Granjon italic.
- LUI KARNER (1948– ) Austrian typographer and letterpress printer. Codesigner, with Giovanni DeFaccio, of the Rialto family and partner in the digital foundry df Type.
- MIKLÓS TÓTFALUSI KIS (1650–1702) Hungarian scholar, printer and typecutter. Kis was trained in Amsterdam and worked there and in Kolozsvár (now Cluj, Romania). Stempel Janson is struck and cast primarily from his surviving punches. Linotype Janson Text (both the metal and digital versions) and Monotype Erhardt are based on his work.
- RUDOLF KOCH (1876–1934) German calligrapher and artist. His titling faces include Koch Antiqua and Neuland. His blackletters include Claudius, Jessen, Wallau and Wilhelm Klingspor Schrift. Kabel is his only sanserif. Much of his material, formerly in the Klingspor Archive, Offenbach, is now in the Haus für Industriekultur, Darmstadt.
- HENK KRIJGER (1914–1979) Dutch typographer and visual artist, born and raised in Sumba, Indonesia. His Indonesian name is Senggih. Designer of several titling faces, the most important of which is Raffia.
- JOOS LAMBRECHT (c. 1510–1556) Flemish punchcutter, typefounder and printer. Author of several fine romans, one italic and at least one textura. All of his original material has perished, but printed specimens survive.

In addition to his 16 pt roman, Jenson cut at least the caps for a 12 pt font. In addition to his five rotundas (ranging from 12 to 21 pt), he also cut at least the lower case for a sixth and smaller font.

- VADIM VLADIMIROVICH LAZURSKI (1909–1994) Russian calligrapher and book designer. His Lazurski family includes both Cyrillic and Latin alphabets. The Cyrillic also exists in a proprietary foundry version known as Pushkin.
- GUILLAUME LE BÉ *the elder* (1525–1598) French punchcutter working in Paris, Florence, Venice and Rome. Author of many Hebrew fonts, some fine romans and music types.

- HENRIC PIETERSZOON LETTERSNIDER (fl. 1492–1511) Dutch punchcutter working at Gouda, Antwerp, Rotterdam and Delft. Author of a substantial number of blackletter types and fonts of large initials.
- ZUZANA LIČKO (1961- ) Slovakian immigrant to the USA. Cofounder of *Emigre* magazine and its offshoot, the Emigre digital foundry. Designer of Journal, Electrix, Modula and other faces. With John Downer, codesigner of Triplex.
- RICHARD LIPTON (1953 ) American graphic artist. Designer of Arrus. Codesigner, with Jacqueline Sakwa, of the script face Cataneo.
- MARTIN MAJOOR (1960- ) Dutch graphic artist trained at the Arnhem Academy. Designer of the Scala and Seria families.
- GIOVANNI MARDERSTEIG (1892–1977) German immigrant to Italy. A master printer, scholar, typographer and type designer. Author of Dante, Fontana, Griffo and Zeno. His material is at the Officina Bodoni, Verona.
- GABRIEL MARTÍNEZ MEAVE (1972- ) Mexican type designer, working near Mexico City. His faces include Organica, Integra, Neocodex and Mexica.
- ROD MCDONALD (1947– ) Canadian graphic artist and type designer working in Toronto and, since 2002, in Halifax. His work includes the Laurentian family and Cartier Book, a family of type begun by Carl Dair.
- HANS EDUARD MEIER (1922 ) Swiss typographer. Designer of Barbedor, Syndor and the several versions of Syntax.
- JOSÉ MENDOZA Y ALMEIDA (1926—) French graphic artist and type designer, working in Paris. His faces include Mendoza, Photina, Pascal, Fidelio (a chancery script), Sully Jonquières (an upright italic) and Convention.
- OLDŘICH MENHART (1897–1962) Czech type designer and calligrapher. His serifed Latin faces include Figural, Menhart and Parliament. His Manuscript family includes both Latin and Cyrillic faces. His titling faces include Czech Uncial and Monument.

- WILLIAM ROSS MILLS (1970– ) Canadian type designer. Cofounder with John Hudson of Tiro Typeworks in Vancouver. Author of the Plantagenet Novus family (Latin, Greek and Cherokee) and two families of Canadian Syllabic type, Uqammaq and Pigiarniq, for setting Inuktitut. His historical revivals include the 1520 Garamond Roman.
- antonio di Bartolomeo Miscomini (c. 1445–c. 1495) Italian punchcutter and printer, probably born in Bologna. He did most of his work in Venice, Modena and Florence, where he printed during the early 1490s and brought his roman and orthotic Greek types to final form.

GERRIT NOORDZIJ (1950– ) Dutch typographer and teacher. From 1960 to 1990 he was responsible for training type designers at καβκ (Koninklijke Academie van Beeldende Kunsten: The Royal Academy of Fine Arts) in The Hague, and thereby profoundly affected the course of modern type design in the Netherlands and elsewhere. Only one of his own designs is publicly available at present: the Ruse family, issued in digital form by the Enschedé Font Foundry.

PETER MATTHIAS NOORDZIJ (1961– ) Dutch typographer and digital founder. Designer of PMN Caecilia and proprietor of the Enschedé Font Foundry.

- FRIEDRICH PETER (1933 ) Canadian calligrapher and visual artist, born in Dresden and trained in Berlin. Designer of the script faces Vivaldi and Magnificat.
- ALEXANDER PHEMISTER (1829–1894) Scottish punchcutter. Author of the Old Style Antique issued by Miller & Richard, Edinburgh, beginning in 1858. In 1861 he moved to Boston where he worked for the Dickenson Foundry.
- FRIEDRICH POPPL (1923–1982) German calligrapher. His serifed faces include Pontifex and Poppl Antiqua. His sanserif is Laudatio. His titling faces include Nero and Saladin. His script types include Poppl Exquisit and Residenz.
- JEAN-FRANÇOIS PORCHEZ (1964– ) French type designer; founder and proprietor of Porchez Typofonderie in Malakoff, near Paris. Designer of Angie, Apolline, Parisine, and the extensive Le Monde family, created for the Paris newspaper *Le Monde*.
- RICHARD PORSON (1759–1808) English classical scholar. He designed the original Porson Greek, which was cut in steel by Richard Austin. Monotype Porson and the digital GFS Porson are based closely on his work.

Type Designers

Noordzij's 'Ruse' was originally 'Rus-E' version E of a face designed for a Russian bibliography Specimens of five of his romans, four italics, two Greeks and one bastarda are included in Lommen & Verheul, *Haagse Letters* (1996).

- EUDALD PRADELL (1721–1788) Catalan punchcutter and typefounder, working in Barcelona and Madrid. Some of the best eighteenth-century Spanish books are printed in his types.
- VOJTĚCH PREISSIG (1873–1944) Czech artist, typographer and teacher, working in Czechoslovakia and in New York City. Preissig designed several text and titling faces, including the one that bears his name. His surviving drawings are in the Strahov Abbey, Prague.

- ERHARD RATDOLT (1447–1528) German punchcutter and printer working at Augsburg and Venice. Author of at least ten blackletters, three romans and one Greek. In 1486 he issued the first known type specimen. (The one surviving copy is in the Munich State Library.)
- IMRE REINER (1900–1987) Hungarian artist and designer working in Germany, the USA and Switzerland. He was a skilled wood engraver and book illustrator. Author of several Expressionist script faces.
- PAUL RENNER (1878–1956) German typographer, type designer and teacher. Designer of Futura, Renner Antiqua, Renner Grotesk and the blackletter Ballade. His drawings for Futura are now in the Fundición Tipográfica Bauer, Barcelona.
- JIM RIMMER (1934– ) Canadian punchcutter and type designer. He has produced digital revivals of several of Frederic Goudy's faces and made new text faces notably Amethyst and Albertan in similar spirit. His titling faces include Credo, a revival of Robert Foster's Pericles.
- BRUCE ROGERS (1870–1957) American typographer, working chiefly in Boston, London and Oxford. Designer of Montaigne and Centaur. The original drawings for Centaur are now in the Newberry Library, Chicago.
- SJOERD HENDRIK DE ROOS (1877–1962) Dutch designer, typographer and printer. Author of the uncials Libra and Simplex, the Nobel sanserif, and De Roos roman and italic.
- RUDOLPH RŮŽIČKA (1883–1978) Czech-born American typographer. Designer of Linotype Fairfield and Primer.
- JACQUES DE SANLECQUE the elder (1558–1648) French punchcutter, student of Guillaume Le Bé the elder. Author of several fine romans and italics, music type, and a number of non-Latin faces, including Armenian, Samaritan and Syriac.
- JACQUES DE SANLECQUE the younger (1613-1659) Son of the preceding. French punchcutter and founder revered for his technical finesse in cutting small sizes.

- VICTOR SCHOLDERER (1880–1971) English classical scholar and librarian. Designer of the New Hellenic Greek.
- FRANTSYSK HEORHII SKARYNA (c. 1488–c. 1540) Belarusian physician, translator and printer, educated at Kraków and Padova. Author of several fonts of Cyrillic type, with which he printed at Prague and Vilnius.
- ROBERT SLIMBACH (1956—) American type designer, on staff at Adobe since 1987. His faces include Cronos, Adobe Garamond, Giovanni, Minion, Poetica, Slimbach, Utopia, Kepler and Warnock. His script faces include Sanvito and Caflisch. The Myriad family is a joint design by Slimbach and Carol Twombly.

- FRED SMEIJERS (1961– ) Dutch typographer and type designer. Author of the Quadraat family, Reynard, and the useful book *Counterpunch*.
- ERIK SPIEKERMANN (1947 ) German graphic artist and one of the founders of the FontShop digital foundry. Designer of the Meta and Officina families.
- SUMNER STONE (1945 ) American type designer and first director of the type department at Adobe Systems. Author of Silica, Cycles, Stone Print, and of the Stone typeface family, which includes serifed, unserifed and 'informal' series.
- KONRAD SWEYNHEYM (c. 1415–1477) German monk and letterpress printer, working in central Italy. He is probably the author of the two romans and one Greek which he and his partner Arnold Pannartz used at Subiaco and Rome between 1464 and 1473.
- GIOVANANTONIO TAGLIENTE (fl. 1500–1525) Italian calligrapher and designer of at least one chancery italic type. Monotype Bembo italic is derived from this font.
- AMEET TAVERNIER (c. 1522–1570) Flemish typecutter and printer working primarily at Antwerp. Author of many romans, italics, blackletters and civilité script types.
- GEORG TRUMP (1896–1985) German artist and type designer, initially a pupil of Ernst Schneidler. His serifed text faces include Mauritius, Schadow and Trump Mediäval. His blackletters include Trump Deutsch. His titling faces and scripts include Codex, Delphin, Jaguar and Time.
- JAN TSCHICHOLD (1902–1974) German immigrant to Switzerland. Designer of the Sabon family and the Saskia script. Several of Tschichold's unproduced phototype designs were destroyed in the Second World War.

CAROL TWOMBLY (1959 – ) American type designer and visual artist. From 1988 to 1999 she was one of two type designers on staff at Adobe Systems. Her work includes the text family Chaparral and the titling faces Charlemagne, Lithos, Nueva, Trajan and Viva. Adobe Caslon is her digital revival of the work of William Caslon. With Robert Slimbach, she is the codesigner of the Myriad family.

- GERARD UNGER (1942 ) Dutch type designer and teacher. His serifed faces include Amerigo, Demos, Hollander, Oranda, Paradox and Swift. His unserifed faces include Argo, Flora and Praxis.
- HENDRIK VAN DEN KEERE (c. 1540–1580) Belgian typecutter, working at Ghent and Antwerp. He cut many romans and blackletters, at least one script type (a civilité) and several fonts of music type. DTL Van den Keere roman is based on his work.
- CHRISTOFFEL VAN DIJCK (1606–1669) Dutch punchcutter. Author of several Baroque romans, italics and blackletters. Monotype Van Dijck and DTL Elzevir are based on his work. Jan van Krimpen's Romanée and Gerard Unger's Hollander echo it in various ways. Most of Van Dijck's material has perished. The few surviving punches and matrices are at the Enschedé Museum, Haarlem.
- JAN VAN KRIMPEN (1892–1958) Dutch typographer, for many years chief designer at Joh. Enschedé en Zonen, Haarlem. His type designs include Lutetia, Romanée, Romulus, Sheldon, Spectrum, Haarlemmer, Cancelleresca Bastarda (a chancery italic), Romulus Sans, Antigone Greek, Double Augustin Open Capitals, Lutetia Open Capitals and Romulus Open Capitals. Except for Haarlemmer and Sheldon, all these faces were first cut at Enschedé by Paul Helmuth Rädisch. Much of his work is still awaiting digital revival.
- JOVICA VELJOVIĆ (1954– ) Calligrapher and type designer born in Kosovo, trained in Belgrade, now working in Germany. His types include Gamma, Esprit, Ex Ponto, Silentium and Veljović.
- JUSTUS ERICH WALBAUM (1768–1837) German typefounder and printer, author of several Neoclassical and Romantic faces. Both Berthold Walbaum and Monotype Walbaum are based on his surviving punches and matrices.
- FREDERIC WARDE (1894-1939) American typographer, working chiefly in France, Italy and England. Designer of the

Vicenza and Arrighi italics. Some of Warde's drawings are in the Newberry Library, Chicago. Punches and matrices for the early (handcut) Arrighi are now at the Rochester Institute of Technology.

rapher and type designer. Author of a fraktur, a textura (Weiss Gotisch), a rotunda (Weiss Rundgotisch), Weiss Antiqua roman and italic, a suite of typographic ornaments, and three series of titling caps or initials. All these were cut by Louis Hoell and issued by the Bauer Foundry, Frankfurt.

- ALEXANDER WILSON (1714–1786) Scottish punchcutter, typefounder and astronomer, working at Camlachie, near Glasgow. Author of the best romans, italics and Greeks produced in the Scottish Enlightenment.
- BERTHOLD WOLPE (1905–1989) German calligrapher and typographer who spent his later life in England. Pegasus is his text face. His titling faces include Albertus and Hyperion.
- HERMANN ZAPF (1918– ) German master calligrapher, type designer, artist and teacher. His types include the roman and italic faces Aldus, Comenius, Euler, Hunt Roman, Marconi, Melior, Optima, Orion, Palatino, Zapf Book and Zapf Renaissance; the blackletters Gilgengart, Winchester and Stratford; the titling faces Kompakt, Michelangelo, Sistina and Zapf International; the Greeks Attika, Euler, Heraklit, Optima, Palatino Greek and Phidias; and the script faces Venture, Zapf Chancery, Zapf Civilité and Zapfino.
- GUDRUN ZAPF-VON HESSE (1918– ) German calligrapher and book artist. Her text and titling faces include Alcuin, Carmina, Diotima, Nofret, Ariadne and Smaragd.

A reliable encyclopedia of the world's typefoundries – metal, photographic and digital; present and past – would be a very useful document. It would also be a thick one. This brief list is limited to metal and digital foundries and matrix engravers that have issued or preserved original designs that seem to me of lasting value for setting text in Latin, Greek or Cyrillic.

Many of the type designers listed in appendix D (Robert Granjon, William Caslon, Hendrik van den Keere, for instance) also cast and sold their own type. Their foundries are listed again here only if (1) the foundries outlived their founders and developed into independent entities or (2) they are currently active.

The phone numbers, fax numbers and physical locations of foundries are subject to frequent change. Under present conditions, so is their financial health and consequent legal status. Current information is obtainable through the internet and the trade press. Other useful references include the consolidated catalogues of vendors such as Precision Type, in Commack, New York, and FontShop in Berlin, and the websites of on-line retailers such as MyFonts and Identifont.

Adobe Systems, San Jose, Calif. Fundamentally a software company, founded in 1982 by John Warnock and Charles Geschke. Adobe was the original developer of the PostScript computer language – one of the foundation stones of digital typography. It is also, with Microsoft, co-creator of the OpenType font format. In the early 1980s it established a digital foundry and an ambitious type development program directed by Sumner Stone. Adobe has issued digital versions of many historical types as well as original designs by Robert Slimbach, Carol Twombly, Jovica Veljović and many others.

Agfa, Wilmington, Mass. In 1988 Agfa-Gevaert absorbed the Compugraphic Corporation, a manufacturer of photosetting machines and film matrices. A digital foundry known as Agfa-Compugraphic was then formed and passed from hand to hand (e.g., it was for a time part of the Bayer Corporation). In 1997, Agfa acquired the remains of Monotype, and in 1998 a new firm, Agfa Monotype, was formed. Agfa per se issued new designs by Otl Aicher, David Siegel and others.

Amsterdam Foundry, Amsterdam. A metal foundry established in Rotterdam in 1851 by Nicolaas Tetterode with stock from the Broese Foundry in Breda. The firm moved to Amsterdam in 1856 and in 1892 changed its name from Lettergieterij N. Tetterode to Lettergieterij Amsterdam. Typecasting operations waned in the 1970s and ceased altogether in 1988. During the twentieth century it issued new designs by Sjoerd de Roos and Dick Dooijes. The surviving matrices and other materials are now at the library of the University of Amsterdam.

**Typefoundries** 

ATF (American Type Founders), Elizabeth, New Jersey. This was the largest metal typefoundry in North America, formed in 1892 by amalgamating a number of smaller firms. In its best days, it issued original designs by M.F. Benton, Lucian Bernhard, Frederic Goudy and many others. Though the company began to falter in the 1920s, it clung to life until 1993. Its library is now at Columbia University, New York. Much of the older typographic material is in the Smithsonian Institution, Washington, DC.

Bauer Foundry, Frankfurt. A metal foundry established in 1837 by Johann Christian Bauer. It expanded into an international network toward the end of the nineteenth century. The Bauer Foundry as such ceased to exist in 1972, but one branch of the old empire – the Fundición Tipografica Bauer (FTB) in Barcelona – has survived. (It is separately described in this list.) Bauer issued original faces by its founder and later by Lucian Bernhard, Imre Reiner, Paul Renner, Emil Rudolf Weiss and others. The surviving punches and matrices are now at FTB in Barcelona and at wmd in Leipzig.

Berlingska Stilgjuteriet, Lund, Sweden. A metal typefoundry and printing house important for its castings, during the twentieth century, of original faces by Karl-Erik Forsberg.

H. Berthold, Berlin. Hermann Berthold's metalworks entered the typefounding business in 1893. It acquired the original punches and matrices of J. E. Walbaum and later issued original faces by Günter Gerhard Lange, Herbert Post, Imre Reiner and others. Berthold was involved in the creation of phototype as early as 1935. It ceased casting metal type in 1978 and turned to producing digital fonts in the 1980s. This activity all but ceased in 1993, but the company has resumed selling its own digital fonts. The foundry's collection of punches and matrices is now in the care of the Museum für Verkehr und Technik, Berlin.

Bitstream, Cambridge, Mass. A digital foundry established in 1981 by Matthew Carter and Mike Parker, both of whom later left the company. Bitstream has issued digital revivals of many earlier faces and new designs by Carter, John Downer, Richard Lipton, Gerard Unger, Gudrun Zapf-von Hesse and others.

**Typefoundries** 

Carter & Cone, Cambridge, Mass. A digital foundry established in 1992 by Matthew Carter and Cherie Cone. It issues original designs and historical revivals by Carter.

Caslon Foundry, London. A metal typefoundry established by William Caslon about 1723 and maintained as a family business for four generations. It survived as the firm of H.W. [Henry William] Caslon until 1936. Most of the older surviving punches are now in the St Bride Printing Library, London. The newer material passed to Stephenson, Blake. In 1998, Justin Howes acquired rights to the name H.W. Caslon & Co. Under this name, his digital foundry in Northamptonshire issues the series known as Founder's Caslon.

Deberny & Peignot, Paris. Joseph Gaspard Gillé the elder, one of Fournier's apprentices, opened his own foundry in Paris in 1748 and left the business to his son in 1789. In 1827, the novelist Honoré de Balzac acquired this foundry as part of his intended writing, printing and publishing empire. The scheme failed at once, but the foundry was rescued by its manager and bought by Alexandre de Berny.

Gustave Peignot entered separately into the typefounding business in 1865. His own foundry entered its first creative phase under his son and grandson Georges and Charles Peignot, who issued historical revivals of the work of Jean Jannon and created a series of types based on the lettering of the eighteenth-century engraver Nicolas Cochin.

The De Berny and Peignot foundries merged in 1923. Under the guidance of Charles Peignot, the enlarged firm issued new designs by Adolphe Cassandre, Adrian Frutiger and others. When D&P ceased production in 1975, the type drawings and company library went to the Bibliothèque Forney, Paris, and most of the typographic material – including a set of original Baskerville matrices – to the Haas (now Fruttiger) Foundry, Münchenstein. Baskerville's punches, also formerly held by D&P, are now at the University Library, Cambridge.

df Type, Texing, Austria. A digital foundry established in 1999 by the Venetian calligrapher Giovanni DeFaccio and the Austrian printer-typographer Lui Karner. The foundry issues the Rialto family and other text and titling faces, rooted in DeFaccio's calligraphy.

DTL (*Dutch Type Library*), 's-Hertogenbosch, Netherlands. A digital foundry established by Frank Blokland in 1990. It has issued original faces by Blokland, Chris Brand, Gerard Daniëls, Sjoerd de Roos, Gerard Unger and others, and historical revivals of types by Christoffel van Dijck, Jan van Krimpen, J.M. Fleischman and Hendrik van den Keere.

**Typefoundries** 

ΕΕΤS (Εταιρεία Ελληνικών Τυπογραφικών Στοιχείων). Listed here under its English name, GFS: *Greek Font Society*.

Elsner & Flake, Hamburg. A digital foundry established in 1989 by Günther Flake and Veronika Elsner. The firm has produced a large number of digital revivals and made the original digital versions of a number of LTC faces.

Emigre, Sacramento. A digital foundry established in Berkeley in 1985 by Rudy VanderLans and Zuzana Ličko. In 1992, the office moved to Sacramento. The firm issues original faces by Ličko, VanderLans, John Downer and others.

Joh. Enschedé en Zonen (Johann Enschedé & Sons), Haarlem, Netherlands. A printing plant and typefoundry operating from 1743 to 1990. In two and a half centuries of operation, the firm acquired material from many sources, including some of the punches and matrices of J.M. Fleischman and Christoffel van Dijck. During the early twentieth century, it issued in foundry form the types of its chief designer, Jan van Krimpen. In 1990, its stock of matrices and punches was transferred to the Enschedé Museum.

*The Enschedé Font Foundry*, Hurwenen, Netherlands. A digital foundry established in 1991 under the direction of Peter Matthias Noordzij. It has issued original designs by Bram de Does, Gerrit Noordzij, Christoph Noordzij, and Fred Smeijers.

Esselte Letraset, London. Letraset Ltd. was founded in 1959 as a manufacturer of dry transfer lettering. It was acquired by the Swiss firm Esselte in 1981 and a few years later began to issue its faces in digital form. The digital library now includes both historical revivals and original designs by Michael Gills, Michael Neugebauer and others.

Fann Street Foundry, London. A metal foundry established in 1802 by Robert Thorne. Its creative period came in the 1850s, when it was owned by Robert Besley and issued original designs cut by Benjamin Fox. The surviving material was acquired by Stephenson, Blake in 1905.

Font Bureau, Boston. A digital foundry established in 1989 by David Berlow and Roger Black. It has issued both historical revivals and original designs by John Downer, Tobias Frere-Jones, Richard Lipton, Greg Thompson and others.

FontShop International, Berlin. A digital foundry established in 1989 by Erik Spiekermann. It has issued original designs by Spiekermann, Erik van Blokland, Martin Majoor, Just van Rossum, Fred Smeijers and many others.

**Typefoundries** 

- Walter Fruttiger, Münchenstein, Switzerland. The Fruttiger Foundry, operating under this name since 1989, traces its roots to an operation founded by Jean Exertier in 1580. For more than two centuries it was known as the Haas Foundry, after Johann Wilhelm Haas, who acquired the company in 1740. It now possesses little material from before the eighteenth century, and in its long life has not been the source of many original faces. In the first half of the twentieth century, however, Haas issued new designs by Walter Diethelm and, in 1951, the first versions of Max Miedinger's Helvetica. It does possess some original Baskerville matrices, acquired by Haas from D&P.
- FTB (Fundición Tipográfica Bauer), Barcelona. A metal foundry established in 1885. It is the last surviving branch of the old Bauer network and now holds much of the Bauer Foundry's surviving typographic material. From 1922 to 1995 it was known as FTN, the Fundición Tipográfica Neufville a name still used by the digital arm of the company.
- Genzsch & Heyse, Hamburg. A metal foundry established in 1833 and absorbed by Linotype in 1963. It issued both blackletter and whiteletter types designed by Friedrich Bauer, Otto Hupp and others.
- Golgonooza Letter Foundry, Ashuelot, New Hampshire. Established in 1980 by Dan Carr and Julia Ferrari, who cast type from Monotype matrices and issue Carr's own faces, some cut by hand in steel and others created in digital form.
- *Grafotechna*, Prague. A metal typefoundry important for its castings of the work of Miloslav Fulín, Oldřich Menhart, Vojtěch Preissig and other Czech designers.
- GFS (*Greek Font Society*), Athens. A digital foundry established in 1992. It has issued digital versions of historically important Greek types designed by Ambroise Firmin-Didot, Richard Porson and Victor Scholderer, as well as new Greek designs by Takis Katsoulides and George Matthiopoulos.

Haas Foundry. See Walter Fruttiger.

Hoefler & Frere-Jones, New York. Jonathan Hoefler established his own digital foundry in Manhatten in 1989. In 2004 the name was changed to reflect the increased role of his associate Tobias Frere-Jones. The firm has produced important designs by Hoefler and useful digital revivals of the Fell types.

Dr-Ing. Rudolf Hell. See Linotype.

Imprimerie Nationale, Paris. A printing house and foundry established by Louis XIII in 1640 as the Imprimerie Royale. With the French Revolution (1789), the Imprimerie Royale became first l'Imprimerie Nationale and then l'Imprimerie de la République. With the coronation of Napoleon 1 in 1804, it became l'Imprimerie Impériale. After the Restoration of 1815, it was again l'Imprimerie Royale. In 1848, after two more revolutions, it was l'Imprimerie Nationale once more. It has retained this name ever since - except for the hiatus, 1852-1870, under Napoleon III, when it reverted to l'Imprimerie Impériale. It owns the surviving punches and matrices of Jean Jannon (the source of most of the world's 'Garamonds') and a large quantity of historically important material for the typography of Asian languages. Over the years it has sponsored new designs by many hands, including Firmin Didot, Philippe Grandjean, Marcellin Legrand, Louis-René Luce and José Mendoza y Almeida. It is the one surviving institution with punchcutters on salary.

Intertype (International Typesetting Machine Co.), New York. When the basic Mergenthaler Linotype patents expired in 1912, a group of investors had assembled in New York, ready to build a competing, and very similar, machine. Its matrices included new adaptations of foundry faces designed by Dick Dooijes and S.H. de Roos. The firm was involved in phototypesetting as early as 1947. After a merger in the 1950s, it was known as the Harris Intertype Corporation and became a principal manufacturer of photographic matrices.

Aaron Burns and Herb Lubalin in 1969 as a typeface licensing and distribution agency. The original domain was limited to phototype. In the 1980s, ITC began to license digital designs as well. Not until 1994 did it start to produce and market its faces directly. For more than a decade, there was a readily identifiable ITC style: a standardized large torso with interchangeable serifs that reduced the alphabet and its history to superficial costume. This Procrustean approach to type design

**Typefoundries** 

faded in the 1980s. Coincidentally, the company was bought in 1986 by Esselte Letraset. The list includes original designs by Ronald Arnholm, Matthew Carter, Erik Spiekermann, Hermann Zapf and many others.

**Typefoundries** 

Klingspor Brothers, Offenbach. A metal foundry established in 1842 and operated under several different names before its acquisition in 1892 by Karl Klingspor. It issued original faces by Peter Behrens, Rudolf Koch and Walter Tiemann. After its closure in 1953, the library and drawings were transferred to the Klingspor Museum, Offenbach, and most of the matrices to the Stempel Foundry, Frankfurt.

Lanston Monotype Machine Co., Philadelphia. The Monotype machine as we know it was devised by John Sellers Bancroft of Philadelphia in 1900. It grew, however, from a series of earlier machines invented by Tolbert Lanston of Washington, DC, beginning in 1887. The American company created to manufacture and sell these devices started slowly and was soon outdistanced by its English counterpart, formed a decade later with the same objective and almost the same name (see below: The Monotype Corporation). The American firm nevertheless remained in business, moving to Philadelphia in 1901 and pursuing on a smaller scale its own design agenda. This included cutting mats for historical revivals and original designs by Frederic Goudy, Sol Hess and others. The surviving material was dispersed in 1983.

Lanston Type Co., Mt Stewart, Prince Edward Island. In 1983 Gerald Giampa acquired a collection of patterns and drawings from the Lanston Monotype Company of Philadelphia. With this foundation, he established a digital foundry in Vancouver, moving to PEI in 1994. The library consists almost entirely of digitized versions of American Monotype faces, especially work by Frederic Goudy.

LetterPerfect, Seattle & New York. A digital foundry established in 1986 by Paul Shaw and Garret Boge. It has specialized in titling faces, including many with carefully researched inscriptional pedigrees.

Linotype Library, Bad Homburg. In Brooklyn in 1886, Ottmar Mergenthaler began to sell his newly invented Linotype machine. This led to the founding of the Mergenthaler Linotype Co., Brooklyn, and Mergenthaler Linotype & Machinery Ltd., Manchester, both in 1890. Their German ally, Mergenthaler Setzmaschinen-Fabrik, Berlin, was created in 1896. Many

of the early matrices were produced under contract by the Stempel Foundry, Frankfurt, from designs by artists such as Warren Chappell, Georg Trump and Hermann Zapf. Others were produced in England from the designs of George W. Jones, and in the USA from designs by W. A. Dwiggins, Rudolph Růžička and others.

Linotype began producing photosetting equipment in the 1950s, CRT (cathode ray tube) photosetters in the 1960s, and high-resolution laser setters in the 1980s. The German firm, which had relocated to Frankfurt in 1948, merged in 1990 with Dr.-Ing. Rudolf Hell Gmbh of Kiel.

In 1997, Linotype's digital foundry was spun off under the name the Linotype Library, which relocated to Bad Homburg, north of Frankfurt, in 1998. It has issued many of the old Linotype faces in digital form, and new designs by Adrian Frutiger, Hermann Zapf and many others. A large collection of early material from the American branch of the company is now at the Rochester Institute of Technology, Rochester, New York, and the University of Kentucky, Lexington.

The Ludlow Typograph Co., Chicago. Washington Ludlow of Chicago began making typecasting machinery in 1906, but the Ludlow caster which his company sold throughout the early twentieth century was a later device, designed and built by William Reade in 1909. The machine casts slugs from handset proprietary matrices and was therefore used for little except display type, but several Ludlow faces have been successfully adapted for digital text composition. The company issued both historical revivals and original designs, chiefly by its director of typography, R.H. Middleton. It ceased operation in North America in 1986. The English arm, founded in the early 1970s, closed in 1990.

Ludwig & Mayer, Frankfurt. A metal foundry established circa 1920 and closed in 1985. The surviving material was transferred to FTB in Barcelona. During its heyday, the firm issued original designs by Jakob Erbar, Helmut Matheis, Ilse Schüle and others.

Mergenthaler. See Linotype.

Miller & Richard, Edinburgh. A metal foundry established in 1809 by George Miller, joined by Walter Richard in 1832. The foundry issued original designs by Richard Austin, Alexander Phemister and others. When it ceased operation in 1952, the surviving material went to Stephenson, Blake.

**Typefoundries** 

The Monotype Corporation, Redhill, Surrey, England. An entity called the Lanston Monotype Company was first formed in the USA in 1887. Another, called the Lanston Monotype Corporation (later simply the Monotype Corporation) was formed in England a decade later. For the American firm, see Lanston Monotype.

## **Typefoundries**

The typographically creative phase of the English firm began in 1922 with the appointment of Stanley Morison as typographic advisor. Over the next few decades, English Monotype cut a number of meticulously researched historical revivals as well as new designs by Eric Gill, Giovanni Mardersteig, José Mendoza y Almeida, Victor Scholderer, Jan van Krimpen, Berthold Wolpe and others. The firm began producing photosetting equipment and photographic matrices in the 1950s, and laser typesetting machines in the 1970s.

In the early 1990s a new and smaller company, Monotype Typography, was spun off to produce and market digital type, including digital reincarnations of the faces originally cut in metal for the Monotype machine. This firm merged with Agfa in 1999, becoming Agfa Monotype. Metal matrices are still made on demand in England by the Monotype Trust.

Nebiolo Foundry, Torino. A metal typefoundry established in 1878 by Giovanni Nebiolo through the amalgamation of several older and smaller firms. It is important for its castings of original designs by Alessandro Butti and Aldo Novarese. Nebiolo ceased operation about 1990.

Neufville Foundry, Barcelona. See FTB.

Norstedt Foundry, Stockholm. A metal foundry, formerly supplied with matrices by Robert Granjon, François Guyot, Ameet Tavernier and others. The surviving material is now in the Nordiska Museet, Stockholm.

Fonderie Olive, Marseilles. A metal foundry which ceased operation in 1978. It issued a number of original designs by Roger Excoffon, François Ganeau and others. The surviving material is now at the Fruttiger Foundry, Münchenstein.

ParaType, Moscow. Successor (as of 1998) to the ParaGraph (or Parallel Graphics) digital foundry, which was founded in 1989. It issues original designs and historical revivals of Cyrillic, Latin, Georgian, Arabic, Hebrew and Greek faces.

Pie Tree Press & Foundry, New Westminster, British Columbia. Jim Rimmer's press and foundry, started in 1960, now produces both metal and digital type by Rimmer and others.

Plantin-Moretus Museum, Antwerp. The printing house and foundry established by Christophe Plantin about 1555 was conserved for nearly three centuries by descendants of Plantin's son-in-law, Jan Moretus. It was converted to a museum in 1877. It includes a rich collection of original material by Claude Garamond, Robert Granjon, Hendrik van den Keere, Ameet Tavernier and other early artists.

**Typefoundries** 

- Polygraphmash (НПО Полиграфмаш), Moscow. The Institute for Machine Printing. Its drawing office, active from 1938 to 1992, issued type designs by Galina Bannikova, Nikolai Kudryashev, Pavel Kuzanyan, Vadim Lazurski, Anatoli Shchukin and others.
- Scangraphic, Hamburg. Formerly Mannesmann Scangraphic, a manufacturer of photosetting equipment. In the 1980s it began to issue digital fonts. These were poorly finished but included one important design by Hermann Zapf.
- Schelter & Giesecke, Leipzig. Johann Gottfried Schelter and Christian Friedrich Giesecke established this foundry in 1819. Many of the early faces were designed by Schelter himself. In 1946 the firm was nationalized as Typoart.
- D. Stempel, Frankfurt. After its foundation by David Stempel in 1895, this firm absorbed the holdings of many other German foundries. It also issued many original faces by Hermann Zapf, Gudrun Zapf-von Hesse and others, and sold type cast from the original matrices of Miklós Kis. After the foundry closed in 1986, the typographic material was transferred to a museum known as the Haus für Industriekultur in Darmstadt. The tools of Stempel's last master punchcutter, August Rosenberger (who cut the original versions of Zapf's Palatino) are now in the Gutenberg Museum, Mainz.
- Stephenson, Blake & Co., Sheffield, England. A metal foundry established in 1819 by John Stephenson, James Blake and William Garnet, using materials acquired chiefly from William Caslon Iv. Over time, the firm has added further material from the Fann Street Foundry, the original Caslon Foundry, and other operations. Much of the inherited typographic material is now in the fledgling London Type Museum, though the company still casts and sells some type.
- Stone Type Foundry, Palo Alto. A digital foundry established in 1991 by Sumner Stone. It issues Cycles, Silica and other faces designed by its proprietor.

Tetterode. See Amsterdam Foundry.

Tiro Typeworks, Vancouver. A digital foundry established in 1994 by John Hudson and William Ross Mills. It is named for Marcus Tullius Tiro, the Roman slave (freed in 53 BC) who served as Cicero's scribe. Tiro has developed extensive expertise in the design and encoding of non-Latin faces, especially those involving many contextual alternates.

## **Typefoundries**

- Typoart, Dresden & Leipzig. A metal foundry formed in 1946 by nationalizing the existing operations of Schelter & Giesecke and Schriftguss. From 1964 until 1995, when operations ceased, the head of design was Albert Kapr. The surviving typographic material is now at WMD, Leipzig.
- URW (Unternehmensberatung Karow Rubow Weber), Hamburg. Established as a software firm in 1971, URW was diverted into digital typography by Peter Karow, a physicist excited by typography, who joined it in 1972. It was the original developer of the Ikarus system for digitizing type and of the Hz system for paragraph-based justification. It issued a large number of historical revivals as well as original faces by Hermann Zapf, Gudrun Zapf-von Hesse and others. The firm entered receivership in 1995. Its library has since been distributed by a corporate successor known as 'URW++.'
- Johannes Wagner, Ingolstadt. Established at Leipzig in 1902 by Ludwig Wagner and relocated to Ingolstadt in 1949 by his son Johannes. It has acquired matrices from Berthold, Johns, Weber and other foundries, and continues to cast type.
- C.E. Weber Foundry, Stuttgart. A metal foundry established in 1827. It issued original faces by Georg Trump and others before it closed in 1971. The surviving material was bought by the Stempel and by Wagner foundries.
- WMD (Werkstätten und Museum für Druckkunst), Leipzig. A working typographic museum founded in 1994 by Eckehart Schumacher-Gebler. Its large stock of typographic material includes original punches and matrices by Johann Christian Bauer, Lucian Bernhard, Jakob Erbar, Albert Kapr, Paul Renner, Jacques Sabon and many others.
- Y&Y, Carlisle, Mass. A digital foundry specializing in fonts and system software for the setting of mathematics and scientific texts. It has issued original designs by Charles Bigelow, Kris Holmes and Hermann Zapf.

The items flagged by small caps seem to me essential works of reference or benchmark publications in the field.

## 1. BOOKS & ARTICLES

- Adobe Systems Inc. *PostScript Language Reference Manual.* 3rd ed. Reading, Mass. 1999.
- Amert, Kay. "Origins of the French Old Style: The Types of Simon de Colines," *Printing History* 26/27 (1992): 17–40.
- Anderson, Donald M. *The Art of Written Forms*. New York. 1969.
- Avrin, Leila. Scribes, Script and Books: The Book Arts from Antiquity to the Renaissance. Chicago & London. 1991.
- Barker, Nicolas. *Aldus Manutius and the Development of Greek Script and Type in the Fifteenth Century.* 2nd ed. New York. 1992.
- Benjamin, Walter. "The Work of Art in the Age of Mechanical Reproduction," in Benjamin, *Illuminations*. London. 1970.
- Bennett, Paul A., ed. *Books and Printing: A Treasury for Typophiles*. Cleveland. 1951.
- Berry, John, ed. Language Culture Type: International Type Design in the Age of Unicode. New York. 2002.
- BIGELOW, Charles, & Donald DAY. "Digital Typography." Scientific American 249.2 (August 1983): 106-119.
- Bloomfield, Leonard. Language. New York. 1933.
- Blumenthal, Joseph. Art of the Printed Book, 1455–1955. New York. 1973.
- Bringhurst, Robert. "On the Classification of Letterforms" et seq. Parts 1–5. Claremont, Calif.: *Serif* 1–5 (1994–97).
- -----. The Solid Form of Language: An Essay on Writing and Meaning. Kentville, Nova Scotia. 2004.
- Burke, Christopher. Paul Renner. New York. 1998.
- CARTER, Harry. A View of Early Typography. Oxford. 1969.
- Carter, Sebastian. *Twentieth-Century Type Designers*. London & New York. 1987.
- Carter, Thomas F. *The Invention of Printing in China and Its Spread Westward.* 2nd ed, revised by L. Carrington Goodrich. New York. 1955.

- Catalogue of Books Printed in the xvth Century Now in the British Museum. 12 vols. London. 1908–85.
- Chappell, Warren, & Robert Bringhurst. A Short History of the Printed Word. 2nd ed. Vancouver. 1999.
- Chiang Yee. Chinese Calligraphy: An Introduction to Its Aesthetic and Technique. 3rd ed. Cambridge, Mass. 1973.
- Books & Articles
- Chicago Manual of Style. 15th ed. Chicago. 2003.
- Consuegra, David. American Type Design and Designers. New York. 2004.
- Coulmas, Florian. The Writing Systems of the World. Oxford. 1989.
- Dair, Carl. Design with Type. 2nd ed. Toronto. 1967.
- DANIELS, Peter T., & William BRIGHT, ed. The World's Writing Systems. New York. 1996.
- Davids, Betsy, & Jim Petrillo. "The Artist as Book Printer." In Joan Lyons, ed., Artists' Books. New York. 1985.
- Day, Kenneth, ed. Book Typography 1815-1965. London. 1966.
- DeFrancis, John. Visible Speech: The Diverse Oneness of Writing Systems. Honolulu. 1989.
- Degering, Hermann. Lettering. New York. 1965.
- Diringer, David. *The Hand-Produced Book*. London. 1953. Reprinted as *The Book Before Printing*, New York. 1982.
- Dowding, Geoffrey. Finer Points in the Spacing and Arrangement of Type. 3rd ed. London. 1966.
- Dreyfus, John, ed. *Type Specimen Facsimiles*. 2 vols. London. 1963-72.
- ———. The Work of Jan van Krimpen. The Hague. 1952.
- Duncan, Harry. Doors of Perception. Austin, Texas. 1987.
- EISENSTEIN, Elizabeth L. The Printing Press as an Agent of Change: Communications and Cultural Transformations in Early-Modern Europe. 2 vols. Cambridge, UK. 1979.
- ———. The Printing Revolution in Early Modern Europe. Cambridge, UK. 1983.
- Enschedé, Charles. *Typefoundries in the Netherlands*, translated with revisions and notes by Harry Carter. Haarlem, Netherlands. 1978.
- Fairbank, Alfred, & Berthold Wolpe. Renaissance Handwriting. London. 1960.
- Felici, James. *The Complete Manual of Typography*. Berkeley. 2003.
- Fine Print on Type: The Best of Fine Print Magazine on Type and Typography. San Francisco. 1988.

- Fournier, Pierre Simon. *Fournier on Typefounding*, translated & edited by Harry Carter. London. 1930.
- Friedlaender, Henri. Typographische ABC: Een beknopt overzicht der grondbeginselen van degelijke typographie. Den Haag. 1939.
- Gaur, Albertine. A History of Writing. London. 1984.
- Gelb, Ignace J. A Study of Writing. 2nd ed. Chicago. 1963.
- GILL, Eric. An Essay on Typography. 2nd ed. London. 1936.
- Goudy, Frederic W. *Goudy's Type Designs*. 2nd ed. New Rochelle, NY. 1978.
- ———. Typologia: Studies in Type Design and Type Making. Berkeley & Los Angeles. 1940.
- GRAY, Nicolete. A History of Lettering. Oxford. 1986.
- ------. *Lettering as Drawing.* 2 vols. Oxford. 1970. Reprinted as one vol., 1971.
- Grimes, Barbara F., ed. *Ethnologue: Languages of the World.* 14th ed. 2 vols. Dallas. 2000.
- [Grinevald, Paul-Marie.] *Les Caractères de l'Imprimerie nationale*. Paris. 1990.
- Handbook of the International Phonetic Association. Cambridge, UK. 1999.
- [HART, Horace, et al.] *Hart's Rules for Compositors and Readers*. 39th ed. Oxford. 1983.
- Hlavsa, Oldřich. A Book of Type and Design. New York. 1961.
- Huntley, H.E. *The Divine Proportion: A Study in Mathematical Beauty.* New York. 1970.
- Huss, Richard E. *The Development of Printers' Mechanical Typesetting Methods* 1822–1925. Charlottesville, Virginia. 1973.
- Hutner, Martin, & Jerry Kelly, ed. A Century for the Century: Fine Printed Books from 1900 to 1999. New York. 1999.
- International Organization for Standardization. *Information Processing: Eight-bit Single-byte Coded Graphic Character Sets.* 180 8859. Parts 1–9. Geneva. 1987–89.
- ------. Information Technology: Universal Multiple Octet Coded Character Set. 180 10646. Parts 1–3. [Rev. ed.] Geneva. 2000–2003.
- Искусство шрифта: Работы московских художников книги. Москва. 1977.
- Itten, Johannes. *The Art of Color*, translated by Ernst von Haagen. New York. 1961.
- JASPERT, W. Pincus, et al. *Encyclopedia of Typefaces*. 5th ed. London. 1983.

Further Reading

- Jeffery, Lilian H. *The Local Scripts of Archaic Greece*. 2nd ed. Oxford. 1990.
- Jensen, Hans. *Sign*, *Symbol*, *Script*, translated by George Unwin. London. 1970.
- JOHNSON, Alfred F. Selected Essays on Books and Printing. Amsterdam. 1970.
- Books & Articles
- Johnston, Edward. Formal Penmanship and Other Papers, edited by Heather Child. New York. 1971.
- ———. Writing and Illuminating and Lettering. Rev. ed. London. 1944.
- Kapr, Albert. The Art of Lettering. Munich/New York. 1983.
- ———. Fraktur: Form und Geschichte der gebrochenen Schriften. Mainz. 1993.
- \_\_\_\_\_. Johann Gutenberg. Aldershot, Hants. 1996.
- Karow, Peter. Digital Typefaces: Description and Formats. 2nd ed. Berlin. 1994.
- Kenney, Edward J. The Classical Text: Aspects of Editing in the Age of the Printed Book. Berkeley. 1974.
- Kinross, Robin. *Modern Typography: An Essay in Critical History.* London. 1992.
- Knight, Stan. *Historical Scripts*. 2nd ed. New Castle, Delaware. 1998.
- KNUTTEL, Gerard. *The Letter as a Work of Art.* Amsterdam. 1951.
- Koch, Peter, et al. Carving the Elements. Berkeley. 2004.
- Lange, Gerald. Printing Digital Type on the Hand-Operated Flatbed Cylinder Press. 2nd ed. Marina del Rey, Calif. 2001.
- Lawson, Alexander. Anatomy of a Typeface. Boston. 1990.
- Layton, Evro. *The Sixteenth Century Greek Book in Italy.* Venice. 1994.
- Le Bé, Guillaume [le jeune]. Sixteenth-Century French Typefounders, edited by Harry Carter. Paris. 1967.
- Le Corbusier. The Modulor. 2nd ed. Cambridge, Mass. 1954.
- Legros, Lucien A., & John C. Grant. *Typographical Printing Surfaces*. London. 1916.
- Lommen, Mathieu, & Peter Verheul, ed. *Haagse letters*. [Amsterdam.] 1996.
- Lunde, Ken. *CJKV Information Processing*. Sebastopol, California. 1999.
- McGrew, Mac. American Metal Typefaces of the Twentieth Century. New Castle, Delaware. 1993.

- McLean, Ruari. Jan Tschichold: Typographer. London. 1975.
- ———. Thames and Hudson Manual of Typography. London. 1980.
- Macrakis, Michael S., ed. *Greek Letters: From Tablets to Pixels.* New Castle, Delaware. [1997.]
- MARDERSTEIG, Giovanni. Scritti di Giovanni Mardersteig sulla storia dei caratteri e della tipografia. Milano. 1988.
- Martin, Douglas. *Book Design: A Practical Introduction*. New York. 1989.

Massin, [Robert]. Letter and Image. London. 1970.

Meggs, Philip B. A History of Graphic Design. New York. 1983.

Middendorp, Jan. Dutch Type. Rotterdam. 2004.

- Millington, Roy. Stephenson Blake: The Last of the Old English Typefounders. London. 2002.
- MORISON, Stanley. First Principles of Typography. New York. 1936.
- ———. Letter Forms: Typographic and Scriptorial. New York. 1968.
- ----. Politics and Script. Oxford. 1972.
- ——. Selected Essays on the History of Letter-forms. 2 vols. Cambridge, UK. 1981.
- Morison, Stanley, & Kenneth Day. *The Typographic Book*, 1450–1935. London. 1963.
- Morison, Stanley, et al. A *Tally of Types*. 2nd ed. Cambridge, Uκ. 1973.
- Mumford, Lewis. Art and Technics. New York. 1952.
- NOORDZIJ, Gerrit. The Stroke of the Pen. The Hague. 1982.
- ——. De Streek: Theorie van het schrift. Zaltbommel, Netherlands. 1985.
- Pankow, David, ed. *American Proprietary Typefaces*. [Rochester, NY.] 1998.
- Panofsky, Erwin. Perspective as Symbolic Form. New York. 1991.
- Paput, Christian. *La Gravure du poinçon typographique*. Paris. 1990.
- Parkes, M.B. Pause and Effect. Berkeley. 1993.
- Prestianni, John, ed. Calligraphic Type Design in the Digital Age. San Francisco. 2001.
- Pullum, Geoffrey K., & William A. Ladusaw. *Phonetic Symbol Guide*. 2nd ed. Chicago. 1996.
- Pye, David. The Nature and Art of Workmanship. Cambridge, UK. 1968.

Further Reading

- Re, Margaret, et al. Typographically Speaking: The Art of Matthew Carter. Baltimore. 2002.
- Ritter, Robert M. The Oxford Guide to Style. Oxford. 2002.
- ROGERS, Bruce. Report on the Typography of the Cambridge University Press. Cambridge, UK. 1950.
- Ryder, John. Flowers and Flourishes. London. 1976.

## Books & Articles

- Sampson, Geoffrey. Writing Systems: A Linguistic Introduction. Stanford, Calif. 1985.
- Scholderer, Victor. *Greek Printing Types 1465–1927.* London. 1927.
- Senner, Wayne M., ed. *The Origins of Writing*. Lincoln, Nebraska. 1989.
- Шицгал, А.Г. *Русский типографский шрифт.* Москва. 1985. Smeijers, Fred. *Counterpunch.* London. 1996.
- Snyder, Gertrude, & Alan Peckolick. *Herb Lubalin*. New York. 1985.
- Spencer, Herbert. *Pioneers of Modern Typography*. Rev. ed., Cambridge, Mass. 1982.
- STEINBERG, S.H. *Five Hundred Years of Printing.* 3rd ed., rev. by James Moran. London. 1974. 4th ed., rev. by John Trevitt. New Castle, Delaware. 1996.
- STEVENS, Peter S. Patterns in Nature. Boston. 1974.
- Stevick, Robert D. *The Earliest Irish and English Bookarts*. Philadelphia. 1994.
- SUTTON, James, & Alan BARTRAM. An Atlas of Typeforms. London. 1968.
- Thompson, Bradbury. *The Art of Graphic Design*. New Haven, Connecticut. 1988.
- THOMPSON, D'Arcy. *On Growth and Form*. Cambridge, UK. 1917. Rev. ed., 1942; abridged by J.T. Bonner, 1961.
- Tracy, Walter. Letters of Credit. London. 1986.
- Tschichold, Jan. Asymmetric Typography. New York. 1967.
- -----. *The Form of the Book*, edited by Robert Bringhurst. Vancouver. 1991.
- TUFTE, Edward R. *Envisioning Information*. Cheshire, Connecticut. 1990.
- ——. The Visual Display of Quantitative Information. 2nd ed. Cheshire, Connecticut. 2001.
- ——. Visual Explanations: Images and Quantities, Evidence and Narrative. Cheshire, Connecticut. 2001.
- Twitchett, Denis. *Printing and Publishing in Medieval China*. London. 1983.

- *Type and Typography: Highlights from Matrix.* West New York, NJ. 2003.
- UNICODE Consortium. *The Unicode Standard*. Version 4.0.0. Boston. 2003. [Online at www.unicode.org.]
- UPDIKE, Daniel Berkeley. *Printing Types: Their History, Forms and Use.* 2nd ed. 2 vols. Cambridge, Mass. 1937.
- Vervliet, H.D.L. Cyrillic and Oriental Typography in Rome at the End of the Sixteenth Century: An Inquiry into the Work of Robert Granjon. Berkeley. 1981.

Further Reading

- Sixteenth-Century Printing Types of the Low
  Countries, translated by Harry Carter. Amsterdam. 1968.
  , ed. The Book through Five Thousand Years. London. 1972.
- Veyrin-Forrer, Jeanne. La Lettre et la texte. Paris. 1987.
- Warde, Beatrice. The Crystal Goblet. London. 1955.
- WARDROP, James. The Script of Humanism. Oxford. 1963.
- washburn, Dorothy K., & Donald W. Crowe. Symmetries of Culture: Theory and Practice of Plane Pattern Analysis. Seattle. 1988.
- West, Martin L. Textual Criticism and Editorial Technique Applicable to Greek and Latin Texts. Stuttgart. 1973.
- Wick, Karl. Rules for Typesetting Mathematics. Prague. 1965.
- Williamson, Hugh. Methods of Book Design. London. 1983.
- Wilson, Adrian. The Design of Books. New York. 1967.
- Yardeni, Ada. The Book of Hebrew Script. Jerusalem. 1991.
- ZAPF, Hermann. The Fine Art of Letters. New York. 2000.
- -----. Hermann Zapf and His Design Philosophy. Chicago. 1987.
- ———. *Manuale Typographicum*. Frankfurt. 1954. Rev. ed., Cambridge, Mass. 1970.
- ———. *Manuale Typographicum 1968*. Frankfurt & New York. 1968.
- ——. *Typographic Variations*. New York. 1963. Reissued, New Rochelle, NY. 1978.
- Zimmer, Szczepan K. *The Beginning of Cyrillic Printing*. New York. 1983.

## 2. PERIODICALS

Fine Print. San Francisco. Quarterly. 16 vols, 1975–90. [Complete index published as issue 16.4, 2003. See also Fine Print on Type (1988).]

The Fleuron. Cambridge, UK. Annual. 7 vols, 1923–30. Journal of the Printing Historical Society. London. Annual, 1965–.

Letter Arts Review. Published 1982–93 as Calligraphy Review. Norman, Oklahoma. Quarterly, 1982– .

Further Reading

- Letterletter. Journal of the Association Typographique Internationale. Münchenstein, Switzerland. Semiannual through 1990, then biennial. 15 issues in all, 1985–96. [See also Gerrit Noordzij, Letterletter (2001).]
- Matrix. Andoversford, Glos. Irregular, 1981 . [See also *Type and Typography: Highlights from Matrix* (2003).]
- Parenthesis. Journal of the Fine Press Book Association. London, San Francisco, etc. Irregular, then semiannual, 1993-.
- Printing History. Journal of the American Printing History Association. New York. Semiannual, 1979 .
- Serif. Claremont, California. Irregular. 6 issues, 1994–98. Typografische Monatsblätter. St Gallen, Switzerland. Monthly, then bimonthly, 1881– .
- *Typographica*. London. Irregular, then semiannual. 13 + 16 issues. 1949–59; new series, 1960–67.

Typography Papers. Reading, Berks. Annual, 1996 - . Visible Language. Published 1967-70 as the Journal of Typographic Research. Cleveland. Quarterly, 1967 - .

## 3. A SAMPLING OF WEB RESOURCES

Alphabets of Europe: www.evertype.com/alphabets
Ethnologue: www.ethnologue.com/web.asp
International Phonetic Association: www.arts.gla.ac.uk/IPA/
ipa.html

Microsoft Digital Foundry List: www.microsoft.com/ typography/links/links.asp?type=foundries&part=1 Omniglot: www.omniglot.com/writing/atoz.htm Type Libraries & Museums: www.tug.org/museums.html Unicode: www.unicode.org Typography, like language, is more important to me for what it allows to happen than for anything it accomplishes on its own. I hope that in writing a book on the subject I have not given the

impression that either typography or design is an end in itself.

A few old friends and typographic mentors are mentioned in the foreword. I owe thanks to many others. These include Christian Axel-Nilsson, Charles Bigelow, Frank Blokland, Fred Brady, Dan Carr, Matthew Carter, Sebastiano Cossia Castiglioni, Bur Davis, James Đỗ Bá Phưôc, Bram de Does, the late John Dreyfus, Paul Hayden Duensing, Richard Eckersley, Peter Enneson, Christer Hellmark, Richard Hendel, Sjaak Hubregtse, John Hudson, Peter Karow, Peter Koch, John Lane, Ken Lunde, Linnea Lundquist, Jim Lyles, Rod McDonald, the late Michael Macrakis, George Matthiopoulos, William Ross Mills, Thomas Milo, Gerrit Noordzij, Peter Matthias Noordzij, Thomas Phinney, Will Powers, lim Rimmer, Richard Seibert, Robert Slimbach, Jack Stauffacher, Sumner Stone, Adam Twardoch, Carol Twombly, Gerard Unger, Ken Whistler, Glenda Wilshire, Vladimir Yefimov, Doyald Young and Maxim Zhukov - who have made this a much better book, and its author a less ignorant human being, in a variety of ways.

Translations of the work – especially those into Russian and Greek – have put me increasingly in touch with typographers far more at home than I with Greek, Cyrillic and other non-Latin type. Their careful reading and engagement with the text has taught me many things. In this regard, I'm especially grateful to Vladimir Yefimov and Maxim Zhukov.

Most of the drawings were made by hand for the original edition and recreated for the second in digital form by Glenn Woodsworth.

For those concerned about such things, I might record that the first edition of this book was set in Ventura Publisher software, the second edition in Quark, and the third in InDesign. With each such shift has come a marked increase in technical capability. I have still, in every case, been obliged at times to subvert the software, forcing it to do things its makers didn't foresee, or things they did foresee and expressly excluded.

The book has involved the close testing of many fonts of type, most of them digital, some of them metal. These have come from

nearly all the active foundries listed in appendix E, and from some whose operations have now ceased.

It remains the case that I have never yet tested a perfect font, no matter whether it came in the form of foundry metal, a matrix case, a strip of film or digital information. I have tested very beautiful and powerful designs, and extraordinary feats of hardware and software engineering, but no font has crossed my path that could not be improved by sensitive editing. One reason is, the task is never done: no designer can foresee the inner logic of all possible texts and languages, nor all the other uses to which type is rightly put. Another reason is that setting type is a collaborative exercise, like acting from a script or playing from a score. The editing of type, like the editing of music, and the tuning of fonts, like the tuning of instruments, never ends.

Afterword to the Third Edition

There are those who dream of a perfect world in which copyrighted text is translated into copyrighted glyphs through copyrighted rules with no more human intervention than it takes to feed a tape to a machine, while money flows in perpetuity to everyone involved. There are also those who think that putting chairs and air-conditioners in hell will make it just as good as heaven. Actually, working with type is an earthly task, much less like sitting down and turning on TV than like walking on your hands across an ever-varied, never-ending landscape that is otherwise too far away to see.

## INDEX

The names of typefaces are italicized in this index, but no distinction is made between generic names, such as *Garamond* or *Bodoni*, and specific ones, such as *Bembo* or *Aldus*.

abbreviations 30

punctuation of 88 accents see diacritics acronyms 30, 48-49, 88 acute accent 301 Adobe Systems 184, 199, 346, &c Aeneas 338 aesc 50, 288, 289, 301 African languages 116, 288-95, 319 see also Hausa; Khoisan languages Agfa Monotype 199, 207, 346 see also Monotype Aicher, Otl 346 Akhmatova, Anna 110 Akzidenz Grotesk 97, 132 Albanian 91, 291, 306 Albertan 213, 342 Albertina 213, 275, 280, 334 Albertus 282, 287, 345 Alcuin 100, 120, 212, 213, 247, 345 Aldine types 125, 225, 321 Aldus 52, 64, 78, 96, 104, 137, 214-15, 277, 282, 284, 345 alpha iota 301 Amasis 94 American Standard Code for Information Interchange (ASCII) 180 American Type Founders (ATF) 100, 141, 212, 347 American Uncial 269, 338 Amerigo 344 Amethyst 215, 342 ampersand 78, 301 Amsterdam Type Foundry 347 analphabetics 75-92, 300-320, 321 Andromache 338 Angelico, Fra 284 angle brackets 302 angle quotes see guillemets Anglo-Saxon 288-89, 301, 308, 318, 320 Antigone 274, 275, 344

antiqua, defined 84

aperture 12, 97, 119, 120, 132, 321 Apollinaire, Guillaume 21 Apolline 341 Apollo 104, 139, 215, 238, 257, 336 apostrophe 87-88, 302, 310 reversed 316 apprenticeship system 139 Arabic 23, 65, 106, 111, 114, 142, 181, 184, 186, 205, 291-95, 303, 310, 311, 313, 319, 322, 336, 337 arch (diacritic) 302 architectural scripts 270-71 Architype Renner 212 Argo 344 Ariadne 226, 282, 345 arithmetical signs 302, 319, 320 Armenian 142, 343 Arnholm, Ronald 53, 222, 234, 235, 258, 339, 352 Arnold, Matthew 191 Arrighi 32, 67, 79, 124, 140, 186, 206, 217, 222, 233, 333, 345 Arrighi, Ludovico degli 85, 124, 140, 173, 222, 227, 235, 243, 244, 333 Arrus 215, 340 artistic styles & typography 119-42 ASCII 180 Asian languages 201, 288-95 asterisk 77, 303 asymmetry 164 at sign 303 ATF see American Type Founders Athapaskan languages 301 Attika 345 Augereau, Antoine 230, 333 Augustea 282, 287 Auriga 334 Austin, Richard 47, 129, 216, 228, 278, 333, 341, 353 Avant Garde 282, 287 Avenir 336 Avestan 117 axis (of letterforms) 12, 123, 127, 128, 321, 325, 329 back matter 72-73 see also endnotes backslash 303

Bahasa Indonesia 91 bicycle racing & typography 95 Bigelow, Charles 58, 258, 334, 338, 356 Baker, Arthur 270 Bikol 91 Ballade 342 Balzac, Honoré de 348 bilingual typography Bancroft, John Sellers 137, 352 see multilingual typography Bannikova, Galina 279, 355 binding 195 bar 303, 307, 316 Binney, Archibald 334 Barbedor 340 bitmapped fonts 182 Barbou 229, 336 bitmaps 182, 322-23 Baroque 12, 51, 57, 84, 86, 94, 97, 98, 101, Bitstream 348, &c 126-27, 128, 221, 228, 229, 231, 235, type taxonomy 202-3 252, 260, 276, 336, 339 Black, Roger 350 baseline 322 blackletter 32, 103, 127, 266-68, 323, 339 Baskerville 51, 56, 77, 82, 84, 85, 96-98, Blado 79, 140, 206, 241, 243, 333 Blado, Antonio 243 97, 98, 104, 105, 129, 206, 209, 216, 273, 331 Blake, James 355 Cyrillic 279, 280 blam 288, 292 Baskerville, John 77, 97, 129, 138, 188, bleed (in printing) 323 211, 216, 218, 228-29, 274, 333, 348 Blokland, Erik van 350 Basque 91, 290-94 Blokland, Frank 122, 226, 233, 252, 258, bastarda 266, 267, 322 334, 349 Bauer, Johann Christian 267, 347, 356 Bodoni 37, 94, 105, 106, 131, 217, 279, Bauer Foundry 212, 347, &c 324, 334 Behrens, Peter 352 Greek 113, 276 Belarusian 298-99, 304 Bodoni, Giambattista 106, 128, 131, 211, 217, 228, 253, 274, 276, 334 Bell 47, 95, 99, 129, 216, 228, 249, 331 Bell, John 47, 129, 216 body (of type) 323 Bell, Marvin 99 Boge, Garret 352 Bembo 37, 51, 84, 93, 94, 96, 104, 105, boldface 53-56, 60, 103-5 122, 124, 125, 140, 216-17, 227, 242, Borchtorp, Ludolf 279, 334 bowl (of letterform) 324 243, 244, 338 Bembo, Pietro: De Aetna 217 braces 303-4 Bengali 181 brackets 76-77, 84-85, 302, 304, 318 Benjamin, Walter 19 Brand, Chris 213, 275, 280, 334, 349 Benton, Morris Fuller 132, 218, 222, Breton 91, 306 223, 231, 234, 347 Breughel 336 Beowolf 190 breve 304 Broese Foundry 347 Berenice 334 Berkeley 219, 220 bullet 304 Berling 84, 85, 217, 322, 336 Bulmer 131, 218, 324 Berling Foundry 347 Bulmer, William 218 Burns, Aaron 351 Berlow, David 206, 219, 350 Bernard, Saint, of Clairvaux 267 Butti, Alessandro 282, 354 Bernhard, Lucian 333, 347, 356 Byron, George Gordon 217 Berry, Jean, duc du 267 Caecilia 94, 112, 218, 331, 341 Berthold, Hermann 347 Berthold Foundry 132, 348, &c Caecilia Metella 218 Besley, Robert 131-32, 223, 349 caesura 303 Bézier, Pierre 182 Caflisch 270, 343 Bézier splines 182-83 Caledonia 137, 226, 273, 333, 336 Bí Shēng 119 Californian 219, 220 bibliographies 81 Calisto 322 bicameral alphabets 322 Cancelleresca bastarda 246, 344

Index

Bahasa -

Cancelleresca

capitals, height of 324 Cherokee 96, 113, 142, 241 see also case; small capitals chevrons caret, dumb 308 see guillemets Carmina 47, 100, 219, 345 Chinese 142, 181, 184, 301, 304, 313 Carolina 120 Ching, Frank 272 Chipewyan 117 Caroline script 120-21, 176, 212, 215, Choc 270 247 Carolus 336 chromatic scale & page caron 304 proportions 146 Carr, Dan 334, 350 cicero (type measure) 324, 329 Carter, Harry 280 circumflex 305 Carter, Matthew 87, 186-87, 229, 243, Cistercian Order 267 City 251 278, 284, 286, 334, 337, 348, 352 Carter, Thomas F. 119 civilité types 188, 271, 344 Carter & Cone 348 Clairvaux 267 Cartier 219, 221, 282, 287, 335, 340 Clarendon 59, 106, 132, 223 case, upper & lower 49, 53-55, 120, 179, clarendon types 223, 330-31 class-based kerning 203 classification of typefaces 12-15, Caslon 51, 59, 67, 98, 113, 126, 221-22, 121-36 234, 279, 331, 334, 344 Caslon, William 51, 126, 211, 221-22, Claudius 339 255, 273, 274, 276, 334-35, 344, 346, Cloister 222, 234 Cobden-Sanderson, Thomas 222 Caslon, William IV 255, 355 Cochin, Nicolas 348 Codex 251, 282, 287, 343 Caslon Foundry 348, 355 Caspari 226, 256, 264, 265, 335 Codex Sinaiticus 175 Colines, Simon de 85, 189, 210, 273, Cassandre, Adolphe Mouron 348 Castagno, Andrea del 284 277, 335 Casteljau, Paul de 182 colon 35, 76, 305 Colonna, Francesco: Hypnerotomachia Castellar 62, 64, 160, 282, 287, 327 Catalan 91, 290-92, 304, 310, 313 Poliphili 171, 241 Cataneo 216, 340 color, typographic 25, 107, 194, 324 Catches, Violet 115 Colwell, Elizabeth 100 Colwell Handletter 100 Cebuano 91 cedilla 304 Comenius 47, 85, 223, 345 Centaur 67, 79, 84, 94, 105, 122, 140, Comenius, Jan 223 comma 77, 78, 305 202, 206, 217, 222, 233-34, 244, 333, inverted 311 339, 342 Complutensian Greek 273, 274, 338 Century Schoolbook 223 chancery types 256, 273-74, 324 Compugraphic 346 Chaparral 100, 222, 344 Cone, Cherie 348 Chappell, Warren 79, 249, 281, 335, 353 Consort 223 contrast 60, 102, 111, 130, 324 chapter openings 62-63 Convention 340 character count 29 character sets 76, 179-82, 258-59, copyfitting 26-31, 35, 36-39, 73 288-95, 301-20 copyright (symbol) 305 vs glyph palettes 185-88, 331 Cornford, Francis M. 108, 109 Charlemagne 100, 120, 283, 287, 344 Cossgrove, Carl 227 Charlemagne (Carolus Magnus) 120, counter (of letterform) 194, 324 Courbet, Gustave 131 124 Charter 96, 279, 334 Credo 342 Cheltenham 96 Cree 113, 142 Chêneau 334 Cristal 282, 287

Index
capitals Cristal

Cronos 343	dialogue, typography of 81
crossheads 65-67, 324	'didone' types 121
culture & typography 22, 99–114,	Didot 94, 131, 210, 276, 335
119–42, 143, 180, &c	Greek 112, 113, 276, 336
curl (diacritic) 311	Didot, Ambroise Firmin
currency symbols 305-6, 317-18	see Firmin-Didot, Ambroise
cursives 32, 56-59, 76, 112, 265, 324	Didot, Firmin 128, 131, 210, 253, 335, 35
Cyrillic 279	Didot, Francois-Ambroise 335
Greek 273–74	diesis 307
see also chancery types	Diethelm, Walter 350
Cycles 343, 355	digital typography 94–95, 111, 136, 137,
Cyrillic 32, 96, 107, 110, 114, 142, 179,	142, 182-85, 196-97, 198-99, 203,
181, 185, 205, 279-81, 298-99, 334	207, &c
pryamoi 279–80	Dijck, Christoffel van
Czech 180, 289-95, 301, 302, 304, 315	see Van Dijck, Christoffel
Czech Uncial 340	dimension sign 82, 307
<b>W</b>	dingbats 324, 325
dagger 306, 307	Diogenes 277
Dair, Carl 219, 221, 282, 335, 340	Diotima 100, 219, 224, 225-26, 239,
Daniels, Gerard 226, 256, 265, 335, 349	282, 345
Danish 50, 91, 301, 314, 317	Diotima of Mantinea 225-26
Dante 125, 133, 206, 225, 244, 282, 338,	dipthongs, typographic 92
340	see also ligatures
dashes 76, 80-84, 306	Documenta 226, 334
em dash 80-81, 83	Does, Bram de 79, 139, 236, 249, 335,
en dash 80-81	349
swung dash 314, 318	Dooijes, Dick 351
three-to-em dash 80, 332	Dostoevsky, Fyodor 107
see also hyphen	dot leaders 35, 71, 324
Davenport, Guy 21	dotless i 51, 288, 307
David, Ismar 335	double acute 306, 307
David Hebrew 335	double grave 307
Davis, Miles 36	Doves Roman 222
De Roos 342	Double Augustin Open Capitals 344
Dead Sea Scrolls 171	Downer, John 136, 265, 340, 348, 349,
Deberny & Peignot 141, 348	350
Deepdene 209, 225, 337	DPI see resolution, digital
DeFaccio, Giovanni 244, 285, 335,	drama, typography of 21
339, 348	drop caps see versals
degree sign 306	dropline paragraphs 40, 325
Delphin 251, 282, 287, 343	DTL see Dutch Type Library
Demos 102, 256, 344	Duc de Berry 267
Denise 334	duck-foot quotation marks 86
depth of page 37-38	dumb quotes 308
Derby 270	Dutch 34, 50, 91
Detterer, Ernst 222	Dutch Type Library 128, 349
Devanagari 142, 181, 184, 322	Dwiggins, William Addison 79, 113,
df Type 245, 348	137, 226, 227, 269, 333, 336, 353
diacritics 34, 76, 89-92, 299, 300-320	dyet 288, 308
editing 200-201	
Greek 110-11, 112, 179, 296-97, 328,	Eaglefeather 57, 270-71, 330
329	Eaves, Sarah Ruston 188
diaeresis 306-7, 328	Edo 116

Index Cronos - Edo

EETS (Greek Font Society) 350 Fairbank 216, 227, 336 Egyptian 505 59, 236 'egyptian' types see slab-serif types Fairbank, Alfred 140, 227, 336 Eichenauer 335 Fairfield 137, 226, 227, 342 Eidenbenz, Hermann 132, 223 Falcon 137, 336 El Greco 270 families, typographic 53-59, 102-6, Eldorado 336 140, 208 Fann Street Foundry 349, 355 Electra 79, 113, 137, 226, 227, 336 Electrix 340 Faroese 91, 288, 295, 308 elevated caps see versals 'fat face' 267 Elizabeth 100 Faulkner, William 83-84 ellipsis 82-83, 308 Ferrari, Julia 334, 350 Elsner, Veronika 349 Fibonacci, Leonardo 155 Fibonacci series 155-58, 167, 196 Elsner & Flake 349 &c Elsschot 334 Fidelio 340 Elzevir 126, 265, 344 Figural 79, 108, 109, 228, 236, 340 em 25-26, 138, 325, 328, 332 figures 46-48, 53, 309, 326, 327, 328, em dash 80-81, 83 329, 331, 332 Emigre Foundry 340, 349, &c spacing & kerning of 31, 33-34, en 325 71-72 en dash 80-81 Fijian 91, 313 endnotes 68-70 Finnish 91, 306 eng 288, 308 Firmin-Didot, Ambroise 273, 274, 276, Enschedé, Johann en Zonen 141, 349, Fishman, Janice Prescott 100, 338 Enschedé Font Foundry, The 141, 341, fist 309-10 Flake, Gunther 349 349, &c Erasmus, Desiderius 271 Fleischman, Johann Michael 128, 228, Erbar, Jakob 353, 356 273, 276, 336, 349 Erhardt 235, 339 Fleischmann 128, 228 Flemish 91 Ericus 336 Esprit 113, 135, 226, 252, 344 fleurons 63, 221, 285, 311, 325 Esselte Letraset 349 Flora 79, 102, 249, 256, 264, 344 Estienne 339 FL&R see justification Estienne, Henri 11 85 flush & hung 325 Estienne, Robert 78, 85 folios (page numbers) 165-66, 175, Estonian 306, 318 323, 325 eszett 50, 288, 308 Fonderie Olive 354 eth 288, 308 Font Bureau, The 350 &c ethel 50, 288, 309 Fontana 340 ethnocentricity, typographic 89-90 fonts Euler 345 bitmapped 182 Eusebius 222 defined 325-26 ew (1) 288, 292, 303 digital 111, 182-85, 206-7, 209, &c Ex Ponto 252, 271, 344 editing 35, 79, 181, 184-85, 198-207 exclamation mark 35, 77, 309 GX 184, 190 Excoffon, Roger 270, 354 licensing 199-201, 209, 211 Exertier, Jean 350 naming 208, 211-13 Expressionism 83, 134, 228 OpenType 34, 52, 184-85, 190, 202, extenders 325 205, 206, 237, 240 extension (of letterform) 112 pi 110, 238 eye (of letterform) 324, 325 PostScript 182-84, 189, 201, 202 ezh 289, 309 pretypographic 121

Index
EETS fonts

fonts (continued) Garamond, Claude 74, 78, 101, 122, 123, selection of 93-117, 198-208 141, 172, 188, 189, 230-32, 245, 246, TrueType 182-84 337, 355 Greeks 188, 273, 274, 277, 337 TrueType Open 184, 190 FontShop 190, 198-99, 208, 350, &c italics 235, 245, 337 food & drugs 19, 49, 94, 96, 117 Garamont 231 footnotes 68-69 Garnet, William 355 fore-edge 326 Geoffrey of Anjou 241 Forsberg, Karl-Erik 84, 85, 217, 336, 347 geometric form 95, 132-33, 136, 139, Forum 337 144-53, 257, 258, 274, 328 Foster, Robert 283, 342 Geometric Modernism 14 Georgia 96 Foundry, The 133, 212 Fournier 129, 206, 228-29, 331, 336 Gering, Ulrich 219 Fournier, Pierre Simon 129, 228-29, German 34, 37, 43, 50, 91, 114, 180, 288-94, 306, 316 Geschke, Charles 346 Fox (Algonquian language) 114 Fox, Benjamin 132, 223, 349 Gestalt 338 fractions 81-82, 310, 329 GFs see Greek Font Society fraktur 32, 266, 267, 326 Gilgengart 345 Franklin, Benjamin 129 Gill, Eric 47, 53, 57, 58, 140, 207, 234, Franklin Gothic 132, 255 246, 258, 260, 277, 337, 354 French 34, 37, 43, 50, 82, 91, 100, 180, Gill Sans 47, 53, 206, 234, 258, 264, 277, 288-95, 304, 305, 306, 307, 316 279, 324, 337 Gills, Michael 349 Frere-Jones, Tobias 350, 351 Friar 337 Giovanni 343 Friedlaender, Henri 336 glam 297 Friedlander, Elizabeth 100 glottal stop 310, 311 glottalization 114, 115, 116, 302 Frisian 91 Froben, Johann 85, 210 Glypha 336 front matter 72-73 glyphic (vs graphic) form 270 Frutiger 96, 105-6, 237, 253, 257, 264, glyphs & glyph palettes 179, 185-90, 265, 279, 336 325, 326, 331 Frutiger, Adrian 47, 58, 101, 105-6, editing 200-207 118, 131, 139, 141, 215, 235, 237, 238, golden section 150, 155-60, 175 Golden Type 222 243, 253, 257, 271-72, 283, 286, 335, Golgonooza Letter Foundry 350 336-37, 348, 353 Fruttiger, Walter, Foundry 350, 354 Gothic art 136, 266 Fulfulde 116 Goudy, Frederic 31, 79, 102, 140, 201, Fulín, Miloslav 350 213, 219, 220, 225, 231, 234, 267, 268, Fundición Tipográfica Bauer 347, 350 269, 337, 339, 342, 347, 352 Fundición Tipográfica Neufville 350 Goudy Old Style 337 Goudy Sans 337 Futura 47, 95, 96, 106, 133, 212, 253, 257, Goudy Text 267, 337 264, 279, 342 Goudy Thirty 268, 337 Gaelic 310, 290-94 Grafotechna Foundry 141, 350, &c Galliard 87, 229, 243, 331, 334, 337 Grandjean de Fouchy, Philippe 351 Gamma 252, 344 Granjon 230, 339 Ganeau, François 100, 101, 354 Granjon, Robert 125, 188, 229, 230, 243, 'garalde' types 121 271, 273, 276, 337, 346, 354 Garamond 51, 85, 100, 101, 104, 105, grave 310 106, 122, 189, 230-32, 343 Greek 24, 89, 96, 100-102, 107-13, 142, Jannon's types known as 101, 126, 162, 179, 181, 184, 185, 205, 255, 256, 273-75, 296-97 231-32, 339, 351

Index

fonts -

Greek

Greek (continued) Heraklit 209, 240, 274-75, 277, 345 diacritics 110-11, 296-97 Herculanum 118, 283, 286, 337 Hermes Trismegistos 286 linguists' 297 Modernist 274-75 Hess, Sol 212, 352 monotonic 110, 328 Hiligaynon 91 numeric 297 hinting, digital 207, 326 polytonic 110, 274, 329 historical authenticity 98-99 taxonomy of 273-75, 328 history of letterforms 12-16, 98-99, Greek Font Society 349 119-42 Hoefer, Karlgeorg 105, 255, 268, 269, Greenlandic 288, 318 grids 166-67 270, 339 Griffo 338, 340 Hoefler 338 Griffo, Francesco 122, 125, 140, 164, 171, Hoefler, Jonathan 244, 285, 338, 351 Hoefler & Frere-Jones 351 188, 189, 210, 211, 216, 225, 227, 241, Hoell, Louis 217, 345 243, 273, 274, 277, 321, 337-38 guillemets 86, 310, 316 hoi 311 Guillén de Brocar, Arnaldo 273, 274, Holiday, Billie 36 Hollander 233, 256, 344 277, 338 Gurtler, André 59 Holmes, Kris 58, 100, 258, 334, 338, 356 Gutenberg, Johann Gensfleisch 103, Hopi 113, 293 119, 120, 155, 179-80, 188, 189, 190, horizontal motion 25-36, 163 Howes, Justin 221-22, 348 42-line Bible 180, 188 Hudson, John 282, 338, 356 gutter 326 humanism 12, 260, 321, 326 Humanist 521, 531, 777 (= Gill Sans, Guyot 334 Syntax, Frutiger) 202 Guyot, Francois 252, 338, 354 GX fonts 184, 190 Hungarian 43, 91, 180, 301, 306, 307 Hunt Roman 345 Haarlemmer 96, 233, 245-46, 247, 248, Hyperion 345 hypertext 193 258, 344 Haarlemmer Sans 258 hyphen Haas, Johann Wilhelm 350 forms 76, 78-80, 311 Haas Foundry 132, 350 usage 42-44, 88-89 háček 304, 315 see also dashes Hadassah Hebrew 336 Hadriano 337 Icelandic 91, 288-95, 308, 318 Haida 114, 115 Igbo 116 Hammer, Victor 269, 338 lkarus 356 illustrated books 21-22, 161 Hammer Uncial 338 handsetting 179-80, 186 Ilocano 91 Handy, John 216, 218 Imprimerie Nationale 351 Harris Intertype 351 indents 39-43 Hartz, Sem 137, 245, 247 Indonesian 91 Industrial Revolution 255 Hausa 116, 180, 313 Hauy, Valentin 255 initials Hawaiian 91, 115 large see versals headings 65-67 in personal names 30, 33, 34 Hebrew 23, 65, 89, 106, 111, 142, 162, ink 195 inline letters 62, 326-27 179, 181, 205, 311, 313, 319, 322 inscriptional letterforms 75-76, hedera 311 Hell, Rudolf 353, &c 119-20, 255, 256, 259, 326-27 Helvetica 32, 78, 95, 96-98, 97, 106, 132, instinct & typography 143-45 Integra 340 211, 255, 265, 273, 279, 350

Index Greek – Integra

International Organization for	Jessen 339
Standardization (180) 327	Joanna 234, 246, 337
character sets 76, 180, 301-20	Jones, George W. 141, 222, 230, 339, 353
paper shape & sizes 148, 153, 154, 175	Journal 100, 134, 234, 340
International Phonetic Alphabet (IPA)	Juliana 137
116, 299, 327	justification 26-27, 42-44, 190-92,
International Typeface Corporation	325, 327
(ITC) 351	ON.
Intertype (International Typesetting	Kaatskill 213, 337
Machine Co.) 351	Kabel 279, 339
intonation 88-89	Kaiser, Erhard 128, 228
Inuktitut 113, 341	Kapr, Albert 355, 356
Ionesco, Eugène 21	Karner, Lui 244, 285, 335, 339, 348
iota subscript 110-11, 296-97, 329	Karow, Peter 190-92, 356
Iridium 336	Katsoulides, Takis 113, 276, 278, 350
Isadora 338	Kazcun, Alex 227
150 see International Organization for	Keere, Hendrik van den
Standardization	see Van den Keere, Hendrik
Italian 91, 289-94	Kennerley 79, 201, 234, 337
Italian Old Style 337	Kennerley, Mitchell 234
italic 53-55, 56-59, 60, 74, 103, 112,	Kepler 343
124-25, 137, 140, 265, 275, 327	kerning 32-34, 50, 69, 87, 137, 138, 199,
Aldine 125, 210	203-7, 327
alphabet length 27, 57	polynomial vs binomial 35
capitals 54-55, 59, 331	Kesey, Ken 21
Colines 210	keyboard layouts 75, 90–92, 138, 180
Dante 125	Khoisan languages 115, 309, 320
Didot 210	Kinesis 235, 338
Fournier 229	Kis, Miklós 126, 137, 141, 235, 273, 276,
origins 124	339
transitivity 56	Kis (= Janson) 235, 331
unserifed 255, 264	Klingspor, Karl 352
upright 57, 271	Klingspor Bros. Foundry 352
vs sloped roman 56-59	Kobayashi, Akira 259-60
italicization quotient 264	Koch, Peter Rutledge 277
a quotient 204	Koch, Rudolf 134, 267, 268, 284–85, 335,
Jaguar 251, 270, 343	339, 352
Jamille 338	Koch Antiqua 339
Jamra, Mark 235, 338	Kokoschka, Oskar 134
Jannon (= Monotype 'Garamond')	Komenský, Jan Ámos 223
100, 101, 230–32, 279, 331	Kompakt 345
Jannon, Jean 100, 101, 126, 230-32, 276,	Korean 142, 181, 185, 304
338-39, 348, 351	11010411 142, 101, 103, 304
	kra 188
lanson 126 127 225 220	kra 288 Krijger Henk 220
Janson 126, 137, 235, 339	Krijger, Henk 339
Janson, Anton 235	Krijger, Henk 339 Krimpen, Jan van
Janson, Anton 235 Japanese 76, 142, 181	Krijger, Henk 339 Krimpen, Jan van <i>see</i> Van Krimpen, Jan
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339	Krijger, Henk 339 Krimpen, Jan van <i>see</i> Van Krimpen, Jan kroužek 317
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339 Jenson, Nicolas 16, 112, 122, 189, 339	Krijger, Henk 339 Krimpen, Jan van see Van Krimpen, Jan kroužek 317 Kudryashev, Nikolai 355
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339 Jenson, Nicolas 16, 112, 122, 189, 339 blackletters 104-5, 268	Krijger, Henk 339 Krimpen, Jan van see Van Krimpen, Jan kroužek 317 Kudryashev, Nikolai 355 Kuzanyan, Pavel 279, 355
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339 Jenson, Nicolas 16, 112, 122, 189, 339 blackletters 104-5, 268 Greek 211, 273, 274, 277	Krijger, Henk 339 Krimpen, Jan van see Van Krimpen, Jan kroužek 317 Kudryashev, Nikolai 355
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339 Jenson, Nicolas 16, 112, 122, 189, 339 blackletters 104-5, 268 Greek 211, 273, 274, 277 roman 16, 104-5, 211, 222, 233, 235,	Krijger, Henk 339 Krimpen, Jan van see Van Krimpen, Jan kroužek 317 Kudryashev, Nikolai 355 Kuzanyan, Pavel 279, 355 Kwakwala 114, 289-95
Janson, Anton 235 Japanese 76, 142, 181 Jenson 112, 184, 222, 233-34, 235, 339 Jenson, Nicolas 16, 112, 122, 189, 339 blackletters 104-5, 268 Greek 211, 273, 274, 277	Krijger, Henk 339 Krimpen, Jan van see Van Krimpen, Jan kroužek 317 Kudryashev, Nikolai 355 Kuzanyan, Pavel 279, 355

Index

International
- Lambrecht

Lange, Gunter Gerhard 269, 270, 347 Lanston, Tolbert 137, 352 Lanston Monotype 140, 212, 352 Lanston Type Co. 352, &c Lardent, Victor 97 Latienne 338 Latin 24, 37, 114, 181, 184, 185, 205 Latvian 180, 304, 313, 319 Laudatio 341 Laurentian 340 lay of the case 179 Lazurski 96, 110, 280, 340 Lazurski, Vadim 110, 279, 280, 340, 355 Le Bé, Guillaume, the elder 243, 340 Le Corbusier [Édouard Jeanneret] Modulor system 157, 158, 167, 169 Le Monde 96, 341 leading 36-37, 327, 328 Legacy 96, 102, 222, 234, 235-36, 246, Legacy Sans 53, 264, 265 Legende 271 Legrand, Marcellin 351 letterfit 35 LetterPerfect 352 letterpress 93-94, 138 Lettersnider, Henric 266, 340 letterspacing 30-32, 202-3 lettrines see versals Lexicon 236, 335 Libra 342 licensing 199-201, 209, 211 Ličko, Zuzana 100, 134-35, 136, 188, 234, 340, 349 ligatures 31, 50-53, 179, 188, 312, 327 line length see measure Linotype Library 198, 350, 352-53, &c Linotype machine 137-42, 139, 352, &c Lipton, Richard 215, 340, 348, 350 lists (typography of) 35-36, 70-72 Liszt, Ferencz 217 lithography 138-39 Lithos 100, 118, 281, 283, 344 Lithuanian 304, 312, 313, 314, 315 logic, symbolic 303, 305, 313, 314, 318 logical form 20-24 logical not 312, 314 logograms 49, 76, 327 logotypes 49 Lombardic Capitals 267 long s 51, 288, 294, 312 louse 313

lowline 313

Lubalin, Herb 282, 351 Luce, Louis-René 351 Lucida 57, 94, 100, 102, 264, 334, 338 Lucida Sans 96, 116, 258-59 Ludlow Typograph 353 Ludwig & Mayer 353 Lunda 336 Lutetia 103, 245-46, 275, 281, 344 Lutetia Open Capitals 344 Lydian 249, 335 Lyrical Modernism 15, 133 Macedonian 291, 301, 308 macron 313 Magnificat 270, 341 Majoor, Martin 53, 79, 208, 246, 247, 260-62, 340, 350 Malay 91 Malayalam 142, 184 Malin, Charles 225 Maltese 288-295, 303, 315 Manfredi, Victor 116 Mannerism 97, 125-26, 229, 243, 276, Mantegna, Andrea 284 Manticore 282, 338 Mantinia 186, 229, 284, 334 Manuscript 209, 228, 236 Manutius 334 Manutius, Aldus 85, 125, 171, 241 Maori 115, 289-94 Marconi 345 Mardersteig, Giovanni 125, 133, 225, 280, 282, 338, 340, 354 margins 165-78, 323 Marigold 270 Maring, Herbert 267 Martin, Robert 218 Martin, William 131, 218 Martínez Meave, Gabriel 340 Massin, Robert 21 Master of Basel 210, 227 Matheis, Helmut 353 mathematical symbols 302 mathematics & typography 145 Matthiessen, Peter 21 Matthiopoulos, George 278, 350 Matura 270 Mauritius 343 Mayan languages 116

McDonald, Rod 221, 335, 340

measure 26-28, 161, 163, 328

mechanical typesetting 137-42

*Index*Lange –
mechanical

'mediaval' types 84	Morison, Stanley 97, 140, 207, 227, 246,
Medici (= Palatino) 211	270, 354
Meier, Hans Eduard 47, 106, 141, 261,	Morris, William 222
340	Mosley, James 255
Melior 52, 85, 345	movable type, early history of 119
Memphis 133, 331	Mozart, Wolfgang Amadeus 229
Mendoza 52, 100, 101, 108, 112, 237, 340	Mrs Eaves 188
Mendoza y Almeida, José 79, 101, 112,	mu (µ) 313
200, 237, 240, 340, 351, 354	multicultural typography 102–17, 142
Menhart 340	multilingual typography 22, 50, 91–92,
Menhart, Oldřich 79, 134, 141, 228, 236,	106-17, 142
269, 284, 340, 350	multiple-column pages 37-38, 39, 44
Mergenthaler, Ottmar 137, 352	multiple master (MM) typefaces 184
Méridien 47, 58, 96, 100, 101, 105-6, 215,	music & typography 19, 21, 24, 35, 45,
237, 238, 243, 257, 265, 322, 336	83, 100, 117, 144, 146-47, 162, 163,
Meta 343	166–67, 198, &c
Metro 336	musical signs 313
Mexica 340	mutton see em
Michelangelo 215, 240, 277, 284, 287, 345	
Microsoft 204, &c	Myriad 96, 343, 344
Middleton, Robert Hunter 353	nang 319
midpoint 75-76, 313	nasal hook 304, 314
Miedinger, Max 97, 211, 350	nationalism, typographic 100-102
Miller & Richard 353	Native American languages 34, 113–16,
Millet, François 131	201, 288–95, 304, 314, 319
Mills, William Ross 230, 240, 338,	Syntax character set 261
341, 356	Navajo 113, 115, 180, 289-94, 303, 314
Mincho katsuji 76	Nebiolo Foundry 354
Minion 49, 59, 96, 106, 107, 201, 281,	negation sign 314
237, 343	Neo Hellenic 108
Cyrillic 107, 280	see also New Hellenic
Greek 107, 275	Neoclassicism 13, 57, 77, 84, 94–95, 97,
Miscomini, Antonio 219, 277, 341	99, 101, 113, 128–30, 135, 136, 138, 162,
Mistral 270	216, 229, 241, 259, 274, 278
Miyamoto, Kenneth 21	Neocodex 340
'modern' types 121	Neogothicism 129
Modernism 14, 15, 48, 95, 97, 132-34,	Neohumanism 77, 97, 133, 217, 225, 237,
243	239, 241, 244, 246, 328
Modula 340	Nero 341
modular scales 166-69	Neue Hammer Unziale 269
modulation	Neufville Foundry
between roman and italic 57	see Fundición Tipográphica Bauer
of penstroke 76, 120, 130, 255, 328	Neugebauer, Michael 270, 349
Modulor system 157	Neuland 284–85, 287, 339
monitors, typography for 192–93	New Hellenic 111, 112, 274, 277-78, 343
monochrome types 95	Nicholas, Robin 227
monotonic, Greek 110	Nigerian languages 116, 288-95
Monotype 122, 133, 206-7, 354, &c	Nobel 342
machine 137-42, 139, 180, 354	Nofret 100, 104, 135, 219, 224, 226, 239,
see also Agfa Monotype	345
Monotype, Lanston 140	nomenclature 211-13
Montaigne 342	Noordzij, Christoph 349
Monument 228, 284, 287, 340	Noordzij, Gerrit 335, 341, 349
111011111111111111111111111111111111111	11001421, 001111 333, 341, 349

Index

mediäval – Noordzij Noordzij, Peter Matthias 112, 218, 341, Palatino 52, 59, 77, 94, 95, 96-98, 97, 104, 115, 133, 141, 204, 209, 211, 214, Norstedt Foundry 354 215, 239-40, 253-54, 274-75, 277, Norton, Robert 219-21 278, 282, 284, 345 Norwegian 50, 91, 288, 301, 314, 317 Cyrillic 281 notes, textual 68-70 origin of name 211 Novarese, Aldo 282, 354 Palatino, Giovanni Battista 211 novels, typography of 20-21, 81 Palomba 251, 270 Pan-Nigerian alphabet 115-16 Nueva 344 null 314 Pannartz, Arnold 212, 343 numerals 46, 95-96, 314 paper 94-95, 100, 138, 143-45, 162, 195 see also figures Paradox 344 nut see en ParaGraph International 354, &c paragraphs 39 obelisk 306, 307, 314 ParaType 354, &c obelus 306 parentheses 76-77, 84-85, 315 obliques 54-55, 56-59, 126 Parker, Douglass 21 octothorp 77, 313, 314 Parliament 340 Odd-job Sanserif 97 Parmenides 107, 277 Officina 96, 136, 239, 279, 343 Parmenides 334 offset printing 93-94, 136, 139 Pascal 340 ogonek 115, 304, 314 Pegasus 345 Ojibwa 113 Peignot, Charles 348 Old Style Antique 341 Peignot, Remy 282 'old style' types 121 Pepita 270 Olive Foundry 354 Pericles 283, 287, 342 Olivieri, Ruggiero 280 period (full stop) 77, 315 Omnia 269 Perpetua 58, 322, 337 omicron iota 309 personality 99-102 Peter, Friedrich 270, 341 Ondine 271-72, 283, 337 Open Kapitalen 281 Peters, John 282 openings, textual 61-65, 281 Phemister, Alexander 131, 341, 353 OpenType fonts 34, 52, 184-85, 190, Phidias 240, 277, 284, 345 202, 205, 206, 237, 240 Philippine languages 91 Optima 47, 94, 137, 211, 259, 264, 345 phonetic types 116-17, 327 Oranda 233, 344 phonomark 315 ordinal letters 312 Photina 79, 200, 209, 240, 340 Organica 340 phototype 139-40 Orion 345 pi fonts 110, 328 ornaments 40 pica 25, 73, 177-78 see also fleurons; hedera defined 328-29 orphans (typographic) 43 Pie Tree Press & Foundry 354 orthographies, new 113-17 Pigiarniq 341 orthotic types 89, 273-74, 277, 328 pilcrow 77, 315-16 outdents 40 Pilgrim 337 outline letters 326-27 Pindar 269, 338 overdot 115, 315 pipe 316 Ovid 271 pixels 192-93 Plantagenet 96, 240-41, 341 page shapes 10, 143-78 Plantin 279 Plantin, Christophe 78, 122, 252, 338, pagination 42-44, 165-66, 175, 178 see also folios palatal hook 315 Plantin-Moretus Museum 74, 355

*Index* Noordzij – Plantin

Plato	Quadraat Sans 260, 264
Symposium 226	quaints 329
Timaeus 168	Quay, David 212
Poetica 125, 186, 188, 189, 237, 241, 244,	question mark 35, 77, 316
331, 343	Quiché 116
poetry, typography of 21	quill, pointed 130
point, typographic 25, 73, 177-78, 323	quotation
defined 329	block form 40-41, 86, 323
Didot point 323, 324, 329	marking 64-65, 77, 86-87, 311, 316
Poliphilus 79, 125, 140, 206, 241-43,	(No.
333, 338	racism, typographic 89-90, 180
Polish 50, 91, 180, 288-95, 303, 314, 315	Radisch, Paul Helmuth 344
Polk, Noel 83	Raffia 339
Polygraphmash 355	ragged setting 27-28, 325, 326
Polynesian languages 115	see also justification
Pompeijana 286, 337	Raleigh 221
Pontifex 78, 95, 133, 176, 211, 243, 322,	random variation 188–90
•	
341  Popul Friedrich 78 122 176 211 242	rasterization 326, 330
Poppl, Friedrich 78, 133, 176, 211, 243,	Ratdolt, Erhard 189, 342
341	rationalism 128, 216, 329
Poppl Antiqua 341	Realism 14, 95, 97, 131–32, 136, 321, 322
Poppl Exquisit 341	Reformation 100
Porchez, Jean-François 341	Regulus 334
Porson 108, 111-13, 278, 333, 341	Reiner, Imre 270, 342, 347
Porson, Richard 111, 113, 274, 278, 341,	religion & typography 100, 231, 333
350	Renaissance form 12, 30, 32, 78, 86, 94
Portuguese 91, 304, 305, 306, 318	97, 98, 99, 106, 122–25, 127, 134, 138,
Post, Herbert 347	156, 157, 162, 201, 222, 230, 234, 241,
Postmodernism 15, 135–36, 227, 240,	246, 251, 261, 337
252	Renner, Paul 47, 133, 212, 253, 257, 342,
PostScript fonts 182–84, 189, 201, 202	347, 356
Pott, Gottfried 120, 267	Renner Antiqua 342
Pradell, Eudald 342	Renner Grotesk 342
Praxis 102, 249, 256, 344	Requiem 244, 285, 338
Preissig 134	resolution, digital 94, 192, 324, 330
Preissig, Vojtěch 134, 342, 350	screen monitors 192
prelims 35-36, 72-73	Reynard 343
Present 272	Rhapsodie 100, 268
prime 307, 316	rhythm 25 -44, 45, 193
Primer 342	Rialto 244-45, 285, 335, 339
Prince, Edward 222	Riggs, Stephen R. 115
printing 93-94, 136, 138-39, 194-95,	Rimmer, Jim 213, 342
203	ring (diacritic) 306, 317
proofing type 193-94	Rockwell 331
proportion 25-44, 143-78	Rococo 127-28, 228, 229, 336
punchcutting 133, 138, 186–87	Rogers, Bruce 79, 105, 122, 140, 207,
punctuation 30, 35, 75–89	222, 233, 339, 342
Pushkin 280, 340	romain du roi 129
Pye, David 189	Roman Empire 120, 124, 152, 162, 317
Tyc, David 109	roman type
quad see em	alliances 53-55
Quadraat 96, 102, 244, 246, 260, 343	allphabet length 27,57
Cyrillic 281	boldface 55-56, 60

*Index*Plato –
roman

roman type (continued) Scala 79, 96, 104, 208, 246-47, 260, components 124 262-63, 340 historical development 119-42 Scala Sans 53, 208, 260, 262-63, 264 sloped 56-59, 126, 251, 261 Scangraphic 355 &c specimens 213-65, 281-87 Schadow 343 vs script 270-72 Schelter & Giesecke 355, 356 see also case; small capitals Schneidler, Ernst 271, 343 Romanée 103, 245, 246, 275, 344 Schoeffer, Peter, the elder 274 Romanesque art 332 Schoeffer, Peter, the younger 200 Romansch 91 Scholderer, Victor 111, 112, 274, 277-78, Romanticism 13, 86, 95, 128, 130-31, 343, 350, 354 135, 138, 217, 218, 253, 274, 321, 322 Schule, Ilse 100, 268, 353 Romulus 58, 233, 245-46, 248, 260, 282, schwa 288, 290, 317 287, 327, 344 Schwabacher 266, 268 Romulus Sans 209, 260, 344 Scotch Roman 333 Ronaldson, James 334 screen monitors, typography for Roos, Sjoerd Hendrik de 269, 342, 192-93 screened text 62 349, 351 Rosart, Jacques-François 228 scribal tradition 136, 138-39 Rosenberger, August 239, 259, 284 broadpen vs pointed quill 130 Rossum, Just van 188, 190, 350 Chinese & Japanese 10,76 rotunda 105, 255, 266, 268, 330, 339 Egyptian 10, 161-62, 173, 175 Ruano, Ferdinando 244 European 10, 120-21, 161, 164, 173, Rumanian 91, 180, 279, 304, 305, 319 196, 215, 255, 269, 281 Greek 162 running heads & footers 20-21, 65, 70, 166 Hebrew 162 Ruse 341 justification 190 Russian 32, 111, 298, 304 modulation of penstroke 75-76, 255 see also Cyrillic punctuation 76, 77, 78, 86 Rusticana 118, 286, 337 Roman 75-76, 255 Růžička, Rudolph 137, 226, 227, 342, 353 scribes 32, &c script types 89, 127, 270-72 Saami languages 288, 303, 308, 309 scroll form 162, 171 Sabon 34, 52, 104, 106, 230, 246, 343 section sign 77, 317 Sabon, Jacques 246, 356 semicolon 35, 317 Sack, Freda 212 Serbo-Croatian 279, 288-99, 302, Safaev, Tagir 239 307, 308 Sakwa, Jacqueline 340 Seria 96, 102, 247, 340 Saladin 341 Seria Sans 53, 261 Sallwey, Friedrich 272 Serifa 331 Salto & Saltino 270 serifs Samaritan 343 abrupt & adnate 321 Samson 269, 338 bilateral & unilateral 322, 330 San Marco 105, 255, 268, 339 concave & convex 93 Sanlècque, Jacques de, the elder 243, defined 93 inscriptional 119-20 Sanlècque, Jacques de, the omission of 255-56 younger 342 reflexive & transitive 56, 329, 332 sanserif types 97, 102, 105-6, 255-56, roman & italic 56, 330 on screen 193 Sanskrit 292-94, 313, 318, 319 scutulate 330 Sanvito 270, 343 slab 330-31 Saskia 343 see also sanserif; slab-serif

Index roman – serifs

set-width 71–72, 137, 205	spaces (continued)
Shannon 100, 338	hair 326
Shaw, Paul 352	hard 43, 326
Shchukin, Anatoli 279, 355	mid 328, 332
Sheffer's stroke 303	thick 331
Sheldon 245, 344	thin 331
Shěn Kuò 119	Spanish 43, 50, 91, 180, 289–94, 306,
sidebearings 202-3	309, 311, 312, 316
sideheads 65-67, 330	Spectrum 94, 96, 133, 233, 246, 247-48,
sidenotes 68, 161, 176	275, 344
Siegel, David 271, 272, 346	speech, as reference for typography
Sierra 100, 338	49, 88-89
sigma 110	Spiekermann, Erik 136, 239, 343, 350,
signatures (gatherings) 73	352
signposts, textual 20-21	sputnik 313
Silentium 247, 344	square brackets 318
Silica 343, 355	Squire 270
Simoncini, Francesco 231	Stan, Tony 219, 231
Simplex 342	stem 331
sinkage 160	Stempel 106
Sistina 215, 240, 284, 287, 345	Stempel Foundry 101, 133, 141, 355, &c
sizes, typographic 45, 157, 321, 323	Stephenson, Blake & Co. 223, 348, 349
Skaryna, Frantsysk 279, 343	353, 355
Skolt 289, 295, 309	Stinehour, Christopher 277
slab-serif (egyptian) types 132, 136,	Stone 94, 96, 102, 115, 343
218, 239, 330	phonetic 116
Slimbach 343	Stone, Sumner 343, 346, 355
Slimbach, Robert 49, 59, 107, 122, 125,	Stone Print 343
188, 200, 222, 230, 233, 237, 241,	Stone Type Foundry 355, &c
244, 270, 274–75, 280, 281, 339, 343,	Stradivari, Antonio 141
344, 346	Stratford 345
slope, defined 331	subheads 38, 65–67
sloped roman 54-55, 56-59, 126	subscripts 309
Slovak 290–95, 302, 304	Sulla, Lucius Cornelius 218
	Sully Jonquières 340
Slovene 304	superscripts 68-69, 71, 309, 316
small capitals 31, 46, 48-49, 53-55, 60, 63, 103, 312, 322	swash 54, 55, 59, 324, 331
Cyrillic 32, 279 Smaragd 281, 286, 327, 345	Swedish 91, 301, 306 Sweynheym, Konrad 212, 274, 343
· ·	• •
Smeijers, Fred 244, 260, 281, 343, 350	Swift 79, 233, 249, 256, 344
Smith, Eve 191	swung dash 314, 318
software, typesetting 51-52, 90-91, 180,	syllabics, Canadian 341
188-90, 192, 196-97, 198-207	symmetry 164
solid setting 37, 331	Syndor 340
solidus 81–82, 317–18	synonymy 211–13
Soncino, Gershom 85	Syntax 32, 47, 96, 106, 202, 261, 264,
Song of Songs 64	265, 279, 340
Sophia 186-87, 189, 286, 334	Native American character set 261
Sorbian 293, 295, 304	Syriac 343
sorts (typographic) 22, 179-88, 331	system maintenance 195-97
spaces	(W)
between sentences 28-30	tables 36, 70-72
between words 26-31, 332	Tagalog 91, 318

Index

set-width – Tagalog

Trump Mediäval 52, 78, 84, 85, 95, 243, Tagliente, Giovanantonio 124, 140, 217, 343 Tschichold, Jan 106, 173, 230, 246, 343 Tahitian 91 Takaichi Hori 76 Tsimshian 114, 289-95 Tavernier, Ameet 343, 355 Turkish 51, 180, 288, 304, 306, 307, 315 taxonomy 12-16, 121-36, 211-13 Twitchett, Denis 119 Tedlock, Dennis 21 two-column pages 37-38, 39, 44 Tekton 270-71, 272, 330 Twombly, Carol 51, 100, 118, 120, 126, Telingater, Solomon 279 221, 222, 281, 283, 286, 334, 343, terminals (of letterform) 12-15, 312, 344, 346 type library 117 322, 331 Tetterode Foundry 347 typefounding 138, 140-42 textblock 145, 148-53, 163-78, 331 typefoundries 346-56 Typoart Foundry 356 textura 266, 332 texture, typographic 25, 114 typography, defined 9-11, 17-24, 209 Thai 24, 100-102, 181 theatrical typography 21,83 u&lc 38, 332 Thompson, Bradbury 61 umlaut 306-7 Thompson, Greg 350 uncials 120, 269, 275 Thoreau, Henry David 66-67, 156 undercomma 319 thorn 288, 318 underdot 319 Thorne, Robert 349 underscore 319 Thoth 286 Unger, Gerard 79, 102, 233, 249, 256, three-em rule 81 344, 348, 349 three-to-em dash 80, 332 "Dutch Landscape with Letters" 256 Tibetan 181, 184 unicameral alphabets 312, 322, 332 Unicode character set 179-82, 185, 332 Tiemann, Walter 352 Univers 31, 58, 105-6, 174, 240, 273, tilde 318 Time 251, 343 279, 337 Times New Roman 96-98, 204, 273, University of California Old Style 206, 219, 220, 337 phonetic 116 unserifed types 102, 105-6, 136, 255-56, Tiro Typeworks 356 &c 264, 330 title pages 61 Uqammaq 341 titles 30, 61-62 URW 356 &c titling faces 281-87 Utopia 94, 343 Tlingit 113, 115, 291-95, 302 uvular consonants 115 Toriumi-Lawrence, Carol 271 Uzbek 299, 304 torso 48, 193 see also x-height Vafflard, Pierre-Louis 335 Trajan 100, 120, 286, 344 Van Blokland, Erik 190 Van den Keere 122, 252, 334, 344 Trajanus 52, 79, 82, 95, 249, 335 Van den Keere, Hendrik 122, 252, 344, Cyrillic 249 'transitional' types 121 349,355 Van Dijck 206, 207, 252, 331, 344 tréma 306 tribes, typographic 53-59 Van Dijck, Christoffel 51, 126, 245, 252, tricameral alphabets 311-12, 322 265, 344, 349 Trinité 79, 139, 249-51, 265, 335 Van Gogh, Vincent 134 Triplex 136, 264, 265, 340 Van Krimpen, Jan 58, 103, 133, 140, TrueType fonts 182-84, 190, 201, 202 141, 207, 233, 245-46, 247-48, 249, Trump, Georg 78, 84, 85, 243, 251, 268, 251, 258, 260, 274, 275, 281-82, 344, 270, 282, 343, 353, 356 349, 354 Trump Deutsch 268, 344 Van Rossum, Just 188, 190, 350

*Index* Tagliente – Van Rossum VanderLans, Rudy 349 white line 332 Veljović 252, 322, 344 whiteletter 89, 332 Veljović, Jovica 113, 135, 226, 247, 252, widows (typographic) 44 271, 344, 346 widths of letters 35, 71-72, 137, 192, 215 Vendôme 100, 101, 209 Wilhelm Klingspor Schrift 268, 339 Wilson, Alexander 274, 278, 345 Venezia 222, 339 Wilson Greek 278, 334 Venture 345 versals 63-65, 281-87, 325, 332 Winchester 336, 345 Wolf, Rudolf 133 verse 41-42 vertical motion 36-39, 163 Wolpe, Berthold 140, 282, 345, 354 women in type design 100 Vicenza 333, 345 word space 26-31, 206-7, 332 Vietnamese 180, 205, 288-95, 304, 308, Wright, Frank Lloyd 271 310, 311, 318, 319 Village Nº 1 337 wynn 289, 320 Village N° 2 337 vinculum 320 x-height 48, 112, 113, 332 virgule 76, 81-82, 320 see also torso Visigoth 270 xylography 119 O Viva 344 Vivaldi 270, 341 Y&Y 356 Yasubumi Miyake 76 a Yeats, William Butler 41, 189 Wagner, Johannes, Foundry 356 Yefimov, Vladimir 280 Walbaum 131, 253, 331, 344 Walbaum, Justus Erich 131, 253, 344, yogh 289, 320 Yoruba 116, 180, 293, 294 Walker, Emery 222 Zapf, Hermann 47, 57, 77, 78, 85, 97, Wallau 339 Warde, Frederic 79, 124, 140, 222, 233, 104, 116, 133, 137, 141, 190-92, 211, 215, 223, 235, 239, 249, 253, 259-60, 333, 344-45 Warnock 96, 281, 343 272, 274-75, 277, 278, 281, 284, 345, Cyrillic 281 352, 355, 356 Warnock, John 346 Zapf Book 345 Zapf Chancery 57, 345 Weber Foundry 356 wedge (diacritic) 304 Zapf Civilité 345 weight of typeface 332 Zapf International 85, 95, 104, 331 see also color Zapf Renaissance 189, 253-54, 278, Weiss 95 331, 345 Weiss, Emil Rudolf 345, 347 Zapf-von Hesse, Gudrun 47, 100, 120, Weiss Antiqua 345 135, 212, 215, 219, 224, 225, 239, 247, Weiss Gotisch 345 281, 282, 286, 345, 348, 355, 356 Weiss Initials 345 Zapfino 186, 190, 272, 345 Weiss Rundgotisch 345 Zeno 340 Welsh 91, 180, 201, 289-95, 305, 306 Zippora 334 Werkstätten und Museum fur

Druckkunst, Leipzig 356

Index

VanderLans

- Zippora

This book was designed by Robert Bringhurst. It was edited and set into type in Canada, then printed and bound by C&C in Hong Kong.

The text face is Minion Pro, designed by Robert Slimbach.

This is an enlargement and revision of Slimbach's original Minion type issued by Adobe Systems, Mountain View, California, in 1989.

The captions are set in Scala Sans, part of a family of type designed in the Netherlands by Martin Majoor. The face was issued by FontShop International, Berlin, and its affiliates in 1994.

The paper is Glatfelter Laid, made at the Spring Grove Mill in Pennsylvania. It is of archival quality and acid-free.

